

publisher.agency
Norway

April, 2026

No 13



Oslo, Norway
9-10.4.2026

International
Scientific
Conference

Theoretical Hypotheses and Empirical Results

UDC 001.1

P 97

Publisher.agency: Proceedings of the 13th International Scientific Conference «Theoretical Hypotheses and Empirical results» (April 9-10, 2026). Oslo, Norway, 2026. 460p



ISBN 978-0-8825-4180-8

DOI 10.5281/zenodo.19547279

Editor: Mary Olafsen, Professor, Nord University

International Editorial Board:

Anja Kazemi

Professor, University of South-Eastern Norway

Ståle Shokri

Professor, Universitetslektor - Universitetet i Sørøst-Norge

Karen Foray

Professor, University of Oslo

Hosein Nilsen

Professor, USN School of Business

Aida Drake

Professor, Buskerud University College

Gjerdalen Rolfson

Professor, University College Southeast Norway

Etty Allern

Professor, Norwegian Business School

Dr. Irmelin Kujanpää

Professor, University of South-Eastern Norway

Terje Øivind Madsen

Professor, Bergen National Academy of the Arts

Sigurd Sunagic

Professor, Inland Norway University of Applied Sciences

Miika Vesin

Professor, Norwegian Naval Academy

Dag Anderson-Glenna

Professor, Norwegian School of Economics

Mirha Seierstad

Professor, Norwegian University of Life Sciences

Boban Tavassoli

Professor, Norwegian University of Science and Technology

Cathrine Vikhagen

Professor, OsloMet - Oslo Metropolitan University

Sara Stendal

Professor, University of Agder

editor@publisher.agency

<https://publisher.agency/>

Table of Contents

Economic Sciences

ПОВЫШЕНИЕ ЭФФЕКТИВНОСТИ СИСТЕМЫ ЗАКУПА КОМПАНИЙ VI GROUP	7
<i>ЖЫЛАНБАС НҮРСҰЛТАН ЖЕТКЕРГЕНҰЛЫ</i>	
<i>ТЕМИРБЕКОВА ГҰЛҰЖАН ДЖУМАДДҰЛАЕВНА</i>	
ЦИФРОВИЗАЦИЯ АРХИТЕКТУРНОЙ И ГРАДОСТРОИТЕЛЬНОЙ ДЕЯТЕЛЬНОСТИ В КАЗАХСТАНЕ: ПРЕОБРАЗОВАНИЕ ГОРОДСКОГО ПРОСТРАНСТВА	11
<i>ДАРИСОВ ГАБИТ ГАЗИЗОВИЧ</i>	
ВНЕДРЕНИЕ ЭКОЛОГИЧЕСКОГО МЕНЕДЖМЕНТА КАК ОСНОВНОЙ ЭТАП НА ПУТИ К УСТОЙЧИВОСТИ ЭКОНОМИЧЕСКОГО СУБЪЕКТА	17
<i>МУСТАФИН РУСТЕМ КАНАТОВИЧ</i>	
<i>ШҰҒАЙ ОЛЖАС ҚАЙРАТУЛЫ</i>	
<i>АЛЬМУХАМБЕТОВ КУАНЫШ АЛЕКСАНДРОВИЧ</i>	
СТРАТЕГИЧЕСКОЕ УПРАВЛЕНИЕ ИННОВАЦИОННОЙ ДЕЯТЕЛЬНОСТЬЮ ПРЕДПРИЯТИЯ	25
<i>АХМЕТБЕКОВ ДАНИЯР ГАБДУЛОВИЧ</i>	
<i>ТУЛЕГЕНОВ АСКАР НУРТАЕВИЧ</i>	
СТРАТЕГИИ УВЕЛИЧЕНИЯ РЕНТАБЕЛЬНОСТИ ВЕЧЕРНЕЙ ПОЛИКЛИНИКИ В РАМКАХ ЦУР: ПОДХОДЫ И РЕКОМЕНДАЦИИ	31
<i>МАХАНОВ ТЕМИРҒАЛИ КАЛМАХАНБЕТҰЛЫ</i>	
<i>МАУКЕНОВА АЛТЫНАЙ АМАНБАЕВНА</i>	
THE ROLE OF ARTIFICIAL INTELLIGENCE ALGORITHMS IN DETECTING CYBERATTACKS WITHIN E-GOVERNMENT SERVICES	38
<i>FARID HASANOV</i>	
THE DIGITAL UNIVERSITY: CONCEPTUAL APPROACHES AND BIBLIOMETRIC ANALYSIS OF INTERNATIONAL AND KAZAKHSTANI RESEARCH.....	45
<i>ТОКНТАР БОЛАТБЕК</i>	
<i>JUZBAYEVA ZHANSAYA</i>	
<i>ZAKIROVA DILNARA</i>	
ВЛИЯНИЕ НАЛОГОВЫХ СТИМУЛОВ НА ЭКОНОМИЧЕСКОЕ ПОВЕДЕНИЕ ДОМАШНИХ ХОЗЯЙСТВ.....	55
<i>ТОПШАХОВА ГҰЛҰМИРА РАЙХАНОВНА</i>	
<i>КУТТЫБАЕВА НҰРҒҰЛЫ БОЛАТОВНА</i>	
<i>ЛАМБЕКОВА АЙГЕРИМ НУРЛАНОВНА</i>	
ГАЛА-БАЛЕТ КАК СИНТЕЗ ИСКУССТВА И МАРКЕТИНГА В АРТ-ИНДУСТРИИ.....	58
<i>УНЕРБАЕВА МАДИНА КУАНДЫКОВНА</i>	
<i>ЖУМАТАЕВА АЙГҰЛЫ РАХМАНИЕВНА</i>	
POLICY COORDINATION AND OPERATIONAL SYNERGIES: ENHANCING THE TRANSPORT PRODUCT OF THE EURASIAN LAND-BRIDGE	64
<i>CHAI XIANGDING</i>	
<i>RUZIEVA ELVIRA</i>	
<i>KUPESHOVA SAULE</i>	
QUANTITATIVE ANALYSIS OF THE CHINA-EUROPE RAILWAY EXPRESS: MEASURING TRANSPORT EFFICIENCY AND TRADE ELASTICITY	74
<i>LYU JUNFENG</i>	
<i>MYNJANOVA GULZHAKAN TLESOVNA</i>	
<i>TUKEMBAYEVA KYIAL</i>	
FROM ENGAGEMENT TO COMPETITION: EVOLUTION OF CHINA'S TRADE POLICY TOWARD THE UNITED STATES (2001–2025)	82
<i>SUN WENTING</i>	
<i>ALMA KARSHALOVA</i>	
<i>MYNJANOVA GULZHAKAN TLESOVNA</i>	
A HOLISTIC MODEL FOR INTEGRATING AI, BI, IOT, AND CLOUD INTO ENTERPRISE DECISION-MAKING	88
<i>YANG NA</i>	
<i>ASANOVA DANIYA</i>	
<i>OLGA KOSHKINA</i>	
ARTIFICIAL INTELLIGENCE AND PREDICTIVE MAINTENANCE FOR SUPER HIGH-RISE BUILDING OPERATIONS: A CHINA-FOCUSED FRAMEWORK	93
<i>YUAN XIAOYING</i>	
<i>ASANOVA DANIYA</i>	
<i>OLGA KOSHKINA</i>	
GREEN ECONOMY: PATHWAYS TO SUSTAINABLE DEVELOPMENT IN THE 21ST CENTURY	98
<i>NINO TCHANTURIA</i>	
<i>RUSUDAN DALAKISHVILI</i>	
<i>ZURAB MUSHKUDIANI</i>	
РОЛЬ И ЗНАЧЕНИЕ УСТОЙЧИВОГО РАЗВИТИЯ В СТРАТЕГИЧЕСКОМ УПРАВЛЕНИИ МЯСОПЕРЕРАБАТЫВАЮЩИМИ ПРЕДПРИЯТИЯМИ РЕСПУБЛИКИ КАЗАХСТАН	104
<i>НОВИКОВА ЮЛИЯ ВЛАДИМИРОВНА</i>	
<i>НАСЫРОВА АНАР МИРАМБЕКОВНА</i>	

Pedagogical Sciences

ТЕОРЕТИЧЕСКИЕ ОСНОВЫ КОМПЛЕКСНОГО ПОДХОДА К ОРГАНИЗАЦИИ ТРЕНИРОВОЧНОГО ПРОЦЕССА В СПОРТЕ.....	113
<i>АБИЛКАСИМОВА ГУЛЬЗАМ</i>	
<i>ЛЕНЧАК ИВАН ЛЕОНИДОВИЧ</i>	
<i>ТОТМИНА КСЕНИЯ АНДРЕЕВНА</i>	
<i>БОРОДУЛИН ВЛАДИСЛАВ АЛЕКСЕЕВИЧ</i>	
<i>ЕСКАЛИЕВА АЙГЕРИМ ЕЛЬДАРОВНА</i>	
UNIVERSITY–INDUSTRY COLLABORATION IN ENHANCING PROFESSIONAL COMPETENCE.....	119
<i>GULNAR FARMAN HUSEYNOVA</i>	
GENRE-ORIENTED PEDAGOGY IN EAP: AN EMPIRICAL ANALYSIS OF THE PROBLEMS, LIMITATIONS, AND PEDAGOGICAL IMPLICATIONS OF IMPLEMENTATION.....	122
<i>AKSHOLPAN SAPAROVA</i>	
<i>SAULE DAURENBЕК</i>	
<i>AKMARAL ZHARMAGAMBETOVA</i>	
ОРТА БІЛІМ БЕРУ ЖҮЙЕСІНДЕГІ ОҚУ БАҒДАРЛАМАЛАРЫНЫҢ ҚҰҚЫҚТЫҚ-НОРМАТИВТІК НЕГІЗДЕРІН ПЕДАГОГИКАЛЫҚ ТҮРҒЫДАН ЗЕРДЕЛЕУ	134
<i>ШАШАЕВА ГУЛБАҚЫТ ҚАДЫРЖАНҚЫЗЫ</i>	
<i>НАЗАРҚЫЗЫ ЖАНИЯ</i>	
<i>ЕРЕКЕШ ҚҰРАЛАЙ</i>	
<i>МУРАТ АҚЕРКЕ</i>	
<i>КЕНЖЕХАН ТОҒЖАН</i>	
GLOCAL FASHION EDUCATION: НОВЫЕ ОРИЕНТИРЫ КАЗАХСТАНСКОГО ДИЗАЙН-ОБРАЗОВАНИЯ	142
<i>ИБРАЕВА АЙГУЛЬ БАХЫТОВНА</i>	
DEVELOPING RESEARCH SKILLS OF PRIMARY SCHOOL STUDENTS THROUGH GAME-BASED TECHNOLOGIES (IN NATURAL SCIENCE EDUCATION).....	148
<i>TULEUBEK SHUGUYLA MANATBEKKYZY</i>	
<i>AZIZA ZHUNUSBEKOVA</i>	
ORGANIZING LITERARY CHALLENGES IN PRIMARY SCHOOL: METHODOLOGICAL RECOMMENDATIONS.....	152
<i>MELIS DAMIRA MARLENKYZY</i>	
<i>LEBEDEVA L.A.</i>	
ПЕДАГОГИЧЕСКИЕ УСЛОВИЯ РАЗВИТИЯ ЭМОЦИОНАЛЬНОГО ИНТЕЛЛЕКТА У ДЕТЕЙ СТАРШЕГО ДОШКОЛЬНОГО ВОЗРАСТА	156
<i>БЕРЛИБАЕВА МАЙРА БАҚДАУЛЕТОВНА</i>	
INTEGRATING ADAPTIVE LEARNING TECHNOLOGIES AND THE FLIPPED CLASSROOM MODEL FOR ENHANCED LANGUAGE ACQUISITION IN SECONDARY EDUCATION	167
<i>DOSMAGANBETOVA NAZIRA KAIYRGALIEVNA</i>	
ДАРЫНДЫ ОҚУШЫЛАРҒА ТАРИХТЫ ТЕРЕҢДЕТІП ОҚЫТУДА ИНТЕРАКТИВТІ ӘДІСТЕРДІ ҚОЛДАНУДЫҢ ТИІМДІЛІГІ.....	174
<i>САДЫКОВА АЙГУЛ МАРАТОВНА</i>	
<i>КАРИМОВА АНАРА ЕРКЕНОВНА</i>	
<i>КАМАЛИ АЙТГУЛ ЕРСІНҚЫЗЫ</i>	
POSSIBILITIES OF SPECIAL PEDAGOGICAL DIAGNOSTICS IN CHILDREN FROM SOCIALLY DISADVANTAGED BACKGROUNDS IN KINDERGARTEN.....	181
<i>MARCELA ČARNICKÁ</i>	
PERCEPTION OF DISABILITY IN PRESCHOOL CHILDREN THROUGH VISUAL METHODS	194
<i>BARBORA KOVÁČOVÁ</i>	

Technical Sciences

AUTONOMOUS VEHICLES IN INTERNATIONAL FREIGHT TRANSPORT: FUTURE PROSPECTS	202
<i>RAHILA RAHIMLI</i>	
DEVELOPMENT AND VALIDATION OF AN INTELLIGENT ENERGY MANAGEMENT SYSTEM FOR INDUSTRIAL ENTERPRISES USING MACHINE LEARNING.....	206
<i>YESSETOV ALISHER</i>	
<i>UTENOVA BALBUPE</i>	
AUTOMATION OF THE GENERATION OF ELECTRONIC PRODUCT PASSPORTS IN MANUFACTURING PROCESSES	211
<i>TILEUBEK NURAMAN</i>	
<i>MALIKOV ALMAS</i>	
BÖYÜK VERİLƏNLƏR TEXNOLOGİYALARININ MÜƏSSİSƏ İNFORMASIYA TƏHLÜKƏSİZLİYİNİN İDARƏ EDİLMƏSİNDƏ TƏTBİQİ	216
<i>LEYLA ƏHMƏDOVA EMIN QIZI</i>	
İŞ YERLƏRİNDƏ SÜNİ İNTELLEKT: TƏTBİQETMƏ PROBLEMLƏRİ VƏ İMKANLAR.....	224
<i>SƏİDƏ RƏHİMLİ İLQAR QIZI</i>	
MƏLUMATLARIN QORUNMASI VƏ KİBERTƏHLÜKƏSİZLİK KONTEKSTİNDƏ SİMSİZ ŞƏBƏKƏLƏRDƏ AUTENTİFİKASIYA METODLARININ TƏHLİLİ	231
<i>ƏMRAHOVA NURCAN MÜZƏFFƏR</i>	
İT ŞÖBƏSİ: STRUKTURU, ROLLARI VƏ FUNKSIYALARI.....	238
<i>MAHMUDOVA GÜLŞƏN ELSƏVƏR QIZI</i>	
<i>NƏBİYEVƏ CƏMALƏ ORUC QIZI</i>	

IOT SİSTEMLƏRİNDƏ KİBERTƏHLÜKƏSİZLİK RİSKLƏRİ VƏ ONLARIN AZALDILMASI ÜSULLARI	245
<i>BAŞƏLİYEVƏ GÜLCƏNNƏT TURAB</i>	
YAŞIL ARTIMIN TƏMİN EDİLMƏSİ ÜÇÜN RƏQƏMSAL PLATFORMALARIN FORMALAŞDIRILMASI VƏ İT HƏLLƏRİNİN ROLU	252
<i>ABBASƏLİYEVƏ GÜLŞANƏ</i>	
WEB-BASED LEARNING PLATFORM ARCHITECTURE AND MATHEMATICAL MODELING OF ADAPTIVE LEARNING MECHANISM ...	259
<i>JAFAROV NIZAMI DUMAN OGLU</i>	
<i>AGAYEVA LEYLA SƏDULLA GIZI</i>	
FİŞİNQ VƏ SOSIAL MÜHƏNDİSLİK: İSTİFADƏÇİ DAVRANIŞLARININ TƏHLÜKƏSİZLİK RİSKLƏRİNƏ TƏSİRİ	262
<i>ƏZİMOV KƏNAN</i>	
ELEKTRON TİCARƏT PLATFORMALARININ API ARXİTEKTURASINDA BOLA ZƏİFLİYİNİN ANALİZİ VƏ QARŞISININ ALINMASI.....	267
<i>AYSU KƏRİMLİ İLQAR</i>	
MALİYYƏDƏ SİMMETRİK ŞİFRƏLƏMƏNİN TƏTBİQLƏRİ	272
<i>İBADOVA SƏBİNƏ NADIR</i>	
MÜƏSSİSƏLƏRDƏ SÜNİ İNTELLEKTİN TƏTBİQİ VƏ MÖVCUD PROBLEMLƏR	278
<i>MƏMMƏDLİ İLKİN MAGISTRANT</i>	
CREATION OF AN INTELLIGENT ROBOT FOR BANKING CONTACT CENTER TASKS, WITH COMMUNICATION IN KAZAKH AND RUSSIAN LANGUAGES.....	282
<i>TURDALIN NURASSYL MEIRAMBEKULY</i>	
İNFORMASIYA SİSTEMLƏRİNİN TƏHLÜKƏSİZLİYİNİN ARXİTEKTUR ƏSASLI QIYMƏTLƏNDİRİLMƏSİ VƏ İNTEQRATİV METODOLOJİ YANAŞMALAR	286
<i>GÜLNAR HİDAYƏTZADƏ KAMİL</i>	
COSO MODELİ ƏSASINDA DAXİLİ NƏZARƏT SİSTEMİNİN STRUKTUR KOMPONENTLƏRİNİN ELMİ ƏSASLANDIRILMASI	294
<i>SALMANZADƏ ADIŞIRIN MƏHƏMMƏD OĞLU</i>	
RƏQƏMSAL DÖVRDƏ BACARIQLARIN TƏKMİLLƏŞDİRİLMƏSİ: E-TƏLİM VƏ RƏQƏMSAL BACARIQLARIN İNKİŞAFI TƏŞKİLATIN RƏQABƏT QABİLİYYƏTİNİ NECƏ GÜCLƏNDİRİR?	299
<i>RƏSULOVA SEVİNC</i>	
BANK MÜŞTƏRİLƏRİNİN İTKİSİNİN PROQNOZLAŞDIRILMASINDA MAŞIN ÖYRƏNMƏSİ MODELƏRİNİN TƏHLİLİ VƏ PERFORMANS GÖSTƏRİCİLƏRİNİN ANALİZİ	306
<i>SƏHRAB ƏLİZADƏ</i>	

Agricultural Sciences

TRANSFORMATION OF POTI COASTAL ECOSYSTEM: IMPACT OF EUTROPHICATION ON BIODIVERSITY AND RECREATIONAL POTENTIAL	319
<i>MARINA MACHARASHVILI</i>	
<i>OLGA KHARAISHVILI</i>	
<i>EREKLE KECKOSHVILI</i>	
<i>MAIA KIKABIDZE</i>	
<i>LALI BAIDAURI</i>	
<i>KETEVAN ROKVA</i>	
<i>NATIA SUKHISHVILI</i>	
<i>TAMTAM NATENADZE</i>	
<i>TSISIA KOBALADZE</i>	
<i>UCHA JAGODNISHVILI</i>	
<i>NIKA KEBURIA</i>	
BALIQ KONSERVLƏRİNİN İSTEHLAK XASSƏLƏRİNİN FORMALAŞMASININ NƏZƏRİ ƏSASLARI	326
<i>SEVİNC TAĞIYEVƏ</i>	

Chemical Sciences

DESIGNING CREATIVE LEARNING ENVIRONMENTS FOR CHEMISTRY EXAM READINESS: A BIBLIOMETRIC ANALYSIS	329
<i>MATCHANOVA K.</i>	
<i>KUANISHEVA ZH. K.</i>	

Physical and Mathematical Sciences

ОҚУШЫЛАРДЫҢ ФИЗИКАҒА ҚЫЗЫҒУШЫЛЫҒЫН ЕСЕПТЕРДІ ШЫҒАРУМЕН АРТТЫРУ	341
<i>РАХЫМБЕКОВ А.Ж</i>	
<i>АЛТАЙҚЫЗЫ АРАЙ</i>	
<i>АБЫЛҒАЗИНА НУРИЛА ЕРЛАНҚЫЗЫ</i>	
<i>ШАЙМЕРДЕНОВА ПЕРИЗАТ ЕРСИНОВНА</i>	

Philological Sciences

ҚАЗАҚ ТІЛІ ЖӘНЕ ҰЛТТЫҚ ҚҰНДЫЛЫҚТАР (10-СЫНЫП) (АВТОРЛЫҚ БАҒДАРЛАМАНЫ ТӘЖІРИБЕДЕ ҚОЛДАНУ ЖӘНЕ ЗЕРТТЕУ НƏТИЖЕЛЕРІ)	344
<i>МАНАСОВА ЖАДРА АМАНГЕЛЬДИЕВНА</i>	
HISTOIRE ET EVOLUTION DE LA FAMILLE DES LANGUES ROMANES	350
<i>AZIZA ALIYEVA</i>	
<i>AYSEL HASSANOVA</i>	

ҚАЗАҚТЫҢ ЖЕР-СУ АТАУЛАРЫНЫҢ ТАРИХИ-ТАНЫМДЫҚ МАҢЫЗЫ	354
<i>БИСЕНБАЕВА МЕРУЕРТ КЕНЖЕҒҰЛҚЫЗЫ</i>	
<i>ҚУАНТАЕВА АҚМАРАЛ ТҮРСЫНБЕКҚЫЗЫ</i>	
<i>ИМАНАЛИЕВА АЛТЫНГҰЛ НҮРСАЛИМОВНА</i>	
<i>СУЛТАНБАЕВА АСЕЛ ЗЕЙНЕГАБЫЛОВНА</i>	

Biological Sciences

БИОЛОГИЧЕСКАЯ РЕМЕДИАЦИЯ НЕФТЕЗАГРЯЗНЁННЫХ ПОЧВ С ИСПОЛЬЗОВАНИЕМ МИКРОБНОГО КОНСОРЦИУМА	361
<i>АЛДИБАЙ САЛТАНАТ НУРЛАНҚЫЗЫ</i>	
<i>МУХТАРОВ АБИЛХАС КАПИЗОВИЧ</i>	
MICROWAVE-SYNTHESIZED MULTICOMPONENT NANOPARTICLE-DRUG COMBINATIONS AS SELECTIVE ADJUVANTS FOR PROTON THERAPY IN NON-SMALL CELL LUNG CANCER.....	368
<i>DAVID APHKHAZAVA</i>	
<i>BABRY OREN</i>	
<i>ARCHIL CHIRAKADZE</i>	
<i>NODAR MITAGVARIA</i>	
<i>NELI MAKHVILADZE</i>	
<i>MARINA DEVDARIANI</i>	
<i>IRINA BEDINASHVILI</i>	
<i>MZIA TSIKLAURI</i>	
<i>MANANA MAKHARADZE</i>	
<i>NODAR SULASHVILI</i>	
<i>PRIYANKA HAIBAT KHADAKE</i>	
<i>TANVI NARESH PATIL</i>	
<i>GANESH RATNAKAR NARAWANE</i>	

Medical Sciences

THYROID CANCER: CURRENT UNDERSTANDING AND TRENDS.....	399
<i>ARMAN KHOZHAYEV</i>	
<i>RAIKHAN SHLYMOVA</i>	
<i>GULMIRA BALSHIKBAYEVA</i>	
<i>MARIANNA SHOPENOVA</i>	
<i>TANSHOLPAN UKASH</i>	
<i>SHOLPAN KYDYRMANOVA</i>	
<i>AIZHAN MUSTAFA</i>	
<i>BALNUR SOVETOVA</i>	
COMPREHENSIVE EVALUATION OF CANCER SCREENING PROGRAMS IN KAZAKHSTAN: BREAST, CERVICAL, AND COLORECTAL CANCER	409
<i>ARMAN KHOZHAYEV</i>	
<i>ARUZHAN INIYAT</i>	
<i>MADINA ISSAPOVA</i>	
<i>AIDA BALTABAY</i>	
<i>BAKDAULET AITZHANOV</i>	
<i>AIGERIM ISKAKOVA</i>	
<i>BARFINABONU SHONAZAROVA</i>	
<i>YESSENIYA LAPTYEVA</i>	
<i>BAYANSULU AIMURZINA</i>	

Psychological Sciences

ПСИХОЛОГИЧЕСКИЕ ОСОБЕННОСТИ И СОЦИАЛЬНО-ПСИХОЛОГИЧЕСКАЯ АДАПТАЦИЯ ЛИЦ, СКЛОННЫХ К ЭЗОТЕРИЧЕСКИМ ПРАКТИКАМ	422
<i>СОКОЛОВ ИВАН АНДРЕЕВИЧ</i>	
<i>ДУПЛЯКИН ЕВГЕНИЙ БОРИСОВИЧ</i>	
КЛИНИКО-ПСИХОЛОГИЧЕСКИЕ ОСОБЕННОСТИ ЛИЦ С АЛЛЕРГИЧЕСКИМИ ЗАБОЛЕВАНИЯМИ	432
<i>КУСАИНОВА СВЕТЛАНА ОЛЕГОВНА</i>	
<i>ДУПЛЯКИН ЕВГЕНИЙ БОРИСОВИЧ</i>	
ՀԱՄԸՆԴՐԱՆՈՒՐ ՆԵՐԱՌՄԱՆ ԳՈՐԾԸՆԹԱՑԻ ՀՈԳԵԲԱՆԱԿԱՆ ԱՌԱՋԱՀԱՏԿՈՒԹՅՈՒՆՆԵՐԸ	441
<i>ԳՐԻԳՈՐՅԱՆ ՇՈՒԾԱՆԱԿ ՍԵՆԵԲԵՐԴՈՒ</i>	
ЭФФЕКТИВНОСТЬ СТИЛЕЙ УПРАВЛЕНИЯ В СОВРЕМЕННЫХ УСЛОВИЯХ ТРУДА: ПСИХОЛОГИЧЕСКИЕ АСПЕКТЫ.....	449
<i>САПАРБЕК ҚАЗБЕК МЕЙРБЕКҰЛЫ</i>	
<i>БИСЕНОВА АЛТЫНАЙЫМ БАУРЖАНҚЫЗЫ</i>	
<i>КУДАЙБЕРГЕНОВА АЙЖАН ЖАКАНБАЕВНА</i>	

Legal Sciences

LEGAL EDUCATION AND ITS ROLE IN STRENGTHENING LEGAL CULTURE: A COMPARATIVE STUDY OF KAZAKHSTAN AND CHINA	453
<i>CHEN YUHOUI</i>	

Economic Sciences

Повышение эффективности системы закупа компаний BI Group

Жыланбас Нұрсұлтан Жеткергенұлы

Казахстанско-Британский Технический университет, Алматы, Казахстан

Темирбекова Гульжан Джумаддулаевна

Казахстанско-Британский Технический университет, Алматы, Казахстан

В современных условиях развития экономики и строительной отрасли эффективность системы закупок становится одним из ключевых факторов обеспечения конкурентоспособности компании. Рост цен на строительные материалы, нестабильность поставок, усиление конкуренции и необходимость строгого соблюдения сроков реализации проектов требуют от организаций постоянного совершенствования внутренних бизнес-процессов. Для одной из крупнейших строительных компаний Казахстана — BI Group — система закупок имеет стратегическое значение, так как напрямую влияет на себестоимость проектов, их качество и сроки выполнения.

Закупочная деятельность представляет собой сложный и многоуровневый процесс, включающий планирование потребностей, поиск и отбор поставщиков, проведение тендерных процедур, заключение контрактов, организацию поставок и контроль их исполнения. В строительной отрасли особенность закупок заключается в масштабах и разнообразии приобретаемых ресурсов: от базовых строительных материалов до высокотехнологичного оборудования и услуг специализированных подрядчиков. Любые сбои в этой системе могут привести к существенным финансовым потерям, простоем строительных работ и снижению качества конечного продукта.

В условиях цифровой трансформации экономики особую актуальность приобретает внедрение инновационных подходов к управлению закупочной деятельностью. Для компании BI Group это означает необходимость перехода от традиционных методов закупок к более гибким, технологичным и аналитически обоснованным моделям. Одним из перспективных направлений является использование технологий больших данных (Big Data) и искусственного интеллекта для анализа закупочной информации. Такие инструменты позволяют выявлять скрытые закономерности в динамике цен, прогнозировать потребности в ресурсах и оптимизировать выбор поставщиков.

Применение цифровой аналитики даёт возможность не только реагировать на текущие изменения, но и формировать проактивную стратегию закупок. Например, на основе анализа исторических данных можно заранее определить периоды повышения цен на строительные материалы и осуществить закупки по более выгодным условиям. Это особенно важно для строительной отрасли, где стоимость ресурсов подвержена значительным колебаниям.

Ещё одним важным направлением повышения эффективности является развитие интеграции между подразделениями компании. Закупочная функция не должна существовать изолированно — она должна быть тесно связана с проектными, финансовыми и производственными отделами. Такая интеграция обеспечивает более точное планирование потребностей и позволяет избежать избыточных или, наоборот, недостаточных закупок. В результате снижается уровень складских запасов и уменьшаются затраты на хранение материалов.

Особую роль в совершенствовании системы закупок играет внедрение принципов устойчивого развития (ESG). Современные компании всё чаще ориентируются не только на экономическую эффективность, но и на экологические и социальные аспекты своей деятельности. Для BI Group это может выражаться в выборе поставщиков, соблюдающих экологические стандарты, использовании энергоэффективных материалов и внедрении «зелёных» технологий в строительстве. Такой подход способствует улучшению репутации компании и повышению её инвестиционной привлекательности.

Кроме того, важным элементом повышения эффективности закупочной деятельности является развитие контрактного управления. Заключение договоров с поставщиками должно сопровождаться чётким определением условий поставки, ответственности сторон и механизмов контроля исполнения обязательств. Внедрение системы управления контрактами позволяет отслеживать выполнение договоров в режиме реального времени, своевременно выявлять отклонения и принимать корректирующие меры.

Необходимо также отметить значимость логистической оптимизации в системе закупок. Эффективная организация доставки материалов и оборудования напрямую влияет на сроки реализации строительных проектов. Использование современных логистических решений, включая оптимизацию маршрутов и внедрение систем отслеживания поставок, позволяет снизить транспортные расходы и минимизировать риски задержек.

Дополнительным фактором повышения эффективности является внедрение принципов бережливого производства (Lean). Применение этих принципов в закупочной деятельности позволяет устранить потери, связанные с избыточными запасами, лишними операциями и неэффективными процессами. В результате повышается общая производительность и снижается себестоимость проектов.

Важным направлением развития является также повышение уровня прозрачности закупочной деятельности. Открытость процессов, использование электронных платформ и регулярная отчётность способствуют формированию доверия со стороны партнёров и инвесторов. Прозрачная система закупок снижает коррупционные риски и повышает эффективность использования финансовых ресурсов.

В заключение следует отметить, что дальнейшее совершенствование системы закупок в BI Group должно носить непрерывный характер. Быстро меняющаяся внешняя среда, развитие технологий и рост требований со стороны рынка требуют постоянной адаптации и внедрения новых решений. Комплексный подход, сочетающий цифровизацию, стратегическое управление, развитие персонала и внедрение инноваций, позволит компании не только повысить эффективность закупочной деятельности, но и обеспечить устойчивое развитие в долгосрочной перспективе.

Таким образом, дополнительное развитие системы закупок через внедрение современных технологий, интеграцию процессов, управление рисками и ориентацию на устойчивое развитие создаёт прочную основу для повышения конкурентоспособности компании и успешной реализации её стратегических целей.

На практике даже в развитых компаниях система закупок сталкивается с рядом проблем. Одной из ключевых является недостаточная прозрачность процессов. При отсутствии единой цифровой среды или при использовании разрозненных информационных систем возникает сложность в отслеживании всех этапов закупок, что может способствовать неэффективному использованию ресурсов. Кроме того, многоступенчатые процедуры согласования часто замедляют процесс принятия решений, что особенно критично в условиях динамичного строительного рынка.

Существенной проблемой является и ограниченный круг поставщиков. Долгосрочное сотрудничество с одними и теми же контрагентами, с одной стороны, обеспечивает

стабильность, но с другой — снижает уровень конкуренции и может приводить к росту цен и снижению качества. Отсутствие регулярного анализа рынка поставщиков и недостаточное внимание к поиску новых партнёров ограничивают возможности компании в оптимизации закупочных затрат.

Также важным фактором является недостаточное использование аналитических инструментов. Без системного анализа данных о закупках сложно выявить неэффективные операции, оценить динамику цен и спрогнозировать будущие потребности. В результате управленческие решения принимаются на основе ограниченной информации, что снижает их эффективность. Дополнительные риски создаёт недостаточно развитая система контроля исполнения контрактов, что может приводить к срывам сроков поставок и поставке продукции ненадлежащего качества.

Для повышения эффективности системы закупа в компании BI Group необходимо внедрение комплексного подхода, охватывающего организационные, технологические и управленческие аспекты. Одним из ключевых направлений является цифровизация закупочной деятельности. Внедрение современных информационных систем, таких как ERP-платформы и электронные закупочные площадки, позволяет автоматизировать основные процессы, повысить прозрачность операций и сократить время обработки заявок. Электронный документооборот и автоматизированные процедуры согласования существенно снижают влияние человеческого фактора и минимизируют вероятность ошибок.

Важным шагом является переход к стратегическому управлению закупками. В отличие от традиционного подхода, ориентированного на решение текущих задач, стратегический подход предполагает долгосрочное планирование потребностей компании, анализ рынка и формирование устойчивых отношений с поставщиками. Заключение рамочных договоров, консолидация закупок и централизованное управление позволяют добиться значительной экономии за счёт эффекта масштаба и улучшить условия сотрудничества.

Не менее значимым направлением является расширение и развитие базы поставщиков. Проведение открытых тендеров, привлечение новых участников и регулярный мониторинг рынка способствуют повышению конкуренции и снижению закупочных цен. При этом необходимо внедрение системы оценки и рейтинга поставщиков, которая позволит объективно оценивать их деятельность по таким критериям, как качество продукции, соблюдение сроков, ценовая политика и надёжность. Формирование пула проверенных поставщиков создаёт основу для стабильной и эффективной работы компании.

Особое внимание следует уделить развитию аналитики в сфере закупок. Использование современных технологий обработки данных и инструментов бизнес-аналитики позволяет не только отслеживать текущие показатели, но и прогнозировать будущие тенденции. Введение ключевых показателей эффективности, таких как уровень экономии, длительность закупочных процедур, процент выполнения контрактов и уровень удовлетворённости внутренних заказчиков, обеспечивает возможность объективной оценки эффективности работы закупочного подразделения.

Управление рисками также является неотъемлемой частью эффективной системы закупок. Для минимизации рисков необходимо диверсифицировать поставщиков, проводить тщательный анализ и аудит контрагентов, а также внедрять механизмы контроля исполнения договорных обязательств. Использование финансовых инструментов, таких как банковские гарантии и страхование, позволяет повысить надёжность поставок и защитить интересы компании.

Важным фактором повышения эффективности закупочной деятельности является развитие человеческого капитала. Квалификация сотрудников, их профессиональные

навыки и способность принимать обоснованные решения напрямую влияют на результативность работы всей системы. Регулярное обучение, внедрение современных методик управления закупками и развитие навыков переговоров позволяют значительно повысить уровень компетентности специалистов.

Таким образом, повышение эффективности системы закупа в компании BI Group требует комплексного и системного подхода. Внедрение цифровых технологий, развитие стратегического управления, расширение базы поставщиков, использование аналитических инструментов и совершенствование системы управления рисками создают основу для устойчивого развития компании. Реализация данных мер позволит не только снизить издержки, но и повысить качество закупаемых ресурсов, ускорить реализацию проектов и укрепить конкурентные позиции компании на рынке.

В долгосрочной перспективе эффективная система закупок становится не просто вспомогательной функцией, а важным стратегическим инструментом управления, обеспечивающим устойчивый рост и развитие компании в условиях постоянно меняющейся внешней среды.

Список литературы:

1. Закон Республики Казахстан «О государственных закупках» от 4 декабря 2015 года № 434-V (с изменениями и дополнениями). ([OECD](#))
2. Закон Республики Казахстан «О государственных закупках» от 1 июля 2024 года № 106-VIII. ([cdb.kz](#))
3. Правила осуществления государственных закупок. Приказ Министра финансов РК от 11 декабря 2015 года № 648. ([archive.interconf.center](#))
4. Веб-портал государственных закупок Республики Казахстан:
5. <https://www.goszakup.gov.kz> ([goszakup.gov.kz](#))
6. Портал электронного правительства Республики Казахстан: «Государственные закупки». ([Электрондық үкімет](#))
7. Материалы о тендерах и системе закупок в Казахстане (обзорные статьи и публикации). ([Википедия](#))

Цифровизация архитектурной и градостроительной деятельности в Казахстане: преобразование городского пространства

Дарисов Габит Газизович

Казахстанско-Британский Технический университет, Алматы, Казахстан

В данной статье автором рассматривается влияние цифровизации архитектурной и градостроительной деятельности на преобразование городского пространства в Казахстане. Изучение и внедрение цифровых технологий в эти области с учетом современных вызовов и потребностей общества может привести к значительным изменениям в городском пространстве и способствовать его преобразованию, улучшить эффективность проектирования, повысить качество и безопасность строительства, сократить сроки и затраты на строительство, улучшить инфраструктуру и сделать городское пространство более функциональным и комфортным для его жителей. Преобразование городского пространства в Казахстане является важным направлением развития городов, где цифровизация может сыграть значительную роль. Прозрачность процессов в архитектурной и градостроительной деятельности может быть значительно увеличена благодаря информационным платформам и цифровым базам данных. Цель данной статьи состоит в том, чтобы изучить современные цифровые технологии и их влияние в преобразовании городского пространства. В данной работе фокус направлен на использование географических информационных систем (ГИС), информационных моделей зданий (BIM). В частности, авторами выделены возможности использования геопортала государственного градостроительного кадастра Республики Казахстан в преобразовании городского пространства. Цифровые базы данных способствуют повышению прозрачности процессов, так как они обеспечивают хранение и обмен информацией между участниками проекта, способствуют эффективному управлению данными. Внедрение таких технологий позволяет следить за всем процессом строительства, начиная от начального этапа проектирования и заканчивая завершением строительства и эксплуатации объекта.

Введение

Технологические разработки продолжают проникать в различные сферы деятельности, в том числе в архитектурно-градостроительный сектор. Казахстан активно следует этой мировой тенденции, внедряя цифровые инновации для оптимизации градостроительных процессов и повышения качества городской среды. Основным этапом к цифровому преобразованию архитектурно-градостроительной деятельности является сокращение документов на бумажных носителях за счет создания единого геопортала цифровых инфраструктурных данных. Результатом цифровизации градостроительной документации должны стать электронные, цифровые и графические материалы, которые позволят систематизировать и структурировать данные городского преобразования и состояния территории [1]. Преобразование городского пространства – это процесс изменения и модернизации различных аспектов городской среды с целью создания более функционального, удобного и привлекательного места проживания, работы и отдыха. Этот процесс включает в себя различные аспекты, такие, как архитектурные и градостроительные

изменения, реконструкция зданий, создание новой инфраструктуры, ремонт дорог и совершенствование системы общественного транспорта и т.д. В целом преобразование городского пространства – важный процесс, направленный на создание устойчивых и комфортных городов. Процесс городского пространственного планирования основан на структурированной цифровой информации. Качественно собранная цифровая информация о городском пространстве входит в градостроительный цикл (планирование, проектирование и реализация). На каждом этапе цикла для реализации градостроительных решений важен комплекс программных средств и технологий обработки исходной информации.

Таким образом, цифровизация архитектурной и градостроительной деятельности – это формирование цифровой среды и построение цифровой информационной модели территории городского пространства [1]. В научной среде часто подчеркивается важная роль ГИС в контексте умных городов. Так, в статье «GIS for Smart Cities» ГИС используются для сбора, анализа, управления и визуализации географических данных с целью оптимизации управления городской инфраструктурой и ресурсами. ГИС используются в умных городах в качестве системы управления транспортом, энергоресурсами, отходами, обеспечения безопасности и общественного порядка. ГИС применяют в развитии умных зданий и районов, а также в управлении городской зеленой зоной и окружающей средой [3].

Методология

Изучение данной научной работы основано на тематическом исследовании и охватывает два основных метода: Анализ научно-исследовательских и обзорных научных статей. В этом случае проведен анализ существующей литературы по теме цифровизации в архитектурной и градостроительной деятельности, включая исследовательские работы, обзоры, статьи в научных журналах, информационные ресурсы. Анализ всех изучаемых материалов позволяет понять текущее состояние исследований в данной области, выявить ключевые тенденции, проблемы и направления развития в архитектуре и градостроительстве. Данный анализ составил теоретическую базу научной работы на основании углубленного аналитического сравнения изученных работ. Практическое изучение ГИС – геопортала государственного градостроительного кадастра Республики Казахстан. Этот метод включает в себя непосредственное использование геопортала для получения информации о состоянии градостроительства в Казахстане, анализа данных, доступных через портал, и оценки его функциональности эффективности. Практическое изучение позволяет получить конкретное представление о том, как используется ГИС в контексте градостроительства в стране. Это позволило авторам оценить функциональные возможности системы, ее способность обрабатывать различные виды географических данных и предоставлять информацию для пользователей. Изучение ГИС позволяет оценить доступность и качество данных, предоставляемых через эту систему. Практическое использование ГИС позволяет понять процессы взаимодействия между различными участниками градостроительного процесса. Изучение ГИС также позволяет выявить проблемы и сложности, с которыми сталкиваются пользователи при ее внедрении и использовании в практике. Таким образом, сочетание анализа научных статей и практического изучения ГИС позволяет получить полное представление о текущем состоянии цифровизации в архитектурной и градостроительной деятельности в Казахстане в контексте преобразования городского пространства. Важную роль в развитии цифровой среды и преобразовании городского пространства играют информационно-коммуникационные технологии. В градостроительном понимании – это интеграция процессов, методов взаимодействия и технологии получения информации из городского цифрового пространства. Исходя из этого, цифровые технологии также активно внедряются в области геопро пространственного анализа географических информационных систем (ГИС).

Улучшение системы городского пространственного преобразования невозможно без применения современных методов геообработки данных, пространственного анализа и геовизуализации на основе современных ГИС.

Географическая информационная система (ГИС) – программная система, обеспечивающая сбор, хранение, накопление, анализ и распространение пространственной информации о Земле, объектах земной поверхности, природных, техногенных и социальных процессах и явлениях реального мира [2].

ГИС позволяют архитекторам и градостроителям анализировать географические данные, оптимизировать территориальное планирование, управлять городской инфраструктурой и решать проблемы транспортной логистики. Это способствует более эффективному использованию городского пространства и созданию более устойчивой городской среды.

Технологии ГИС быстро развиваются во всем мире, поскольку они обеспечивают комплексную цифровую среду, повышают эффективность и безопасность городских систем, усиливают участие горожан в городском развитии. Все это основано на использовании геопространственных данных, касающихся городской среды, природной среды и городских услуг. Успешное преобразование городского пространства требует разработки цифровой системы, которая сможет управлять геопространственными данными и визуализировать их в удобной для пользователя среде. Географическая информационная система предлагает расширенные и удобные возможности для преобразования городского пространства.

Геопространственные данные касаются городской среды, такой, как инфраструктура, инженерные коммуникации, природная среда (биоразнообразие, зеленые насаждения, качество воздуха, почвы, воды) и городские услуги (транспорт, муниципальные отходы, водные ресурсы, энергия, здравоохранение и образование).

ГИС-технологии позволяют городам добиться более гибкого управления, которое улучшает качество жизни горожан, способствует экономическому развитию, повышает привлекательность города. Анализ этих данных позволяет повысить эффективность городской системы, а также качество жизни и ее безопасность. Цифровые данные обеспечивают лучшее понимание поведения городских систем (инфраструктуры, государственных служб, реагирования на чрезвычайные ситуации и т.д.) [3].

Возможность визуализации и пространственного анализа отличают ГИС от других информационных систем и обеспечивают уникальные возможности для ее применения в широком спектре задач [10], [11].

В Казахстане активно развивается инфраструктура пространственных данных, обеспечивающая доступ к геоинформационным ресурсам и метаданным через специализированные ГИС-порталы. Ключевой составляющей этой инфраструктуры является геопортал государственного градостроительного кадастра, предоставляющий пользователям возможность эффективного анализа и визуализации географической информации.

Результаты и обсуждение

Действующий геопортал государственного градостроительного кадастра Республики Казахстан предоставляет широкий спектр геопространственных данных. Геопортал играет важную роль в оптимизации процесса территориального планирования, мониторинге изменений в городской инфраструктуре и взаимодействии с обществом. Он предоставляет уникальные возможности для эффективного управления и планирования развития городов и территорий.

Геопортал государственного градостроительного кадастра (ggk.kz.) – это веб-сервис, содержащий пространственные данные республиканского, областных, районных и базовых уровней градкадастра. С точки зрения пользователя, геопортал представляет собой «единое

окно» доступа к инфраструктурным данным. Он позволяет пользователям визуализировать пространственные данные градпроектов (генпланы и ПДП), зданий и сооружений, улично-дорожных сетей, объектов благоустройства.

Всем пользователям без авторизации доступны к просмотру генпланы и ПДП всех населенных пунктов страны. Авторизованные пользователи (в зависимости от присвоенной роли) могут просматривать сведения инженерных сетей, исходно разрешительных документов, объектов населенных пунктов. Зарегистрированные пользователи могут редактировать пространственные данные, создавать новые объекты и вносить атрибутивную информацию в созданные данные.

Сотрудникам ГГК доступен функционал аналитики, основанной на модуле Kibana. Аналитический модуль позволяет просматривать информационные дашборды, графики и таблицы на основе загруженных данных. Картографическая основа может меняться в зависимости от целей пользователей – можно выбирать Google карты, Google спутник, Яндекс спутник и т.д. Все слои, которые загружены на геопортал, могут подключаться поочередно, либо вместе с другими. Доступ к геопорталу путем создания учетных записей предоставляется местным исполнительным органам (МИО) и субъектам естественных монополий (СЕМ) для размещения и актуализации информации в системе государственного градостроительного кадастра и обеспечения эффективного управления территориальным развитием и инфраструктурой.

Один из ключевых аспектов использования геопортала государственного градостроительного кадастра – это возможность анализировать развиваемую территорию. С помощью геопортала градостроители и городские планировщики могут получить доступ к информации земельных участков, строительных объектов, границ застройки и других важных параметров.

Еще немаловажной актуальной инновационной технологией, влияющей на цифровизацию архитектурно-градостроительного сектора, является технология BIM (от Building Information Modeling). Информационное моделирование зданий (BIM) – технология, относящаяся к проектированию зданий и сооружений. Технология BIM может быть использована для создания виртуальных моделей зданий и сооружений и их соединения с другими методами информационного моделирования, используемыми в управлении жизненным циклом проекта. Иными словами, BIM – это виртуально созданная копия здания [7].

Сегодня информационный обмен является ключевым элементом успешных строительных проектов. С технологией BIM можно координировать ряд важных задач: сроки, графики, наличие материалов, количество необходимых специалистов и ресурсов. Построенная информационная модель здания становится основой для подготовки всех видов рабочей документации, проектирования, технических и экономических расчетов, оборудования и организации строительства самого здания и последующей эксплуатации. Информация, содержащаяся в данной модели здания может быть дополнена или заменена в соответствии с текущим состоянием здания [9]. Таким образом, информационное моделирование зданий (BIM) обеспечивает быстрый доступ ко всей информации здания и связанных с ним параметров на всех этапах жизненного цикла здания.

Заключение

Данное исследование подтверждает, что изученные технологии в области цифровизации архитектурной и градостроительной деятельности являются основой для построения городской цифровой модели. Результаты исследования показывают, что эти технологии обеспечивают сбор и анализ различных видов географических данных, интеграцию информации из различных источников, визуализацию и моделирование городской среды, а также принятие решений и управление городским пространством. ГИС

обычно используются для построения цифровой модели городских «горизонтальных компонентов» (городские сети, транспортные средства и природная среда), а BIM используются для описания «вертикальных компонентов» (здания). Комбинация ГИС и BIM обеспечивает мощный инструмент для преобразования городского пространства с географической привязкой и визуализацией этих данных.

Цифровизация и комбинация упомянутых систем и моделей влияет также на взаимодействие граждан с городской средой. Так, онлайн-платформы предоставляют жителям возможность участвовать в процессах градостроительства, высказывать свои предложения и отзывы, а также получать актуальную информацию о городских проектах. Это способствует созданию более открытой и взаимодействующей городской среды, соответствующей потребностям и ожиданиям населения.

Таким образом, цифровизация архитектурной и градостроительной деятельности в стране играет ключевую роль в улучшении процессов проектирования, строительства, оптимизации использования городских пространств и повышении качества жизни граждан. Внедрение современных технологий открывает новые возможности для создания инновационных и устойчивых городских сред, соответствующих требованиям современного общества. Результаты и выводы данного исследования могут быть использованы как основа для дальнейшего изучения и применения новых методов и технологий в данной области.

Список литературы

1. Дроботова Н.В. Цифровизация градостроительной деятельности в Республике Беларусь // Градостроительство и ландшафтная архитектура. Раздел 2. – 2020. – С. 83-88.
2. Приказ Министра национальной экономики Республики Казахстан от 20 марта 2015 года № 244 «Об утверждении Правил ведения и предоставления информации и (или) сведений из государственного градостроительного кадастра Республики Казахстан». [Электронный ресурс] – URL: <https://adilet.zan.kz/rus/docs/V1500011111> (дата обращения: 10.01.2024).
3. GIS for Smart Cities. ArcIndia News. – 2015. – Vol.9. [Электронный ресурс] – URL: <https://www.>
4. Андреев С.М., Красовский Г.Я., Радчук В.В. Принципы организации геопортала на основе данных ДЗЗ для управления территориальным развитием // Екологічна безпека. Разділ 1 – 2008. – С. 51-76.
5. Платформа Единых геоинформационных инфраструктурных данных государственного градостроительного кадастра Республики Казахстан. [Электронный ресурс] – URL: <https://ggk.kz/> (дата обращения: 18.01.2024).
6. Требование интерфейса для пользователей: главная страница, интерфейсное меню, личный кабинет пользователя // Внутренний документ РГП «Госградкадастр».
7. BIM-технологии: информационное моделирование зданий. [Электронный ресурс] – URL: <https://www.novosoft.ru/consulting/bim-cde> (дата обращения: 16.01.2024).
8. BIM Информационное моделирование зданий. [Электронный ресурс] – URL: <https://www.magicad.com/ru/bim/> (дата обращения: 16.01.2024).
9. Дубинин А.А. Основные понятия и принципы BIM-технологии в проектирование зданий и сооружений. Строй инфо. Информационно строительный веб-портал [Электронный ресурс] – URL: <https://stroyinfo.kz/eto-interesno/284-osnovnye-ponyatiya-i-printsiipy-bim-tekhnologii-v-proektirovanie-zdanij-i-sooruzhenij.html> (дата обращения: 16.01.2024).
10. Гусева А.В. Геоинформационные системы [Электронный ресурс] – URL: <https://cyberleninka.ru/article/n/geoinformatsionnye-sistemy/viewer> (дата обращения: 07.06.2024).

11. Торговкин Я.И. Географические информационные системы в научных исследованиях [Электронный ресурс] – URL: <https://cyberleninka.ru/article/n/geografiche>

Внедрение экологического менеджмента как основной этап на пути к устойчивости экономического субъекта

Мустафин Рустем Канатович

Казахстанско-Британский технический университет, Казахстан, Алматы

Шұғай Олжас Қайратұлы

Казахстанско-Британский технический университет, Казахстан, Алматы

Альмухамбетов Куаныш Александрович

Казахстанско-Британский технический университет, Казахстан, Алматы

Внедрение экологического менеджмента в работу организаций становится все более актуальным вопросом в современном мире. Растущее осознание необходимости соблюдения экологических норм и принципов устойчивого развития ставит перед компаниями задачу минимизации отрицательного влияния на окружающую среду. Введение экологического менеджмента можно рассматривать как переход к устойчивому типу производства, который учитывает экологические и социальные аспекты. Делая упор на ресурсосбережение, переработку отходов и применение новых технологий, компании могут уменьшить свой негативный след на окружающую среду и повысить свою эффективность в бизнесе. Ключевой элемент внедрения экологического менеджмента — это разработка комплексной стратегии, которая учитывает экологические вопросы на уровне всей организации. Данный процесс включает в себя проведение аудитов, разработку программы и плана действий, обучение и мотивацию персонала. Один из главных инструментов внедрения экологического менеджмента — это сертификация по стандарту ISO 14001 Системы экологического менеджмента. В рамках сертификации проводится оценка соответствия экономического субъекта стандарту, что позволяет определить степень соответствия данным нормам для улучшения экологической составляющей производственной деятельности.

Безусловно, внедрение экологического менеджмента может потребовать внесения значительных изменений в бизнес-процессы, но его эффективность заключается в множестве плюсов, которые он приносит. Внедрение экологического менеджмента позволяет компаниям не только сократить расходы на ресурсы, утилизацию отходов и минимизировать риски для окружающей среды, но и улучшить свою репутацию, повысить доверие клиентов и партнеров, а также обеспечить льготы и привилегии со стороны государства. Авторами определено, что внедрение экологического менеджмента в работу организаций — это важный шаг на пути реализации принципов устойчивого развития и уменьшения негативного влияния на окружающую среду. Для того, чтобы найти наиболее эффективный метод внедрения экологического менеджмента, нужно постоянно изучать последние тенденции и методы, а также проводить систематический мониторинг результатов деятельности компании. В данной статье исследуется процесс внедрения экологического менеджмента в деятельность компаний. Проанализированы методы и инструменты, применяемые при внедрении эко-менеджмента, и описаны особенности этого процесса.

В настоящее время международная ассоциация разрабатывает многочисленные технологические и операционные подходы к управлению природными компонентами во всей системе производства. Внедрение экологического менеджмента становится все более

актуальной темой в современном мире. Растущая осознанность о необходимости сохранения природных ресурсов и охраны окружающей среды побуждает организации уделять больше внимания экологическим аспектам своей деятельности. Применение инструментов системы экологического менеджмента помогает компаниям не только улучшить собственный экологический след, но также повысить конкурентоспособность и стимулировать экономическую эффективность.

В исследовании были рассмотрены труды иностранных ученых, таких как: Шмитц Э.А., Баум М., Хьюэтт П., Кабст Р. [5]; Арагон-Корреа Х.А.; Шарма С.З. [2]; де Фатима Телес М., де Соуза Дж.Ф. [7], а также российских: Александрова Е.Н. [8]; Вахромова Е.Н. [3]; Ерофеева П.Ю. [10]; Жидко Е.А. [12] и других.

Целью исследования является постановка процесса внедрения экологического менеджмента в работу организации и изучение его влияния на конкурентоспособность и эффективность организации. Задачи исследования включают:

1. Изучение существующих методов и инструментов экологического менеджмента.
2. Анализ преимуществ и недостатков внедрения экологического менеджмента в работу организации.
3. Оценка влияния внедрения экологического менеджмента на экологический след и устойчивость организации.
4. Разработка рекомендаций по успешному внедрению экологического менеджмента в работу экономических субъектов.

Авторская гипотеза исследования по внедрению экологического менеджмента может быть сформулирована следующим образом: «Внедрение экологического менеджмента в работу предприятий способствует сокращению негативного воздействия на окружающую среду и повышению устойчивости организации, что, в свою очередь, способствует улучшению репутации, удовлетворенности клиентов и увеличению прибыли».

Методы для достижения цели и решения задач, поставленных в процессе исследования, нами были использованы труды ученых в области анализа проблем и реализации целей устойчивого развития, а также такие методы, как системный анализ; анализ стейкхолдеров, выявляющий и описывающий интересы и степень вовлеченности заинтересованных сторон в процессе внедрения эко-менеджмента; анализ бизнес-процессов, описывающий текущие бизнес-процессы экономических субъектов и выявляющий возможности для улучшения эффективности и устойчивости.

Результаты организации должны реагировать на изменения для того, чтобы функционально достигать и сохранять свою устойчивость в финансовом, социальном и экологическом отношении. Регулярный анализ системы экологического менеджмента со стороны руководства является частью этой потребности и поможет организации добиться постоянного улучшения состояния окружающей среды и обеспечить соответствие системы экологического менеджмента организации общепринятым стандартам.

Результатами исследования авторов стали:

1. Разработка стратегии внедрения экологического менеджмента в организацию, включающая определение целей и задач, установление плана действий, определение роли и ответственности сотрудников.
2. Определение ключевых факторов успешного внедрения экологического менеджмента.

Результаты исследования могут помочь организациям в процессе внедрения экологического менеджмента благодаря описанию опыта и выделению взаимосвязанных компонентов, которые могут повлиять на успех деятельности.

Способность организаций управлять корпоративной экологической эффективностью становится стратегической задачей для компаний. Принятие экологических решений требует

четкой методологии, в которой должна быть возможность конкретно сформулировать участие различных заинтересованных сторон, включать междисциплинарные знания и интегрировать критерии, включающие компромиссы, чтобы иметь дело с различными мнениями и разнородными факторами [1].

Проведенное авторами исследование может предложить новые идеи и рекомендации для успешного внедрения экологического менеджмента в работу предприятий, которые включают развитие новых инструментов и практических решений, а также стратегии конкретных действий, которые могут помочь организациям лучше управлять своим экологическим следом. Выбор устойчивых вариантов для экономических субъектов и создание обязательств среди заинтересованных сторон являются первостепенными для бизнеса, так как экологизация всех управленческих и производственных процессов формирует высокую конкурентоспособность фирмы [2].

Экологическая устойчивость экономического субъекта — это способность организации удовлетворять свои потребности и достигать своих целей, минимизируя негативное влияние на окружающую среду. Такие действия подразумевают принятие ответственных экологических практик, таких, как эффективное использование ресурсов, снижение выбросов и отходов, защита биоразнообразия и содействие устойчивому развитию.

Предприятия, стремящиеся к экологической устойчивости, могут разрабатывать и реализовывать планы действий и политики с целью минимизации их негативного воздействия на природу, что может включать в себя инвестиции в энергетически эффективные технологии, использование возобновляемых источников энергии, улучшение системы управления отходами и рекультивацию земель [3].

Кроме того, экологическая устойчивость может быть включена в корпоративную социальную ответственность организации, целью которой является достижение баланса между экономическими, социальными и экологическими показателями. Внедрение экологически устойчивых практик помогает компаниям обеспечить долгосрочное благосостояние, улучшить свою репутацию и взаимодействие с заинтересованными сторонами [4].

В целом, экологическая устойчивость экономического субъекта представляет собой неотъемлемую часть современного бизнеса, обеспечивающую баланс между экологической ответственностью и достижением бизнес-целей. Исследование организационных стратегий и практик, ведущих к экологически устойчивым системам производства и потребления, представляет собой одну из основных экологических проблем.

В процессе внедрения экологического менеджмента особое внимание уделяется заинтересованным сторонам, поскольку они могут положительно или отрицательно повлиять на деятельность компании, что активно рассматривается в исследовании Шмитц Э.А., Баум М., Хьюэтт П., Кабст Р. [5].

В связи с этим необходимо разрабатывать вариативность подходов к анализу стейкхолдеров. Заинтересованные лица, участвующие в производственном процессе, принято делить на две категории:

- ожидающие получить существенное влияние от деятельности / продукции / услуги;
- влияющие на способность организации успешно реализовывать свои цели.

Широкий круг стейкхолдеров задействован в решение вопросов устойчивого экологического развития: сотрудники, профсоюзы, подрядчики, поставщики, клиенты, акционеры, кредиторы, органы государственной власти, и другие. Им уделяется особое внимание с точки зрения компетентности в использовании методов идентификации и анализа устойчивых показателей [6].

Разработка и внедрение экологического менеджмента требует детального пересмотра всей стратегии, миссии и видении деятельности компании, включает комплексный подход совершенствования бизнес-процессов на каждом из его этапов [7].

Для внедрения стратегии устойчивости необходимо найти связующее звено экономических, социальных и экологических проблем, которое будет поддерживаться интеграционными целями.

В нормативно-правовом аспекте экологический менеджмент в организации должен опираться, помимо локальных актов, на международные стандарты (ISO). Коды стандартных международных систем менеджмента включают экологию — ISO 14001 Системы экологического менеджмента — Требования с руководством по использованию¹, качество — ISO 9000 Системы менеджмента качества 2 и национальные нормы по безопасности и охране труда.

Система экологического менеджмента — это способ, позволяющий экономическому субъекту решать и управлять множеством экологических проблем, с которыми он сталкивается. Эффективная экологическая политика должна включать:

- структурированный и системный подход к соблюдению экологического законодательства;
- правовую защиту от судебного преследования;
- инструмент для определения и соответствия будущим экологическим и законодательным изменениям;
- более четкое определение экологических ценностей организации;
- подход к управлению и мониторингу экологических показателей;
- документальное сопровождение;
- предоставление информации, необходимой для внутренней и внешней экологической отчетности;
- формирование имиджа на рынке;
- основа доведения показателей организации, выходящих за рамки соответствия и, возможно, в сторону устойчивости.

Фундаментальная цель экологического менеджмента — дать возможность организации соблюдать действующее законодательство. Это аргументируется тем, что некоторые законы теперь квалифицируют загрязнение как уголовное преступление, как для компании, так и для ее членов, поэтому соблюдение требований по защите окружающей среды требуется как от организации, так и от ее отдельных членов, особенно от ее директоров и ключевых менеджеров. Другие непосредственные цели могут включать улучшение экологических показателей экономического субъекта по сокращению загрязнения, минимизации использования природных ресурсов и защите окружающей среды.

После того, как система экологического менеджмента создана и организация начинает интегрировать экологические вопросы в свою общую деятельность, она может ставить более долгосрочные цели, такие как устранение всех загрязнений, ликвидация всех отходов, использование только возобновляемых ресурсов и улучшение состояния окружающей среды [8].

Системы управления могут иметь тенденцию к усложнению и, соответственно, потребовать больших усилий при их внедрении и эксплуатации, и в результате стать конечными целями [9].

Когда в организации есть все инструменты системы экологического менеджмента, стоит понимать, что это всего лишь система управления, помогающая организации решать экологические проблемы, и средство, помогающее достигать экологических целей. Для того чтобы данная концепция устойчивости приносила пользу окружающей среде, компания должна ставить перед собой реальные и достижимые экологические задачи, которые можно

постоянно улучшать с течением времени. Например, цель «сокращения выбросов углекислого газа на 5 % в год» является более позитивной целью и с большей вероятностью принесет пользу окружающей среде, чем цель «свести к минимуму выбросы парниковых газов». Стандарт ISO 14000 Менеджмент окружающей среды¹, который принимается во всем мире, представляет собой серию кодексов, охватывающих системы экологического менеджмента, аудита, оценку экологических характеристик, жизненного цикла и управление экологическими рисками.

На сегодняшний день более 160 государств и 223 000 организаций официально сертифицированы по стандарту ISO 14001 Системы экологического менеджмента — Требования с руководством по использованию.

Компании могут использовать этот кодекс в качестве основы для своей собственной системы или решают внедрить весь документ и получить сертификацию внешним органом по аккредитации [10]. ISO 14000 Менеджмент окружающей среды основан на простой модели процесса управления с петлей обратной связи, чтобы гарантировать достижение установленных целей или задач путем измерения производительности и регулярного пересмотра целей и процессов.

Обязательные требования экологической политики стандарта ISO 14001 Системы экологического менеджмента являются:

- соблюдение природоохранного законодательства и нормативных актов;
- предотвращение загрязнения;
- стремление к постоянному совершенствованию;
- сделать политику доступной для общественности.

Другие элементы экологической политики, которые организация должна рассмотреть и принять, включают [12]:

- его отношение к окружающей среде;
- установление количественных экологических целей;
- приверженность к соблюдению и превышению экологических стандартов;
- сохранение природных ресурсов;
- минимизация последствий своих продуктов и услуг;
- обеспечение безопасного рабочего места;
- связь с местными организациями и обществом;
- обучение персонала и поставщиков;
- приверженность пересмотру экологических показателей;
- стремление к созданию экологически устойчивой компании и отсутствие чистого воздействия на окружающую среду.

Планирование процедуры внедрения экологического менеджмента является важным этапом по формированию надежной системы устойчивого развития жизненного цикла организации.

Выводы

Новизна данного исследования заключается в разработке новых рекомендаций и практических решений. Авторы выдвинули на обсуждение новые идеи и стратегии для успешного внедрения экологического менеджмента в работу организации. Выделен ряд новых инструментов и конкретных действий, которые могут помочь организациям внедрить инновационную систему. Некоторые из них включают:

1. Разработка и внедрение экологической политики. Это является одним из основных шагов при внедрении экологического менеджмента. Разработка экологической политики помогает организации определить свои цели и обязательства в сфере окружающей среды и создать рамки для внедрения экологических программ.

2. Оценка экологического следа. Экологический след оценивает воздействие организации на окружающую среду в различных аспектах, например, выбросы парниковых газов, использование ресурсов и генерация отходов. Разработка и проведение экологической оценки помогает организации определить основные области, требующие улучшения, и выработать стратегии снижения экологического следа.

3. Сотрудничество с заинтересованными сторонами. Взаимодействие и сотрудничество с заинтересованными сторонами, такими как поставщики, клиенты, правительство, неправительственные организации и общественные группы, может способствовать эффективному внедрению экологического менеджмента. Диалог и партнерство с этими сторонами помогают определить приоритеты, обмениваться передовыми практиками и ресурсами, а также улучшить прозрачность и отчетность.

Внедрение системы экологического менеджмента требует комплексного и систематического подхода. Конкретные инструменты и решения могут варьироваться в зависимости от особенностей организации, отрасли и региональных контекстов. Целесообразно провести анализ запросов и потребностей вашей организации и обратиться к внешним экспертам для разработки наиболее эффективных и оптимальных решений при внедрении экологического менеджмента. Однако в ходе исследования авторы провели анализ преимуществ и недостатков внедрения экологического менеджмента в работу организаций. Преимущества внедрения экологического менеджмента:

1. Снижение негативного воздействия на окружающую среду. Внедрение экологического менеджмента позволяет организации определить свои основные окружающие проблемы и принять меры по их устранению. Это может включать снижение выбросов загрязняющих веществ, экономию водных ресурсов и уменьшение использования энергии.

2. Соответствие законодательству. Законодательство в области охраны окружающей среды становится все более строгим, и организации, внедряющие экологический менеджмент, могут быть ощутимо снижены риски наложения штрафов и выплаты компенсаций за нарушение этих законов.

3. Увеличение эффективности использования ресурсов. Внедрение экологического менеджмента позволяет организации определить области рационального использования ресурсов и принять меры по улучшению их эффективности. Это может привести к сокращению затрат и повышению прибыльности организации.

4. Улучшение репутации. Организации, заботящиеся об окружающей среде и внедряющие экологический менеджмент, могут получить преимущество перед конкурентами в глазах потребителей. В современном обществе все больше людей предпочитают приобретать товары и услуги у компаний, заботящихся об окружающей среде.

Недостатки внедрения экологического менеджмента:

1. Высокие затраты. Постановка экологического менеджмента может потребовать значительных финансовых вложений, особенно в начальный период. Это включает в себя обучение и подготовку сотрудников, разработку и внедрение новых технологий и систем контроля.

2. Сложности внедрения. Внедрение экологического менеджмента может вызывать сложности в организационном и процессном аспекте. Оно требует изменений в стратегии и культуре организации, а также привлечение и вовлечение всех уровней и сотрудников.

3. Непредсказуемые результаты. Применение экологического менеджмента не всегда приводит к ожидаемым результатам. Это может быть связано с такими факторами, как изменение потребительских предпочтений, конкуренция на рынке или недостаточное понимание преимуществ и методов экологического менеджмента.

Авторы предложили следующие мероприятия на пути оптимизации деятельности экономического субъекта:

- во-первых, необходимо создание специального отдела или подразделения в организации, ответственного за экологические вопросы и внедрение экологического менеджмента. Это позволит обеспечить четкое планирование и контроль за экологическими аспектами деятельности организации;
- во-вторых, важно проводить обучение персонала, чтобы сотрудники понимали идеи и принципы этики, связанные с экологическим менеджментом, и могли повысить свою компетенцию в этой области;
- в-третьих, необходимо установить цели и показатели для оценки достижений внедрения экологического менеджмента и регулярно проводить мониторинг и анализ результатов.

Таким образом, авторская гипотеза подтвердилась, результаты исследования указывают на необходимость внедрения экологического менеджмента в деятельность организации, что поможет не только снизить негативное влияние на окружающую среду, но и повысить эффективность и конкурентоспособность организации. Это также способствует общественной ответственности и социальному развитию.

ЛИТЕРАТУРА

1. Кленова, Я.А. Система экологического менеджмента на предприятиях / Я.А. Кленова, О.А. Нечаева // Теоретический и практический потенциал современной науки: Сборник научных статей / Научный редактор С.П. Акутина. Том Часть I. — Москва: Издательство "Перо", 2018. — С. 185–189. — EDN OTVXSB. — URL: <https://elibrary.ru/item.asp?id=37338125> (дата обращения: 07.06.2023).
2. Aragón-Correa, J.A. A contingent resource-based view of proactive corporate environmental strategy / J.A. Aragón-Correa, S. Sharma. — DOI: 10.2307/30040690 // Academy of Management Review. — 2003, Т. 28(1). — С. 71–88. — URL: https://www.researchgate.net/publication/271777382_A_Contingent_ResourceBased_View_of_Proactive_Environmental_Strategy (дата обращения: 05.06.2023).
3. Вахромов, Е.Н. Оценка устойчивого развития и функционирования предприятия: факторы, критерии, особенности / Е.Н. Вахромов, Д.Ю. Маркарян // Нефтегазовые технологии и экологическая безопасность. — 2008. — № 4. — URL: https://cyberleninka.ru/article/n/otsenka-ustoychivogo-razvitiya_funktsionirovaniyapredpriyatiya-factory-kriterii-osobennosti (дата обращения: 07.06.2023).
4. Магомедамирова, З.Г. Экологический менеджмент и концепция устойчивого развития / З.Г. Магомедамирова, Л.И. Саидова — DOI: 10.47576/2782-4586_2023_2_83 // Journal of Monetary Economics and Management. — 2023. — № 2. — URL: <https://cyberleninka.ru/article/n/ekologicheskii-menedzhment-ikontseptsiya-ustoychivogo-razvitiya> (дата обращения: 06.06.2023).
5. Schmitz, E.A. The contextual role of regulatory stakeholder pressure in proactive environmental strategies: An empirical test of competing theoretical perspectives / E.A. Schmitz, M. Baum, P. Huett, R. Kabst — DOI:10.1177/1086026617745992 // Organ. Environ. — 2017. — Т. 32. С. 281–308. — URL: https://www.researchgate.net/publication/321909910_The_Contextual_Role_of_Regulatory_Stakeholder_Pressure_in_Proactive_Environmental_Strategies_An_Empirical_Test_of_Competing_Theoretical_Perspectives (дата обращения: 05.06.2023).
6. Вонг, В.Х. Роль внешних стейкхолдеров в экологическом, социальном и корпоративном управлении компаний (ESG) / В.Х. Вонг, Б.Х. Тэ, С.Х. Тан // Форсайт. — 2023. — № 2. — URL: <https://cyberleninka.ru/article/n/rol-vneshnihsteykholderov-v-ekologicheskom-sotsialnom-i-korporativnom-upravlenii-kompaniyesg> (дата обращения: 08.06.2023).

7. De Fátima Teles, M. Integrating Environmental Policies into Business Strategy: The Problem Structuring Stage in a Framework for Decision Support / M. de Fátima Teles, J.F. de Sousa. — DOI: https://doi.org/10.1007/978-3-319-11364-7_9 // In: Dargam, F., et al. Decision Support Systems III — Impact of Decision Support Systems for Global Environments. EWG-DSS EWG-DSS. — 2013. Lecture Notes in Business Information Processing. — Т. 184. — Springer, Cham. — URL: https://link.springer.com/chapter/10.1007/978-3-319-11364-7_9 (дата обращения: 05.06.2023).
8. Александрова, Е.Н. Направления внедрения экологического менеджмента в российской экономике на основе зарубежного опыта / Е.Н. Александрова, С.А. Дарбинян // Международный журнал гуманитарных и естественных наук. — 2023. — № 4-1(79). — URL: <https://cyberleninka.ru/article/n/napravleniyavnedreniya-ekologicheskogo-menedzhmenta-v-rossiyskoy-ekonomike-na-osnovezarubezhnogo-opyta> (дата обращения: 07.06.2023).

СТРАТЕГИЧЕСКОЕ УПРАВЛЕНИЕ ИННОВАЦИОННОЙ ДЕЯТЕЛЬНОСТЬЮ ПРЕДПРИЯТИЯ

Ахметбеков Данияр Габдулович

Казахстанско-Британский Технический университет, Алматы, Казахстан

Тугеленов Аскар Нуртаевич

Казахстанско-Британский Технический университет, Алматы, Казахстан

В современных условиях быстроменяющейся экономической ситуации, нарастания глобализации, слияния экономических и политических интересов, без инновационной деятельности казахстанскому предприятию выжить невозможно. Абсолютно любое предприятие сталкивается с необходимостью в той или иной мере модернизировать производственную систему, искать новые возможности для улучшения своей продукции, внедрения инноваций, заниматься конкурентной борьбой, разрабатывать стратегию своего развития.

Таким образом, вопросы стратегического управления инновационной деятельностью являются весьма актуальными для современного казахстанского предприятия. Стратегическое управление, несомненно, является одной из важных составляющих системы инновационного менеджмента, так как оно нацелено на решение проблем в сфере планирования и реализации долгосрочных инновационных проектов [1]. При этом данные инновационные проекты по своему содержанию ориентированы на существенные, качественные изменения в производственно-коммерческой деятельности предприятия.

В целом задачи стратегического управления в сфере разработки и реализации инноваций позволяют ответить на следующие вопросы:

1. На каких рынках и с какими инновационными продуктами будет работать предприятие в краткосрочной и долгосрочной перспективе?
2. Какие инновации, какие методы и средства позволят достигнуть стратегических целей развития предприятия?
3. Какие размеры финансовых средств необходимо привлечь для реализации выбранной стратегии и каковы финансирования?
4. Какой состав сотрудников (количественный и качественный) способен реализовать выбранную стратегию инновационного развития предприятия?

В общем виде стратегия развития предприятия представляет собой поиск наиболее перспективных вариантов реализации его производственных и финансовых ресурсов с учетом ситуации на рынке, в отрасли и экономике страны в целом [1]. Стратегия предполагает разработку обоснованных мер в виде конкретных программ и бизнес-проектов, нацеленных на достижение ранее установленных целей развития предприятия. При этом в данных инновационных, инвестиционных программах и бизнес-проектах должны быть учтены как научно-технический, производственный, финансовый, кадровый потенциалы предприятия, так и его рыночно-сбытовые возможности.

Стратегия инноваций нацелена на объединение целей технического развития предприятия, направленного на внедрение новых технологий и видов продукции с его инвестиционными возможностями. Поэтому деятельность в рамках стратегического менеджмента инноваций однозначно начинается с постановки целей и задач развития инновационной организации, с учетом возможности корреляции изменений внешней среды

функционирования предприятия и его внутренних параметров производственно-коммерческой деятельности.

В отличие от оперативного менеджмента, который призван обеспечить выживаемость предприятия на сегодняшний день, система стратегического управления инновационной деятельностью нацелена на завоевание лидирующих позиций бизнеса в долгосрочном временном диапазоне. Таким образом, процесс стратегического управления инновациями может быть представлен в виде ряда последовательных этапов [1, 2]:

1. Этап «стратегический анализ». Разработка инновационной стратегии начинается с формулировки общих целей развития организации, при этом цели должны быть конкретными, измеримыми и реализуемыми. Важно, чтобы при утверждении стратегических целей развития организации были учтены финансовое положение фирмы, специфика ее производственно-коммерческой деятельности, ее положение (имидж, авторитет) во внешней среде, а также корпоративная культура, традиции и рабочий климат в трудовом коллективе.

2. Этап «анализ источников инновационных возможностей». Второй этап по своей сложности и неоднозначности применяемых инструментов не менее важен, чем первый. Анализ источников возможностей фирмы для ее успешной инновационной деятельности предполагает поиск и оценку внешних факторов, которые окажут стимулирующий эффект как для конкретного бизнеса, так и отрасли в целом. Например, в качестве факторов, способствующих развитию казахстанского инновационного предприятия, могут выступать наличие высокотехнологичных производств в отрасли; частота обновления производственных технологий; отсутствие сильных конкурентов на отечественном рынке (отрасли); уровень государственной поддержки программ развития конкретной отрасли; интенсивность использования государством отдельных инструментов по обеспечению экономической безопасности отрасли (или экономики в целом); уровень инвестиционной привлекательности отрасли и др.

В инновационном менеджменте такой этап, как анализ среды рыночного окружения, на который нацелена разрабатываемая предприятием инновация, должен охватить следующие основные факторы:

- объем, доступность, возможность роста целевых сегментов рынка;
- уровень, динамика, тенденции в изменениях покупательских требований к показателям качества и цены продукции;
- степень диверсификации поставщиков основных видов ресурсов, а также характеристика их деятельности в сфере инноваций;
- доступность инвестиционных ресурсов для конкретного субъекта производственно-хозяйственной деятельности и в экономике государства в целом;
- наличие, масштабы и качественный уровень работы организаций, составляющих инновационную инфраструктуру региона (бизнес-инкубаторы, технопарки, научные, образовательные, юридические организаций);
- наличие и характер конкурентных преимуществ экономически сильных компаний (основных конкурентов на рынке), динамика их рыночных позиций, а также интенсивность инвестиционно-инновационной деятельности данных организаций.

Неоспорим тот факт, что на этапе поиска инновационных возможностей необходимо выполнить оценку стратегического потенциала всех функциональных подразделений исследуемого предприятия, входящих в структуру «инновационной цепи» организации, реализующей инновационный проект. В общем виде к данным подразделениям относятся: служба маркетинга, НИОКР, основное и вспомогательное производство, финансовый, кадровый, юридический отделы, служба информационного обеспечения и т.д.

Оценка стратегического потенциала каждой из данных подсистем выполняется по следующим параметрам: уровень технического оснащения; финансовая независимость; уровень специализации и кооперации подразделения; квалификационный уровень персонала; степень вертикальной и горизонтальной дифференциации структуры управления, а также степень развития корпоративной культуры в подразделении.

3. Этап «стратегический выбор». С помощью аналитического, логического обобщения всех полученных опытно-статистических данных осуществляется выбор стратегии инновационного развития организации. Целесообразно процедуру проектирования и отбора наиболее приемлемой инновационной стратегии развития предприятия провести с использованием популярных как в зарубежной практике, так и в отечественном бизнесе, специализированных матричных методик (например: матрица стратегического анализа, матрица БКГ, «Мак-Кинси» и др).

4. Этап «реализация выбранной инновационной стратегии». На данном этапе, как правило, выполняется следующий комплекс управленческих работ [3]:

- проводится модернизация организационно-управленческой структуры предприятия, формируются проектные группы, которые будут работать над реализацией выбранной инновационной стратегии;
- осуществляется перераспределение личной и групповой ответственности между руководителями линейных и функциональных подразделений, корректируются должностные инструкции и, если необходимо, вносятся изменения в штатно-должностную структуру организации;
- реализуется программа привлечения дополнительных инвестиционных ресурсов и (или) перераспределяются финансовые ресурсы по этапам реализации инновационного проекта в целях мотивации и стимулирования работы по данному проекту;
- формируются системы сбора и обработки аналитической информации, нацеленной на своевременную и эффективную корректировку хода выполнения проекта согласно полученным промежуточным результатам реализации инновационной стратегии.

5. Заключительный этап «координации и контроля». По результатам, полученным на предыдущей стадии реализации инновационной стратегии, анализируется динамика показателей, характеризующих эффективность инновационной деятельности организации. Если полученные результаты не совсем устраивают руководителей фирмы или собственника бизнеса, то осуществляется перераспределение материальных, финансовых, трудовых, информационных ресурсов, вносятся корректирующие изменения в структуру портфеля инвестиционно-инновационных проектов, закрываются неперспективные проекты, разрабатывается новая инновационная стратегия и т.д. Теоретической и методологической основой стратегического планирования инновационного развития предприятия является научное прогнозирование тенденций как во внешней, так и во внутренней среде [1–3].

Основная функция прогнозирования в системе инновационного менеджмента заключается в поиске наиболее перспективных направлений развития исследуемых объектов на основе всестороннего анализа динамики изменений как во внешней, так и во внутренней среде. Получение достоверного и точного прогноза позволит предприятию решить следующие задачи: определить стратегические цели и приоритетные направления инновационного развития объекта; оценить социальные и экономические последствия реализации инновационного проекта, при этом оценка должна быть получена для каждого из альтернативных вариантов реализации проекта; определить организационные мероприятия, необходимые для обеспечения эффективности реализации инновационного проекта.

Современная отечественная и зарубежная практика менеджмента насчитывает более 130 различных методов разработки прогнозов, при этом все многообразие методик и

инструментов прогнозирования сводится к трем важнейшим группам: прогнозирование на основе экстраполяции, экспертные методы прогнозирования и методы моделирования [4]. **Методы экстраполяции**, применяемые при прогнозировании инновационной деятельности, предполагают анализ изменений отдельных параметров инновационного объекта (науки, техники, технологии) в прошлом, установление факторов, обуславливающих эти изменения, что позволит менеджеру сделать вывод о закономерностях развития объекта и, как следствие, получить прогноз его будущего состояния.

Суть экспертных методов прогнозирования инноваций состоит в том, что на основе субъективных и объективных оценок квалифицированного специалиста (если используются индивидуальные методы экспертизы, предусматривающие персональную работу эксперта) или группы специалистов (коллективные методы используются в целях повышения точности прогнозов на основе работы группы экспертов) делается заключение о направлениях динамики развития НТП.

Огромный вклад в развитие методологии инновационного прогнозирования внесли такие заслуженные деятели экономической науки, как Н. Д. Кондратьев [5] и Нобелевский лауреат В. В. Леонтьев [6]. Они доказали, что в инновационном прогнозировании необходимо отказаться от однофакторных и линейных моделей, которые могут быть пригодны лишь при разработке краткосрочных прогнозов.

Н. Д. Кондратьев в своей научной работе («Большие циклы экономической конъюнктуры», 1926 г.) [5], посвященной исследованию экономических циклов и построению на их основе прогнозов, определил три типа прогнозов:

- первый тип прогноза осуществляется для событий, которые по своей сути нерегулярные, как правило, такие события бывают однократными и, соответственно, не могут быть включены ни в какой экономический закон;
- второй тип прогноза – это предвидение более или менее повторяющихся событий, при этом прогноз не принимает количественную форму, а заключается в утверждении вероятного наступления времени события, возникающего более или менее периодически;
- третий тип прогноза представляет собой предвидение общей модели событий в социально-экономических тенденциях, но нет возможности точно установить их количественные параметры.

В. В. Леонтьев («Глобальная модель», нобелевская лекция 1973 г.) [6] в качестве методов прогнозирования развития объекта предлагал использовать воспроизводственно-циклическую макромоделю для анализа и прогнозирования сдвигов в технологической структуре экономики – модель экономического анализа «затраты – выпуск». Согласно данной модели, прогнозирование инноваций возможно осуществить по модели нелинейной динамики, которая учитывает фазы жизненных циклов различных поколений техники и технологий (динамику технологических укладов), что позволит оценить влияние распространения базисных инноваций на структуру экономики и ее межотраслевые сдвиги.

Еще одним общеизвестным инструментом прогнозирования инноваций является метод Дельфи (разработан в 1950–1960 гг. в США для прогнозирования влияния будущих научных разработок на методы ведения войны, разработан корпорацией RAND, авторы Olaf Helmer, Norman Dalkey, Nicholas Rescher) [7]. Сущность данного метода заключается в сочетании процедуры интуитивно-логического мышления человека и количественных методов оценки полученных результатов. Основные характеристики данного метода:

- 1) избежание личных контактов между экспертами, опрашиваемыми по конкретной проблеме, что позволяет получить более широкий спектр объективных экспертных оценок;
- 2) обеспечение экспертов необходимой дополнительной информацией, включая обмен мнениями между ними, но только после каждого тура опроса;

3) обеспечение системы защиты информации от утечки, а также гарантии анонимности экспертных оценок;

4) наличие обратной связи по процессу прогнозирования в целях своевременной корректировки информации.

На основе метода Дельфи зарубежными и отечественными экономистами были разработаны различные методики прогнозирования, включающие в инструментарий новые элементы, но все они сохранили основные моменты классического метода [8].

Организационное обеспечение системы прогнозирования инновационных процессов на государственном уровне предусматривает создание специальных субъектов, осуществляющих сбор, систематизацию и анализ научно-технической информации, разработку прогнозов развития науки и техники в стране и мире.

Необходимость процесса прогнозирования в инновационной сфере обусловлена тремя основными причинами:

– во-первых, изменения рыночной конъюнктуры, рост требований к ассортименту и качеству товаров (услуг), жесткость экономических условий хозяйствования, связанная с усилением экономических санкций западных держав относительно нашей страны – все это диктует требования к своевременной адаптации отечественного производителя к новым условиям, заставляет заниматься инновационным прогнозированием для освоения новых видов технологий, инновационной продукции;

– во-вторых, возникающие новые научно-технические идеи и изобретения должны быть поддержаны и внедрены именно в Казахстане, что позволит отечественному товаропроизводителю своевременно включиться в освоение и распространение новых поколений техники и технологий и что в свою очередь станет импульсом для инновационного развития государства и общества в целом;

– в-третьих, правильное прогнозирование динамики инновационных процессов позволит снизить финансовые риски в сфере инноваций, а значит, дополнительно привлечет инвестиции в данную сферу, направит инвестиционный поток на обновление и расширение производства конкурентоспособных отечественных товаров (услуг).

В качестве еще одного фактора, оказывающего влияние на инновационные процессы в государстве, можно выделить миграцию. На сегодняшний день проблемы, связанные с миграционными потоками, особо остро стоят перед Европой, но и Казахстан не может полностью изолировать себя от них. Целый комплекс мероприятий, разработанный на государственном уровне, должен стимулировать граждан своей страны к работе на территории РК, вкладывая свой опыт и профессионализм в инновационное развитие экономики и повышение благосостояния граждан страны.

Другими словами, стратегическое управление инновационной сферой просто обязано учитывать международную и внутригосударственную миграцию как одни из главных факторов политического давления, связанного с обострением социальной напряженности в обществе и, безусловно, ужесточением экономических требований, предъявляемых государством к сфере инноваций.

Таким образом, в условиях международной глобализации, когда ни одна страна (даже экономически сильная держава) не может добиться инновационного лидерства абсолютно во всех сферах, казахстанским компаниям (организациям, предприятиям) необходимо тщательно прогнозировать, оценивать и анализировать структурные сдвиги в глобальном инновационном технологическом пространстве, учитывать возможности и перспективы совместного объединения усилий (рамках интеграционных объединений Евроазиатского союза, СНГ и т.п.) для осуществления приоритетных инновационных проектов. Только грамотная стратегия развития инновационной сферы позволит решить ряд сложных общенациональных, международных проблем, в частности, в сфере экологии,

освоения космоса, обеспечении безопасности и борьбе с международным терроризмом, и другие важные вопросы.

Список литературы:

1. Аверина, Т. А. Инновационный менеджмент: учеб. пособие / Т. А. Аверина, С. А. Баркалов, И. С. Суровцев, И. Ф. Набиуллин. – Воронеж, 2010. – 483 с.
2. Дандон, Э. Инновации: как определять тенденции и извлекать выгоду / Элейн Дандон ; пер. с англ. С. Б. Ильина; под общ. ред. М. Б. Шифрина. – М. : Вершина, 2006. – 304 с.
3. Давил, Т. Работающая инновация: как управлять ею, измерять ее и извлекать из нее выгоду / Т. Давил, М. Дж. Эпштейн, Р. Шелтон; пер. с англ. под науч. ред. Т. Ф. Козицкой. – Днепропетровск: Баланс Бизнес Букс, 2007 – 320 с.
4. Вертакова, Ю. В. Управление инновациями: теория и практика : учеб. пособие / Ю. В. Вертакова, Е. С. Симоненко. – М. : Эксмо, 2008. – 432 с.
5. Теория конъюнктуры и проблемы народнохозяйственного планирования в работах Н. Д. Кондратьева. – URL: <http://closelook.narod.ru/MSU/Kondratiev.html>.
6. Нобелевская премия. Успех Леонтьева в применении моделей экономического анализа «затраты – выпуск». – URL: <http://www.wleontief.ru/rus/22.html>.
7. Метод «Дельфи». – URL: https://ru.wikipedia.org/wiki/Метод_«Дельфи»
8. Гольдштейн, Г. Я. Стратегический инновационный менеджмент : учеб. пособие / Г. Я. Гольдштейн. – Тагменеджмент:о ТРТУ, 2014. – 267 с.

СТРАТЕГИИ УВЕЛИЧЕНИЯ РЕНТАБЕЛЬНОСТИ ВЕЧЕРНЕЙ ПОЛИКЛИНИКИ В РАМКАХ ЦУР: ПОДХОДЫ И РЕКОМЕНДАЦИИ

Маханов Темірғали Калмаханбетұлы

Магистрант 2-го курса, MBA «Менеджмент в здравоохранении»

Руководитель:

Маукенова Алтынай Аманбаевна

Кандидат экономических наук, асс. Профессор кафедры политики и менеджмента здравоохранения, Казахский национальный медицинский университет имени С.Д. Асфендиярова, г. Алматы, Казахстан

Аннотация. Вечерняя поликлиника рассматривается как управленческий инструмент повышения доступности амбулаторной помощи и достижения Цели устойчивого развития 3 (ЦУР 3 «Хорошее здоровье и благополучие»). На основе анализа внутренней статистики Больницы А за 2024–2025 гг. и 01.01.2025–27.01.2026 г. выявлены ключевые проблемы: крайне низкая загрузка (2,1 визита/день), высокая концентрация потока на трёх специальностях (79,5%), выраженная сезонная вариабельность ($CV=58,4\%$) и значительный разрыв в средней стоимости амбулаторной услуги (10 365 тг.) относительно диагностических направлений (МРТ — 23 825 тг., КТ — 19 776 тг.). Предложены организационно-экономические меры: управление спросом на основе данных, снижение неявок, пакетирование услуг, TDABC-микрокостинг, корпоративные программы и телемедицина.

Ключевые слова: вечерняя поликлиника; рентабельность; ЦУР 3; доступность; управление спросом; неявки; TDABC; KPI.

Введение

Глобальная повестка устойчивого развития ООН определяет доступность качественных медицинских услуг как стратегический приоритет: Цель устойчивого развития 3 (ЦУР 3 «Хорошее здоровье и благополучие») предусматривает обеспечение всеобщего охвата медицинской помощью, включая доступность услуг для работающего населения, которое объективно ограничено в возможности посещать медицинские учреждения в дневное время [1]. В этом контексте вечерняя поликлиника представляет собой не только коммерческий формат оказания платных услуг, но и инструмент реализации ЦУР 3 на уровне конкретной медицинской организации.

Для медицинской организации вечерний приём — это одновременно управленческая задача: необходимо обеспечить положительный вклад в маржу при сохранении качества и безопасности [2]. В условиях Казахстана развитие платных амбулаторных услуг и гибких форм организации приёма регулируется Кодексом РК «О здоровье народа и системе здравоохранения» [3] и профильными подзаконными актами МЗ РК.

Цель исследования — разработать и обосновать управленческие рекомендации по повышению рентабельности вечерней поликлиники Больницы А на основе эмпирического анализа и международных данных.

Материалы и методы

Использованы: (1) систематизированный обзор публикаций по расширению часов приёма (after-hours, extended access) и управлению доступом [4–6]; (2) анализ внутренней отчётности организации за 2024–2025 гг. и за период 01.01.2025–27.01.2026 по посещениям, объёму услуг и выручке; (3) управленческий анализ «unit economics» и портфеля услуг (ABC/маржинальный подход, TDABC); (4) SWOT-анализ вечерней поликлиники; (5) формирование системы KPI.

Результаты и обсуждение

Структура и финансовые показатели проекта «Вечерняя поликлиника»

По данным управленческой отчётности за 2024–2025 гг. совокупная выручка проекта «Вечерняя поликлиника» составила 49 502 725 тенге при 2 511 услугах. Структура доходов существенно неравномерна (таблица 1).

Таблица 1 — Структура доходов проекта «Вечерняя поликлиника», 2024–2025 гг.

Направление	Кол-во услуг	Выручка, тг.	Доля, %
Вечерняя поликлиника (амбулат.)	893	9 256 190	18,7%
МРТ круглосуточно	1 201	28 613 955	57,8%
КТ круглосуточно	294	5 814 340	11,7%
Вечерний стационар	123	5 818 240	11,8%
Итого по проекту	2 511	49 502 725	100%

Примечание — составлено автором по данным управленческой отчётности.

Амбулаторный приём формирует лишь 18,7% выручки при 35,5% услуг, тогда как МРТ обеспечивает 57,8% выручки. Анализ средней стоимости одной услуги (таблица 2) выявляет принципиальный экономический разрыв между направлениями.

Таблица 2 — Сравнительный анализ средней стоимости услуги по направлениям

Направление	Кол-во услуг	Выручка, тг.	Ср. стоимость, тг.
Вечерняя поликлиника (амбулат.)	893	9 256 190	10 365
МРТ круглосуточно	1 201	28 613 955	23 825 (+2,3×)
КТ круглосуточно	294	5 814 340	19 776 (+1,9×)
Вечерний стационар	123	5 818 240	47 303 (+4,6×)

Примечание — составлено автором; кратность рассчитана относительно амбулаторного направления.

Таким образом, амбулаторный приём является наименее доходным направлением в расчёте на одну услугу. Вместе с тем именно он формирует маршрутизирующую функцию: пациенты, получившие консультацию в вечерней поликлинике, могут быть направлены на МРТ/КТ и в вечерний стационар — более высокодоходные направления. Это делает развитие амбулаторного потока стратегически важным для роста совокупной выручки проекта.

Анализ посещаемости и выявление ключевых проблем

За период 01.01.2025–27.01.2026 амбулаторный прём зафиксировал 562 посещения. Среднемесячное значение — 43,2 визита, что в пересчёте на рабочие дни составляет лишь 2,1 посещения/день на всю вечернюю поликлинику. Коэффициент вариации помесечной посещаемости — 58,4% (min: 9 визитов в июне, max: 80 — в мае), что свидетельствует о нестабильности пациентопотока и отсутствии управления спросом (таблица 3).

Таблица 3 — Помесячная динамика посещений вечерней поликлиники и лучевой диагностики, 2025 г.

Показатель	Янв	Фев	Мар	Апр	Май	Июн	Июл	Авг	Сен	Окт	Ноя	Дек	Янв'26 / Итого
Амбул. приём, визиты	15	64	45	79	80	9	35	27	35	33	50	55	35 / 562
МРТ+КТ, исследований.	69	49	37	75	178	177	192	128	64	91	64	70	45 / 1239

Примечание — красным выделен минимум амбулаторного приёма; зелёным — пик лучевой диагностики. Составлено автором.

Принципиально важно обратное соотношение: июнь — минимум амбулаторных визитов (9), но высокий пик МРТ+КТ (177). Это подтверждает, что летний спад связан не с отсутствием пациентов в учреждении, а с неэффективной маршрутизацией и отсутствием перекрёстных продаж между направлениями проекта.

Структура по специальностям демонстрирует критическую концентрацию: невропатолог — 267 визитов (47,5%), хирург — 97 (17,2%), нейрохирург — 83 (14,8%). Три специальности формируют 79,5% всего потока. Остальные 6 специалистов обеспечивают 20,5% — при неизменном составе штата и накладных расходах в периоды низкого спроса это приводит к прямым экономическим потерям.

Описанные закономерности согласуются с международными данными: систематические обзоры показывают, что эффект вечернего расширения доступа зависит от дизайна модели записи, структуры спроса и кадровой обеспеченности [4, 5], а гипотеза «вечером нет спроса» в большинстве случаев объясняется не отсутствием потребности, а несовпадением предложения с реальными сегментами рынка [6].

Отдельным фактором, влияющим на концентрацию потока, является репутация конкретного врача. Данные вечерней поликлиники демонстрируют это наглядно: невропатолог формирует 47,5% всех посещений — показатель, несопоставимый с долей специальности в штатном расписании. С высокой вероятностью это объясняется не только профильным спросом на неврологическую помощь в вечернее время, но и личным брендом специалиста: пациенты записываются к конкретному врачу, а не просто в поликлинику. Такая зависимость носит двойственный характер. С одной стороны, репутация врача выступает точкой роста: она обеспечивает стабильный поток даже при слабом общем маркетинге учреждения и формирует лояльность пациентов. С другой стороны, это создаёт критический операционный риск: уход или длительное отсутствие одного специалиста способно обвалить почти половину объёма амбулаторных приёмов. Международная литература подтверждает, что continuity of care — непрерывность наблюдения у одного врача — является значимым фактором удовлетворённости пациентов и их возвращаемости [6], что дополнительно усиливает эту зависимость. Следовательно, стратегия развития вечерней

поликлиники должна предусматривать одновременно два направления: использование репутации ключевых специалистов как маркетингового актива и целенаправленное снижение зависимости от одного врача через развитие институционального бренда учреждения в целом.

SWOT-анализ и идентификация резервов

На основе SWOT-анализа, проведённого с участием заместителя директора по поликлинической работе, главного бухгалтера и ведущих специалистов, идентифицированы ключевые управленческие зоны (таблица 4).

Таблица 4 — SWOT-анализ деятельности вечерней поликлиники

Сильные стороны (S)	Слабые стороны (W)
– Единственный в проект, объединяющий амбулаторный приём, МРТ/КТ и вечерний стационар – Мощная диагностическая база: МРТ+КТ генерируют 69,5% выручки проекта (34,4 млн тг.) – Высококвалифицированный персонал по доказанно востребованным специальностям – Интеграция с МИС ДАМУмед и eGov.kz	– Крайне низкая загрузка: 2,1 визита/день на всю вечернюю поликлинику – Концентрация 79,5% потока на 3 специальностях при простое остальных кабинетов – Критическая сезонность: июнь — 9 визитов при неизменных постоянных затратах – Средняя стоимость амбулаторной услуги в 2,3–4,6 раза ниже смежных направлений
Возможности (O)	Угрозы (T)
– 1 239 пациентов МРТ/КТ — потенциал кросс-маршрутизации в амбулаторный приём – Нормативная база телемедицины (Приказ МЗ РК № ҚР ДСМ-12 от 01.02.2021) – Корпоративные программы ДМС и договоры с работодателями – Растущий спрос работающего населения Алматы на вечерний формат	– «Риск одного специалиста»: уход невропатолога — потеря 47,5% потока – Высокая конкуренция со стороны частных неврологических и нейрохирургических центров Алматы – Низкая информированность потенциальных пациентов о формате вечерней поликлиники

Примечание — составлено автором по материалам рабочей группы.

Рекомендации

На основе эмпирических данных и международного опыта предлагается комплекс мер, направленных на повышение рентабельности амбулаторного направления вечерней поликлиники.

1) Управление спросом на основе данных. Расписание необходимо строить исходя из фактической посещаемости по дням недели, специальностям и месяцам. В периоды низкого спроса (июнь–август) следует переходить на усечённый состав специалистов — 3 ключевых профиля вместо 9, сохраняя фиксированные расходы на минимальном уровне. Принципы advanced access (часть слотов под запись «день-в-день») позволяют сократить время ожидания и снизить долю неявок [7, 8].

2) Кросс-маршрутизация пациентов МРТ/КТ. 1 239 пациентов лучевой диагностики — неиспользуемый потенциал амбулаторного потока. Введение алгоритма направления на консультацию невропатолога/нейрохирурга сразу после МРТ-исследования в тот же вечер обеспечит органичный рост визитов без затрат на привлечение новых пациентов.

3) Снижение неявок. Внедрение автоматических напоминаний через SMS/WhatsApp с подтверждением и возможностью переноса снижает долю no-show. Систематические обзоры демонстрируют, что такие программы повышают явку и управляемость записи [9, 10]. Целевой KPI: доля неявок $\leq 10\%$.

4) Оптимизация портфеля и среднего чека. Формирование пакетных предложений «консультация невропатолога + базовое ЭМГ/ЭЭГ» и «хирург + ЭКГ» позволяет повысить среднюю выручку на визит без увеличения числа пациентов. Для услуг с доказанным спросом целесообразно установить предоплату или депозит для снижения неявок.

5) Учёт себестоимости (TDABC). Расчёт себестоимости ключевых услуг методом time-driven activity-based costing [11, 12] и ведение управленческого отчёта по маржинальному вкладу на час работы кабинета создаёт информационную основу для принятия решений о сохранении, развитии или выводе отдельных направлений.

6) Корпоративные программы и маркетинг. Таргетирование работающих пациентов через договоры с работодателями г. Алматы, усиление видимости вечернего приёма в геосервисах и продвижение через цифровые каналы позволит планомерно наращивать поток. Репутация Больницы А выступает значимым конкурентным преимуществом.

7) Управление репутацией врача как активом. Данные показывают, что поток вечерней поликлиники во многом формируется личным брендом конкретного специалиста, а не брендом учреждения в целом. Это необходимо использовать осознанно: публикация профилей ключевых врачей с отзывами пациентов в геосервисах и на сайте, персонализированные рекомендации через систему записи, возможность записи «к конкретному врачу» — всё это повышает конвертацию интереса в реальный визит. Одновременно следует снижать институциональный риск: развивать узнаваемость всей команды вечерней поликлиники, выстраивать систему внутренней маршрутизации между специалистами и поддерживать кадровый резерв по ключевым профилям. Цель — чтобы пациент шёл в Больницу А, а не только к конкретному врачу.

8) Телемедицина. Нормативная база РК (Приказ МЗ РК № ҚР ДСМ-12 от 01.02.2021) позволяет использовать дистанционные консультации для повторных визитов, контроля лечения и маршрутизации, снижая нагрузку на кабинеты в периоды пиковых недель и обеспечивая доступность помощи в рамках ЦУР 3 [13, 14].

Система KPI вечерней поликлиники

Таблица 5 — Рекомендуемые KPI вечерней поликлиники

Показатель	Единица измерения	Целевое значение	Текущее значение
Среднесуточное число визитов	визиты/день	≥ 10	2,1
Доля неявок (no-show rate)	%	$\leq 10\%$	н/д
Коэффициент вариации посещаемости	%	$\leq 30\%$	58,4%
Средний чек амбулаторного приёма	тг.	$\geq 15\ 000$	10 365
Доля топ-3 специальностей в объёме	%	$\leq 65\%$	79,5%
Маржинальный вклад смены	тг./смена	положит.	н/о

Примечание — «н/д» — нет данных; «н/о» — не рассчитывалось. Составлено автором.

Выводы

Проведённый анализ деятельности вечерней поликлиники Больницы А за 2024–2025 гг. и 01.01.2025–27.01.2026 г. позволяет сформулировать следующие выводы.

Во-первых, текущее состояние амбулаторного направления характеризуется крайне низкой загрузкой (2,1 визита/день), высокой сезонной вариабельностью ($CV=58,4\%$) и критической зависимостью от одного специалиста (невропатолог — 47,5% потока). Это несовместимо с устойчивой рентабельностью.

Во-вторых, ключевым стратегическим резервом является кросс-маршрутизация пациентов МРТ/КТ (1 239 исследований в год) в амбулаторный приём, а также разработка дифференцированного расписания, учитывающего сезонность и профильный спрос.

В-третьих, повышение рентабельности требует одновременной настройки нескольких управленческих инструментов: гибкого расписания на основе данных, системы напоминаний и управления неявками, пакетирования услуг, TDABC-микрокостинга и корпоративных программ. Только комплексный подход обеспечивает устойчивый финансовый результат.

В-четвёртых, развитие вечерней поликлиники напрямую содействует ЦУР 3 «Хорошее здоровье и благополучие», обеспечивая доступность качественных медицинских услуг для работающего населения города.

Список литературы

1. United Nations. Transforming our world: the 2030 Agenda for Sustainable Development. Resolution A/RES/70/1. New York: UN; 2015.
2. World Health Organization; UNICEF. Operational framework for primary health care: transforming vision into action. Geneva: WHO; 2020.
3. Кодекс Республики Казахстан от 7 июля 2020 года № 360-VI ЗРК «О здоровье народа и системе здравоохранения».
4. Jerant A, Bertakis KD, Fenton JJ, Franks P. Extended Office Hours and Health Care Expenditures. Ann Fam Med. 2012;10(5):388–395.

5. Hong M, Thind A, Zaric GS, Sarma S. The impact of improved access to after-hours primary care. *Health Policy*. 2020;124(8):812–818.
6. O'Malley AS. After-Hours Access to Primary Care Practices. *Health Aff (Millwood)*. 2013;32(1):175–183.
7. Murray M, Berwick DM. Advanced Access: Reducing Waiting and Delays in Primary Care. *JAMA*. 2003;289(8):1035–1040.
8. Eccles A, Goff M, et al. Access systems in general practice: a systematic scoping review. *Br J Gen Pract*. 2024;74(747):e674–e682.
9. Hasvold PE, Wootton R. Use of telephone and SMS reminders to improve attendance. *J Telemed Telecare*. 2011;17(7):358–364.
10. Boone CE, Celhay P, Gertler P, et al. How scheduling systems with automated appointment reminders improve health clinic efficiency. *J Health Econ*. 2022;82:102598.
11. Kaplan RS, Anderson SR. Time-driven activity-based costing. *Harv Bus Rev*. 2004;82(11):131–138.
12. Keel G, Savage C, Rafiq M, Mazzocato P. Time-driven activity-based costing in health care: A systematic review. *Health Policy*. 2017;121(7):755–763.
13. Приказ Министра здравоохранения РК от 1 февраля 2021 года № ҚР ДСМ-12 «Об утверждении правил организации, предоставления и оплаты дистанционных медицинских услуг».
14. Agarwal P, Fletcher GG, et al. Uses of Virtual Care in Primary Care: Scoping Review. *J Med Internet Res*. 2025;27:e55007.

The Role of Artificial Intelligence Algorithms in Detecting Cyberattacks within E-Government Services

Farid Hasanov

M.Sc. Candidate, Azerbaijan State University of Economics (UNEC), Baku, Azerbaijan,
ORCID: 0009-0008-3819-4978

Abstract

The rapid and irreversible digital transformation of public administration has led to the emergence of complex E-Government ecosystems. These platforms integrate highly sensitive citizen data, financial records, and critical national infrastructure into unified digital portals. However, this centralization has introduced unprecedented cybersecurity challenges, as traditional defense mechanisms—primarily based on static signature matching—are increasingly failing to counter sophisticated, AI-driven threats, polymorphic malware, and zero-day vulnerabilities. This research provides an extensive, multi-dimensional analysis of the integration of Artificial Intelligence (AI) and Machine Learning (ML) algorithms as the primary defensive layer for E-Government services. By synthesizing empirical data and industry insights from 2023–2026 reports, including IBM X-Force, NCSC, and Google Cloud security perspectives, this study evaluates the technical efficacy of diverse algorithmic models. The research methodology involves a comparative simulation of Random Forest (RF), Support Vector Machines (SVM), and Deep Neural Networks (DNN) in detecting diverse attack vectors such as Distributed Denial of Service (DDoS), advanced Phishing, and SQL injection. The results demonstrate that deep-learning-based systems achieve a superior detection accuracy of over 97.8%, significantly reducing false positive rates and incident response times. The paper concludes with a strategic roadmap for government agencies to adopt resilient, AI-managed security frameworks while addressing the ethical, privacy, and computational challenges inherent in modern cognitive defense.

Keywords: E-Government Security, Artificial Intelligence (AI), Machine Learning (ML), Cyberattack Detection, Deep Learning, Public Infrastructure Protection, Zero-day Vulnerabilities, Anomaly Detection.

1. Introduction

The contemporary era of public administration is defined by the transition from "Electronic Government" to "Cognitive Government." Today, E-Government platforms are not merely informational websites but mission-critical infrastructures that manage national identity, healthcare systems, tax portals, and social welfare distribution. In this highly interconnected environment, digital data has become the most valuable national asset, and its protection is a fundamental pillar of national sovereignty and public trust.

However, as noted by **IBM (2026)**, the global landscape of cyber threats has undergone a radical evolution. Adversaries are now utilizing automated "Botnets" and generative AI to scan government networks for vulnerabilities at a speed that human analysts cannot match. Traditional security frameworks, such as standard Firewalls and Intrusion Detection Systems (IDS), are predominantly "reactive." They rely on a database of known "signatures"—essentially fingerprints of past viruses. This means that when a completely new attack, known as a "Zero-day exploit," occurs, the traditional system remains blind until the signature is manually updated.

Artificial Intelligence (AI) introduces a proactive paradigm shift. By utilizing algorithms that can learn from historical network traffic and identify subtle behavioral anomalies, E-Government systems can detect threats in real-time, often before the actual breach occurs. This paper explores the transition from traditional, manual security operations to AI-driven "Self-Healing" networks, analyzing how specific machine learning architectures can be deployed to safeguard the digital future of the state against an increasingly hostile and automated cyber landscape.

2. Literature Review

2.1 The Vulnerability Gap in Public Sector Digital Infrastructure

The academic landscape regarding E-Government security has shifted focus toward the "Legacy Gap" problem. **Abdullayeva (2025)** argues that public sector systems are uniquely vulnerable because they often run modern front-end web services on top of outdated back-end databases and legacy mainframe systems. This architecture creates "security silos" where data moves between different levels of protection, making it easy for hackers to exploit the weakest link. Her research emphasizes that AI is the only technological bridge capable of providing a unified, real-time security view across these fragmented systems. Furthermore, reports from the **NCSC (2023)** indicate that as government services migrate to multi-cloud environments, the "attack surface" expands exponentially. This necessitates an intelligent layer that can monitor cross-departmental data flows for signs of "Lateral Movement," where a hacker enters through a low-security portal to reach a high-security database.

2.2 Algorithmic Optimization and Adaptive Security Architectures

Recent studies by **Jha & Jha (2024)** focus on the transition from "Static Defense" to "Adaptive Security." They contend that because modern E-Government portals handle millions of requests per second, manual monitoring is statistically and physically impossible for human teams. Their research proposes an "Adaptive AI Framework" where the security model retrains itself every 24 hours based on new global threat telemetry. This concept is strongly supported by **Google Cloud (2025)**, which highlights the role of "Cloud-Native AI" in protecting high-velocity data migration. By using AI to automate the process of "Threat Hunting," government agencies can shift from a reactive "Defense-in-Depth" model to a proactive "Intelligence-Driven" model. This allows the system to anticipate attacks based on subtle pre-attack reconnaissance patterns that traditional filters typically ignore.

2.3 The Technical Shift from Machine Learning to Deep Learning Neural Networks

The literature provided by **Gorgadze (2025)** and **Alam et al. (2026)** examines the profound technical evolution from basic Machine Learning (ML) to advanced Deep Learning (DL). Early ML models, such as basic decision trees or linear regression, required human experts to perform "feature engineering" the process of manually identifying which parts of the data were important for detecting a virus. However, modern Deep Neural Networks (DNN) can ingest raw, unstructured network packets and automatically discover hidden correlations and non-linear patterns that signify a sophisticated attack. **Essert (2025)** demonstrates that this automation has reduced the "Mean Time to Respond" (MTTR) by over 60% in public sector agencies. This suggests that as cyber threats become more complex and AI-powered, the reliance on high-dimensional Deep Learning models will become the absolute standard for national digital defense.

3. Methodology

3.1 Data Source and Pre-processing

For the purpose of this simulation, we utilized a combination of the **NSL-KDD dataset**—a benchmark for intrusion detection—and real-time anonymized logs from a simulated government cloud environment. The raw data underwent three critical phases:

1. **Cleaning:** Removal of duplicate entries and null values to prevent model bias.
2. **Feature Selection:** We identified 42 key features, including packet duration, protocol type, service, and source/destination bytes.

3. **Normalization:** Data was normalized to ensure model stability using the following formula:

$$z = \frac{x - \mu}{\sigma}$$

Where x is the raw value, μ is the mean, and σ is the standard deviation.

3.2 Detailed Analysis of Selected Algorithms

1. **Random Forest (RF):** An ensemble method that operates by constructing a multitude of decision trees ($T_1, T_2, \dots, T_n$). The final classification is determined by the majority vote:

$$Y = \text{mode}\{T_1(x), T_2(x), \dots, T_n(x)\}$$

This model is particularly effective for e-government because it handles categorical data (like IP addresses and protocol types) exceptionally well.

2. **Support Vector Machines (SVM):** This algorithm seeks the optimal hyperplane that maximizes the margin between classes:

$$f(x) = \text{sign}(w * x + b)$$

SVM is used to create a clear boundary between "Normal" citizen traffic and "Malicious" bot traffic.

3. **Deep Neural Networks (DNN):** Utilizing multiple hidden layers to map complex inputs to security alerts using activation functions like ReLU (Rectified Linear Unit):

$$f(x) = \max(0, x)$$

DNNs are capable of detecting "Encrypted Malware" by analyzing the timing and size of packets without needing to decrypt the content.

4. Simulation and Results

The simulation involved exposing the AI models to 10,000 diverse attack scenarios over a 30-day period.

4.1 Experimental Environment and Simulation Setup

The reliability of any AI-driven security model depends heavily on the quality of the simulation environment. In this research, we constructed a high-fidelity cloud-based architecture that emulates the network traffic of a typical national E-Government portal. The infrastructure was designed to handle a mixed traffic flow of 70% legitimate citizen requests (HTTP/HTTPS, database queries) and 30% malicious actor interventions.

The experimental setup utilized a high-performance computing cluster (HPC) with NVIDIA Tesla GPUs to facilitate the rapid training of the Deep Neural Network (DNN). The dataset used for this simulation was the **NSL-KDD benchmark**, supplemented by synthetic logs generated by modern penetration testing tools. This combined dataset contained 125,973 records with 42 independent variables. To ensure the model's robustness and eliminate statistical bias, we implemented a **10-fold cross-validation** technique, where the data is divided into ten subsets, and the model is trained and tested ten times, rotating the test set in each iteration.

4.2 Comparative Performance Evaluation and Metric Analysis

In the second phase of the simulation, we compared our proposed Deep Learning (DNN) model against three other benchmarks: a traditional Signature-based IDS, a Random Forest (RF) classifier, and a Support Vector Machine (SVM). The evaluation was conducted using four primary metrics:

- **Accuracy:** The overall rate of predictions.
- **Precision:** The ability of the model to not label a legitimate user as a threat.
- **Recall:** The ability of the model to find all actual threats (critical for preventing breaches).
- **F1-Score:** The harmonic balance between Precision and Recall.

Table 1: Comprehensive Performance Evaluation of Cybersecurity Models

Evaluation Metric	Legacy IDS	Random Forest	SVM	Deep Learning (DNN)
Global Accuracy (%)	61.42	92.15	89.50	98.24
Precision (%)	58.70	93.41	90.25	98.88
Recall / Sensitivity (%)	63.25	90.82	88.74	97.62
F1-Score (%)	60.91	92.10	89.49	98.25
Mean Response Time (ms)	580.4	125.2	180.7	38.1
Training Time (sec)	N/A	45.2	82.5	1240.0

Detailed Analysis of Table 1: The empirical data presented in Table 1 confirms a significant technological leap. While the Legacy IDS provides a mediocre accuracy of 61.42%, it is virtually useless against modern, evolving threats. The transition to AI-driven models immediately pushes accuracy above 90%. However, the **Deep Learning (DNN)** model stands out with an unprecedented **98.24% accuracy**. Most notably, the "Mean Response Time" for the DNN is only **38.1 milliseconds**, which is nearly 15 times faster than the traditional system. This sub-50ms response time is the "Golden Standard" for real-time E-Government security, ensuring that malicious packets are dropped at the perimeter before they can reach the internal server-side logic.

4.3 Analysis of Attack-Specific Detection and Resilience

E-Government platforms are not hit by a single type of attack; they face a "multi-vector" landscape threat. In this sub-section, we analyze the resilience of each algorithm against specific categories of cyber-attacks that are most prevalent in the public sector.

Table 2: Detection Rate (%) by Attack Taxonomy

Attack category	Legacy IDS	Random Forest	SVM	Deep Learning (DNN)
DDoS / Flooding	72.15	94.50	92.05	99.42
Phishing/Impersonation	45.00	88.22	85.40	96.85
SQL Injection / XSS	55.42	91.05	89.12	97.50
U2R (User to Root) Escalation	12.50	76.80	70.15	88.94
Zero-Day Exploits (Unknown)	0.00	35.62	22.40	91.22

Detailed Analysis of Table 2:

The most critical takeaway from Table 2 is the performance regarding **"Zero-Day Exploits."** Traditional systems rely on signatures, hence their 0.00% detection rate for unknown threats. Machine learning models like Random Forest show some capability (35.62%) but still struggle with high uncertainty. In contrast, the **Deep Learning (DNN) model identified 91.22% of Zero-Day attacks**. This is achieved because the DNN does not look for "what the virus looks like," but rather "how the network behaves."

Furthermore, in **DDoS (Distributed Denial of Service)** scenarios—which are the most common attacks on government portals—the DNN reached a near-perfect detection rate of **99.42%**. This level of resilience ensures that even during a massive, coordinated attack, the E-Government services (such as ASAN or Tax portals) remain accessible to legitimate citizens, maintaining social stability and administrative continuity.

5. Discussion

The simulation outputs yield several critical insights that challenge current paradigms in information security investment. This section contextualizes the findings within the broader literature and outlines their theoretical and managerial implications.

5.1. Interpretation of the Superiority of Deep Learning in Public Infrastructure

The results obtained from the simulation provide conclusive evidence that Artificial Intelligence, particularly Deep Neural Networks (DNN), fundamentally alters the security landscape of E-Government services. The transition from an accuracy of 61.42% (Legacy IDS) to 98.24% (DNN) is not merely a quantitative improvement; it represents a qualitative shift in how digital sovereignty is maintained. The primary reason for this superiority lies in the "feature hierarchy" that Deep Learning models construct. Unlike Random Forest or SVM, which may struggle with the high dimensionality of global network traffic, DNNs utilize multiple hidden layers to identify non-linear relationships between packet arrival times, payload sizes, and header metadata.

In the context of E-Government, this means the system can distinguish between a "Flash Crowd" (a legitimate spike in traffic, such as citizens rushing to check exam results or tax deadlines) and a "DDoS Attack" (a malicious flooding attempt). Traditional systems often fail in these scenarios, leading to high False Positive Rates that block innocent citizens. Our findings show that AI reduces this error rate to below 1%, ensuring that public services remain accessible and reliable, which is a critical factor for maintaining public trust in digital state institutions.

5.2. The Emergence of Adversarial AI and the "Arms Race"

While the technical results are promising, the discussion must address a rising threat identified in recent reports from **NCSC (2023)** and **IBM (2026)**: the phenomenon of **Adversarial Machine Learning**. As governments adopt AI for defense, cyber-adversaries are simultaneously deploying AI to conduct automated reconnaissance and exploit discovery. This creates a "Cat-and-Mouse" game or a digital arms race.

Adversarial attacks involve "poisoning" the training data or creating "evasion samples"—malicious packets designed with minor, invisible perturbations that trick the AI into classifying them as "Normal." For instance, a hacker could slightly alter the timing interval of an SQL injection attack to mimic a slow, legitimate database query. Our study suggests that to counter this, E-Government systems must move beyond "Static AI" and adopt "Moving Target Defense" (MTD) strategies. This involves constantly retraining models and using "Generative Adversarial Networks" (GANs) to simulate potential future attacks, thereby teaching the defensive AI to recognize even the most subtle deceptive patterns before they are deployed by attackers.

5.3. Ethical Governance, Transparency, and the "Black Box" Dilemma

A critical challenge discussed by **Fortinet (2025)** and **Gorgadze (2025)** is the inherent "Black Box" nature of Deep Learning. In a democratic E-Government framework, transparency and accountability are paramount. If an AI-driven security system automatically blocks a citizen's IP address or restricts access to a digital service, there must be a mechanism to explain that decision. Traditional logic-based systems are easy to audit, but a Neural Network with millions of weights and parameters does not offer an easy "explanation" for its output.

This leads to the urgent need for **Explainable AI (XAI)** in the public sector. The discussion highlights that for AI to be legally and ethically integrated into national security, it must be accompanied by "Interpretability Modules" that can translate complex algorithmic decisions into human-readable reports for security analysts. Furthermore, the massive data collection required to train these models raises significant privacy concerns. Governments must implement "Privacy-Preserving Machine Learning" techniques, such as **Federated Learning**, where the AI learns from decentralized data across different departments without ever actually seeing or storing the private personal information of individual citizens. This balance between "Total Security" and "Individual

Privacy" will be the most significant policy challenge for E-Government administrators in the coming decade.

6. Conclusion

The comprehensive analysis conducted in this research underscores a fundamental reality: the digital sovereignty of modern E-Government services is inextricably linked to the integration of advanced Artificial Intelligence. As public administration moves toward a "Cognitive Government" model, the volume and complexity of data being processed across national networks have surpassed the capacity of traditional, human-managed security frameworks. This study has empirically demonstrated that legacy, signature-based Intrusion Detection Systems (IDS) are no longer viable in an era characterized by polymorphic malware, state-sponsored cyber warfare, and AI-driven automated exploits.

The core contribution of this research lies in the comparative evaluation of machine learning architecture. Our simulation results provide a clear hierarchy of effectiveness, with **Deep Neural Networks (DNN)** emerging as the definitive gold standard. Achieving a 98.24% detection accuracy and a revolutionary response time of under 40 milliseconds, DNNs offer the only proactive solution capable of identifying "Zero-Day" vulnerabilities with a high degree of confidence. By shifting the defensive focus from "Known Threat Recognition" to "Behavioral Anomaly Detection," AI-driven systems empower government agencies to neutralize cyber threats at the reconnaissance stage, long before they can penetrate core databases containing sensitive citizen information.

However, the path toward a fully automated "Digital Fortress" is not without significant socio-technical hurdles. As this paper has discussed, the emergence of **Adversarial Machine Learning** represents a new frontier of risk, where the very models used for defense can be manipulated by sophisticated adversaries. Furthermore, the "Black Box" nature of deep learning necessitates a parallel evolution in **Explainable AI (XAI)**. For public trust to be maintained, government-managed AI must not only be effective but also transparent and ethically aligned with the privacy rights of the citizenry. The implementation of "Privacy-Preserving" techniques like Federated Learning is no longer a theoretical preference but a necessity to ensure that national security does not come at the cost of individual liberty.

In conclusion, the strategic roadmap for E-Government administrators must prioritize three key areas: first, the rapid migration from legacy security silos to centralized, AI-powered Security Operations Centers (SOC); second, the continuous retraining of defensive models using real-time global threat intelligence; and third, the development of robust legal and ethical frameworks to govern automated decision-making in the public sector. The future of the state is digital, and that digital future can only be secured through the intelligence, speed, and adaptability of Artificial Intelligence.

References

1. **Abdullayeva, N. (2025).** AI-Driven Threat Detection for Public Sector Systems. *World Journal of Innovation and Modern Technology*, 9(10), 231-254.
<https://iiardjournals.org/get/WJIMT/VOL.%209%20NO.%2010%202025/AI-Driven%20Threat%20Detection%20for%20Public%2031-254.pdf>
2. **Alam, S., Khan, M., & Rahman, A. (2026).** Application of AI in Cyberattack Detection: A Review. *PMC Articles*, PMC12986954. <https://pmc.ncbi.nlm.nih.gov/articles/PMC12986954/>
3. **Bobrovnikova, K. (2022).** Machine Learning Based Techniques for Cyberattacks Detection in the Smart City Infrastructure. *CEUR Workshop Proceedings*, 3156, 1-10. <https://ceur-ws.org/Vol-3156/paper31.pdf>
4. **Essert. (2025).** How AI is revolutionizing government cybersecurity. *Essert Digital Defense Insights*. <https://essert.io/how-ai-is-revolutionizing-government-cybersecurity/>
5. **Fortinet. (2025).** AI in Cybersecurity: Key Benefits, Defense Strategies, & Future Trends. *Fortinet Cyber Glossary*. <https://www.fortinet.com/resources/cyberglossary/artificial-intelligence-in-cybersecurity>
6. **Google Cloud. (2025).** Cloud CISO Perspectives: How governments can use AI to improve threat detection. *Google Security Blog*. <https://cloud.google.com/blog/products/identity-security/cloud-ciso-perspectives-how-governments-can-use-AI-improve-threat-detection>
7. **Gorgadze, N. (2025).** The Role of Artificial Intelligence in Detecting Cyberattacks. *Journal of Smart Cities and Society Applications*, 1(1), 1-15. https://journal.scsa.ge/wp-content/uploads/2025/10/0101_the-role-of-artificial-intelligence-in-detecting-cyberattacks.pdf
8. **IBM. (2026).** Safeguarding national & public infrastructure: AI-driven threat detection. *IBM Think Insights*. <https://www.ibm.com/think/insights/safeguarding-national-public-infrastructure-ai-driven-threat-detection>
9. **Jha, R., & Jha, S. (2024).** Optimizing E-Government Cybersecurity through Artificial Intelligence. *Transactions on Computer Science and Software Technology*, 6(1), 5.
<https://irojournals.com/tcsst/article/view/6/1/5>
10. **NCSC. (2023).** Case study: The cyber security of artificial intelligence. UK National Cyber Security Centre Annual Review. <https://www.ncsc.gov.uk/collection/annual-review-2023/technology/case-study-cyber-security-ai>

THE DIGITAL UNIVERSITY: CONCEPTUAL APPROACHES AND BIBLIOMETRIC ANALYSIS OF INTERNATIONAL AND KAZAKHSTANI RESEARCH

Tokhtar Bolatbek

DBA Student, Turan University

Juzbayeva Zhansaya

LMS and E-Learning Resources Administrator, Turan University

Zakirova Dilnara

PhD, Professor, Turan University

Abstract: This article examines the conceptual foundations of the digital university and analyzes the dynamics of international and Kazakhstani scholarly discourse on this topic. Based on a bibliometric analysis of the Web of Science (WoS) database covering the period 1974-2026 (a sample of 1,170,245 documents), the study identifies key publication trends, including sustained long-term growth (CAGR 2000-2024: 8.37%), a pandemic-related acceleration in 2019-2022 (CAGR 17.76%), and subsequent stabilization of growth dynamics. The Kazakhstani sub-corpus (1,812 documents) demonstrates a pronounced pedagogical focus, with 32.29% of publications classified under Education & Educational Research, compared to 12.20% in the global corpus. The study systematizes the thematic contributions of Kazakhstani scholars and formulates theoretical and practical implications for the development of digital universities in the Central Asian context.

Keywords: higher education, Kazakhstan, digitalization of education, digital transformation

1. Introduction

Digital transformation, currently permeating key spheres of social life, manifests most intensely in the higher education system, where the integration of advanced technologies is accompanied not only by technical renewal but also by a deep rethinking of the content, forms, and methodological foundations of the educational process. The conceptual apparatus of this field has developed gradually, reflecting the evolving understanding of the role of digital technologies in university operations. In the initial stage, researchers focused on individual e-learning tools - online courses (MOOCs, SPOCs, etc.), educational platforms, digital libraries, and other elements of digital infrastructure. Subsequently, the emphasis shifted from individual tools to issues of systemic management of digital processes: first, the concept of the “e-university” was formulated, followed by the more comprehensive notion of the “digital university,” implying end-to-end integration of digital technologies across all areas of university activity.

Despite the growing number of publications on this topic, several research gaps persist in the existing literature. In particular, the contribution of Kazakhstani researchers to the international discourse on the digital university has not yet been systematically analyzed. Moreover, the three-year post-pandemic period of 2022-2024, in terms of publication dynamics and transformation of the research agenda, remains insufficiently studied.

The aim of this article is to conduct a bibliometric analysis of publications in the Web of Science database to characterize global trends in the scholarly understanding of the digital university concept, to determine the place of Kazakhstani research in the international academic

discourse, and to address the identified research gaps. The study addresses the following questions: the dynamics of publication activity on the topic of digital transformation of higher education in the Web of Science database for the period 1974-2026; the structural characteristics of the global publication corpus, including document types, subject categories, and geographic distribution; and the contribution of Kazakhstani researchers to the formation of the international scholarly discourse on the digital university.

2. Literature review

Scholarly reflection on digitalization has a longer history than is commonly assumed: the first references to the use of digital technologies in education date back to the early 1970s. For a long time, digitalization was understood primarily as a technical process - the conversion of data into electronic format - what today is referred to as "digitization." Professor M. Vitali-Rosati of the University of Montreal characterizes this threshold as the emergence of a fundamentally new world - after the advent of digital technologies [1]. It is precisely this shift that marks the transition from a narrowly technical understanding of the process to a broad concept of digital transformation encompassing not only the technological, but also the organizational, cultural, and pedagogical dimensions of university life.

Linguistic analysis reveals a parallel conceptual shift. According to the Russian National Corpus, in the 1990s, the adjective "digital" was predominantly used with material objects ("digital camera", "digital terminal", and similar expressions). By 2018-2019, the term had become firmly established in combination with abstract concepts: "digital strategy," "digital space," "digital transformation" [2]. This trend reflects not only lexical development but also a real change in the practices of implementing digital technologies in organizations. Contemporary research interprets the concept of "digital" broadly, encompassing changes in the content, structure, and organization of the educational process, as well as the formation of new principles of interaction within the organization and the university.

Researcher at the Royal College of Art and the European Academy of Design, Dr. S. Bofylatos (RCA Royal College of Art and European Academy of Design) describes digital transformation as a "multifaceted metamorphosis at the intersection of technology, society, and economy" - a dynamic process of integrating contemporary technological solutions into organizational structures, opening new opportunities within an interconnected ecosystem of participants. Crucially, the author emphasizes that technologies serve as a catalyst, not the ultimate goal of transformation: genuine change occurs when digital tools become organically embedded in the organizational culture, fostering innovative thinking and process optimization [3]. This position resonates with the approaches of Kazakhstani researchers. T.O. Balykbayev, E.Y. Bidaibeykov, and V.V. Grinshkun were among the first to raise the question of building a digital university, developing proposals and approaches to the use of digital technologies across the multifaceted activities of a pedagogical university, using Abai KazNPU as a case study [4]. In turn, T.O. Balykbayev and N.A. Kurmangaliyeva examine the model of a digital educational environment of a university in the context of the transition to the era of the Fifth Industrial Revolution [5]: according to this concept, technologies do not replace humans but augment human potential, ensuring harmonious human-machine interaction. In the Kazakhstani institutional context, these ideas are reflected in the Addresses of the Head of State K.-J. Tokayev [6].

From the perspective of the drivers of transformation, A.A. Safonov and M.A. Safonova highlight the importance of the readiness of the new generation of learners - so-called "digital natives," or the "net generation" - in the use of digital technologies as a key social driver of change in the university environment [7]. At the same time, the intensification of global competition among universities is making digital competencies an increasingly significant factor in the international competitiveness of institutions: according to World Economic Forum reports, the

competitiveness of a national economy is determined by a set of institutions, policy measures, and factors affecting productivity levels - and the digital readiness of universities occupies an increasingly prominent place in this set [8].

3. Data and methodology

In this article, in order to identify relevant publications, a search strategy using Boolean operators was applied, incorporating keywords and phrases related to the topic of digital transformation in higher education: “digital transformation” OR “digitalization” OR “digitization” OR “digital maturity” AND “higher education” OR “universities” OR “university.” The strategy was developed by researchers at the Vietnam National University, T.M.N. Luu, P.M. Nguyen, X.H. Nghiem, and V.T. Dinh [9]. Unlike the original study, which used the Scopus database, the present analysis is based on data from the Web of Science (WoS). The search was conducted twice: in November 2025 and in March 2026, which made it possible to capture indexing dynamics and compare data from two time points. The total WoS corpus comprised 1,170,245 documents; when applying the “Country: Kazakhstan” filter - 1 812 documents.

To quantitatively assess long-term trends, the Compound Annual Growth Rate (CAGR) was calculated using the formula:

$$CAGR = \left(\frac{V_{final}}{V_{begin}} \right)^{\frac{1}{t}} - 1 \quad (1),$$

where V_{begin} is the number of publications in the initial year of the period;

V_{final} is the number of publications in the final year;

t is the duration of the period in years.

Calculations were performed in Google Sheets. Data for 2025-2026 were excluded from the CAGR calculation as preliminary due to ongoing indexing. The analysis of the publication corpus structure included an examination of document types, subject categories (WoS Subject Categories), and geographic distribution of publications.

4. Results and discussion

The obtained results confirm the exponential growth of scholarly interest in the digital transformation of higher education. According to Web of Science data (Figure 1), the earliest publications indexed in the database date back to 1974 (three documents), which is consistent with earlier evidence indicating that academic reflection on the use of digital technologies in education began in the early 1970s. Over the subsequent two decades, growth remained slow and gradual, with fewer than 15,000 publications annually until the early 2000s. Since the 2000s, the rate of publication has steadily increased.




Figure 1. Publication trends on the topic “Digital University” in the Web of Science database, 1974-2025 (search conducted on March 29, 2026)

A comparison of the two search time points - November 2025 and March 2026 - reveals a critically important indexing pattern. In November 2025, the figure for 2025 stood at 71,048 entries, while the 2022 data showed – 86,450 documents; against this backdrop, an impression of slowing growth rates could have formed. However, the March 2026 data radically changed the picture: the 2025 figure rose to 94,415 publications, and the 2022 and 2024 data were also revised upward (Figure 2). This significant increase is explained by the specifics of WoS indexing - a significant proportion of publications enter the database with a delay of several months after publication. This methodologically important observation must be taken into account when interpreting “current” indicators.




Figure 2. Comparison of publication counts on the topic “Digital University” in the Web of Science database for 2020-2025 based on data retrieved in November 2025 and March 2026

The sustained growth observed over more than two decades makes it possible to apply quantitative analytical tools. The results of calculating the compound annual growth rate (CAGR) for key periods are presented in Table 1.

Table 1 - Key periods of publication growth (WoS) and CAGR calculations

	Period	V_begin	V_final	t (years)	CAGR	Description
		A	B	C		
1	2000-2024 (long-term)	12,616	86,748	24	8.37%	Baseline growth
2	2010-2024 (main period)	27,539	86,748	14	8.54%	Sustained growth
3	2015-2019 (pre-pandemic)	38,932	53,052	4	8.04%	Stable pace
4	2019-2022 (pandemic surge)	53,052	86,636	3	17.76%	Sharp acceleration
5	2022-2024 (post-pandemic stabilization)	86,636	86,748	2	0.06%	Saturation

Note. Compiled by the author based on WoS data as of March 2026. CAGR was calculated in Google Sheets using the formula $= (B1/A1)^{(1/C1)} - 1$ based on Web of Science data (search date: 29.03.2026). Data for 2025-2026 were excluded from the calculation as preliminary.

The results obtained allow us to identify three qualitatively distinct phases in the development of this research area. The first - the accumulation phase (up to 2019) - is characterized by a stable CAGR of approximately 8%, comparable to overall scientific output growth. The second - the pandemic phase (2019-2022) - is marked by a sharp acceleration to 17.76% per year: the COVID-19 pandemic acted as a structural break, moving digital transformation of universities from the realm of strategic agenda to that of urgent institutional practice. The third - the stabilization phase (2022–2024) - with a CAGR of 0.06% indicates not a loss of interest but rather the saturation of the initial publication impulse and a transition toward qualitative systematization of accumulated knowledge. Notably, 2025 shows 94,415 publications - the highest value in the entire observation history, refuting the hypothesis of the “fading” of this research topic.

In the global WoS corpus, journal articles (Article) dominate, accounting for 74.68% of the total. Conference proceedings (Proceeding Paper) account for 18.10%, reflecting high event activity in related fields. Review articles (Review Article) constitute 2.70% - an indicator of sufficient accumulation of primary research requiring systematization (Table 2).

Table 2 - Document Types in WoS

Document Type	Count	Share, %
Article	874 003	74.68
Proceeding Paper	211 749	18.10
Review Article	31 604	2.70
Editorial Material	27 962	2.39
Meeting Abstract	21 833	1.87
Book Chapters	18 585	1.59
Book Review	15 145	1.29
Early Access	14 707	1.26
Other	6 781	0.58

Note: Total percentages may exceed 100% due to dual classification of some documents.

Across thematic categories, Education & Educational Research ranks first, accounting for 12.20% of the global dataset. The second and third positions are held by medical (Medicine,

General & Internal - 4.72%) and engineering (Engineering, Electrical & Electronic - 3.60%) disciplines, reflecting the broad application of the concept of digitalization beyond the education sector. In the Kazakhstani sub-corpus (1,812 documents), the dominance of the pedagogical focus is considerably more pronounced: Education & Educational Research accounts for 32.29%, which is nearly three times higher than the global share.

Based on WoS data, a geographical distribution analysis was also conducted. The United States is the undisputed leader (268,802 documents; 22.97%), more than doubling China (145,453; 12.43%). England ranks third (66,422; 5.67%) (Table 3).

Table 3 - Geographic distribution of publications in WoS (top 10 countries and Kazakhstan)

Country	Documents	Share, %
USA	268,802	22.97
China	145,453	12.43
England	66,422	5.67
Germany	62,371	5.33
Spain	49,002	4.19
Canada	42,652	3.64
Italy	42,243	3.61
Australia	41,682	3.56
Japan	39,655	3.39
Brazil	28,416	2.43
...		
Kazakhstan	1,812	0.15

Source: Web of Science, search date: 29.03.2026

Kazakhstan, with 1,812 documents, is among the countries actively building research capacity in the field of digital transformation of education. The concentration of publications in the “Education & Educational Research” category (32.29%) reflects the clearly expressed pedagogical focus of the Kazakhstani academic community.

Having identified the sectoral and geographic structure of the publication corpus, it is appropriate to proceed to the analysis of the thematic content of Kazakhstani research. For a more detailed examination of the research agenda of Kazakhstani authors, a bibliometric co-occurrence analysis of keywords was conducted using VOSviewer software. The visualization was performed based on a sample of Web of Science publications comprising 1,812 documents affiliated with Kazakhstani researchers. This approach allows for the identification of the thematic structure of research, the determination of key directions of scholarly discourse, and the establishment of relationships between the main research themes (Figure 3).




Figure 3. Co-occurrence network of keywords in publications of Kazakhstani authors on digital transformation of higher education

The visualization results show that the central place in the Kazakhstani research space is occupied by concepts related to higher education and digital transformation, including higher education, Kazakhstan, education, university, and digital transformation. Around this core, several stable thematic clusters emerge, reflecting the main directions of scholarly research. One cluster brings together works devoted to digital transformation of education and the introduction of new technologies, including digitalization, artificial intelligence, machine learning, big data, and Industry 4.0. Another cluster relates to research on the consequences of the COVID-19 pandemic, online learning, and issues of students' psycho-emotional well-being, including COVID-19, online learning, mental health, well-being, and academic performance. A separate direction is formed by research on digital educational technologies and pedagogical practices, including e-learning, blended learning, curriculum, competence, and training. A cluster related to the internationalization of higher education and academic mobility is also distinguished, represented by the terms internationalization, study abroad, and academic writing.

The results indicate the dominance of digital transformation of higher education in Kazakhstani research discourse, as well as the expansion of the thematic field through research on pedagogical technologies, pandemic consequences, and the internationalization of the educational space.

The overlay visualization of keyword co-occurrence allows for tracing the temporal dynamics of Kazakhstani research development (Figure 4).



on digital transformation of higher education

Earlier publications focus on issues of distance learning, pedagogical practices, and the structure of university education. In the subsequent period, research interest shifts to online learning and the impact of the COVID-19 pandemic on the educational process and students' psycho-emotional well-being. The most recent research directions relate to digital transformation of higher education, the introduction of artificial intelligence technologies, machine learning, Industry 4.0, as well as issues of sustainable development and student motivation formation. The results indicate a shift in Kazakhstani scholarly discourse from the study of distance learning toward a broader consideration of digital transformation of higher education.

The totality of the results obtained allows for the formulation of several generalizing observations. First, the identified exponential growth in publication activity with a pronounced acceleration during the pandemic period confirms that COVID-19 acted not so much as an independent cause but rather as a catalyst for digital transformation processes in higher education that had been forming over the preceding decade. The mass transition to distance learning in 2020 activated the accumulated technological potential of universities and created a large-scale experimental environment for testing digital educational solutions, which was reflected in a sharp increase in the number of studies on this topic.

Second, the post-pandemic stabilization of publication activity while maintaining high absolute values indicates a transition of scholarly discourse to the stage of conceptual understanding of university digital transformation. This is manifested in the expansion of research topics to include issues of artificial intelligence integration, digital competencies, sustainable development, and systemic modernization of the educational environment, as confirmed by the results of keyword co-occurrence analysis and their temporal dynamics.

Third, the more pronounced pedagogical focus of the Kazakhstani sub-corpus compared to the global corpus reflects the specifics of the national research agenda and the dominance of

works devoted to the digitalization of the educational process and the development of digital educational technologies. The keyword visualization results show that Kazakhstani research concentrates around issues of digital transformation of higher education, online learning, competency formation, and the introduction of artificial intelligence technologies. This thematic orientation indicates the formation of a stable research direction aimed at developing models of the digital university adapted to the regional conditions and characteristics of the Kazakhstani higher education system.

5. Conclusion

The study allows for the formulation of the following key conclusions. Publication activity dynamics based on WoS data confirm sustained long-term growth in the topic of digital transformation of higher education (CAGR 2000-2024: 8.37%), with a pronounced pandemic-driven acceleration in 2019-2022 (CAGR 17.76%) and subsequent stabilization in 2022-2024 (CAGR 0.06%). The growth of 2025 figures to 94 415 publications - the highest value for the entire observation period - refutes the hypothesis of the “fading” of this topic and confirms its stable institutionalization in the international scholarly discourse.

A consensus has formed in the academic community regarding the multi-level nature of university digital transformation: it is not reducible to technological infrastructure renewal but implies systemic changes in pedagogical approaches, organizational culture, and strategic management. The concept of technologies as a catalyst, rather than an end goal of transformation, has gained wide recognition in the research community.

The theoretical significance of the study is related to the verification of the applicability of the Luu et al. [9] search strategy to the WoS database and the demonstration of the importance of dual data retrieval for the correct interpretation of indexing dynamics. An additional result is the systematization of the Kazakhstani contribution, including an analysis of the thematic structure and temporal dynamics of research, which creates a foundation for establishing regional research consortia and increasing the international visibility of national science.

The present analysis is limited to the WoS database, which does not allow for a comprehensive picture of the publication landscape. It should be noted that the applied search strategy, by covering a wide range of related topics (medicine, engineering, etc.), includes publications only indirectly related to the digital university; a narrower strategy may yield different quantitative results. Furthermore, the content analysis of Kazakhstani publications is primarily descriptive and does not include in-depth content analysis, which defines directions for further research.

6. References

1. Vitali-Rosati Marcello Digital culture, philosophy and metaontology. 2012. [website]. - URL: <https://www.semanticscholar.org/paper/Digital-culture%2C-philosophy-and-metaontology-Rosati/9cd95b315445c1342e00f4d383d5ff146006d9b7> (accessed: 16.11.2025).
2. Uchaikina, E.V. “The Digital University in the Russian Language in the Context of Analog and Digital Reality.” // Current Issues of Modern Philology and Journalism. 2021. No. 3 (42). Pp. 91-98. [website]. - URL: <https://cyberleninka.ru/article/n/tsifrovoy-universitet-v-russkom-yazyke-v-kontekste-analogovoy-i-tsifrovoy-realnosti> (accessed: 17.11.2025).
3. Bofylatos, S. Digital Transformation. European Academy of Design. - 2022.
4. Khrustaleva, N.V. Conceptualization of the Concept of “Digital University” // Bulletin of the Altai Academy of Economics and Law. 2024. No. 22 (5-1). Pp. 147-152; DOI: <https://doi.org/10.17513/vaael.3426> [website]. - URL: <https://vaael.ru/ru/article/view?id=3426> (accessed: 10.08.2025).

5. Balykbayev, T.O., Kurmangaliyeva, N.A. Model for the Formation of a Digital Educational Environment of a University // Informatization of Education: Theory and Practice. Proceedings of the International Scientific and Practical Conference in Memory of Academician of the Russian Academy of Education M.P. Lapchik. Omsk, 2023. Pp. 10-13. [website]. - URL: <https://elibrary.ru/item.asp?id=61747419> (accessed: 14.07.2025)
6. Address of the Head of State Kassym-Jomart Tokayev to the People of Kazakhstan “A Fair State. A United Nation. A Prosperous Society.” [website]. - URL: <https://www.akorda.kz/ru/poslanie-glavy-gosudarstva-kasym-zhomarta-tokaeva-narodu-kazahstana-181130> (accessed: 16.11.2025)
7. Safonov, A.A., Safonova, M.A. Digital Transformation of Education: Textbook and Practicum for Universities. - Moscow: Yurait Publishing House, 2025. - 100 p. - (Higher Education). - ISBN 978-5-534-21363-8 // Yurait Educational Platform [website]. - URL: <https://urait.ru/bcode/569813> (accessed: 17.03.2025).
8. International competitiveness of the national economy - a set of institutions, policy measures, and factors determining a country's level of productivity [World Economic Forum, 2016] <https://www.weforum.org/meetings/world-economic-forum-annual-meeting-2016/> (accessed: 10.08.2025).
9. Luu, T.M.N., Nguyen, P.M., Nghiem, XH. et al. A bibliometric analysis of digital maturity and digital transformation at universities. Discover Sustainability 6, 646 (2025). <https://doi.org/10.1007/s43621-025-01527-9> - URL: <https://rdcu.be/eQuJ6> (accessed: 10.08.2025).

ВЛИЯНИЕ НАЛОГОВЫХ СТИМУЛОВ НА ЭКОНОМИЧЕСКОЕ ПОВЕДЕНИЕ ДОМАШНИХ ХОЗЯЙСТВ

Топшахова Гульмира Райхановна

Докторант 1 курса специальности Экономика, КарНИУ им. Е.А.Букетова

Куттыбаева Нургуль Болатовна

PhD, ассоциированный профессор кафедры, Экономики и международного бизнеса
КарНИУ им. Е.А.Букетова

Ламбекова Айгерим Нурлановна

PhD, ассоциированный профессор кафедры, Бухгалтерского учета и аудита, КарНИУ
им. Е.А.Букетова

В контексте трансформации глобальных налоговых систем и поиска оптимального соотношения между обеспечением фискальной устойчивости и стимулированием экономической активности особую актуальность приобретает изучение поведенческих эффектов налоговых реформ на уровне физических лиц. Для стран с развивающейся экономикой, включая Республику Казахстан, процессы модернизации налоговой системы сопровождаются внедрением цифровых решений в администрировании и расширением спектра налоговых преференций. Это обуславливает необходимость комплексной оценки влияния налоговой политики не только на бюджетные показатели, но и на модели экономического поведения населения, что определяет научную и прикладную значимость исследования.

Научная новизна работы состоит в системном анализе воздействия налоговых стимулов на дифференцированное поведение домохозяйств с опорой на актуальные эмпирические исследования за 2010–2025 годы. В отличие от преобладающих в литературе подходов, ориентированных на развитые страны, в исследовании предпринята адаптация международного опыта к институциональным и социально-экономическим условиям Казахстана. Обоснована целесообразность учета таких параметров, как уровень ликвидности домохозяйств, доступность информации и степень доверия к институтам при разработке налоговых льгот. Предлагается подход к таргетированию налоговых стимулов, направленный на повышение общественного благосостояния через учет поведенческих факторов.

Теория общественных финансов предполагает, что налогоплательщики рационально реагируют на изменения налоговой нагрузки, максимизируя полезность. Снижение предельных ставок индивидуального подоходного налога влияет на предложение труда через эффект замещения и эффект дохода [1]. Снижение налоговой нагрузки обычно приводит к увеличению официальной занятости, но не всегда сопровождается значительным увеличением рабочего времени. Это демонстрирует ограниченную гибкость предложения труда в отношении налогов. Современные эмпирические исследования показывают, что эластичность предложения труда для основной группы занятых остается относительно низкой, а среди вторичных работников наблюдается выраженная реакция [2].

Налоговые льготы и вычеты оказывают значительное влияние на потребительское поведение физических лиц по сравнению с изменением базовых налоговых ставок. Целевые налоговые стимулы, направленные на поддержку социально значимых расходов, таких как образование, здравоохранение и покупка жилья, особенно эффективны. Временное

налоговое стимулирование способствует краткосрочному росту потребления, а постоянные изменения в налоговой политике влияют на долгосрочные решения домохозяйств.

В последние годы активно изучается влияние временного налогового стимулирования на потребление. Анализ программы Child Tax Credit в США показал, что получение авансовых платежей сопровождается ростом текущих расходов домохозяйств, особенно среди малоликвидных групп[3]. Это подтверждает гипотезу о важности поведенческих факторов и ограниченной рациональности в формировании потребительских решений.

Отдельное направление исследований связано с налоговым администрированием. Современные работы подчеркивают, что повышение добровольного соблюдения налогового законодательства достигается не только за счет усиления контроля, но и за счет цифровизации администрирования, упрощения процедур и повышения прозрачности [4].

С 2026 года в Республике Казахстан вступил в силу новый Налоговый кодекс, который существенно изменил систему налогообложения физических лиц. в частности, вместо ранее действовавшей плоской ставки ИПН (10 %) введена прогрессивная шкала индивидуального подоходного налога: доходы до 8500 минимального расчетного показателя (МРП) облагаются налогом по ставке 10%, а на сумму, превышающую этот предел - по ставке 15%. К дивидендам применяется такой же прогрессивный подход: до 230 000 МРП - ставка 5%, к превышению - свыше 15%. Эти изменения направлены на снижение налогового бремени для малообеспеченных и среднеобеспеченных групп и повышение справедливости налоговой системы.

Кроме того, пересмотрена система налоговых льгот и вычетов. Вместо многих целевых вычетов (образование, медицинские услуги, проценты по ипотеке ит.д.) был введен единый базовый стандартный вычет, который рассчитывается как фиксированная сумма в размере 30МРП. Также с 2026 года выплаты из Единого накопительного пенсионного фонда (ЕНПФ), в том числе единовременные пенсионные выплаты, освобождены от ИПН для резидентов Республики Казахстан[5]. Это изменение способствует увеличению располагаемого дохода пенсионеров и может стимулировать участие населения в накопительной пенсионной системе.

Поскольку развитие налогового контроля доходов и расходов физических лиц в направлении развития цифровой экономики является ключевым аспектом совершенствования налоговой системы, возникает необходимость использования современных инструментов налогового контроля для предупреждения бюджетных долгов и обеспечения справедливого распределения налогового бремени. Доказано, что совершенствование процессов налогового контроля в условиях цифровизации осуществляется за счет расширения использования информационных технологий, в частности, внедрения искусственного интеллекта и использования машинного обучения для выявления аномалий и подозрительных операций. Перспективным направлением развития налогового контроля является усиление информационного обмена между различными государственными ведомствами и финансовыми учреждениями с целью получения более полной информации о доходах и расходах физических лиц, сопоставления данных с декларированными доходами и выявления задолженности. Также можно ожидать повышения общего уровня прозрачности налоговой системы и повышения осведомленности граждан о цифровых возможностях налоговой службы РК.

Цифровизация администрирования и упрощение процедур взаимодействия с налоговыми органами остаются важным элементом налоговой политики, что способствует улучшению налоговой дисциплины и снижению транзакционных издержек для налогоплательщиков. В сочетании с прогрессивной системой ИПН и переработанных льгот

это создает условия для более сбалансированного воздействия налоговых стимулов на экономическое поведение физических лиц, чем предыдущая плоская система.

Внедрение прогрессивной шкалы ИПН в Казахстане соответствует мировой практике, реализованной в Германии, США и Швеция, где прогресс используется как инструмент перераспределения доходов при сохранении мотивации к труду. Опыт этих стран показывает, что умеренное повышение ставок для высокодоходных групп оказывает ограниченное влияние на предложение труда, но способствует снижению неравенства. Аналогами перехода к единым вычетам являются Эстония и Канада, где простота налоговой структуры повышает прозрачность и снижает административные расходы. Освобождение от пенсионных выплат, применяемых в Великобритании и Австралия, усиливает долгосрочные стимулы к накоплению и укрепляет доверие к системе сбережений. Цифровизация администрирования по модели способствует снижению затрат на соблюдение налогового законодательства Финляндии и Сингапура и росту добровольных выплат[6]. Кроме того, использование распространенных поведенческих инструментов в Великобритании и Соединенные Штаты, повышает налоговую дисциплину без изменения ставок. Международный опыт подтверждает, что эффективность налоговых реформ в совокупности определяется не только уровнем ставок, но и институциональным качеством системы. Это позволит сделать вывод о целесообразности комплексного подхода к реформированию ИПН в Казахстане с учетом поведенческих и административных факторов.

Таким образом, международный опыт показывает, что введение умеренной прогрессивной шкалы, унификация налоговых вычетов и цифровизация администрирования соответствуют современным тенденциям развития налоговых систем в странах ОЭСР. Практика Германии, США, Эстонии и Финляндии подтверждает, что сочетание прогрессивного налогообложения и институциональной прозрачности обеспечивает баланс между фискальной устойчивостью и поведенческими стимулами. Налоговые стимулы редко вызывают резкие изменения в экономическом поведении, но в долгосрочной перспективе могут корректировать решения домохозяйств. Актуальным направлением для Казахстана является развитие поведенческих инструментов налоговой политики и проведение микроэкономических исследований на основе административных данных.

Библиографический список

1. Mirrlees J. Tax by Design. Oxford: Oxford University Press, 2015.
2. Saez E., Slemrod J., Giertz S. The Elasticity of Taxable Income with Respect to Marginal Tax Rates: A Critical Review // Journal of Economic Literature. 2019. № 57(1). С. 3–50.
3. Baker S., Johnson S., Kueng L. The Consumption Response to Temporary Tax Incentives // Journal of Public Economics. 2022. № 210.
4. Luttmer E., Singhal M. Tax Morale // Journal of Economic Perspectives. 2018. № 28(4). С. 149–168.
5. New Tax Code of the Republic of Kazakhstan from 2026 // BPO.kz. – 27.08.2025. URL: <https://bpo.kz/en/news/nalogovyj-kodeks-rk-2026>
6. OECD. Tax Policy Reforms 2025: Inclusive Growth and Fair Taxation. OECD Publishing, 2025. URL: https://www.oecd.org/en/publications/tax-policy-reforms-2025_de648d27-en/full-report/tax-policy-reforms_c57e058c.html

Гала-балет как синтез искусства и маркетинга в арт-индустрии

Унербаева Мадина Куандыковна

Казахская национальная академия хореографии, г. Астана)

Жуматаева Айгуль Рахманиевна

к.э.н., доцент (Казахская национальная академия хореографии, г. Астана)

Аннотация: Статья посвящена гала-балету как междисциплинарному явлению на стыке искусства и маркетинга в современной арт-индустрии. Рассматривается его трансформация в многофункциональный культурный продукт, объединяющий классический балет, мультимедийные технологии и перформативные практики, а также роль бизнеса в его продвижении и расширении аудитории.

Ключевые слова: гала-балет, продюсирование, социальные сети, маркетинг, продвижение

Когда зритель впервые приходит в балет, восприятие полного спектакля может вызывать определённые сложности, связанные с многослойностью художественного языка, музыкальной драматургией и условностью сценического действия. В этой связи особую значимость приобретает формат гала-балета, который выступает как эффективная «входная точка» в мир хореографического искусства, позволяя в сжатой и доступной форме познакомиться с его лучшими образцами.

Гала-балет в арт-индустрии выступает не только как художественное событие, но и как эффективный инструмент культурного маркетинга, объединяющий эстетику высокого искусства и стратегии продвижения. Необходимость рассмотрения гала-балета обусловлена трансформацией форм потребления искусства, при которой зритель ориентируется на динамичные, визуально насыщенные и событийные форматы. Формат гала-концерта, предполагающий участие ведущих солистов, фрагментарность программы и зрелищность постановок, позволяет привлекать широкую аудиторию, формируя устойчивый интерес к балетному искусству. В условиях усиливающейся конкуренции за внимание зрителя гала-балет становится своеобразной точкой пересечения творчества и коммерции, где художественная ценность дополняется грамотным позиционированием, брендингом и медиаподдержкой.

Гала-балет, как разновидность дивертисментной программы, объединяет отдельные номера па-де-де, вариации, миниатюры, представляя наиболее выразительные фрагменты классического и современного репертуара. Такая концентрация художественно значимых элементов облегчает первичное восприятие и формирует устойчивый интерес к дальнейшему знакомству с балетом (1).

С развитием технологий многие скептики и футуристы предрекали снижение интереса к классическим видам искусства. Подобные дискуссии находят отражение и в публичных высказываниях современных медийных фигур, включая голливудского актёра Тимоти Шаламе (2).

Однако практика крупнейших театров мира фактически опровергает подобные прогнозы. Устойчивые аншлаги, рост интереса со стороны молодёжной аудитории и активная культурная повестка ведущих сцен свидетельствуют о высокой востребованности балетного искусства. Театры не только сохраняют зрителя, но и расширяют его, адаптируя

формы представления и коммуникации, в том числе через гала-балеты и современные форматы взаимодействия с аудиторией (2).

Это подтверждает, что роль искусства в жизни человека остаётся неизменно значимой: оно формирует эстетическое восприятие, помогает осмысливать действительность и открывает пространство для переживания прекрасного.

Знакомство с балетом представляет собой поэтапный процесс формирования эстетического опыта, в ходе которого зритель постепенно расширяет свои художественные предпочтения и углубляет понимание языка танца. В этом контексте гала-балет играет ключевую роль как доступный формат популяризации, способствующий привлечению новой аудитории (3).

В то же время балет остаётся динамично развивающейся системой, адаптирующейся к современным условиям при сохранении своих художественных принципов. Гала-балет, объединяющий традиционные и современные формы, выступает эффективным инструментом актуализации балетного искусства и его диалога с современным зрителем. Именно в этом контексте особую значимость приобретает понимание балета как части более широкой театральной системы.

Театр представляет собой целостную систему, функционирующую одновременно в трёх ипостасях: как вид искусства, как социальный институт и как производство. Каждая из этих ипостасей имеет свою цель, не вполне совпадающую с целями двух других. В то же время для их реализации необходима совокупность и взаимодействие всех трёх составляющих. Такое комплексное устройство театра позволяет глубже осмыслить место и роль балета внутри данной системы (4).

Балетный театр сегодня сохраняет свою значимость, выполняя важные культурные и социальные функции. Он способствует эстетическому воспитанию, формирует художественный вкус и приобщает к культурному наследию, передавая его будущим поколениям. Благодаря этому балет не только сохраняет традиции, но и активно участвует в формировании современного культурного пространства. Одновременно он оказывает глубокое эмоциональное и психологическое воздействие, помогая зрителю переживать и осмысливать общечеловеческие чувства.

Актуальность балета обусловлена его вневременной природой. Как искусство движения, он обладает языком, понятным вне культурных и исторических границ. Через пластику и музыку балет передаёт разные эмоции: любовь, радость, страдание, надежду, которые остаются неизменными на протяжении веков. Классические постановки при этом выступают не только как сценические произведения, но и как культурные артефакты, отражающие историческое развитие искусства.

Вместе с тем, в современных условиях особую значимость приобретает не только художественная, но и организационно-экономическая трансформация балета, проявляющаяся в формате гала-балет, который позволяет адаптировать классическое искусство к требованиям культурного рынка и запросам аудитории. Экономический и управленческий аспект определяет важность гала-балетов в казахстанском культурном пространстве: эти проекты стимулируют развитие событийной индустрии, вовлекают различные сегменты креативной экономики и способствуют формированию устойчивых моделей финансирования сценического искусства. Гала-балеты требуют комплексного проектного управления, что способствует развитию профессиональных компетенций в области культурного менеджмента и продюсирования (5).

В условиях современной культурной индустрии особое значение приобретает грамотное продвижение балетного искусства, позволяющее сохранить его актуальность и расширить аудиторию. В этом контексте гала-балет рассматривается не только как художественный формат, но и как конкурентоспособный культурный продукт.

Одной из ключевых задач маркетинговой стратегии гала-балет является его позиционирование как уникального культурного предложения, сочетающего традиции классического балета и современные формы сценического представления. В классическом понимании маркетинговая стратегия включает анализ целевой аудитории, формирование ценностного предложения и выбор эффективных инструментов коммуникации, направленных на установление устойчивого диалога со зрителем.

Стратегия позиционирования направлена на то, чтобы проект получил чёткое место в культурном пространстве, отличающееся от конкурентов, таких как сезонные спектакли, фестивали и другие балетные события. Позиционирование отражает ответ на вопрос «чем наш проект ценен для аудитории и почему он заслуживает внимания?» и именно оно станет основой для всех последующих маркетинговых шагов.

Одним из ключевых направлений в продвижении культурного проекта является работа с целевой аудиторией и коммуникативными каналами. Социальные сети, платформы для событий, такие как Facebook, Instagram и TikTok, дают возможность создавать специализированные страницы мероприятий, делиться визуальным контентом, историей подготовки, интервью с артистами и репетиционными материалами. Создание уникального контента не только повышает вовлечённость, но и увеличивает вероятность того, что публика станет активным распространителем информации. Контент-маркетинг как инструмент продвижения направлен на информирование и вовлечение аудитории через высококачественные публикации, статьи, видео и другие материалы, которые не выглядят как прямая реклама, но формируют доверие и интерес.

Цифровые стратегии могут включать также performance-маркетинг, ориентированный на достижение измеримых результатов, таких как продажи билетов или рост посещаемости страниц мероприятия. Такой подход предусматривает использование инструментов аналитики, таргетированной рекламы и оптимизации бюджета на основе показателей эффективности. Performance-маркетинг позволяет адаптировать рекламные сообщения в режиме реального времени и обеспечивать максимальную отдачу от каждой вложенной денежной единицы (6).

Важно не ограничиваться только цифровыми каналами. Для гала-балета существует потенциал привлечь внимание через традиционные методы коммуникации, такие как сотрудничество с местными СМИ, радио, печатные материалы в культурных изданиях, интервью с артистами и художественным руководством балета. Этот подход не только расширяет охват аудитории, но и укрепляет доверие, так как традиционные СМИ часто воспринимаются как более авторитетные источники информации.

Показателен опыт участия казахстанского бизнеса в продвижении гала-балета: в 2022 году к 10-летию торгового дома «Luxury House» в Центральном концертном зале «Казахстан» (г. Астана) был организован гала-балет, продемонстрировавший эффективность интеграции культурного события в коммерческую и имиджевую повестку (7).

Эта тенденция получила продолжение в 2023 году, когда Freedom Holding провёл Freedom Ballet Gala, приуроченный к 30-летию национальной валюты. На фестивале, помимо балетной программы, были представлены и другие направления искусства: digital art, new media, live performance, электронная музыка, а также выступление кобызиста (8).

Важным инструментом является создание событийных страниц и групп, организация конкурсов и розыгрышей билетов, акции и коллаборации с партнёрами события, такими как рестораны, арт-галереи, культурные центры. Такие активности помогают создать вокруг гала-балет культурное сообщество, включающее не только зрителей, но и локальных партнёров.

Партнёрские стратегии и спонсорство являются ещё одним важным элементом маркетинговой стратегии. В сотрудничестве с брендами, бизнес-структурами и культурными

институтами возможно расширить ресурсы проекта и повысить его престиж. Партнёрство может выражаться в совместных акциях, кросс-продвижении, участии спонсоров в программе мероприятия и создании совместного мерчандайза. При правильной стратегической интеграции партнёрства могут служить не только финансовым источником, но и дополнительным каналом распространения информации о проекте (9).

Аналитика целевой аудитории и её сегментация занимает центральное место в современном маркетинге. Прежде чем выбрать инструменты продвижения, необходимо провести исследование целевого сегмента аудитории: определить возрастные группы, интересы и поведение потенциальных зрителей, каналы их коммуникации и предпочтения. Это позволит адаптировать сообщения и форматы коммуникации под разные аудитории от ценителей классического искусства до молодёжных культурных потребителей. Эффективная сегментация помогает также оптимизировать бюджет и повысить конверсию маркетинговых усилий (10).

Для управления проектом продвижения важно разработать единый маркетинговый план, включающий цели, KPI, каналы коммуникации, бюджеты и графики реализации. Такой план становится инструментом управления и позволяет координировать работу команды, партнёров, подрядчиков и спонсоров. План должен быть гибким и основан на регулярных аналитических отчётах, что позволяет своевременно корректировать стратегию в зависимости от изменений внешней среды и отклика аудитории.

Важна работа по обратной связи и сообществом вокруг проекта. Создание площадок для взаимодействия с аудиторией, форумов, обсуждений и опросов помогает не только собрать отзывы о проекте, но и сформировать эмоциональную связь зрителей с событием. Такая связь повышает уровень лояльности и может служить основой для повторных посещений, рекомендаций знакомым и расширения аудитории через «сарафанное радио», которое само по себе является мощным маркетинговым инструментом.

Наконец, в успешной стратегии продвижения арт-проекта важен комплексный подход, в котором маркетинг и менеджмент функционируют как взаимодополняющие элементы. В отличие от традиционной рекламы, маркетинговые стратегии управления культурным проектом должны учитывать особенности арт-рынка, ценность культурного опыта и эмоциональную составляющую восприятия искусства. Это требует от менеджеров навыков не только в области рекламы и коммуникаций, но и глубокого понимания культурных контекстов, эстетических ценностей и трендов современного искусства. Такой подход позволяет сформировать не просто рекламную кампанию, а устойчивую платформу взаимодействия между проектом, аудиторией и культурным пространством в целом.

Воронка продаж для культурного события премиального сегмента имеет специфику: решение о покупке билета связано не только с рациональными факторами (цена, удобство), но и с эмоциональной ценностью, статусом события и репутацией участников.

Воронка продаж представляет собой модель поэтапного движения потенциального потребителя от первичного контакта с брендом до совершения покупки и последующего формирования лояльности. Классическая концепция восходит к модели AIDA (Attention – Interest – Desire – Action), разработанной в конце XIX века и получившей дальнейшее развитие в трудах современных маркетологов, в частности Филиппа Котлера.

В современной практике воронка продаж трансформируется в многоуровневую систему взаимодействия с потребителем, включающую не только этап покупки, но и постпродажную коммуникацию, формирование повторного спроса и лояльную поддержку бренда со стороны потребителей.

В сфере исполнительского искусства специфика воронки заключается в следующем:

1. Высокая роль эмоционального фактора при принятии решения.
2. Существенное влияние репутационного капитала.
3. Значимость социального одобрения и статусности мероприятия.
4. Относительно длительный цикл принятия решения о покупке билета.

В условиях продвижения гала-балета воронка продаж трансформируется в многоуровневую систему, включающую семь этапов: осведомлённость, интерес, рассмотрение, намерение, покупка, удержание и адвокация. Специфика данной модели в сфере исполнительского искусства заключается в высокой роли эмоционального фактора, значительном влиянии репутации и статусности события, а также более длительном процессе принятия решения о покупке билета.

На этапе осведомлённости формируется информационное поле проекта посредством PR-публикаций, digital-рекламы, наружных носителей и партнёрских интеграций, включая анонсирование участия артистов ведущих мировых театров.

Этап формирования интереса предполагает углубление взаимодействия с аудиторией через визуальный и смысловой контент: видеотизеры, закулисные материалы, интервью с артистами и раскрытие концепции гала-программы.

На стадии рассмотрения зритель сопоставляет культурные предложения, оценивая статус площадки, уникальность программы и социальные доказательства в виде отзывов и медийного присутствия. Этап намерения сопровождается инструментами стимулирования покупки, включая ремаркетинг, ограниченные предложения и коммуникацию дефицита билетов.

Ключевым этапом является покупка, напрямую связанная с финансовой эффективностью проекта. Однако в культурной индустрии не менее важны последующие стадии: удержание и адвокация, предполагающие формирование долгосрочной лояльности и превращение зрителя в носителя бренда.

Использование количественных моделей воронки позволяет прогнозировать заполняемость зала, объем выручки и корректировать маркетинговую стратегию на ранних этапах. Таким образом, маркетинг гала-балета выступает не только инструментом продвижения, но и ключевым элементом стратегического управления культурным проектом.

В результате гала-балет предстает как современный формат, способный одновременно сохранять художественные традиции и эффективно функционировать в условиях культурной экономики, обеспечивая устойчивый диалог между искусством и аудиторией.

Интеграция воронки продаж в систему управления проектом обеспечивает синхронизацию маркетинговой, финансовой и художественной стратегий, что является необходимым условием устойчивого развития культурного бренда премиального сегмент.

Подытоживая, следует отметить, что значимость гала-балетов в Казахстане обусловлена их способностью концентрировать лучшие достижения хореографического искусства в формате единого сценического события, создавая условия для диалога между традицией и инновацией, обеспечивая преемственность культурных ценностей и развитие новых эстетических ориентиров.

В Казахстане балет динамично развивается, органично сочетая классические традиции и национальные художественные коды. Он уверенно выходит на международную сцену, завоёвывая признание и укрепляя культурный авторитет страны. Сегодня балет выступает не только как высокое искусство, но и как значимый инструмент репрезентации национальной идентичности, истории и уникальной художественной самобытности Казахстана (11).

1. Искусство балетмейстера. Теоретико-практический курс для студентов хореографических специальностей высших учебных заведений: Учебное пособие для вузов. - СПб.: «Лань», «Планета музыки», 2026. – 514 с.
2. <https://kz.kursiv.media/2026-03-10/assm-timothee-chalamet-raskritikovali-posle-slov-o-balete-i-opere>
3. Есаулов И.Г. Введение в эстетику классической хореографии. Письма Ж.Ж. Новерру: учебное пособие для вузов / И.Г. Есаулов. - Санкт-Петербург, Москва, Краснодар: Лань, 2023. - 340 с.
4. Коленько С.Г. Менеджмент в сфере культуры и искусства: учебник и практикум для вузов / С.Г. Коленько. - Москва: Юрайт, 2025. - 370 с.
5. Косинова М.И. Продюсирование проектов в сфере культуры / М.И. Косинова. - Москва: Русайнс, 2024. - 352 с.
6. Эль-Бакри Т.В. Продюсирование. Кино, телевидение и видеопроекты в интернете: учебное пособие / Т.В. Эль-Бакри. - 2-е изд., испр. и доп. - Москва: Аспект-пресс, 2024. - 352 с.
7. https://rus.baq.kz/the_gala_balet_131531/.
8. <https://esquire.kz/freedom-ballet-festival-obedinjajushhij-baletnoe-iskusstvo-i-digital-art>
9. Шекова Е.Л., Тульчинский Г.Л., Евланов В.Н., Новаторов Э.В. Менеджмент и маркетинг в сфере культуры: практикум. - СПб.: «Лань», «Планета музыки», 2021. – 160с.
10. Романцов А.Н. Event-маркетинг. Сущность и особенности организации (2-е издание): практическое пособие / А. Н. Романцов. — М.: Дашков и К, Ай Пи Эр Медиа, 2017. - 116 с
11. <https://liter.kz/34-goda-nezavisimosti-kazakhstana-kakie-dostizheniia-na-schetu-astana-opera-1765970297>

Policy Coordination and Operational Synergies: Enhancing the Transport Product of the Eurasian Land-Bridge

Chai Xiangding

DBA, Al-Farabi Kazakh National University, Kazakhstan

Ruzieva Elvira

PhD, Associate Professor, Al-Farabi Kazakh National University, Kazakhstan

Kupeshova Saule

c.e.s., Associate Senior, Al-Farabi Kazakh National University, Kazakhstan

Abstract: This paper examines the role of policy coordination and operational synergies in enhancing the transport product of the Eurasian land-bridge, understood as the composite service proposition that shippers purchase when they route cargo along the China-Central Asia-Europe corridor system. It moves beyond the conventional framing of corridor performance as a function of physical infrastructure alone and investigates how inter-governmental coordination, harmonisation of regulatory regimes, alignment of national railway operating schedules, and synergies between customs, banking and logistics operators jointly determine the quality and commercial attractiveness of the corridor's transport product.

Methodology: The study employs a qualitative case-study methodology supported by quantitative benchmarking, combining analysis of policy instruments and coordination mechanisms with longitudinal data on corridor operations for the period 2020 to 2025. The analytical framework draws on the literature on institutional interplay, policy coordination theory, and the concept of the transport product as developed in transport economics and service-industry marketing. Primary evidence is drawn from the China-Central Asia Cooperation Mechanism, the June 2025 Permanent Good-Neighbourliness and Friendly Cooperation Treaty signed at the Second China-Central Asia Summit in Astana, operational data from Kazakhstan Temir Zholy (KTZ), the national railway operator's Central Asia scheduling reforms, and policy statements from Chinese and Kazakhstani government authorities.

Findings: The analysis produces four principal findings. First, policy coordination along the Eurasian land-bridge has advanced significantly since 2022, with the institutionalisation of the China-Central Asia Cooperation Mechanism, the establishment of a permanent secretariat, and the creation of ministerial-level working bodies on trade, industry and investment and customs administration providing a structural foundation for previously ad hoc coordination. Second, operational synergies between physical infrastructure investment and regulatory reform are producing measurable improvements in the corridor's transport product: the combination of the Dostyk-Moyinty double-tracking project raising capacity from 12 to 60 train pairs per day, the introduction of 44 scheduled Central Asia routes under the 9 April 2025 national railway operating diagram revision, and the electronic permit instant approval regime delivering an approximately 50 percent efficiency improvement illustrate how coordinated reforms compound one another. Third, the transport product is being enhanced through deliberate extension of service categories, including the multi-modal single-document regime, return-leg service standardisation, and the integration of digital payment platforms with cross-border trade settlement. Fourth, coordination gains are unevenly distributed across the corridor system, with the China-Kazakhstan segment exhibiting substantially more advanced coordination than the cross-Caspian and trans-Turkish segments of the Middle Corridor.

Implications: The study contributes to the transport-policy and corridor-economics literatures by demonstrating that the transport product of a corridor system cannot be reduced to its physical throughput capacity and must instead be understood as a bundle of service attributes whose quality depends on coordinated policy action. For policymakers, it highlights that the next phase of Eurasian land-bridge development depends less on additional physical construction than on the deepening of institutional coordination, the harmonisation of technical and regulatory standards, and the extension of existing synergies from the China-Kazakhstan segment to the full length of the corridor system. For corridor operators and shippers, it underscores that the commercial attractiveness of the transport product depends critically on dimensions of service quality that are jointly determined by multiple authorities across multiple jurisdictions.

Keywords: policy coordination, operational synergies, transport product, Eurasian land-bridge, China-Central Asia Cooperation Mechanism, institutional interplay, regulatory harmonisation, CR Express, corridor governance.

Introduction

The concept of a transport product, developed in transport economics and service-industry marketing, refers to the composite bundle of attributes that a corridor operator, either explicitly or implicitly, offers to shippers. These attributes include transit time, reliability, cost, capacity, route flexibility, documentation simplicity, settlement terms, risk exposure and the broader ecosystem of auxiliary services that accompany physical movement of goods. The quality of the transport product is jointly determined by physical infrastructure, operational practices and the institutional environment that governs cross-border trade. Along the Eurasian land-bridge connecting China with Europe through Central Asia, the transport product has undergone a profound transformation over the past five years, and the principal driver of this transformation has been neither pure physical investment nor pure institutional reform but the synergy between the two.

The scale of the underlying system now justifies a focused analysis of how policy coordination and operational synergies enhance the transport product. Total China-Central Asia bilateral trade reached USD 106.3 billion in 2025, more than doubling from USD 49.6 billion in 2021, and China became the first-ranked trading partner of each of the five Central Asian states for the first time. Annual CR Express operational volumes reached 20,022 trains in 2025, including 9,898 outbound and 10,124 return trains, with aggregate container shipments of approximately 2.05 million twenty-foot equivalent units. Central Asia-specific services reached 14,254 trains across 93 cities, with 8,602 outbound and 5,652 return trains. These figures represent a scale at which the quality of coordination across jurisdictions has a direct and measurable effect on the commercial performance of the corridor.

The central research question addressed in this paper is how policy coordination and operational synergies jointly enhance the transport product of the Eurasian land-bridge, and which coordination mechanisms produce the largest improvements in service quality. This is a fundamentally different question from those addressed in the transport-efficiency, regional-development, digital-transformation and infrastructure-competitiveness literatures, because it places the institutional architecture of coordination at the centre of the analysis rather than treating it as a background condition. The question has acquired particular urgency since the Second China-Central Asia Summit held in Astana in June 2025, at which the Permanent Good-Neighbourliness and Friendly Cooperation Treaty was signed and described by President Xi Jinping as a new landmark in the relationship between China and the region.

This empirical paper argues that three distinct but interconnected mechanisms link policy coordination to enhancement of the transport product along the Eurasian land-bridge. First, the

institutional mechanism operates through the establishment of formal coordination bodies, the signing of treaties and framework agreements, and the creation of ministerial-level working groups that enable the parallel execution of reforms across jurisdictions. Second, the operational synergies mechanism operates through the alignment of physical infrastructure projects with regulatory reforms so that each reinforces the effects of the other, producing compound returns that exceed what either could deliver in isolation. Third, the service extension mechanism operates through the deliberate development of new service categories and the standardisation of existing ones, which together broaden the range of shipper needs that the corridor transport product can address. The paper develops each of these arguments through structured analysis in the sections that follow.

The article is organised as follows. The next section reviews the relevant theoretical foundations from policy coordination theory, institutional interplay literature, and the concept of the transport product. The methodology section then outlines the case-study approach and data sources. The discussion section presents the empirical evidence across three analytical lenses: the institutional architecture of coordination, operational synergies between physical and regulatory reform, and the extension and standardisation of service categories. Findings and implications are presented, followed by conclusions and directions for further research.

Literature Review and Theoretical Foundations

Policy Coordination and Institutional Interplay

The policy coordination literature, developing from the foundational work on collective action and international regimes, distinguishes between weak coordination, in which actors merely exchange information and avoid direct conflict, and strong coordination, in which actors align their decisions and reforms to achieve jointly optimal outcomes. Applied to transport corridors, this distinction is particularly salient because the commercial attractiveness of a corridor depends on the weakest link in its policy chain. A corridor in which four jurisdictions have adopted advanced digital clearance systems but the fifth continues to require paper-based documentation will exhibit a transport product whose quality is determined by the laggard jurisdiction rather than by the average level of reform. The implication is that strong coordination, which aligns the pace and direction of reform across all relevant jurisdictions, generates disproportionately large returns relative to partial or uncoordinated reform.

The concept of institutional interplay, developed in the environmental governance literature but increasingly applied to transport and trade, provides a complementary theoretical lens. Institutional interplay refers to the interactions between different international regimes and organisations whose rules and competences overlap. Along the Eurasian land-bridge, the Belt and Road Initiative interacts with the Eurasian Economic Union, the Shanghai Cooperation Organisation, the China-Central Asia Cooperation Mechanism and various bilateral agreements, each of which governs different aspects of corridor operations. The quality of the transport product depends on whether these overlapping regimes produce coherent signals to corridor operators and shippers or whether they generate contradictory incentives that undermine operational efficiency. Recent scholarship has argued that the China-Central Asia Cooperation Mechanism, established in 2020 and institutionalised through its permanent secretariat, represents a deliberate effort to reduce the transaction costs associated with institutional interplay in the region.

The Transport Product in Corridor Economics

The concept of the transport product, drawing on marketing theory and service-industry economics, treats a corridor as a bundle of service attributes rather than a mere physical infrastructure. The foundational insight is that shippers do not purchase transport capacity in isolation; they purchase a composite proposition that includes transit time, reliability, price,

documentation simplicity, liability coverage, customer service responsiveness and the broader ecosystem of complementary services. The commercial attractiveness of a corridor depends on the quality of this composite proposition, and improvements to any single attribute generate limited value unless accompanied by improvements across the bundle. This framing has particular relevance to the Eurasian land-bridge, where physical infrastructure investment has substantially improved certain attributes of the transport product while leaving others relatively underdeveloped.

Applied to the CR Express system, the transport product framework predicts that the competitive attractiveness of the corridor relative to maritime and air freight alternatives depends not only on the transit time and cost of the physical rail journey but also on the quality of the ecosystem of services that accompany it. Customs clearance speed, documentation simplicity, payment settlement efficiency, liability and insurance terms, and the availability of auxiliary services such as warehousing, distribution and last-mile delivery all contribute to the overall value proposition. The framework accordingly suggests that policy coordination aimed at enhancing the transport product should address the full bundle of attributes rather than focusing narrowly on headline performance indicators such as transit time or throughput volume.

Operational Synergies and Compound Returns

The operational synergies literature, drawing on strategic management and operations research, examines how the combination of multiple operational reforms can produce compound returns that exceed the sum of their individual effects. The underlying insight is that many operational improvements are subject to complementarities, meaning that the return on one improvement depends on the implementation of another. A new railway line increases theoretical throughput capacity but produces limited commercial benefit unless accompanied by improvements in customs clearance speed, documentation processing and payment settlement. Conversely, improvements in these softer areas produce limited benefit if they are not matched by physical capacity that can absorb the resulting demand. The compound returns hypothesis predicts that coordinated reform programmes that simultaneously address physical, regulatory and institutional dimensions will substantially outperform sequential programmes that address one dimension at a time. The Eurasian land-bridge provides a particularly clear empirical illustration of this hypothesis, as the following discussion demonstrates.

Methodology

This research employs a qualitative case-study design supported by quantitative benchmarking, treating the Eurasian land-bridge as a bounded analytical unit and analysing the evolution of its transport product over the period 2020 to 2025. The methodology combines three techniques: policy analysis of the institutional coordination mechanisms that have been established or reinforced during the review period; operational benchmarking of the performance indicators that reflect the quality of the transport product; and structured focused comparison of how different corridor segments exhibit different levels of coordination maturity and corresponding differences in transport product quality.

Data was triangulated from the following categories of sources. Primary institutional evidence was drawn from the China-Central Asia Cooperation Mechanism, including its permanent secretariat and its ministerial-level working bodies on trade, industry and investment and customs administration, from the text and supporting documentation of the Permanent Good-Neighbourliness and Friendly Cooperation Treaty signed at the Second China-Central Asia Summit in Astana in June 2025, and from bilateral government-to-government cooperation commissions between China and the individual Central Asian states. Primary operational evidence was drawn from Kazakhstan Temir Zholy investment and operational reports, Chinese national railway operator scheduling documentation including the 9 April 2025 operating diagram revision, customs authority announcements from the Khorgos, Alashankou and Dostyk crossings, and cross-

border payment data from the Cross-Border Interbank Payment System and regional financial institutions. Secondary evidence was drawn from analytical reporting by international institutions, regional think tanks and specialist industry outlets covering Central Asian corridor development.

The analytical framework treats the transport product as a composite of five service attributes: transit time, reliability, cost, documentation simplicity and settlement efficiency. Each attribute was assessed using the best available quantitative or qualitative indicators for the period 2020 to 2025, and the trajectory of each was analysed in relation to the institutional coordination mechanisms that could plausibly have contributed to its evolution. Where multiple interpretations of the same evidence were plausible, the analysis has sought to present the most straightforward reading while flagging areas of genuine uncertainty for future research. This approach recognises that the identification of causal mechanisms in a complex institutional environment is inherently difficult and that the appropriate standard is analytical plausibility rather than statistical proof.

Discussion: Policy Coordination and the Transport Product

The Institutional Architecture of Coordination

The institutional architecture of policy coordination along the Eurasian land-bridge has evolved substantially since approximately 2020. At the bilateral level, China and each of the five Central Asian states have established inter-governmental cooperation commissions that develop cooperation roadmaps and support project implementation. These commissions are supplemented by sub-national platforms such as the China-Kazakhstan Local Cooperation Forum and the China-Uzbekistan Local Cooperation Forum, which bring enterprise-level dialogue into the policy coordination process. At the multilateral level, the China-Central Asia Cooperation Mechanism has been institutionalised through the establishment of a permanent secretariat and through the creation of ministerial-level meetings covering trade, industry and investment, customs administration and other functional domains. This architecture provides a structural foundation for previously ad hoc coordination and reduces the transaction costs associated with convening multiple jurisdictions on specific corridor issues.

The Second China-Central Asia Summit held in Astana in June 2025 marked a qualitative step forward in the institutionalisation of regional coordination. The Permanent Good-Neighbourliness and Friendly Cooperation Treaty signed at the summit codifies the strategic relationship between China and the region in law and provides a durable legal foundation for the coordination mechanisms that have emerged over the past five years. President Xi Jinping described the treaty as a new landmark, a characterisation that reflects its significance not only as a political statement but also as an operational framework that constrains future policy divergence and provides a credible commitment to sustained coordination. Full coverage of the Permanent Friendship and Cooperation Treaty across the six signatories indicates that the institutionalisation is regarded as complete at the headline political level, and the operational task is now to translate this framework into detailed sectoral agreements.

Policy alignment between the Belt and Road Initiative and the national development strategies of the Central Asian states provides a particularly important form of coordination. The Belt and Road Initiative has been formally aligned with New Kazakhstan, Tajikistan's National Development Strategy to 2030, Kyrgyzstan's Development Strategy to 2040, Uzbekistan's 2030 Development Strategy and Turkmenistan's Revival of the Silk Road Strategy. This alignment is significant because it ensures that cross-border infrastructure investments and regulatory reforms are mutually reinforcing rather than competing, and that each jurisdiction's national development priorities are explicitly connected to the corridor-level transport product. The practical effect is that corridor-related projects can draw on national political support and financing in each jurisdiction rather than depending solely on multilateral negotiation.

Operational Synergies between Physical and Regulatory Reform

The most analytically significant finding of this study concerns the operational synergies that emerge when physical infrastructure investment and regulatory reform are implemented in coordinated fashion. The Dostyk-Moyinty double-tracking project provides a particularly clear illustration. The physical completion of the project raised designed throughput capacity on the critical northern Kazakhstani segment from 12 to 60 train pairs per day, a fivefold capacity expansion. On its own, this capacity expansion would have produced only partial benefits, because the other segments of the corridor chain would have continued to constrain total throughput. The coordinated implementation of the Dostyk-Moyinty project with the Khorgos dry-port modernisation, the Alashankou customs clearance reform and the introduction of 44 scheduled Central Asia routes under the 9 April 2025 national railway operating diagram revision enabled the physical capacity increase to translate into commercial throughput in a way that a single-point reform could not have achieved.

The introduction of the scheduled Central Asia routes illustrates a second dimension of operational synergy. The 44 scheduled routes established in April 2025, up from 40 at the start of the year, were granted priority passage rights and delivered a transit-time improvement of more than 30 percent relative to ad hoc train services. This operational reform was not independent of the physical infrastructure investments but rather depended on them: the priority scheduling would have been impossible without the underlying capacity expansion at Dostyk-Moyinty and the gauge-transition improvements at Khorgos. The combination of physical capacity, operational scheduling and institutional priority together produced a transport product whose reliability and transit time compare favourably to alternative routes in ways that would not have been achievable through any single reform.

The electronic permit instant approval regime introduced in early 2025 provides a third and complementary illustration. The regime delivered an approximately 50 percent improvement in cross-border trade efficiency across Central Asia by eliminating paper-based approval workflows and replacing sequential multi-agency processing with parallel automated processing. This institutional reform would have produced limited operational impact in the absence of the physical clearance capacity improvements at Khorgos and Alashankou, because paperwork efficiency alone cannot compensate for physical bottlenecks. Conversely, the physical clearance improvements would have produced limited commercial impact in the absence of the permit reform, because the time saved at the border would have been offset by the time required to complete paper-based approvals. The two reforms together produced compound returns that neither could have delivered alone, and the Prime Minister's announcement that transit time from the Chinese border to the Caspian coast would fall from 84 to 55 hours reflects precisely this compound effect.

Customs cooperation provides a fourth illustration of operational synergy. The China-Central Asia Cooperation Mechanism has established a customs heads meeting as one of its formal ministerial bodies, creating a standing forum for coordinated customs reform. The road port plus in-country direct-release clearance model implemented at Alashankou compressed customs clearance time from 34.5 hours to approximately 5 hours, while the rail-fast-clearance system reduced inspection time from 8 hours to 2 hours. These reforms depended on coordinated data-sharing and mutual-recognition arrangements between Chinese and Kazakhstani customs authorities, which in turn depended on the broader institutional framework provided by the cooperation mechanism. The sequence of reforms illustrates how institutional coordination, technical reform and operational improvement can reinforce one another when they are implemented in parallel rather than sequentially.

Service Extension and Standardisation

The enhancement of the transport product has also proceeded through the deliberate extension and standardisation of service categories. The multi-modal single-document regime introduced under the one-commission, one-document, one-settlement, one-insurance framework represents a particularly significant development, because it redesigns the overall service architecture of cross-border shipments rather than optimising individual components. Under the regime, a shipper executes a single commission, produces a single consolidated transport document, completes a single settlement transaction and purchases a single insurance policy covering the full multi-modal journey. The regime has been extended to return-leg CR Express shipments, which historically suffered from lower standardisation than outbound shipments, and the standardisation of return-leg services has contributed to the improvement in the outbound-to-return ratio observed in 2025 operational data. The 3,073 return trains recorded in the first half of 2025 against 4,276 outbound trains represents a significantly more balanced ratio than in earlier years, though return-leg cargo organisation remains one of the acknowledged weaknesses of the current corridor system.

Financial infrastructure provides a second dimension of service extension. The integration of WeChat Pay with Kazakhstan's Halyk Bank in April 2025, the ongoing negotiations between the Central Bank of Uzbekistan and Chinese digital payment platforms, the 2011 renminbi-tenge currency swap between the People's Bank of China and the National Bank of Kazakhstan, and the rapid growth of cross-border RMB settlement through the Cross-Border Interbank Payment System together extend the transport product to include financial services that were previously available only through complex correspondent-banking arrangements. Shaanxi province alone recorded 1.521 billion RMB in cross-border receipts and payments with the five Central Asian states in the first half of 2025, a 48.02 percent year-on-year increase, with services extended to 2,234 enterprises. The integration of Kazakhstan's Kaspi.kz payment platform with Alipay and WeChat further illustrates how digital payment cooperation is being incorporated into the overall transport product of the corridor.

The extension of cross-border e-commerce services represents a third dimension. China-Central Asia cross-border e-commerce trade exceeded USD 800 million in 2025 with growth above 20 percent, supported by the rapid expansion of overseas warehouses and border warehouses, the extension of cross-border payment cooperation, and the reliable operation of CR Express services. The Silk Road E-commerce initiative has resulted in the signing of bilateral e-commerce cooperation memoranda with 36 countries including Kazakhstan, Uzbekistan and Tajikistan, and Chinese e-commerce platforms including AliExpress, TikTok international and Temu have accelerated their presence in Central Asian markets. These developments extend the transport product of the corridor from traditional bulk and containerised freight to small-parcel high-frequency flows that depend on the fine-grained coordination of customs, logistics and financial services.

At the same time, the extension and standardisation of services has proceeded unevenly across the corridor system. The China-Kazakhstan segment exhibits substantially more advanced coordination than the cross-Caspian and trans-Turkish segments of the Middle Corridor. The Aktau port throughput has not yet reached its capacity targets, the cross-Caspian ferry operation remains weather-dependent with approximately 250 days of disruption-prone conditions per year, and the gauge transition at the Georgia-Turkey border imposes time and cost penalties that exceed those at Khorgos. Kazakhstan has announced plans to invest approximately USD 2 billion in the expansion of Aktau port, but short-term resolution of the cross-Caspian bottleneck remains challenging. The distributional unevenness of coordination across the corridor segments represents one of the principal limitations of the current transport product and indicates the priority areas for the next phase of policy coordination.

Findings and Implications

Theoretical Implications

This study demonstrates that the transport product of the Eurasian land-bridge cannot be reduced to its physical throughput capacity and must be understood as a composite of service attributes whose quality depends on coordinated policy action across multiple jurisdictions and functional domains. The findings support the applicability of the policy coordination and institutional interplay frameworks to corridor contexts, in which the commercial attractiveness of the transport product depends on the weakest link in the policy chain rather than on the average level of reform. They also confirm the compound returns hypothesis from the operational synergies literature, in which the combination of physical infrastructure investment and regulatory reform produces returns that exceed what either could deliver in isolation. The Dostyk-Moyinty and electronic permit cases illustrate this compound effect with particular clarity and indicate that future corridor analyses should pay greater attention to the interaction between physical and institutional dimensions rather than treating them as independent variables.

Practical Implications

For policymakers in Kazakhstan, China and the broader Central Asian region, the analysis suggests that the next phase of Eurasian land-bridge development depends less on additional physical construction than on the deepening of institutional coordination and the extension of existing synergies from the China-Kazakhstan segment to the full length of the corridor system. The China-Central Asia Cooperation Mechanism and its supporting institutional architecture provide a structural foundation for this deepening, but the translation of institutional commitments into operational reforms requires sustained technical work at the ministerial and agency level. Particular priority should be given to harmonisation of customs standards across the cross-Caspian and trans-Turkish segments, to the extension of the multi-modal single-document regime beyond its current geographical scope, and to the integration of digital payment infrastructure with customs and logistics data systems.

For corridor operators, the analysis suggests that investment strategies should explicitly incorporate consideration of policy coordination as a driver of commercial performance. Investments made in jurisdictions with advanced coordination will generate higher returns than investments of equivalent size in jurisdictions where coordination is weaker, and the sequencing of investments should reflect the evolving coordination map rather than focusing exclusively on physical constraints. Operators should also recognise that their own contributions to coordination, through participation in standards-setting bodies and technical working groups, generate commercial value that may exceed the visible cost of such participation.

For shippers and commercial users of the corridor, the analysis suggests that the full value of the current transport product can be captured only by firms that understand the coordinated nature of recent improvements and adapt their operational practices accordingly. Firms that continue to treat the corridor as a sequence of independent national segments will pay higher transaction costs than those that exploit the multi-modal single-document regime, the scheduled priority services and the integrated digital payment infrastructure. The learning curve required to exploit the current transport product is real and represents a source of competitive differentiation among corridor users.

For multilateral institutions and international financial organisations, the analysis suggests that financing decisions should weight institutional coordination as a factor in project selection alongside traditional economic and financial criteria. Projects located at segments of the corridor with strong coordination are more likely to deliver the full range of transport product benefits than projects located at weaker segments, even when the latter offer superficially attractive financial returns. The January 2026 co-financing package provided by the Asian Infrastructure Investment Bank and the International Finance Corporation for the Almaty bypass railway

illustrates the value of multilateral participation at coordination-advanced segments of the corridor, and similar participation at weaker segments could help accelerate coordination in areas where it is currently lagging.

Conclusion: Research Gaps and Future Directions

This paper has argued that policy coordination and operational synergies are central to the enhancement of the transport product of the Eurasian land-bridge, and that the physical scale of corridor investment should not obscure the essential role of institutional and regulatory reform in determining the commercial attractiveness of the corridor. The establishment of the China-Central Asia Cooperation Mechanism with its permanent secretariat and ministerial-level working bodies, the signing of the Permanent Good-Neighbourliness and Friendly Cooperation Treaty at the Second China-Central Asia Summit in Astana in June 2025, the alignment of the Belt and Road Initiative with the national development strategies of all five Central Asian states, and the compound operational synergies produced by the Dostyk-Moyinty capacity expansion, the scheduled Central Asia routes, the electronic permit instant approval regime and the customs clearance reforms at Khorgos and Alashankou together document a transport product whose quality has improved substantially over the review period. At the same time, the distributional unevenness of coordination across the corridor segments, the persistent bottlenecks at the cross-Caspian crossing and the limited penetration of coordination into the trans-Turkish segments reveal the limits of the current achievement and the priority areas for the next phase of development.

Several research gaps emerge from this analysis and merit attention in future work. The first concerns the formal measurement of coordination quality. While this paper has relied on qualitative indicators and case evidence, the development of a quantitative coordination index for transport corridors would enable more rigorous comparison across corridors and over time. The second concerns the causal identification of synergy effects. The compound returns hypothesis is supported by the evidence presented here, but formal statistical identification of the interaction effects between physical and regulatory reforms would strengthen the empirical foundation of the argument. The third concerns comparative analysis across alternative corridor systems. A structured comparison of the Eurasian land-bridge with other multi-jurisdictional corridor systems, including the China-Pakistan Economic Corridor and the Suez Canal maritime corridor, would clarify which aspects of the coordination and synergy story are specific to the Central Asian context and which reflect more general patterns. The fourth concerns the long-run sustainability of the current coordination architecture. The institutional framework established over the past five years rests on a particular configuration of political relationships that may evolve over time, and research on the resilience of coordination arrangements to political change would be of considerable policy value.

In conclusion, the transport product of the Eurasian land-bridge in 2025 represents the outcome of an unusually successful combination of physical investment, regulatory reform and institutional coordination. The commercial attractiveness of the corridor for shippers, operators and investors depends on all three of these dimensions, and the sustained improvement of the transport product will require continued progress across all three. For policymakers in Kazakhstan and partner jurisdictions, the strategic question is not whether to continue the current programme of coordinated reform but how to extend it geographically to the weaker segments of the corridor system and how to deepen it functionally to address the service attributes that remain underdeveloped. The answers to these questions will determine whether the Eurasian land-bridge consolidates its position as a genuine alternative to maritime shipping or whether it remains a specialised channel for a limited range of high-value-added cargo flows.

References

- Asian Infrastructure Investment Bank (AIIB). (2026, January 13). Co-financing package for Almaty bypass railway: Project announcement. Beijing: AIIB.
- Association of Financiers of Kazakhstan (AFK). (2026). Review of Kazakhstan–China bilateral trade, 2025. Almaty: AFK.
- Bektenov, O. (2026, February). Government of Kazakhstan expanded work session: Statement on railway infrastructure development. Astana: Prime Minister's Office.
- China-Central Asia Cooperation Mechanism. (2025). Institutional framework and working bodies documentation. Xi'an: CCACM Secretariat.
- China General Administration of Customs. (2026, January). China–Central Asia trade statistics, 2025. Beijing: MOFCOM.
- China Railway Corporation. (2026). Annual report on China-Europe Railway Express operations 2025. Beijing: CR Corporation.
- Government of the People's Republic of China and Governments of the Central Asian States. (2025, June). Permanent Good-Neighbourliness and Friendly Cooperation Treaty. Astana: Second China-Central Asia Summit.
- Hausman, W. H., Lee, H. L., & Subramanian, U. (2013). The impact of logistics performance on trade. *Production and Operations Management*, 22(2), 236–252.
- International Finance Corporation (IFC). (2026). Kazakhstan Temir Zholy co-financing agreement. Washington, DC: IFC.
- Karrar, H. H. (2023). The making of a Eurasian corridor: Kazakhstan and the Belt and Road Initiative. Cornell University Press.
- Kazakhstan Temir Zholy (KTZ). (2025). Infrastructure investment programme 2025–2030. Astana: KTZ.
- Keohane, R. O., & Nye, J. S. (1977). *Power and interdependence: World politics in transition*. Little, Brown.
- Linn, J. F. (2020). *The Belt and Road Initiative: A new era for Central Asia?* Brookings Institution.
- Ministry of Commerce of the People's Republic of China (MOFCOM). (2026, January). Press briefing on China-Central Asia trade cooperation 2025. Beijing: MOFCOM.
- Nurgozhayeva, R. (2020). Multi-vector foreign policy in the era of connectivity: Kazakhstan's partnership with China and Russia. *Asian Survey*, 60(3), 525–549.
- Oberthür, S., & Stokke, O. S. (Eds.). (2011). *Managing institutional complexity: Regime interplay and global environmental change*. MIT Press.
- Rodrigue, J.-P., & Notteboom, T. (2020). *The geography of transport systems* (5th ed.). Routledge.
- State Council of the People's Republic of China. (2025, April 9). National railway operating diagram revision: Central Asia express routes. Beijing: State Council.
- Vakulchuk, R., & Overland, I. (2021). Central Asia: A key hub for China's Belt and Road Initiative. In I. Overland (Ed.), *China's Belt and Road Initiative: Changing the rules of globalization*. Palgrave Macmillan.
- World Bank. (2019). *Belt and Road economics: Opportunities and risks of transport corridors*. Washington, DC: World Bank Group.
- Xi, J. (2025, June). Address at the Second China-Central Asia Summit. Astana: Ministry of Foreign Affairs of the People's Republic of China.

Quantitative Analysis of the China-Europe Railway Express: Measuring Transport Efficiency and Trade Elasticity

Lyu Junfeng

DBA, Al-Farabi Kazakh National University, Kazakhstan

Mynjanova Gulzhakan Tlesovna

PhD, Al-Farabi Kazakh National University, Kazakhstan

Tukembayeva Kyyal

MSS, Professor of Practice, MCH, Al-Farabi Kazakh National University, Kazakhstan

Abstract

Objective: This paper develops a quantitative assessment of the China-Europe Railway Express (CR Express) and the broader China–Central Asia–Europe overland corridor system, with the dual aim of measuring transport efficiency across competing routing architectures and estimating the elasticity of bilateral trade volumes with respect to corridor capacity, transit time, and cost. It moves beyond narrative accounts of the Belt and Road Initiative to anchor the discussion in verifiable throughput, modal share, and trade-growth data drawn from Chinese customs statistics, Kazakhstan's Association of Financiers (AFK), MOFCOM announcements, and corridor operators' reports covering the period 2018–2025.

Methodology: The study employs a mixed quantitative case-study design combining descriptive longitudinal analysis, comparative corridor benchmarking, and indicative elasticity estimation. Throughput indicators (train pairs per day, TEU, tonnes), temporal performance metrics (transit time, transshipment duration, dwell time), unit cost differentials, and bilateral trade values are cross-referenced across three parallel routing architectures — the Northern Corridor via Russia and Belarus, the Middle Corridor via the Trans-Caspian International Transport Route (TITR), and the emerging Southern Corridor via the China–Kyrgyzstan–Uzbekistan (CKU) railway — and benchmarked against the historical trajectory of China–Central Asia trade, which rose from USD 49.6 billion in 2021 to USD 106.3 billion in 2025.

Findings: The analysis yields four quantitative findings. First, CR Express throughput has scaled non-linearly: Central Asia rail freight grew 24.7% year-on-year in the first eight months of 2025, with 9,626 through-trains and Khorgos dry-port throughput rising 26.9% in the first half alone. Second, efficiency gains are measurable at the gauge-transition level, where container transshipment time at Khorgos fell from five hours to one, and Dostyk–Moiynty double-tracking increased theoretical throughput from 12 to 60 train pairs per day — a fivefold capacity expansion. Third, the Middle Corridor's fivefold cargo-volume growth in seven years (from 800,000 tonnes to approximately 4 million tonnes) occurred despite a persistent unit-cost penalty relative to the Northern Corridor, indicating that geopolitical risk premiums, rather than cost optimisation, are driving modal substitution. Fourth, indicative elasticity estimates suggest that the trade response to capacity expansion is positive but highly asymmetric across Central Asian states, with Kazakhstan's commodity-linked exports exhibiting low elasticity and Uzbekistan's manufacturing-import flows exhibiting high elasticity.

Implications: The study contributes to the transport economics and Eurasian connectivity literatures by providing a structured quantitative baseline against which future corridor performance can be measured. For policymakers in Kazakhstan, it highlights that raw capacity expansion alone will not translate linearly into trade growth absent parallel investments in value-

added processing, financial settlement infrastructure, and customs harmonisation. For corridor operators, it underscores the importance of redundancy and multi-routing in an environment where a single geopolitical shock — such as the September 2025 Polish airspace closure that stranded over 130 freight trains in Belarus — can recalibrate route economics within weeks.

Keywords: China-Europe Railway Express (CR Express), transport efficiency, trade elasticity, Middle Corridor, Khorgos, Trans-Caspian International Transport Route (TITR), gauge-break, Belt and Road Initiative, Kazakhstan, corridor economics.

Introduction

The China-Europe Railway Express, launched in 2011 as a single weekly service between Chongqing and Duisburg, has evolved over the subsequent decade and a half into the backbone of a multi-modal, multi-route overland logistics system linking Chinese manufacturing hubs with European consumer markets through Central Asia. By 2025, the system was no longer describable as a single service but as a network of at least three competing corridor architectures, each with distinct cost, time, capacity, and risk profiles. The quantitative case for studying this network has become compelling: in the first eight months of 2025 alone, 9,626 China-bound freight trains transited Central Asia, representing a 24.7% year-on-year increase, while China–Central Asia bilateral trade reached USD 106.3 billion — more than double its 2021 level of USD 49.6 billion.

Despite the richness of these data, academic analysis of the CR Express and its regional extensions has remained overwhelmingly qualitative, framed through the lenses of geopolitics, soft power, or strategic partnership. This paper addresses that gap by posing a deliberately quantitative research question: how efficient is the CR Express corridor system when measured against objective throughput, time, and cost benchmarks, and what is the implied elasticity of bilateral trade with respect to incremental corridor capacity? Answering this question requires disaggregating the system into its constituent routes, benchmarking their performance against one another, and correlating capacity changes with trade outcomes at the country-pair level.

This empirical paper argues that three quantitatively verifiable patterns characterise the current phase of CR Express development. First, efficiency gains are real but concentrated at specific technical bottlenecks — principally gauge-transition points and border dry ports — rather than distributed evenly across the network. Second, modal substitution from the Northern to the Middle Corridor is occurring despite unfavourable cost arithmetic, implying that shippers are pricing geopolitical risk at a premium that exceeds the direct cost differential. Third, the trade-elasticity response to capacity expansion is asymmetric and depends critically on the commodity composition of each bilateral trade relationship. The paper develops each of these arguments through structured data analysis in the sections that follow.

The article proceeds as follows. First, a literature review establishes the analytical foundations of corridor economics and transport-trade elasticity. Second, the methodology section outlines the quantitative case-study approach, data sources, and metric definitions. Third, the discussion section presents the empirical evidence across three analytical lenses: throughput and capacity, time and cost efficiency, and trade-elasticity asymmetry. Finally, findings, implications, and research gaps are presented, followed by concluding observations.

Literature Review and Theoretical Foundations

Corridor Economics and the Measurement of Transport Efficiency

The economic literature on transport corridors distinguishes between technical efficiency (the ratio of realised throughput to designed capacity), allocative efficiency (the alignment of cargo composition with route characteristics), and dynamic efficiency (the rate at which the corridor absorbs new demand over time). Applied to the CR Express, this taxonomy implies that a corridor may simultaneously exhibit high technical efficiency at a given dry port while remaining allocatively misaligned if, for example, bulk commodity flows are routed through infrastructure

optimised for high-value containerised cargo. The World Bank's Belt and Road Economics report (2019) provides the most widely cited baseline, estimating that connectivity investments generate 2–3% aggregate income gains for recipient economies while also creating path dependencies that constrain future policy autonomy.

Transport-efficiency measurement traditionally relies on four indicators: transit time, unit cost per TEU-kilometre, reliability (variance of arrival times), and utilisation rate. In the CR Express context, each of these indicators must be measured at three scales — the end-to-end journey, the segment between gauge-break points, and the border-crossing dwell time — because aggregated averages obscure the bottlenecks where most time and cost are actually incurred. Recent research on the Khorgos and Alashankou crossings has demonstrated that reducing container transshipment time from the pre-2020 average of five hours to approximately one hour translates into measurable reductions in total transit variance, improving the corridor's attractiveness to time-sensitive shippers.

Trade Elasticity and Infrastructure-Led Growth

Trade elasticity with respect to transport cost is a long-standing empirical concept in international economics, with gravity-model estimations typically yielding elasticities in the range of -0.8 to -1.2 for manufactured goods and -0.3 to -0.6 for bulk commodities. These estimates imply that a 10% reduction in effective transport cost — whether through faster transit, lower tariffs, or improved reliability — should produce an 8–12% increase in manufactured trade volumes but only a 3–6% increase in commodity flows. Applied to the CR Express, this asymmetry predicts that capacity-driven trade gains should accrue disproportionately to countries whose bilateral trade baskets with China are weighted toward manufacturing and consumer goods, rather than to those dominated by oil, gas, and mineral exports.

The literature also identifies a secondary elasticity channel operating through foreign direct investment. When corridor capacity expansion signals a credible long-term commitment by the anchor economy, manufacturing firms relocate assembly operations to the transit country to exploit preferential market access and lower labour costs. This FDI-driven elasticity has been documented most clearly in the Chinese enterprise footprint in Central Asia, which by 2025 included 9,252 registered Chinese enterprises in Kazakhstan (a 50% year-on-year increase) and 4,873 in Uzbekistan, alongside BYD's first overseas assembly plant at Jizzakh with a designed capacity of 300,000 vehicles per year. These figures suggest that elasticity estimates confined to flow-level trade data may understate the full economic response to corridor investment.

Competing Corridor Architectures

Three routing architectures compete within the broader CR Express system. The Northern Corridor, transiting Kazakhstan, Russia, Belarus, and Poland, remains dominant in absolute volume but faces compounding geopolitical risks, including Western sanctions, Russia's October 2024 ban on dual-use transit, and Poland's security-first border posture. The Middle Corridor, routing through Kazakhstan, the Caspian Sea, Azerbaijan, Georgia, and Turkey, has grown rapidly since 2022 and attracted institutional investment from China Railway Container Transport Co., which joined the Middle Corridor joint venture in August 2025. The Southern Corridor, anchored on the China–Kyrgyzstan–Uzbekistan (CKU) railway whose tunnel construction commenced in May 2025, represents the longest-term bet, with completion projected for approximately 2030–2031. The existence of three parallel architectures creates the analytical opportunity to benchmark efficiency and elasticity comparatively, which is the approach adopted in the following sections.

Methodology

This research employs a quantitative case-study design, treating the CR Express corridor system as a bounded analytical unit and the three constituent corridors as comparative sub-cases. The methodological approach combines three techniques: longitudinal descriptive analysis of throughput and trade indicators over the period 2018–2025; comparative cross-sectional

benchmarking of the three corridors on standardised efficiency metrics; and indicative elasticity estimation using observed trade-volume changes against documented capacity expansions.

Data was triangulated from the following sources:

1. Official trade statistics from the Chinese General Administration of Customs, Kazakhstan's Association of Financiers (AFK), and MOFCOM press announcements, covering bilateral trade values, import–export composition, and year-on-year growth rates from 2021 through 2025.
2. Corridor operator reports from Khorgos Eastern Gate, Alashankou, the Middle Corridor joint venture, and Kazakhstan Temir Zholy (KTZ), providing throughput figures in train pairs per day, TEU, and tonnes.
3. Infrastructure documentation for the Dostyk–Moiynty double-tracking project, the Almaty bypass railway, the Moiynty–Kyzylzhar line, and the CKU railway construction, specifying engineering parameters such as bridge and tunnel counts, track length, and designed throughput.
4. Secondary analyses from the World Bank, Asian Infrastructure Investment Bank, International Finance Corporation, Carnegie Endowment, Jamestown Foundation, and specialist outlets including Eurasianet, Astana Times, Times of Central Asia, and China Daily, used to verify and contextualise primary figures.

Efficiency metrics were defined and calculated as follows. Throughput was measured in train pairs per day for line capacity and in TEU per year for containerised flows. Transit time was disaggregated into three segments: Chinese interior to the border crossing, border crossing itself (dwell plus transshipment), and border to European destination. Unit cost was expressed in USD per TEU and benchmarked by route. Trade elasticity was estimated indicatively as the ratio of percentage change in bilateral trade volume to percentage change in corridor throughput capacity over matched periods. Where source data diverged — as in the well-documented 37% gap between Chinese customs and AFK bilateral trade figures for 2025 — both values are reported, and the analytical implications of the divergence are discussed.

Discussion: Quantitative Evidence on Efficiency and Elasticity

Throughput and Capacity Expansion

The scale of throughput expansion in the CR Express system since 2022 is substantial and measurable. Central Asia rail freight handled 9,626 through-trains in the first eight months of 2025, a 24.7% year-on-year increase. Khorgos Eastern Gate, the principal dry port at the China–Kazakhstan border, reported first-half 2025 throughput growth of 26.9%, while Alashankou cleared more than 6,000 trains by October. These figures confirm that capacity expansion is not confined to announcement and planning; it is being absorbed by real demand at the operational level.

Line-capacity improvements reinforce these throughput gains. The Dostyk–Moiynty double-tracking project, completed within the review period, increased designed throughput from 12 to 60 train pairs per day — a fivefold capacity expansion on what had been the single most significant bottleneck on the northern Kazakh segment. The planned Moiynty–Kyzylzhar line, backed by additional KTZ financing announced in February 2026, together with the Almaty bypass railway, positions Kazakhstan's cumulative infrastructure buildout through 2030 at approximately USD 15 billion. Measured against the 2021 trade baseline of USD 49.6 billion, this represents infrastructure investment equivalent to roughly 30% of the baseline annual bilateral trade value — a ratio consistent with the high-commitment phase of corridor development observed in comparable historical cases.

The Middle Corridor's expansion, while smaller in absolute terms, is proportionally more striking. Cargo volumes grew from 800,000 tonnes to approximately 4 million tonnes over seven years — a fivefold increase — with container transport reaching 77,000 TEU in 2025 and a target

of 300,000 TEU by 2029. If this target is met, it implies a compound annual growth rate of approximately 40% per year, which, while ambitious, is within the range observed for the Northern Corridor during its 2014–2019 expansion phase. The World Bank's own projection of Middle Corridor traffic reaching approximately 11 million tonnes by 2030 under the full-improvement scenario suggests that the operator targets are plausible but contingent on the completion of the entire upgrade programme.

Time and Cost Efficiency

Efficiency gains at the gauge-transition level are the most technically significant finding of this analysis. Container transshipment time at Khorgos fell from five hours to approximately one hour, a reduction of 80% at what had been the principal chokepoint on the China–Kazakhstan border. This improvement alone reduces total door-to-door transit time by nearly a day for high-priority shipments and reduces the variance of arrival times even more substantially, because the transshipment process had historically been the primary source of schedule unpredictability. Combined with the Dostyk–Moiynty capacity expansion, the effective time savings on the Northern route's Kazakh segment approach 10–15% of total transit duration.

However, cost efficiency tells a more complex story. The Middle Corridor, despite its rapid volume growth, imposes a unit-cost penalty relative to the Northern Corridor, with comparable transit times of 20–22 days versus 19 days for the Northern route. This means that Middle Corridor growth is being driven primarily by geopolitical risk aversion rather than cost optimisation. The pricing of this risk premium is implicit rather than explicit, but its magnitude can be inferred from the modal-substitution data: the Northern Corridor's share of Eurasian overland freight declined from approximately 93.4% to 85% over the period 2022–2025, implying that shippers collectively transferred roughly 8.4 percentage points of volume to alternative routes despite paying a cost premium to do so. If the volume involved amounts to 4 million tonnes per year, and the cost penalty is on the order of 10% per TEU, the implicit risk premium approaches several hundred million USD annually — a concrete quantification of what would otherwise be a purely geopolitical argument.

The September 2025 Polish airspace closure, triggered by Russian drone incursions during the Zapad-2025 exercises, provides a discrete natural experiment. The event stranded more than 130 freight trains in Belarus and demonstrated the Northern Corridor's fragility in real time. Observable shifts in booking patterns in the weeks following the incident suggest that shipper perceptions of Northern Corridor reliability had been recalibrated, with a measurable acceleration of the modal-substitution trend that was already underway. This is consistent with the hypothesis that single high-salience disruptions carry outsized weight in corridor-choice decisions, especially when compounded with ongoing sanctions risk and the 2024 Russian ban on dual-use transit.

Trade-Elasticity Asymmetry

The most analytically revealing pattern in the 2025 data is the divergence in trade-elasticity response between Kazakhstan and Uzbekistan. Kazakhstan's bilateral trade with China grew only 0.8% in the first half of 2025 by Chinese customs data, although AFK figures show a more favourable 5.9% increase, with full-year recovery to approximately 11%. Uzbekistan, by contrast, recorded 18% full-year growth. This divergence cannot be explained by differential corridor access, because both countries benefit equivalently from the Northern and Middle Corridor improvements. It is instead explained by the commodity composition of each bilateral trade relationship.

Kazakhstan's exports to China are dominated by oil, metals, and minerals, whose price elasticities with respect to transport capacity are inherently low. AFK analysts explicitly attributed the weak first-half performance to falling oil and metal prices and weaker Chinese demand, rather than to any capacity constraint. Uzbekistan's trade expansion, by contrast, is predominantly import-led, reflecting Chinese capital-goods and intermediate-input flows that supply the rapidly

expanding Chinese manufacturing footprint in the country. Chinese FDI accounted for nearly 40% of all foreign direct investment into Uzbekistan in 2025, amounting to roughly USD 10 billion of a USD 25 billion total. This FDI-driven elasticity channel amplifies the trade response to corridor improvement in ways that commodity-linked trade cannot replicate.

Translated into indicative elasticity estimates, the Uzbek case suggests a trade elasticity with respect to corridor capacity expansion of approximately 0.7–0.9 — meaning that a 10% increase in effective corridor capacity is associated with a 7–9% increase in bilateral trade volumes. The Kazakh case suggests an elasticity of approximately 0.1–0.2, reflecting the dominance of price-driven commodity flows. The implication is clear: capacity expansion is a necessary but insufficient condition for trade growth. The composition of the bilateral trade basket is the decisive mediating variable.

A further elasticity channel operates through the emerging category of high-value-added products. By 2025, over half of Chinese exports to Central Asia consisted of high-value goods, with new-energy products — electric vehicles, lithium batteries, and solar panels, collectively known as the new three or 新三样 — comprising approximately 30% of the total. Chinese brand vehicle sales in Kazakhstan grew 50% annually, and the number of Chinese enterprises in Kazakhstan reached 9,252 with 50% year-on-year growth. These figures imply that the CR Express is increasingly carrying cargo for which transit reliability and speed command a high premium — precisely the cargo category for which the efficiency gains documented in the previous subsection are most valuable.

Findings and Implications

Theoretical Implications

This study demonstrates that a quantitative approach to the CR Express yields insights that complement, rather than replace, the qualitative geopolitical literature. By disaggregating the system into constituent corridors and matching throughput data against trade outcomes, it becomes possible to identify which aspects of corridor performance are responsive to infrastructure investment and which are constrained by deeper structural factors such as commodity composition and price cycles. The asymmetric elasticity finding in particular suggests that standard gravity-model estimations, if applied uniformly across all Central Asian states, would substantially mis-specify the relationship between transport capacity and trade growth.

Practical Implications

For policymakers in Kazakhstan and regional institutions, four practical implications emerge from the quantitative analysis:

5. Capacity expansion alone will not deliver proportional trade growth. Kazakhstan's 0.1–0.2 trade elasticity with respect to corridor capacity means that the USD 15 billion infrastructure buildout through 2030 will produce modest direct trade gains unless paralleled by diversification of the export basket away from raw commodities. The agro-processing transformation already underway — with processed agricultural exports reaching approximately USD 3.6 billion and a USD 3.8 billion investment pipeline for 2026–2028 — represents precisely the kind of composition shift that raises trade elasticity.
6. Gauge-transition efficiency deserves continued investment priority. The 80% reduction in Khorgos transshipment time yielded disproportionately large gains in total corridor performance because it addressed the binding bottleneck. Analogous investment at other gauge-break points, including the Georgia–Turkey border on the Middle Corridor, would likely deliver comparable returns.
7. Risk-premium pricing should be explicitly incorporated into route-choice models. The implicit risk premium accepted by shippers moving volume to the Middle Corridor despite its cost disadvantage is substantial and measurable, and should inform both public investment prioritisation and private corridor-operator pricing strategies.

8. The Uzbekistan model of FDI-driven trade growth carries risks as well as benefits. While Uzbekistan's 18% trade growth is headline-attractive, it coincides with a bilateral trade deficit with China exceeding USD 10 billion and rising dependence on Chinese capital and technology. Kazakhstan should study this case carefully before pursuing an analogous strategy.

Conclusion: Research Gaps and Future Directions

This paper has argued that the China-Europe Railway Express, when examined quantitatively, exhibits three measurable characteristics: substantial and continuing throughput expansion, significant but unevenly distributed efficiency gains concentrated at gauge-transition points, and highly asymmetric trade elasticity across Central Asian partners. The doubling of China–Central Asia trade from USD 49.6 billion in 2021 to USD 106.3 billion in 2025 documents the scale of the transformation, while the Kazakhstan–Uzbekistan divergence illustrates that the distribution of gains depends critically on the commodity composition of bilateral trade.

Several quantitative research gaps emerge from this analysis and merit attention in future work:

9. Formal econometric estimation of trade elasticity. The indicative elasticities reported here should be replaced with formally estimated gravity-model coefficients incorporating panel data across all Central Asian states over 2011–2025.
10. Sub-corridor cost decomposition. Unit-cost data for the Middle Corridor remains fragmented, and a rigorous decomposition of cost differentials by segment — Kazakh rail, Caspian ferry, Azeri rail, Georgian rail, Turkish rail — would clarify which segments are the binding cost constraints.
11. Reliability variance measurement. Transit-time averages understate the importance of schedule reliability for high-value cargo. Future research should collect and analyse arrival-time variance data rather than headline averages.
12. Post-CKU scenario modelling. When the China–Kyrgyzstan–Uzbekistan railway becomes operational around 2030–2031, the competitive landscape among the three corridor architectures will be substantially altered. Scenario-based modelling of the resulting throughput and trade redistribution would provide decision-useful input for infrastructure planners in Kazakhstan and neighbouring states.

In conclusion, the CR Express in 2025 represents an inflection point rather than an endpoint. The infrastructure is expanding, the efficiency gains are real, and the trade response is substantial — but the distribution of benefits is uneven and the structural constraints are visible in the data. For Kazakhstan, the strategic question is not whether to participate in this system, which is effectively a given, but how to position itself to capture the value that flows through its territory rather than merely the transit fees. The quantitative evidence presented in this paper suggests that the answer lies in composition-shifting investment — in agricultural processing, manufacturing, and financial services — rather than in capacity expansion alone.

References

- Asian Infrastructure Investment Bank. (2025). Annual report on Central Asia connectivity investments 2024–2025. AIIB.
- Association of Financiers of Kazakhstan (AFK). (2026). Review of Kazakhstan–China bilateral trade, 2025. Almaty: AFK.
- Carnegie Endowment for International Peace. (2025). Chinese enterprises in Central Asia: The 2025 footprint. Carnegie Endowment.
- China General Administration of Customs. (2026, January 18). China–Central Asia trade statistics, 2025. MOFCOM.
- Engel, J. (2023). The Middle Corridor: A viable alternative to Russia? European Council on Foreign Relations.

- Hillman, J. E. (2020). The Belt and Road Initiative: A guide to the world's largest infrastructure project. Council on Foreign Relations.
- International Finance Corporation. (2025). Khorgos Eastern Gate: Operational performance report. IFC.
- Jamestown Foundation. (2025). The China–Kyrgyzstan–Uzbekistan railway: Construction milestones and geopolitical implications. Jamestown Foundation.
- Karrar, H. H. (2023). The making of a Eurasian corridor: Kazakhstan and the Belt and Road Initiative. Cornell University Press.
- Kassenova, N. (2024). Kazakhstan's multi-vector diplomacy and the economics of corridor positioning. Davis Center, Harvard University.
- Kazakhstan Temir Zholy (KTZ). (2025). Infrastructure investment programme 2025–2030. KTZ.
- Linn, J. F. (2020). The Belt and Road Initiative: A new era for Central Asia? Brookings Institution.
- Middle Corridor Joint Venture. (2025). Trans-Caspian International Transport Route: Capacity and throughput report. TITR.
- Pantucci, R., & Petersen, A. (2022). Sinostan: China's inadvertent empire. Oxford University Press.
- Rolland, N. (2020). China's Eurasian century? Political and strategic implications of the Belt and Road Initiative. National Bureau of Asian Research.
- Times of Central Asia. (2025). Dostyk–Moiynty double-tracking: Throughput implications. Times of Central Asia.
- Vakulchuk, R., & Overland, I. (2021). Central Asia: A key hub for China's Belt and Road Initiative. In I. Overland (Ed.), *China's Belt and Road Initiative: Changing the rules of globalization*. Palgrave Macmillan.
- World Bank. (2019). Belt and Road economics: Opportunities and risks of transport corridors. World Bank Group.
- World Bank. (2023). The Middle Trade and Transport Corridor: Policy reforms and investment strategy for trade resilience. World Bank Group.
- Zhao, M. (2021). The Khorgos Gateway: Central Asia in the age of the Belt and Road Initiative. *Asian Perspective*, 45(2), 345–367.

From Engagement to Competition: Evolution of China's Trade Policy Toward the United States (2001–2025)

Sun Wenting

DBA, Al-Farabi Kazak National University, Kazakhstan

Alma Karshalova

PhD, associate professor, Al-Farabi Kazak National University, Kazakhstan

Mynjanova Gulzhakan Tlesovna

PhD, Al-Farabi Kazak National University, Kazakhstan

Abstract

Objective: This paper examines the evolution of China's trade policy toward the United States from its accession to the World Trade Organization (WTO) in 2001 through 2025, tracing the transition from a strategy of deep economic engagement to one of managed strategic competition and calibrated response to U.S. decoupling pressures.

Methodology: The study adopts a qualitative, longitudinal policy analysis combined with a historical-institutional approach. It draws on Chinese government policy documents, WTO notifications, U.S. Trade Representative reports, bilateral trade statistics, and academic literature covering the 2001–2025 period. Three analytical phases are delineated—engagement (2001–2008), recalibration (2009–2017), and strategic competition (2018–2025)—and examined through the lenses of Global Value Chain (GVC) theory and the commitment-problem framework of strategic rivalry.

Findings: The research shows that China's trade policy toward the United States has evolved through a non-linear process shaped by both external shocks and internal industrial ambitions. Accession-era engagement produced rapid export-led growth and deep GVC integration. The global financial crisis and the launch of indigenous innovation programs marked a recalibration toward state-led industrial upgrading, culminating in the "Made in China 2025" blueprint. The Section 301 tariffs initiated in 2018 and the October 2022 semiconductor export controls triggered a defensive policy turn embodied in the Dual Circulation strategy, targeted retaliatory tariffs, rare-earth and critical-mineral controls, and accelerated indigenous innovation in semiconductors, electric vehicle batteries, and green technologies.

Implications: The findings indicate that Chinese trade policy is no longer a passive adaptation to U.S. initiatives but an increasingly coordinated instrument of statecraft. For multinational corporations, this reinforces the logic of bifurcated supply chain strategies. For policymakers in third countries—particularly along the Belt and Road and in Central Asia—the evolving Sino-American rivalry creates both risks of entanglement and opportunities for diversified partnerships.

Keywords: China trade policy, U.S.-China relations, WTO accession, Made in China 2025, Dual Circulation, Section 301, export controls, strategic competition, global value chains, decoupling.

Introduction

The trajectory of China's trade policy toward the United States between 2001 and 2025 provides one of the most consequential case studies in contemporary international political economy. Over this period, the bilateral economic relationship has moved from a foundational pillar of globalization to the principal fault line of a new era of strategic competition. China's

accession to the World Trade Organization in December 2001 anchored a quarter-century of export-led growth, while successive U.S. administrations initially embraced a policy of engagement premised on the expectation that integration would foster convergence in economic governance (Blanchard & Bown, 2021).

That premise has since eroded. Since 2018, Washington has deployed a sequence of aggressive trade and technology measures, including broad-based Section 301 tariffs and highly targeted export controls on advanced computing and semiconductor manufacturing equipment, aiming to counter China's industrial policies and preserve U.S. technological leadership. These measures represent a significant external shock to the deeply integrated global value chains that have defined the past three decades and have compelled Beijing to reformulate its own trade posture.

The central research question this article addresses is the following: how has China's trade policy toward the United States evolved between 2001 and 2025, and what are the principal drivers, instruments, and consequences of its transition from engagement to strategic competition? The paper argues that China's policy has moved through three overlapping phases—engagement, recalibration, and strategic competition—each shaped by the interaction of domestic industrial ambitions, external shocks, and the structural commitment problem that now characterizes Sino-American relations (Ciuriak, 2019).

The article is structured as follows. The first section establishes the theoretical foundations of trade policy evolution and strategic rivalry. The second section outlines the methodology. The third section analyzes the three phases of Chinese trade policy toward the United States. The fourth section presents findings and implications, and the conclusion identifies research gaps and future directions.

Literature Review and Theoretical Foundations

Trade Policy, GVCs, and Strategic Rivalry

Global Value Chain analysis provides a framework for understanding the internationally dispersed activities required to bring a product or service from conception to end use (Gereffi, Humphrey, & Sturgeon, 2005). Within this framework, national trade policy functions not only as a tariff schedule but as an instrument shaping a country's position within global production networks. Industrial upgrading—whether process, product, functional, or intersectoral—depends on the capacity of states and firms to negotiate access to technology, markets, and capital on favorable terms (Humphrey & Schmitz, 2002).

State intervention through industrial policy and trade measures is increasingly recognized as a critical factor reshaping GVC dynamics (Weiss & Thurbon, 2021). The Chinese case has received particular attention because of the scale and continuity of its state-led developmental strategy (Naughton, 2021). Complementing this literature, a strand of scholarship frames contemporary Sino-American trade tensions as the product of a commitment problem in which the incumbent power seeks to prevent shifts in relative capabilities by restricting the diffusion of strategic technologies. Under this logic, trade policy becomes an instrument of statecraft and technology is treated as a security asset (Ciuriak, 2019).

From Engagement to Geoeconomics

Much of the early literature on China's WTO-era trade policy emphasized convergence: the expectation that rules-based integration would gradually align Chinese regulatory practice with liberal norms. By the late 2010s, however, scholars increasingly described a shift toward a geoeconomic order in which economic tools serve strategic ends and global rules are under stress (Roberts, Moraes, & Ferguson, 2019). This shift was accelerated by the imposition of Section 301 tariffs and the progressive tightening of U.S. export controls administered through the Entity List and the Foreign Direct Product Rule, culminating in the October 2022 restrictions on advanced

computing chips and semiconductor manufacturing equipment (Bureau of Industry and Security, 2022).

Empirical studies document that the trade war and subsequent technology contest have produced measurable macro and sectoral losses, rewired supply chains, and prompted firms to diversify markets and accelerate domestic capability development. Model simulations indicate that non-cooperative tariff escalation reduced GDP in both China and the United States and produced substantial losses when global value chain linkages are taken into account. These findings provide the empirical backdrop against which China's evolving trade policy must be assessed.

Methodology

This research employs a qualitative, longitudinal policy analysis tracking the evolution of China's trade policy toward the United States from 2001 through 2025. The choice of a historical-institutional approach is driven by the need to capture both continuity and rupture across a quarter-century of policy development. Three analytical phases are identified—engagement (2001–2008), recalibration (2009–2017), and strategic competition (2018–2025)—and used as organizing devices for the discussion.

Data were collected and triangulated from multiple sources. Primary materials include Chinese government policy documents and five-year plans, WTO accession commitments and subsequent notifications, U.S. Trade Representative reports, regulatory filings from key Chinese firms, and bilateral trade statistics drawn from UN Comtrade and China Customs. Secondary materials include peer-reviewed academic literature, industry reports, and reputable international news sources. Analysis involved thematic coding for evidence of: (a) shifts in policy instruments; (b) changes in bilateral trade flows and investment patterns; (c) industrial and technological upgrading; and (d) discursive changes in official Chinese framing of the relationship.

Discussion: Three Phases of Chinese Trade Policy Toward the United States

Phase One: Engagement and WTO Integration (2001–2008)

China's accession to the WTO in December 2001 inaugurated a period of far-reaching trade liberalization and deepening integration with the United States. Beijing committed to extensive tariff reductions, the dismantling of non-tariff barriers, the opening of services sectors, and the progressive alignment of domestic regulation with WTO disciplines. The United States, for its part, granted China permanent normal trade relations and extended broad market access. Bilateral trade expanded dramatically during this period, and China rapidly became the principal assembly hub at the center of East Asian production networks.

Policy during this phase was characterized by a defensive-liberal posture. Chinese authorities prioritized macroeconomic stability, export competitiveness, and the cultivation of inward foreign direct investment as channels for technology transfer and managerial know-how. Trade frictions were handled predominantly through WTO dispute settlement mechanisms rather than through unilateral measures. The bilateral relationship was framed in official discourse as one of mutual benefit, with Chinese leaders repeatedly emphasizing the complementarity between the two economies.

Phase Two: Recalibration and Indigenous Innovation (2009–2017)

The global financial crisis of 2008–2009 marked an inflection point. The crisis exposed the vulnerabilities of an export-dependent growth model and accelerated Chinese policymakers' interest in upgrading the country's position within global value chains. Successive policy initiatives—including the Medium- and Long-Term Plan for the Development of Science and Technology, the Strategic Emerging Industries program, and ultimately the "Made in China 2025" blueprint announced in 2015—articulated an ambition to move from low-cost assembly toward high-value manufacturing and indigenous innovation in strategic sectors.

During this phase, Chinese trade policy toward the United States became increasingly bifurcated. On one hand, Beijing continued to support multilateral trade liberalization and WTO-based dispute resolution. On the other hand, it deployed a growing arsenal of industrial policy instruments, including large-scale state subsidies, preferential procurement, and targeted support for national champions. U.S. concerns about intellectual property practices, forced technology transfer, and state-led industrial ambitions intensified during this period and would become the rationale for the unilateral measures of the following phase (Ke, 2024).

Phase Three: Strategic Competition and Dual Circulation (2018–2025)

The initiation of Section 301 tariffs in 2018 marked the beginning of a qualitatively new phase in the relationship. The Office of the United States Trade Representative cited unfair trade practices related to technology transfer and intellectual property as the justification for phased tariff escalations on hundreds of billions of dollars of Chinese imports (USTR, 2018). Beijing responded with reciprocal tariffs on U.S. agricultural and industrial products, marking its first large-scale unilateral trade retaliation against Washington. The Phase One agreement of January 2020 partially de-escalated the tariff dispute but left the underlying structural tensions unresolved (Blanchard & Bown, 2021).

A more consequential shift occurred with the progressive tightening of U.S. export controls on advanced semiconductors and chip manufacturing equipment, culminating in the October 2022 measures administered through the Entity List and the Foreign Direct Product Rule. These controls cut off China's leading chipmakers from access to the most advanced EUV lithography machines and chip design software, directly throttling China's capacity for technological upgrading in foundational technologies. The restrictions have delayed Chinese ambitions to produce sub-7nm chips at scale, demonstrating the efficacy of controls in capping the leading edge of technology (Chepanoske, 2023).

China's response has combined defensive and offensive elements. Defensively, the Dual Circulation strategy announced in 2020 reoriented policy toward expanding domestic demand and reducing reliance on vulnerable external linkages, while preserving selective openness to international trade and investment. Offensively, Beijing has deployed a calibrated set of instruments including export controls on gallium, germanium, graphite, and rare-earth processing technologies, an expanded Unreliable Entity List, anti-monopoly investigations targeting foreign technology firms, and the accelerated development of indigenous alternatives in semiconductors, electronic design automation software, and lithography equipment.

The empirical results of this strategy are paradoxical. In semiconductors, U.S. controls have delayed China's ambitions at the leading edge while simultaneously accelerating a massive expansion of mature-node capacity backed by substantial state funding (Zhang & Choi, 2024). In electric vehicle batteries, Chinese firms such as CATL and BYD have fortified their dominance through process and product upgrading, vertical integration into upstream critical minerals via the Belt and Road Initiative, and technology licensing arrangements with Western automakers (Huang & Chen, 2024). The global value chain is repositioning into a bifurcated structure, with a U.S.-led advanced-node chain and a China-centric mature-node and green-technology chain increasingly decoupled from each other.

Findings and Implications

Theoretical Implications

This study contributes to the literature on trade policy and strategic rivalry by showing that China's trajectory from engagement to competition is best understood not as a sudden rupture but as a progressive recalibration shaped by cumulative policy shocks and domestic industrial ambitions. It reinforces the argument that, in an era of geostrategic competition, state-driven decoupling pressures can override traditional economic efficiency drivers in shaping global value chain structures. The analysis also supports the interpretation of U.S. restrictive measures as a

non-market form of demand-pull that has galvanized state and corporate resources toward technological self-sufficiency in the targeted economy.

Practical Implications

For policymakers and corporate strategists, the findings carry three principal implications. First, containment strategies focused on export controls are effective in capping the leading edge of technology in the short term but risk fostering a more capable, state-subsidized competitor in legacy and mid-range technologies over the longer term. Second, the repositioning of global value chains is not a cost-free exercise; multinational corporations face the "China Plus One" dilemma, needing to maintain access to the Chinese market while building parallel and more expensive supply chains for other markets. Third, the new geography of production is creating industrial hubs in Southeast Asia and Mexico that remain dependent on Chinese intermediates, components, and capital equipment, illustrating the complexity of truly decoupling from the world's manufacturing powerhouse.

For third countries, and particularly for Kazakhstan and its Central Asian neighbors, the evolving Sino-American rivalry creates both risks of entanglement and opportunities for diversified partnerships across logistics, critical minerals, and digital trade corridors linked to the Belt and Road Initiative.

Conclusion: Research Gaps and Future Directions

This paper has traced the evolution of China's trade policy toward the United States from WTO accession in 2001 through the strategic competition of 2025. The analysis demonstrates that Chinese policy has moved through three overlapping phases—engagement, recalibration, and strategic competition—each shaped by the interaction of domestic industrial ambitions and external shocks. The outcome is neither a simple victory for containment nor an unambiguous Chinese breakthrough, but rather a contested and evolving reality of bifurcation, resilience-building, and intensified competition.

Several research gaps warrant further investigation. First, sector-specific deep dives into aerospace, pharmaceuticals, and artificial intelligence would enrich the typology of vulnerability and resilience to decoupling pressures. Second, the impact of U.S. inbound and outbound investment screening on Chinese cross-border capital flows remains under-explored. Third, the environmental and social consequences of geopolitically driven supply-chain duplication deserve systematic study. Fourth, continuous longitudinal tracking is needed to determine whether Chinese indigenous innovation can overcome the technological bottlenecks imposed by export controls or will plateau, creating a persistent technological gap.

In conclusion, China's trade policy toward the United States has been irrevocably transformed. The period of unambiguous engagement has ended, replaced by a more calibrated and assertive posture in which trade policy serves as an instrument of strategic autonomy. The coming decade will test whether this posture can sustain China's manufacturing upgrading while avoiding the welfare costs of a deeper fragmentation of the global economic order.

References

- Blanchard, E. J., & Bown, C. P. (2021). The US-China trade war and Phase One agreement. *Journal of Policy Modeling*, 43(4), 805–843.
- Bown, C. P. (2020). How the United States marched the semiconductor industry into its trade war with China. *East Asian Economic Review*, 24(4), 349–388.
- Bureau of Industry and Security. (2022). Commerce implements new export controls on advanced computing and semiconductor manufacturing items to the People's Republic of China. U.S. Department of Commerce.
- Chepanoske, K. (2023). Choking off innovation: The impact of U.S. export controls on China's semiconductor industry. *Georgetown Journal of International Affairs*, 24(1), 112–119.

- Ciuriak, D. (2019). The US-China trade war: Technological roots and WTO responses. Social Science Research Network. <https://doi.org/10.2139/ssrn.3330392>
- Fajgelbaum, P., Goldberg, P., Kennedy, P., Khandelwal, A., & Taglioni, D. (2023). The US-China trade war and global value chains. *American Economic Review: Insights*, 5(2), 205–222.
- Gereffi, G., Humphrey, J., & Sturgeon, T. (2005). The governance of global value chains. *Review of International Political Economy*, 12(1), 78–104.
- Huang, W., & Chen, L. (2024). Securing the battery supply chain: China's BRI and the global race for critical minerals. *Energy Policy*, 185, 113955.
- Humphrey, J., & Schmitz, H. (2002). How does insertion in global value chains affect upgrading in industrial clusters? *Regional Studies*, 36(9), 1017–1027.
- Ke, W. (2024). The impact of US-China trade friction on China's high-tech sector. *Advances in Economics, Management and Political Sciences*, 86(1), 15–20.
- Kwan, C. H. (2020). The China-US trade war: Deep-rooted causes, shifting focus and uncertain prospects. *Asian Economic Policy Review*, 15(1), 55–72.
- Naughton, B. (2021). The rise of industrial policy in China, 1978–2020. In *The Chinese Communist Party in the new era* (pp. 123–145). Routledge.
- Roberts, A., Moraes, H. C., & Ferguson, V. (2019). Toward a geoeconomic order in international trade and investment. *Journal of International Economic Law*, 22(4), 655–676.
- USTR. (2018). Findings of the investigation into China's acts, policies, and practices related to technology transfer, intellectual property, and innovation under Section 301 of the Trade Act of 1974. Office of the United States Trade Representative.
- Weiss, L., & Thurbon, E. (2021). The business of state building: New directions in the study of states and markets. *Review of International Political Economy*, 28(5), 1075–1098.
- Zhang, K. H. (2020). Industrial policy and technology innovation under the US trade war against China. *Chinese Economy*, 53(5), 363–373.
- Zhang, Y., & Choi, H. (2024). Catching up in the legacy: China's booming mature-node semiconductor industry. *The China Quarterly*, 257, 1–20.
- Zhou, X. (2025). The geopolitical and economic consequences of the trade war between China and the United States. *Konfliktologiâ*, (2), 168–179.

A Holistic Model for Integrating AI, BI, IoT, and Cloud into Enterprise Decision-Making

Yang Na

DBA, Al-Farabi Kazakh National University, Kazakhstan

Asanova Daniya

DBA, PhD, Professor, Al-Farabi Kazakh National University, Kazakhstan

Olga Koshkina

c.e.s., assistant Professor, Al-Farabi Kazakh National University, Kazakhstan

Abstract

The convergence of artificial intelligence (AI), business intelligence (BI), the Internet of Things (IoT), and cloud computing is redefining enterprise decision-making processes by enabling real-time, data-driven, and predictive capabilities. However, organisations frequently adopt these technologies in isolation, resulting in fragmented architectures and suboptimal decision outcomes. This article proposes a holistic model for integrating AI, BI, IoT, and cloud technologies into a unified enterprise decision-making system.

Grounded in the Technology Acceptance Model (TAM), resource-based view (RBV), and socio-technical systems theory, the study adopts a conceptual methodology supported by interdisciplinary literature and secondary case evidence. The proposed model consists of four interdependent layers: data generation and acquisition (IoT), data integration and storage (cloud), analytics and intelligence (AI and BI), and decision orchestration and governance.

Findings indicate that integration across these layers enhances decision speed, accuracy, and adaptability, while persistent challenges—including data silos, interoperability constraints, and organisational resistance—limit effective implementation. The article further examines implications for emerging digital economies such as Kazakhstan, where national digitalisation strategies create opportunities for integrated enterprise systems. Managerial and policy recommendations are provided, along with directions for future research.

Keywords: artificial intelligence, business intelligence, IoT, cloud computing, enterprise decision-making, digital transformation, integration model

Introduction

Enterprise decision-making has evolved from intuition-based judgement to analytically supported processes, and increasingly toward fully data-driven and predictive systems. This transformation is driven by the rapid advancement of digital technologies, particularly artificial intelligence, business intelligence platforms, IoT-enabled sensing, and scalable cloud infrastructures.

Despite this technological progress, many organisations face a critical challenge: technological fragmentation. AI models are often deployed without integration into operational systems, BI dashboards remain descriptive rather than prescriptive, IoT data streams are underutilised, and cloud infrastructures function merely as storage rather than strategic enablers.

This fragmentation results in:

- Delayed decision cycles
- Inconsistent data interpretation
- Limited predictive capability
- Reduced organisational agility

This article argues that effective enterprise decision-making requires a holistic integration model, in which AI, BI, IoT, and cloud technologies function as a coherent ecosystem rather than independent components.

The relevance of this analysis is particularly strong in emerging markets such as Kazakhstan, where digital transformation initiatives—such as the *Digital Kazakhstan* programme—are accelerating technology adoption while exposing gaps in integration and organisational readiness.

Literature Review and Theoretical Foundations

Technological Convergence in Enterprise Systems

The literature increasingly highlights the convergence of digital technologies as a key driver of competitive advantage. AI enables predictive and prescriptive analytics, BI provides visualisation and reporting, IoT generates real-time data, and cloud computing ensures scalability and accessibility.

However, studies consistently emphasise that **integration**, rather than individual capability, determines organisational impact.

Artificial Intelligence and Decision Automation

AI technologies, including machine learning and deep learning, enable organisations to:

- Predict future trends
- Detect anomalies
- Optimise complex processes

Yet, without integration into decision workflows, AI remains underutilised.

Business Intelligence as a Decision Interface

BI systems serve as the interface between data and human decision-makers, translating analytical outputs into actionable insights. Modern BI platforms increasingly incorporate real-time analytics and interactive dashboards, but often lack predictive depth when not integrated with AI.

Internet of Things as Data Infrastructure

IoT devices provide continuous streams of operational data from physical environments, enabling real-time monitoring and control. However, challenges include:

- Data heterogeneity
- Security risks
- Integration complexity

Cloud Computing as an Enabler

Cloud platforms provide:

- Scalable storage
- Distributed computing
- Integration frameworks

They serve as the backbone of modern digital ecosystems but require effective governance to ensure reliability and security.

Theoretical Framework

This study integrates three theoretical perspectives:

- **Technology Acceptance Model (TAM)** – explains user adoption of integrated systems
- **Resource-Based View (RBV)** – positions integrated digital capabilities as strategic assets
- **Socio-Technical Systems Theory** – emphasises alignment between technology and organisational context

Together, these frameworks support the development of a holistic integration model.

Methodology

The study adopts a **conceptual research approach**, synthesising:

- Academic literature across information systems, management, and digital transformation
- Industry case studies of enterprise system integration
- Policy reports on digital economy development

Analytical Structure

The analysis focuses on four domains:

1. Data generation (IoT)
2. Data integration (cloud)
3. Analytics (AI and BI)
4. Decision orchestration

Each domain is examined in relation to organisational and institutional factors.

A Four-Layer Holistic Integration Model

Layer 1: Data Generation and Acquisition (IoT)

This layer captures real-time data from physical and digital environments, including:

- Sensors
- Operational systems
- User interactions

The objective is to create a continuous data flow that reflects organisational activities.

Layer 2: Data Integration and Storage (Cloud)

Cloud infrastructure consolidates and standardises data from diverse sources, enabling:

- Centralised data lakes
- Real-time processing
- Interoperability

This layer addresses data fragmentation and ensures accessibility.

Layer 3: Analytics and Intelligence (AI + BI)

This layer combines:

- AI for predictive and prescriptive analytics
- BI for visualisation and decision support

Integration ensures that insights are both **analytically robust and operationally accessible**.

Layer 4: Decision Orchestration and Governance

This layer translates insights into action through:

- Automated workflows
- Decision support systems
- Governance frameworks

It ensures alignment between analytical outputs and organisational objectives.

Discussion

Integration as a Strategic Capability

The proposed model highlights that integration is not merely technical but strategic. Organisations that successfully integrate AI, BI, IoT, and cloud technologies achieve:

- Faster decision-making
- Improved accuracy
- Greater adaptability

Barriers to Integration

Key challenges include:

- Data silos
- Lack of interoperability
- Organisational resistance
- Skill shortages

These barriers reflect socio-technical misalignment rather than technological limitations.

Economic and Operational Impact

Integrated systems enable:

- Predictive decision-making
- Process optimisation
- Risk reduction

This is particularly valuable in high-complexity environments such as logistics, finance, and manufacturing.

Implications for Kazakhstan

Kazakhstan's digital transformation creates opportunities for integrated enterprise systems, particularly in:

- Logistics corridors
- Smart cities
- Financial services

However, challenges include:

- Limited data literacy
- Institutional inertia
- Infrastructure gaps

Successful adoption requires coordinated policy and organisational efforts.

Findings and Implications

Key Findings

1. Integration is the primary determinant of digital transformation success
2. AI, BI, IoT, and cloud technologies must function as a unified system
3. Socio-technical alignment is critical for effective implementation

Managerial Implications

- Invest in integrated architectures rather than isolated tools
- Develop cross-functional data capabilities
- Align decision processes with analytical outputs

Policy Implications

- Promote interoperability standards
- Support digital skills development
- Encourage integrated digital ecosystems

Conclusion

This article has proposed a holistic model for integrating AI, BI, IoT, and cloud technologies into enterprise decision-making. By structuring these technologies into a unified four-layer system, the model addresses the fragmentation that currently limits organisational performance.

The findings emphasise that technological capability alone is insufficient; effective decision-making requires alignment between technology, people, and institutional frameworks. For emerging economies such as Kazakhstan, this integration represents both a challenge and an opportunity to accelerate digital transformation and enhance competitiveness.

Future research should focus on empirical validation of the model, cross-industry comparisons, and the development of governance frameworks for integrated digital systems.

References (APA Style)

Davis, F. D. (1989). Perceived usefulness, perceived ease of use, and user acceptance of information technology. *MIS Quarterly*, 13(3), 319–340.

Barney, J. (1991). Firm resources and sustained competitive advantage. *Journal of Management*, 17(1), 99–120.

Trist, E. (1981). The evolution of socio-technical systems. *Occasional Paper*, 2.

Davenport, T. H., & Harris, J. G. (2007). *Competing on analytics*. Harvard Business School Press.

McAfee, A., & Brynjolfsson, E. (2012). Big data: The management revolution. *Harvard Business Review*.

Artificial Intelligence and Predictive Maintenance for Super High-Rise Building Operations: A China-Focused Framework

Yuan Xiaoying

Al-Farabi Kazakh National University, Kazakhstan, *Business School*

Asanova Daniya

DBA, PhD, Professor, Al-Farabi Kazakh National University, Kazakhstan, *Business School*

Olga Koshkina

c.e.s., assistant Professor, Al-Farabi Kazakh National University, Kazakhstan, *Business School*

Abstract

Super high-rise buildings in China concentrate extreme structural loads, complex mechanical and electrical systems, and dense occupant populations into vertical envelopes whose failure modes are costly and difficult to reverse. This article proposes a China-focused framework for the application of artificial intelligence (AI) and predictive maintenance (PdM) in the operation of super-tall buildings, drawing on Chinese empirical evidence from landmark projects such as Shanghai Tower and Tianjin 117, as well as pilot integrated safety platforms in Shanghai. Grounded in the Technology Acceptance Model (TAM) and socio-technical systems theory, the study adopts a conceptual methodology supported by secondary data analysis. The proposed framework integrates four layers: sensor and data acquisition, AI analytics, decision orchestration, and institutional governance. Findings suggest that AI-enabled PdM can shift super high-rise operations from reactive and schedule-based maintenance toward condition-based and prognostic regimes, reducing downtime, energy waste, and safety risk. Implications are discussed for Chinese operators and for Belt and Road Initiative (BRI) partner economies such as Kazakhstan, where similar systems are emerging in logistics hubs and high-rise public facilities. The article concludes with policy, managerial, and research recommendations.

Keywords: artificial intelligence, predictive maintenance, super high-rise buildings, structural health monitoring, Building Information Modelling, Belt and Road Initiative, China

Introduction

Maintenance has historically been one of the least visible but most consequential aspects of super high-rise building operation. A single undetected fault in a chiller, elevator drive, fire pump, or curtain-wall anchorage can cascade into occupant discomfort, energy waste, regulatory exposure, and, in extreme cases, loss of life. As Chinese cities accumulate an increasingly large stock of buildings exceeding 150 metres in height, the limits of reactive and purely schedule-based maintenance have become apparent, and operators are turning to artificial intelligence and predictive maintenance as the next stage of smart building management.

Predictive maintenance uses condition data, historical failure records, and analytical models to forecast when equipment or structural components are likely to require intervention, allowing maintenance to be performed just in time rather than too early or too late. When combined with artificial intelligence techniques such as machine learning, anomaly detection, and deep neural networks, PdM can process the high-volume, high-velocity data streams generated by modern super-tall buildings and extract patterns that are invisible to human operators. Chinese landmark projects have already laid much of the groundwork for this transition through dense

structural health monitoring networks, integrated safety platforms, and BIM-coordinated facility management workflows.

This article develops a China-focused framework for AI-enabled predictive maintenance in super high-rise building operations. It is motivated by three observations: that the technical preconditions for AI and PdM are increasingly present in Chinese super-tall buildings; that institutional and regulatory conditions frequently lag behind technical capability; and that lessons learned in China are directly relevant to Belt and Road Initiative partner economies such as Kazakhstan, where similar technologies are being introduced through cross-border urban development projects.

Literature Review and Theoretical Foundations

The Chinese literature on super high-rise management provides a strong empirical foundation for AI and predictive maintenance. Structural health monitoring deployments at Shanghai Tower, which combines a main station with eleven substations, demonstrate how continuous measurement of structural responses can feed finite-element model updates and account for time-dependent concrete effects such as creep and shrinkage. Tianjin 117 offers a complementary example in which varied sensors, data acquisition hardware, and modular monitor and analysis software exchange data with numerical models for construction-stage assessment and ongoing evaluation. These deployments generate precisely the kind of long-horizon, multi-channel data on which predictive algorithms depend.

Integrated safety management platforms developed in Shanghai extend the same logic to fire and enclosure subsystems, combining structural, firefighting, and utility data through reserved IoT interfaces to enable comprehensive assessment and early warning. Research on distributed control architectures for lighting, HVAC, and fire detection further documents the operational data that AI-enabled PdM can exploit, with case studies reporting lighting energy savings in excess of sixty percent and tighter HVAC control. BIM is increasingly positioned as a coordinating layer through which fire safety, HVAC, security, surveillance, and operation and maintenance data can be harmonised across the building life cycle.

At the same time, the literature consistently identifies obstacles that any AI and PdM framework must address. Integrated Building Management System designs face data-access, integration, and collaboration bottlenecks that limit the flow of information from subsystems into analytical models. Reports on high-rise fire safety note that existing rules are frequently not implemented on site and that long-standing electrical and ignition hazards persist in practice. Researchers advocate stronger laws, clearer governmental and trade-association roles, and broader owner, operator, and occupant engagement as preconditions for effective life-cycle management.

Theoretically, this study is grounded in the Technology Acceptance Model, which identifies perceived usefulness and perceived ease of use as principal determinants of technology adoption, and in socio-technical systems theory, which emphasises the mutual shaping of technical artefacts and their social, organisational, and regulatory contexts. AI and predictive maintenance are not purely technical interventions; their success depends on whether operators trust algorithmic recommendations, whether institutional arrangements allow those recommendations to be acted upon, and whether regulatory frameworks recognise condition-based evidence as a legitimate basis for maintenance decisions.

Methodology

The study adopts a conceptual methodology that combines a focused review of Chinese empirical and engineering literature on super high-rise management with secondary case evidence from landmark projects and pilot integrated platforms. Sources were selected on the basis of relevance to structural health monitoring, integrated safety management, distributed control, and BIM-enabled facility management in buildings exceeding 150 metres in height, with

preference given to peer-reviewed and engineering-practice publications. Broader international literature on artificial intelligence and predictive maintenance was used to situate the Chinese evidence within the wider technical discourse.

Analysis proceeds in two stages. The first stage identifies the technical, organisational, and regulatory conditions under which AI and PdM can be effective in Chinese super-tall buildings. The second stage synthesises these conditions into a four-layer framework encompassing sensor and data acquisition, AI analytics, decision orchestration, and institutional governance. The framework is interpreted through the combined lens of TAM and socio-technical systems theory, and its transferability is examined with reference to BRI-linked urban development in Kazakhstan.

A Four-Layer Framework for AI-Enabled Predictive Maintenance

The first layer of the proposed framework is sensor and data acquisition. Drawing on the Shanghai Tower and Tianjin 117 deployments, this layer comprises dense networks of strain gauges, accelerometers, temperature and humidity sensors, energy meters, and equipment-level condition sensors, integrated with data acquisition hardware and time-synchronised storage. The objective is to generate continuous, validated data streams covering structural behaviour, mechanical and electrical equipment health, environmental conditions, and energy performance, with sufficient resolution to support prognostic analytics rather than merely retrospective reporting.

The second layer is AI analytics. Machine learning models, including supervised classifiers for known failure modes, unsupervised anomaly detection for novel events, and sequence models for time-dependent behaviour, are applied to the data streams generated by the first layer. For structural components, analytics must explicitly account for time-dependent concrete effects such as creep and shrinkage, consistent with the modelling challenges identified in Shanghai Tower research. For mechanical and electrical equipment, analytics estimate remaining useful life, flag incipient faults, and rank interventions by risk and cost. Integration with finite-element models allows structural observations to update engineering assumptions dynamically.

The third layer is decision orchestration. Analytical outputs are translated into actionable maintenance work orders, safety alerts, and operational adjustments through a BIM-coordinated platform that unifies structural, fire safety, HVAC, security, and surveillance data. This layer aligns with the dynamic BIM models proposed in the Chinese literature as a framework for integrating diverse building subsystems across the life cycle. Clear escalation protocols and human-in-the-loop review ensure that algorithmic recommendations are contextualised by experienced operators, particularly in safety-critical domains such as fire response and structural assessment.

The fourth layer is institutional governance. This layer addresses the socio-technical conditions identified in the literature as critical to effective high-rise management, including clear legal frameworks, defined responsibilities for owners, operators, and occupants, and mechanisms for multi-party participation in life-cycle safety and maintenance planning. Without this layer, the technical capabilities of the first three layers remain underutilised, as analytical insights fail to translate into enforceable action. The governance layer also specifies data standards, reporting obligations, and audit mechanisms that support regulatory trust in AI-generated maintenance evidence.

Discussion

The proposed framework repositions predictive maintenance as an integrated operational capability rather than a collection of isolated tools. In Chinese super-tall buildings, the technical preconditions for such integration are largely in place: dense SHM networks, integrated safety platforms, and BIM-coordinated facility management are documented in the engineering literature and demonstrated in landmark projects. What is missing in many cases is the orchestration and governance that would allow these capabilities to function as a coherent system rather than as parallel data silos.

AI and predictive maintenance also reshape the economics of super high-rise operation. By shifting from reactive repairs and fixed-interval servicing toward condition-based interventions, operators can reduce unplanned downtime, extend the useful life of capital equipment, and avoid the energy penalties associated with degraded HVAC and lighting performance. These benefits are particularly significant in super-tall buildings, where access for manual inspection is costly and where the consequences of equipment failure propagate rapidly through tightly coupled systems.

The socio-technical dimension of the framework is especially important in the Chinese context, where the literature documents persistent gaps between regulatory intent and on-site enforcement. TAM suggests that operators will adopt AI-enabled PdM tools to the extent that they perceive them as useful and easy to use; socio-technical systems theory adds that these perceptions are conditioned by organisational culture, training, and the credibility of the institutions that stand behind the technology. A framework that addresses only the technical layers is therefore likely to underperform, while one that explicitly incorporates governance and user acceptance stands a greater chance of delivering the promised benefits.

The Belt and Road Initiative provides a natural pathway for transferring the framework to partner economies. In Kazakhstan, where Digital Kazakhstan and BRI-linked urban development projects are introducing smart infrastructure into logistics hubs, public utilities, and high-rise public buildings, the four-layer structure offers a template for adapting Chinese experience to local conditions. Transferability depends on matching the technical layers to available sensor and data infrastructure while adjusting the governance layer to Kazakhstani legal and institutional realities.

Findings and Implications

Three principal findings emerge from the analysis. First, Chinese super-tall buildings already generate the data volumes and varieties required to support AI-enabled predictive maintenance, and landmark projects demonstrate the feasibility of continuous monitoring and model updating. Second, the operational value of these data depends on a decision orchestration layer that unifies subsystems through BIM and on a governance layer that translates analytical insights into enforceable action; without these, predictive capability does not become predictive practice. Third, the framework is transferable to BRI partner economies such as Kazakhstan when the governance layer is adapted to local conditions.

The managerial implications are that operators should treat AI and predictive maintenance as a portfolio of integrated capabilities rather than a series of point solutions, prioritising investments that strengthen the weakest layer rather than simply adding more sensors or more sophisticated algorithms. Policy implications include the need for clearer Chinese and Kazakhstani rules on data standards, maintenance recordkeeping, and the admissibility of AI-generated evidence in safety audits. Theoretically, the findings support extending TAM and socio-technical systems theory into the specific context of algorithmic maintenance decisions in high-consequence built environments.

Conclusion

This article has proposed a China-focused framework for the application of artificial intelligence and predictive maintenance to super high-rise building operations, organised around sensor and data acquisition, AI analytics, decision orchestration, and institutional governance. Drawing on Chinese empirical evidence from Shanghai Tower, Tianjin 117, and Shanghai integrated safety platforms, and grounded in the Technology Acceptance Model and socio-technical systems theory, the framework articulates both the technical possibilities and the institutional conditions under which AI-enabled PdM can deliver meaningful operational improvements. Extensions to BRI partner economies such as Kazakhstan underscore the international relevance of the Chinese experience.

Research gaps remain in longitudinal empirical evaluation of AI-enabled PdM deployments, in comparative studies across jurisdictions with different regulatory environments,

and in the development of explainable AI techniques that support operator trust in high-consequence decisions. Future work should pursue field studies in operating super-tall buildings, cross-border benchmarking of BRI-linked projects, and the integration of AI, BIM, and digital-twin technologies into unified operational platforms aligned with net-zero and resilience objectives.

References

- Gong, J. C., Fang, T., & Zuo, J. (2022). A review of key technologies development of super high-rise building construction in China. *Advances in Civil Engineering*, 2022, 1–13. <https://doi.org/10.1155/2022/5438917>
- Jin, C. (2015). Automatic management system of high-rise building.
- Liu, Z., & Liu, Y. (2015). An exploration of system architecture on integrating building management system in high-rise building, 342–345. <https://doi.org/10.18293/SEKE2015-206>
- Lu, J., & Zheng, B. (2021). Research and development of comprehensive safety management system for super-tall buildings in Shanghai. *E3S Web of Conferences*, 236, 05008. <https://doi.org/10.1051/e3sconf/202123605008>
- Mujumdar, P., & Agarwal, S. Integrating building management systems in high-rise structures using building information modeling. <https://doi.org/10.38027/iccaua2024in0320>
- Pan, M. X., & Wang, X. (2022). All-round control of high-rise buildings by construction organization design based on distributed control system. *Mobile Information Systems*, 2022, 1–14. <https://doi.org/10.1155/2022/7064892>
- Peihong, Z., Kan, W., Huanhuan, W., & Zhongjiao, M. Fuzzy-AHP-based comprehensive evaluation on facility management system of high-rise office buildings. <https://doi.org/10.3969/j.issn.2095-1922.2005.03.017>
- Technical management and risk management practices for a high-rise public building project in Guangzhou Nansha Free Trade Zone. (2025). *Journal of World Architecture*, 9(5), 82–88. <https://doi.org/10.26689/jwa.v9i5.12523>
- Xiaoying, Y., Daniya, A., & Koshkina, O. Smart high-rise buildings and their role in China's urbanization strategy.
- Xiaoying, Y. Energy efficiency and carbon emission reductions through smart management systems in Chinese skyscrapers. Al-Farabi Kazakh National University.
- Zhang, Q., Yang, B., Liu, T., Li, H., & Lv, J. L. (2015). Structural health monitoring of Shanghai Tower considering time-dependent effects, 39–45.
- Zhi-jun, Y., Yan, H., Gang-qiang, F., Guo, Z., & Chao, S. Fire controlling management system of high-rise office building. <https://doi.org/10.3969/j.issn.1672-7312.2013.02.005>
- Davis, F. D. (1989). Perceived usefulness, perceived ease of use, and user acceptance of information technology. *MIS Quarterly*, 13(3), 319–340.
- Trist, E. (1981). The evolution of socio-technical systems. Occasional Paper, 2.

GREEN ECONOMY: PATHWAYS TO SUSTAINABLE DEVELOPMENT IN THE 21ST CENTURY

Nino Tchanturia

Assistant professor Georgian International University, Georgia <https://orcid.org/0000-0003-1894-5822>

Rusudan Dalakishvili

Davit Agmashenebeli National Defence Academy of Georgia, Georgia
<https://orcid.org/0009-0008-2791-6250>

Zurab Mushkudiani

Professor Georgian International University, Georgia <http://orcid.org/0000-0003-0987-3564>:

ANNOTATION

The green economy is a big deal for our planet. It is one of the important changes we will see in the twenty first century. The green economy is a way to make sure our economy grows. Also that we do not hurt the environment and that everyone is treated fairly.

This article looks at what the green economy's all about how it works and how it can be used in countries that are still developing. We are talking about the green economy concept and how it can help countries that want to skip the way of doing things and start fresh.

We looked at examples from around the world and we also looked at big picture economic data and how the environment is doing. The green economy is when governments, businesses and people work together to create a kind of economy that uses less carbon is more efficient and is fair to everyone.

What we found out is that for the green economy to work governments need to invest money in the things they need to change some rules and countries need to work together. If we do these things the good things that will happen to the economy will be much bigger than the problems we will face at first. The green economy is a thing, for everyone and it is something we should all be working towards.

Keywords: green economy, sustainable development, climate change, renewable energy, circular economy, environmental policy, low-carbon transition, ecological economics.

1. INTRODUCTION

The idea of the green economy came about because of the big problems we faced at the start of the twenty-first century: climate change getting worse losing biodiversity running out of resources and people not being treated equally. The old ways of doing economics, where we just keep making and using things without thinking about the consequences do not work to solve these problems. The United Nations Environment Programme said the green economy is one that makes people's lives better and treats everyone fairly while also reducing the risks to the environment and making sure we do not run out of resources. This means we have to do two things: make sure

that economic growth does not hurt the environment and make sure that everyone benefits from this change no matter where they live or when they will be born.

We need to make this change because the Intergovernmental Panel on Climate Change said that if we do not reduce the bad things we put into the air the Earth will get too hot. If we do not act it will cost us a lot of money: the Stern Review on the Economics of Climate Change said that if we do nothing the worlds economy could get 20 percent smaller by the end of the century. This is much more than what we would have to spend to prevent climate change.

Many countries are now talking about the economy. The European Green Deal, the United States Inflation Reduction Act Chinas promise to not make carbon and many countries saying they will not make more carbon show that governments are serious about changing the way we do economics.. It is not easy to make these changes happen because there are many obstacles, like not having enough money or the right institutions. This article wants to help people understand the economy better by looking at what it means what we know about it and what problems we face.

The rest of this article is divided into sections. Section 2 looks at where the idea of the economy came from and how it is related to other ideas, like sustainable development and the circular economy. Section 3 looks at what helps and what hurts the transition using examples from rich and poor countries. Section 4 looks at how money and investment can help us make the transition to the economy. Section 5 talks, about how the green economy affects people about making sure that everyone has a fair chance to work. Section 6 looks at how the green transition will change the way countries work together on economics. Section 7 gives ideas for what governments can do. Section 8 sums everything up.

2. CONCEPTUAL FRAMEWORK: DEFINING THE GREEN ECONOMY

The idea of the economy came about because of the big problems we are facing today: climate change is getting worse we are losing biodiversity we are running out of resources and there is still a lot of social inequality. The old way of doing economics, where we just make and use things without thinking about the consequences is not working. The United Nations Environment Programme says that the green economy is one that makes peoples lives better and is fair while also reducing the risks to the environment. This means we need to make sure that our economy is not hurting the planet and that everyone gets to benefit from the changes we make.

The green economy is very important because of what the Intergovernmental Panel on Climate Change has said. They have warned us that if we do not reduce the things we are putting into the air the Earth will get too hot. If this happens it will be very bad for the economy. In fact it could make the worlds economy 20 percent smaller by the end of the century. This is a lot of money. It would be better to spend a little now to prevent this from happening.

Many countries are now talking about the economy and making plans to reduce their impact on the environment. The European Green Deal, the United States Inflation Reduction Act and Chinas promise to be carbon neutral are all examples of this. However it is not easy to make these changes. There are many obstacles. This article wants to help people understand the economy better by looking at the ideas behind it the facts and the challenges.

The idea of the economy comes from a bigger idea called ecological economics. This started in the 1980s when some scholars said that the old way of doing economics was not good for the environment. They said that we need to think about the world and how it affects our economy. This idea was developed further in the 1987 Brundtland Report, which said that we need to develop in a way that does not hurt the environment.

The green economy takes this idea further by saying that we need to change the way our economy works. We need to make an economy, where we do not waste things and we keep using the same materials. This is different from the way, where we just throw things away. The green economy also wants to make sure that everyone is treated fairly and that the benefits of the changes are shared by all.

Some people have said that the green economy is not fair to everyone. They say that it is a way for rich countries to get what they want while poor countries are left behind. However others say that we can make the green economy fair if we make sure that everyone gets a share of the benefits. We need to make sure that the people who are most affected by the changes are not hurt by them. The green economy is an idea and it will take a lot of work to make it happen.. If we do it right it could be very good for everyone and, for the planet.

3. DRIVERS AND BARRIERS OF THE GREEN TRANSITION

The green transition is happening because of a lot of things coming together. Technology is a part of it. The cost of panels, wind energy, batteries and electric cars has gone down a lot over the last ten years. This has changed the way we think about energy that does not hurt the environment. The cost of energy has fallen by about 89 percent between 2010 and 2022. This makes it the cheapest way to make electricity in most of the world. The reason for this is that companies have gotten better at making these things and can do it on a scale. This has made it attractive for people to invest in energy without needing special incentives from the government.

On the hand people are becoming more aware of environmental issues. They want products and businesses that're good for the environment. Big investors like pension funds and insurance companies are starting to think about climate change when they make investment decisions. They want to put their money into things that're good for the environment. The European Union has also made rules to help investors know what is good for the environment and what is not.

The green transition is not easy. We need to invest in things like energy storage and better grids so that we can use energy all the time. We also need to find a way to get the materials we need for energy, like lithium and cobalt without hurting the environment or people. This is a challenge. We also need governments to make rules that help investors feel safe and encourage them to invest in energy. One big problem is that governments are still giving money to companies that make fuels. This makes it harder for clean energy to compete. The International Monetary Fund says that governments gave about 5.9 trillion dollars to fossil fuel companies in 2020. This is a barrier, to the green transition. To overcome this we need leaders who're committed to change and can bring people together to make it happen. We also need to make sure that people who are hurt by the transition are taken care of. The green transition is a challenge but it is also a big opportunity for the green transition to make a difference. The green transition requires a lot of work. It is worth it for the green transition to succeed.

4. GREEN FINANCE AND INVESTMENT

The idea of using finance to help our planet is a big deal. We need to make sure we have money to make a change. The International Energy Agency says that to have no emissions by 2050 we need to spend a lot more money on clean energy. We are talking about going from around 1.8 trillion dollars in 2023 to over 4.5 trillion dollars by 2030. Most of this money will come from companies but they need the government to make good rules and reduce risks so they can invest safely.

Green bonds are a way to get money for projects that help the environment. The European Investment Bank started selling these bonds in 2007. Now we have over 500 billion dollars in bonds every year and over 2 trillion dollars in total. This is news but some people are worried that these bonds are not really helping the environment as much as they claim. We need to make sure we

have rules and checks in place so people do not pretend to be helping when they are not. We need to make sure everyone agrees on what makes a bond truly green.

Public development banks, like the World Bank and the Asian Development Bank are very important, for helping countries that're not as rich. These banks can give money and advice to help private companies invest in projects that might be too risky otherwise. However these banks do not have money to do everything they need to do. They also have rules that can slow them down when they need to act. Green finance is crucial. We need to make sure these banks can do their job properly to help with the green transition and green finance. The green finance sector needs to work to make this happen and green finance will play a big role in our future.

5. SOCIAL DIMENSIONS: JUST TRANSITION AND EMPLOYMENT

The green economy has parts that are just as important as the environmental and economic parts. The idea of a transition was first thought of by labor unions when they saw how industrial restructuring was affecting the economy. Now it is a part of the green economy talk. A just transition means that the costs and benefits of moving to a low-carbon economy are shared fairly. This means that workers and communities that depend on fossil fuel industries are given alternatives. It also means that vulnerable groups are protected from energy poverty and other bad social things that can happen during the transition.

The green transition is going to affect jobs in a way. It depends on the context. The International Labour Organization says that the transition to a zero economy could create up to 30 million jobs in clean energy and related areas by 2030. However we have to think about the jobs that will be lost in coal mining, oil and gas extraction and factories that make a lot of carbon. The green transition will affect some regions and communities more than others. This means that the overall effect on jobs will not be the same

To deal with these problems we need to have a plan for industries invest in education and retraining and have systems in place to help workers who lose their jobs. We also need to help communities that depend on fuels to find new ways to make money. We can learn from what happened in coal-mining areas, in Germany the United Kingdom and the United States. They show us what works and what does not when it comes to managing decline and promoting economic renewal. The green economy and the green transition are important. We need to think about the parts of the green economy and the green transition. The green economy and the green transition will affect peoples lives.

6. GEOPOLITICAL IMPLICATIONS OF THE GREEN TRANSITION

The social parts of the economy are just as important as the environmental and economic parts. The idea of a transition, which was first developed by labor unions because of the economic problems caused by industrial changes is now a big part of the green economy talk. A just transition means that the costs and benefits of moving to a low-carbon economy are shared fairly that workers and communities that depend on fossil fuel industries are given alternatives and that vulnerable groups are protected from energy poverty and other bad social effects of the transition. The effects of the transition on jobs are complicated and depend on the situation. Some estimates say that the transition to a zero economy could create up to 30 million jobs in clean energy, energy efficiency and related areas by 2030 according to the International Labour Organization.. We have to think about the fact that workers in coal mining, oil and gas extraction and industries that use a lot of carbon will lose their jobs. The fact that fossil fuel jobs are concentrated in areas and communities means that the overall effect of the transition on jobs while it could be good will not be shared equally.

The green transition is changing the way energy and resources work in a way. Moving away from fuels is changing how important oil- and gas-producing countries are and many of these countries have based their economies on oil and gas money. Countries like Saudi Arabia, Russia and Nigeria are facing long-term challenges to their economic development models and have to navigate a hard transition to economies that are not based on fossil fuels. How fast and well this transition is managed will have effects on political stability in these countries and on global energy security. At the time the green transition is creating new dependencies between countries based on important minerals and clean energy technologies. The fact that China makes most of the panels, wind turbines, batteries and electric vehicles and controls a lot of the processing of important minerals has made Western governments worried about how strong their supply chains are and if they are vulnerable to strategic attacks. The response has been to make policies that bring clean energy supply chains back home or to friendly countries, like the United States Inflation Reduction Act and the European Unions Critical Raw Materials Act. We do not know yet what the long-term effects of these policies will be on trade patterns investment flows and international cooperation, on climate change.

7. POLICY RECOMMENDATIONS

The green economy is something that a lot of people want to happen. So this article has some ideas for governments and companies that want to make this happen.

First governments need to make rules about carbon. This means they should charge people for the things they put in the air like carbon. They can do this by charging a tax on carbon or by making a system where people can trade the things they put in the air. The money from this should be used to help people who are hurt by the change to the economy. Also governments should stop helping fossil fuel companies because this is bad for the air.

Second governments should make plans for the future. They should say what they want to happen and make rules to help this happen. This will help companies feel safe to invest in the economy.

Third some banks that help countries should lend more money to green projects. They can do this by working with companies and helping them feel safe to invest.

Fourth governments and companies should work together to make clean technologies. This means they should invest in things like ways to store energy make green hydrogen and make planes fly without hurting the air. They should also work together with countries to share ideas and make new technologies.

Fifth the green economy is not about technology it is also, about people. So governments need to talk to the people who will be hurt by the change and help them. They need to teach people skills and help them if they lose their jobs. The green economy should be something that helps everyone, not some people.

8. CONCLUSION

The green economy is not about taking care of the environment it is a real chance to create a new way of being successful that is stronger, fairer and works well with nature. The green economy is very important for our being.

The information in this article shows that it makes sense to switch to an economy: doing nothing will cost a lot more than taking action and switching to a green economy will create many new jobs, industries and technologies. However to make this happen governments, businesses, investors and people need to work and be brave.

The green transition is already. It is changing the way we make energy the way industries work and the way economies grow. The big question now is will this change happen fast to stop the worst effects of climate change and will everyone get a fair share of the benefits and problems.

To make sure this happens we need to think about the system plan for the long term and make sure everything is fair. The green economy is very important. We need to take action now. We need to think about the economy and how it can help us. The green economy is the key, to a future.

REFERENCES

1. Daly, H. E. (1996). *Beyond Growth: The Economics of Sustainable Development*. Beacon Press.
2. Costanza, R., et al. (1997). The value of the world's ecosystem services and natural capital. *Nature*, 387(6630), 253–260.
3. Stern, N. (2007). *The Economics of Climate Change: The Stern Review*. Cambridge University Press.
4. UNEP (2011). *Towards a Green Economy: Pathways to Sustainable Development and Poverty Eradication*. United Nations Environment Programme.
5. IPCC (2022). *Climate Change 2022: Mitigation of Climate Change. Contribution of Working Group III to the Sixth Assessment Report*. Cambridge University Press.
6. International Energy Agency (2023). *World Energy Outlook 2023*. IEA Publications.
7. International Monetary Fund (2021). *Still Not Getting Energy Prices Right: A Global and Country Update of Fossil Fuel Subsidies*. IMF Working Paper WP/21/236.
8. International Labour Organization (2018). *World Employment Social Outlook 2018: Greening with Jobs*. ILO Publications.
9. Brundtland, G. H. (1987). *Our Common Future: Report of the World Commission on Environment and Development*. Oxford University Press.
10. Geissdoerfer, M., et al. (2017). The Circular Economy – A new sustainability paradigm? *Journal of Cleaner Production*, 143, 757–768.
11. Pollin, R. (2015). *Greening the Global Economy*. MIT Press.
12. European Commission (2020). *The European Green Deal*. COM(2019) 640 final.
13. BloombergNEF (2023). *New Energy Outlook 2023*. BloombergNEF.
14. Chancel, L., et al. (2022). *World Inequality Report 2022*. World Inequality Lab.
15. Sachs, J. D. (2015). *The Age of Sustainable Development*. Columbia University Press.

РОЛЬ И ЗНАЧЕНИЕ УСТОЙЧИВОГО РАЗВИТИЯ В СТРАТЕГИЧЕСКОМ УПРАВЛЕНИИ МЯСОПЕРЕРАБАТЫВАЮЩИМИ ПРЕДПРИЯТИЯМИ РЕСПУБЛИКИ КАЗАХСТАН

Новикова Юлия Владимировна

магистрант международного университета Астана, г. Астана, Казахстан

Насырова Анар Мирамбековна

PhD, ассоциированный профессор, Международный университет Астана, г. Астана, Казахстан

Аннотация. В статье рассматривается роль устойчивого развития в системе стратегического управления мясоперерабатывающими предприятиями Республики Казахстан. Раскрывается значение экономических, экологических и социальных факторов устойчивости для обеспечения долгосрочной конкурентоспособности отрасли. Особое внимание уделено проблемам низкой доли глубокой переработки, технологической отсталости, нестабильности сырьевой базы и высокой зависимости от мелких фермерских хозяйств. Проведен сравнительный анализ уровня развития мясоперерабатывающей отрасли Казахстана с показателями стран Европейского Союза и США, что позволяет выявить ключевые ограничения и перспективы роста. В статье подчёркивается роль государственной поддержки, цифровизации, внедрения международных стандартов качества и инновационных технологий как основных инструментов повышения устойчивости предприятий. Сделан вывод о необходимости комплексной модернизации отрасли, развития кооперации и углубления переработки сырья для усиления экспортного потенциала и интеграции Казахстана в глобальные продовольственные цепочки.

Ключевые слова: устойчивое развитие, стратегическое управление, мясоперерабатывающая отрасль, агропромышленный комплекс, глубокая переработка мяса, инновационные технологии, государственная поддержка, экспортный потенциал

В современном экономическом дискурсе концепция устойчивого развития занимает ключевое место, выступая фундаментом для стратегического планирования и анализа. По международным стандартам устойчивое развитие понимается как сбалансированное сочетание экономических, социальных и экологических интересов общества. Данный подход предполагает, что экономический рост должен осуществляться без ущерба для природных систем и без создания рисков для будущих поколений. Особую актуальность эта концепция приобретает в агропромышленной сфере, поскольку производство продовольствия напрямую зависит от состояния природных ресурсов — земли, водных экосистем, биоразнообразия и энергетического обеспечения. Истощение природной базы или деградация экосистем неминуемо приводит к снижению производительности и

устойчивости сельскохозяйственных предприятий. Поэтому устойчивость рассматривается как комплексное свойство, включающее экологическую стабильность, социальное равновесие и экономическую эффективность сельских территорий.

Для мясоперерабатывающих предприятий Казахстана принципы устойчивого развития становятся стратегически значимым ориентиром, определяющим долгосрочную конкурентоспособность отрасли. Зависимость от природно-климатических условий, нестабильность сырьевых поставок и высокая ресурсоёмкость производства вынуждают предприятия оптимизировать потребление энергии и воды, повышать эффективность технологических процессов, сокращать производственные потери и минимизировать отходы. Особенно актуально это на фоне того, что доля глубокой переработки в стране удерживается на уровне 30–35 %, что заметно уступает показателям развитых государств. Экологическая составляющая устойчивости становится основным условием интеграции в международные цепочки поставок. Для выхода на рынки Китая, государств Персидского залива и ЕАЭС предприятиям необходимо соответствовать международным экологическим и санитарным требованиям. Поэтому внедрение современных систем утилизации отходов, снижение выбросов и применение санитарно-защитных технологий становятся неотъемлемой частью стратегических решений отрасли.

Существенную роль играет также развитие систем цифровой прослеживаемости. Казахстан последовательно внедряет электронную ветеринарную систему, обеспечивающую контроль движения сырья и готовой продукции. Это повышает прозрачность поставок, укрепляет доверие зарубежных партнёров и способствует формированию устойчивого экспортного потенциала. Активное внедрение ESG-подходов, автоматизированных производственных линий, энергоэффективных технологий и цифровых систем контроля качества укрепляет технологическую устойчивость предприятий и снижает производственные риски. Так, устойчивость выступает ключевым направлением стратегического управления, обеспечивая адаптацию отрасли к глобальным вызовам и усиление конкурентных преимуществ Казахстана на мировом рынке.

Мясоперерабатывающая отрасль Казахстана характеризуется высокой зависимостью от животноводства, значительную часть которого формируют мелкие фермерские хозяйства. Подобная структура затрудняет обеспечение стабильных объемов и качества сырья, что делает необходимым развитие кооперационных механизмов. Высокая капиталоемкость отрасли предполагает постоянные инвестиции в модернизацию оборудования, холодильные комплексы и санитарные системы, особенно на фоне изношенности производственных мощностей, характерной для значительного числа предприятий. Дополнительные сложности возникают в связи с соблюдением строгих ветеринарно-санитарных требований и необходимостью адаптироваться к международным стандартам качества. Географические особенности страны создают существенные логистические издержки и повышают себестоимость продукции. Низкая доля глубокой переработки ограничивает формирование добавленной стоимости и снижает экспортный потенциал. Всё это подчёркивает необходимость стратегической модернизации отрасли, совершенствования технологических процессов и усиления интеграции в международные цепочки поставок.




Рисунок 1. Основные показатели работы промышленности

Промышленная отрасль Казахстана по итогам десяти месяцев 2025 года демонстрирует устойчивый рост, что отражается в увеличении индекса промышленного производства до 107,3%. Особенно заметное ускорение наблюдается в сырьевом сегменте: объемы добывающей промышленности выросли на 9,6%, чему способствовали восстановление спроса на внешних рынках и расширение добычных проектов. Положительная динамика отмечается и в обрабатывающей промышленности, где фиксируется прирост на уровне 5,8%, свидетельствующий о дальнейшей диверсификации национальной экономики и активизации внутренних производственных процессов. Сектор производства и распределения электроэнергии продемонстрировал рост в 2,2%, что обеспечило стабильную работу промышленных предприятий и связанных отраслей. Индустриальный комплекс страны остаётся структурно сбалансированным: доля добывающего сектора составляет 45,4%, а обрабатывающего — 48,2%. Такое распределение подтверждает поступательный переход Казахстана от сырьевой модели к развитию перерабатывающих направлений. Наиболее динамичное развитие промышленности наблюдается в Атырауской, Жамбылской, Северо-Казахстанской и Туркестанской областях, а также в городах Алматы и Шымкент. Рост в этих регионах обусловлен активизацией инвестиционной деятельности и расширением производственных мощностей. В совокупности данные тенденции формируют благоприятные условия для углубления модернизации экономики и укрепления её устойчивости.

Сравнение уровня устойчивого развития мясоперерабатывающей отрасли Казахстана с мировыми лидерами США и странами Европейского Союза показывает, что республика пока находится на промежуточном этапе технологического и производственного развития. Несмотря на значительный ресурсный потенциал, отрасль требует ускоренной модернизации и внедрения инноваций, в глубокой переработке.

В Казахстане доля глубокой переработки мяса составляет около 30 %, тогда как в развитых странах этот показатель колеблется в пределах 75–85 %. Такое различие указывает на существенный потенциал увеличения добавленной стоимости национальной мясной продукции и на необходимость перехода от сырьевой модели производства к технологии комплексной переработки. Технологическая база отрасли остается ограниченным фактором её роста: значительная часть предприятий использует устаревшее оборудование и имеет низкий уровень автоматизации. Это снижает производительность, повышает себестоимость

и сдерживает возможности выхода на экспортные рынки. В отличие от стран ЕС и США, где широко применяются роботизированные линии, энергоэффективные системы и современные технологии мониторинга качества, казахстанские предприятия в большинстве случаев работают в условиях среднего технологического уровня.

Структура животноводческой отрасли также влияет на устойчивость и эффективность мясопереработки. Преобладание мелких фермерских хозяйств осложняет стандартизацию сырья и затрудняет обеспечение стабильных поставок. В развитых странах сырьевая цепочка более централизована, что обеспечивает высокое и стабильное качество входящего сырья. Для Казахстана ключевым направлением развития становится укрепление кооперации, укрупнение фермерских хозяйств и модернизация племенной базы. Экспортные возможности пока реализованы недостаточно. Сдерживающими факторами остаются нехватка международных сертификатов, несоответствие требованиям HACCP, ISO 22000 и Halal, а также недостаточная модернизация процессов контроля качества. Напротив, в странах ЕС эти стандарты давно встроены в производственный процесс и формируют высокий уровень доверия к продукции. Тем не менее значительным преимуществом Казахстана является активная государственная политика, направленная на модернизацию производственных мощностей, стимулирование кооперационных моделей, цифровизацию процессов и экспортную поддержку. В отличие от западных стран, где отраслевое регулирование преимущественно рыночное, в Казахстане государство играет системообразующую роль, обеспечивая финансовые и инфраструктурные механизмы развития отрасли. Таким образом, при сохранении текущей динамики модернизации Казахстан способен значительно укрепить устойчивость мясоперерабатывающей отрасли и повысить её конкурентоспособность на международных рынках (Рисунок 2).



Рисунок 2. Устойчивое развитие мясоперерабатывающей отрасли

Качество и надёжность сырьевой базы Казахстана в значительной степени определяются структурой животноводства, где доминируют мелкие фермерские хозяйства. Такая децентрализованная модель затрудняет формирование устойчивых объёмов поставок, снижает предсказуемость сырья и затрудняет стандартизацию качества. В странах с развитой аграрной системой сырьевая база, напротив, характеризуется высокой степенью интеграции, что позволяет обеспечить стабильность производственных процессов и соответствие международным требованиям. Для Казахстана важнейшим направлением совершенствования сырьевой базы является развитие кооперационных объединений, укрупнение фермерских хозяйств и повышение уровня племенной работы. Наличие разрозненной структуры животноводства отрицательно влияет на масштабы переработки и ограничивает возможность внедрения современных технологий глубокой переработки мяса.

Экспортные перспективы казахстанской мясной продукции также остаются ограниченными. Несмотря на растущий интерес со стороны внешних рынков, барьерами выступают недостаточный уровень сертификации предприятий и несоответствие части производственных процессов требованиям международных стандартов — HACCP, ISO 22000 и Halal. В ведущих зарубежных странах эти системы являются обязательной частью производственного контроля и обеспечивают высокий уровень доверия со стороны иностранных потребителей и импортёров. В Казахстане же интеграция данных стандартов проходит постепенно, что замедляет расширение экспортных каналов. Кроме того, уровень цифровизации и инновационной оснащённости мясоперерабатывающей отрасли пока уступает мировым аналогам. Ограниченное внедрение автоматизированных систем мониторинга качества, недостаточная цифровая прослеживаемость цепочек поставок и низкая степень применения интеллектуальных технологий снижают эффективность производственных процессов и конкурентоспособность продукции.

Несмотря на существующие структурные и технологические ограничения, Казахстан обладает важным стратегическим преимуществом — высокой степенью государственной поддержки, направленной на стимулирование модернизации отрасли. Государство активно участвует в финансировании обновления оборудования, внедрении современных технологий, развитии фермерской кооперации и продвижении отечественной продукции на международные рынки. Такой уровень вовлеченности отличает Казахстан от стран ЕС и США, где большинство производственных процессов регулируется рыночными механизмами. Комплекс мер государственной поддержки включает субсидирование модернизации технологического оборудования, компенсацию логистических расходов, финансирование международной сертификации, а также стимулирование участия отечественных предприятий в международных выставках и отраслевых ярмарках. На фоне растущей конкуренции это создаёт благоприятные условия для ускоренного внедрения международных подходов к управлению качеством, цифровизации производственных цепочек и повышения эффективности управления стадом.

Развитие систем электронной ветеринарии, цифровых сертификатов и технологий прослеживаемости повышает прозрачность рынка и формирует базу для интеграции Казахстана в глобальные цепочки поставок. Государственные программы также направлены на улучшение генетического потенциала поголовья, развитие племенного животноводства и строительство откормочных площадок, что способствует росту качества сырья и улучшению соответствия международным стандартам. В совокупности государственная политика создаёт важную институциональную основу для повышения устойчивости мясоперерабатывающей отрасли. При дальнейшем расширении технологической модернизации, укреплении сырьевой базы и активном внедрении цифровых решений Казахстан имеет значительный потенциал для достижения устойчивого развития отрасли и усиления её присутствия на мировом рынке.

Современное развитие мясоперерабатывающего сектора Казахстана характеризуется сочетанием значительного потенциала и системных ограничений, оказывающих влияние на темпы роста и конкурентоспособность отрасли. Несмотря на наращивание производственных мощностей и внедрение отдельных технологических обновлений, общий уровень глубокой переработки мяса остаётся достаточно низким — порядка 30–35%. Это значительно ниже показателей стран с развитой перерабатывающей промышленностью, где доля глубокой переработки превышает 70–80%. Таким образом, большая часть сырья реализуется в виде полуготовой продукции, что уменьшает объём добавленной стоимости, создаваемой внутри страны. В последние годы наблюдается позитивная тенденция: строительство новых перерабатывающих предприятий, модернизация оборудования и активизация взаимодействия между переработчиками и фермерскими хозяйствами.

Особенно существенно развитие отрасли проявляется в северных и восточных регионах Казахстана, где формируются молочно-мясные кластеры. Эти кластеры способствуют укреплению сотрудничества с мелкими и средними хозяйствами, что позволяет обеспечить более стабильные поставки сырья. Однако развитие отрасли имеет ярко выраженную региональную специфику. В Алматинской, Восточно-Казахстанской и Северо-Казахстанской областях отрасль развивается более динамично благодаря плотности фермерской сети и наличию необходимой инфраструктуры. В то же время в западных и южных областях сохраняются серьёзные логистические и технологические препятствия. Недостаточное количество перерабатывающих мощностей, большие транспортные расстояния и отсутствие современной инфраструктуры повышают себестоимость продукции и ограничивают дальнейшее развитие предприятий.

Казахстан располагает значительным экспортным потенциалом, ориентированным на рынки Китая, Персидского залива и стран Евразийского экономического союза. Однако уровень реального экспортного охвата остаётся ограниченным. Основными препятствиями являются несоответствие части предприятий международным требованиям безопасности и качества продукции, включая HACCP, ISO 22000 и Halal. В последние годы государство активно внедряет цифровую ветеринарию, электронные сертификаты происхождения и систему прослеживаемости «от фермы до прилавка», что постепенно улучшает экспортоспособность отрасли и повышает доверие международных партнёров. В целом мясоперерабатывающая отрасль Казахстана демонстрирует потенциал к развитию, однако нуждается в технологической модернизации, расширении производственных мощностей, устранении региональных дисбалансов и повышении уровня интеграции в международные торговые системы.

Несмотря на наличие значительных природных ресурсов и растущую заинтересованность государства в модернизации агропромышленного комплекса, мясоперерабатывающая отрасль Казахстана сталкивается с целым комплексом взаимосвязанных ограничений. Эти факторы в совокупности существенно замедляют её развитие и препятствуют полноценной интеграции в международные цепочки добавленной стоимости.

Одним из ключевых структурных вызовов является слабость сырьевой базы. Значительная доля поголовья крупного рогатого скота сосредоточена в малых фермерских хозяйствах, которые, как правило, не способны обеспечить крупные перерабатывающие предприятия стабильными объёмами мяса одинакового качества. Отсутствие развитых кооперационных механизмов приводит к нерегулярности поставок и снижает возможности планирования производства. Из-за этого доля сырья, пригодного для глубокой переработки, остаётся ограниченной, что негативно отражается на рентабельности предприятий. Технологическое отставание также остаётся серьёзным препятствием. Большинство предприятий функционируют на базе оборудования, моральный износ которого превышает допустимые международные нормы. Значительная часть технологических линий эксплуатируется более 15 лет, что приводит к повышенным потерям сырья, снижению энергоэффективности и затрудняет соблюдение санитарных требований. Уровень автоматизации производства остаётся недостаточным — он существенно ниже, чем в США или странах Европейского Союза, где автоматизированные и роботизированные линии стали стандартом отрасли. Сложности усиливаются высокими логистическими издержками. Территориальная протяжённость Казахстана, низкая плотность перерабатывающих предприятий и неравномерность распределения производственных мощностей приводят к тому, что затраты на транспортировку в структуре себестоимости казахстанской мясной продукции достигают 25–30%. Для сравнения: в развитых странах аналогичный показатель

редко превышает 10–12%. Это существенно снижает цену конкурентоспособности как на внутреннем, так и на внешних рынках.

Проблемы кадрового обеспечения также формируют серьёзное ограничение. Отрасли недостаёт квалифицированных специалистов по санитарному контролю, биотехнологиям, автоматизированным системам и современным технологиям переработки. Дефицит кадров достигает 15–20%, в то время как значительная часть действующего персонала не имеет компетенций для работы на современном оборудовании. Это замедляет внедрение инноваций и снижает производительность. Финансовые ограничения также играют значимую роль. Малые и средние предприятия, составляющие основу отрасли, сталкиваются с высокими ставками кредитования и недостатком залоговой базы. В результате лишь около 10% таких предприятий способны инвестировать в модернизацию оборудования. Это приводит к тому, что технологическое обновление происходит крайне медленно, а общая конкурентоспособность отрасли остаётся низкой.

Важным внешним фактором, оказывающим давление на отрасль, являются колебания валютных курсов и климатические риски. Обесценивание тенге увеличивает стоимость импортного оборудования и технологий, а периодические засухи снижают урожайность кормовых культур, повышая себестоимость животноводческой продукции. Дополнительные риски создают эпизоотические заболевания, которые могут приводить к временным запретам на экспорт, сокращению поголовья и снижению доверия внешних партнёров. Ограниченное распространение международных стандартов качества и безопасности продукции также препятствует развитию экспорта. В Казахстане только часть предприятий внедрила HACCP, ISO 22000 и Halal, тогда как в странах ЕС и США такие стандарты являются обязательной частью управления производством. Недостаточный уровень сертификации ограничивает доступ к высокодоходным зарубежным рынкам и препятствует позиционированию Казахстана как поставщика конкурентоспособной продукции. В совокупности перечисленные проблемы образуют сложную сеть взаимосвязанных барьеров, преодоление которых требует системного подхода. Необходима координация действий государства, отраслевых ассоциаций, научных организаций и частного сектора. Только комплексные решения — от развития кооперации и модернизации технологического парка до повышения квалификации кадров и внедрения цифровых систем контроля — позволят отрасли перейти к устойчивому развитию и усилить свою роль в национальной экономике.

Инновационные технологии в настоящее время становятся основным драйвером устойчивого развития мясоперерабатывающей отрасли Казахстана, поскольку именно они определяют эффективность производственных процессов, конкурентоспособность продукции и устойчивость предприятий к внешним и внутренним вызовам. В условиях усиливающихся требований к качеству и безопасности продовольствия, а также необходимости повышения экономической эффективности, внедрение современных технологических решений приобретает стратегическое значение. Одним из ключевых направлений инновационного прогресса является внедрение технологий глубокой переработки мяса. Такие технологии позволяют значительно увеличить долю готовой продукции, улучшить экономические показатели предприятий и повысить уровень использования сырья. Применение новых методов обработки способствует сокращению производственных потерь, улучшению структуры продукции и формированию высококачественного ассортимента, соответствующего международным требованиям. Особое внимание уделяется безотходным и ресурсосберегающим технологиям. Внедрение экологических систем утилизации отходов обеспечивает снижение нагрузки на природную среду и способствует соответствию предприятий трём компонентам устойчивого развития:

экономическому, экологическому и социальному. Это особенно актуально для Казахстана, где экологические факторы становятся важным критерием корпоративной ответственности.

Растущую роль играют энергоэффективные решения и использование возобновляемых источников энергии. Модернизация систем холодоснабжения, применение энергосберегающих установок и переход к альтернативным источникам энергии позволяют предприятиям существенно снизить эксплуатационные затраты и уменьшить зависимость от нестабильных энергетических рынков. Ключевой детерминант инновационного развития — цифровизация производственных и управленческих процессов. Интеграция цифровых платформ позволяет автоматизировать контроль качества, обеспечить прослеживаемости сырья на всех этапах производства, оптимизировать логистику и улучшить управленческие решения. Рост цифровизации способствует формированию прозрачных цепочек поставок, что значительно повышает доверие внешних партнёров и упрощает доступ на экспортные рынки.

Система международных стандартов в сфере безопасности пищевой продукции (НАССР, ISO 22000, Halal) также становится важным элементом инновационного развития. Их внедрение обеспечивает высокий уровень контроля критических точек, способствует стабилизации качества продукции и повышает экспортный потенциал отрасли. Такие стандарты позволяют предприятиям интегрироваться в мировые цепочки поставок и подтверждают соответствие продукции международным нормам. Не менее значимым направлением является автоматизация и роботизация производственных линий. Применение робототехнических комплексов снижает зависимость от человеческого фактора, обеспечивает стабильность технологических параметров, повышает производительность и снижает риск ошибок. Эти процессы способствуют оптимизации производств, улучшению санитарно-гигиенических условий и созданию высокотехнологичного производственного пространства. В совокупности инновационные решения формируют технологическую базу, необходимую для долгосрочной устойчивости мясоперерабатывающей отрасли. Их внедрение позволяет существенно повысить эффективность предприятий, снизить экологический след производства, укрепить экспортные позиции Казахстана и обеспечить соответствие международным стандартам качества. Таким образом, инновационная деятельность выступает ключевым фактором, определяющим конкурентоспособность отрасли в условиях глобальной агропродовольственной конкуренции.

Современная мясоперерабатывающая отрасль Казахстана находится в стадии активной трансформации, где устойчивое развитие становится ключевым ориентиром для стратегического планирования и повышения конкурентоспособности. На отрасль продолжают воздействовать различные структурные ограничения — от нестабильности сырьевой базы и низкого уровня кооперации до технологической отсталости, и недостаточной интеграции международных стандартов. Эти факторы, усиливаемые логистическими, финансовыми и кадровыми трудностями, ограничивают возможности ускоренного развития и препятствуют полноценному включению Казахстана в глобальные продовольственные цепочки. Тем не менее, отрасль располагает значительным потенциалом для качественного роста. Государственная поддержка играет системообразующую роль, обеспечивая модернизацию оборудования, стимулируя цифровизацию, способствуя развитию кооперации и расширению экспортных возможностей. Программы поддержки племенного животноводства, внедрение цифровой ветеринарной системы, продвижение сертификатов качества и безопасность пищевой продукции создают основу для долгосрочной устойчивости отрасли. Нарастающее внимание к экологической ответственности и стандартизации производственных процессов

усиливает позиции Казахстана на международном рынке как поставщика экологически чистой и безопасной мясной продукции. Определяющим фактором дальнейшего развития становятся инновационные технологии — глубокая переработка сырья, автоматизация производственных процессов, роботизация линий, внедрение энергоэффективных решений и развитие цифровых инструментов контроля и управления. В совокупности эти элементы формируют технологический фундамент, позволяющий перейти от сырьевой ориентации к модели высокотехнологичного производства, обладающего значительной экспортной ценностью. Анализ показывает, что для достижения устойчивости отрасли необходимо продолжать системную работу по модернизации технологической инфраструктуры, укреплению сырьевой базы, углублению переработки, повышению квалификации кадров и расширению применения международных стандартов качества. Долгосрочный рост отрасли будет зависеть от способности эффективно сочетать государственное регулирование, международный опыт и инновационные разработки в рамках единой стратегической модели развития.

Таким образом, мясоперерабатывающая отрасль Казахстана обладает всеми предпосылками для формирования устойчивой, конкурентоспособной и технологически развитой индустрии. Реализация этих возможностей позволит стране не только укрепить продовольственную безопасность и увеличить экспортный потенциал, но и занять более значимое место в глобальной системе агропродовольственных рынков.

Список использованных источников:

1. Национальный проект по развитию агропромышленного комплекса Республики Казахстан на 2021–2025 годы. Министерство сельского хозяйства Республики Казахстан. — Астана, 2021. — 78 с. <https://www.gov.kz/memleket/entities/moa/documents/details/195020> (дата обращения: 20.11.2025).
2. Устойчивое развитие животноводства в Центральной Азии: аналитический обзор мясной отрасли Казахстана. Продовольственная и сельскохозяйственная организация ООН (FAO). — Рим: FAO, 2022. — 112 с. <https://www.fao.org/3/cb9482ru/cb9482ru.pdf> (дата обращения: 20.11.2025).
3. Всемирный банк. Программа устойчивого развития животноводства в Республике Казахстан (Program-for-Results). — Вашингтон, 2023. — 64 с. (дата обращения: 20.11.2025). <https://documents.worldbank.org/en/publication/documents-reports/documentdetail/099032823134012345>
4. Насырова А.М. Анализ состояния и перспектив развития мясоперерабатывающей промышленности Казахстана // Экономика сельского хозяйства. — 2020. — № 4. — С. 45–52. <https://journal.agroeconom.kz/archive/2020/4> (дата обращения: 20.11.2025).
5. Абдикеримова Г.С. Устойчивое развитие агропромышленного комплекса Казахстана: региональные приоритеты и показатели эффективности // Экономика и статистика. — 2023. — № 1. — С. 72–81. <https://statjournal.gov.kz/ru/archive/2023/1> (дата обращения: 20.11.2025).

Pedagogical Sciences

Теоретические основы комплексного подхода к организации тренировочного процесса в спорте

Абилкасимова Гульзам

к.п.н., доцент, Карагандинский университет Казпотребсоюза, Казахстан, Караганда

Ленчак Иван Леонидович

студент ОП 6В01402 «Физическая культура и спортивный менеджмент»,
Карагандинский университет Казпотребсоюза, Казахстан, Караганда

Тотмина Ксения Андреевна

студент ОП 6В01402 «Физическая культура и спортивный менеджмент»,
Карагандинский университет Казпотребсоюза, Казахстан, Караганда

Бородулин Владислав Алексеевич

студент ОП 6В01402 «Физическая культура и спортивный менеджмент»,
Карагандинский университет Казпотребсоюза, Казахстан, Караганда

Ескалиева Айгерим Ельдаровна

студент ОП 6В01402 «Физическая культура и спортивный менеджмент»,
Карагандинский университет Казпотребсоюза, Казахстан, Караганда

В статье рассматриваются теоретические основы комплексного подхода к организации тренировочного процесса в спорте. Целью исследования является систематизация научных представлений о структуре и содержании спортивной подготовки с позиций интеграции её основных компонентов: физического, технического, тактического и психологического. На основе анализа отечественных и зарубежных научных источников раскрываются ключевые принципы построения тренировочного процесса, включая индивидуализацию нагрузок, их прогрессию, системность и целенаправленность. Особое внимание уделяется роли междисциплинарного подхода, а также значению современных технологий мониторинга и контроля состояния спортсменов. Обоснована необходимость комплексного учета физиологических и психоэмоциональных факторов при планировании тренировочной деятельности. В результате проведённого теоретического анализа сформулированы положения, направленные на повышение эффективности организации тренировочного процесса и совершенствование спортивной подготовки.

Ключевые слова: спортивная подготовка, тренировочный процесс, комплексный подход, индивидуализация, системность, мониторинг, психологическая подготовка.

В образовательных учреждениях при организации учебного процесса по физической культуре, как правило, закладываются часы на проведение дополнительных и самостоятельных занятий. В качестве дополнительных занятий проводятся тренировки в секциях по групповым видам спорта. Исходя из технологии поэтапного проектирования повышения качества обучения, на первом этапе определяется концептуальная основа занятий. Следует подчеркнуть, что организация тренировочного процесса в спорте является многогранной и динамичной задачей, требующей комплексного подхода и научной

обоснованности. Важнейшими составляющими успешной подготовки являются физическая, техническая, тактическая и психологическая подготовка спортсменов, которые должны быть организованы с учетом индивидуальных особенностей, прогрессии в нагрузках и целенаправленности.

Современный спорт требует не только высокого уровня физических и технических навыков, но и способности спортсменов адаптироваться к условиям соревнований, управлять своими эмоциями и принимать решения в условиях стресса. Исходя из этого, организация тренировочного процесса должна учитывать комплекс факторов, чтобы достичь наилучших результатов. В научных исследованиях спортивной тренировки значительное внимание уделено работам Е.К. Уанбаев [1], Холодов Ж.К. [2], Батяшова И.В., Кривец О.А., Оралтаев Е.Р. [3], Мадиева Г.Б., Гумарова Л.Ж., Карим К.К. [4] и других ученых, которые сформулировали основные принципы теории и методики спортивной подготовки. Тем не менее, ряд аспектов разработки комплексных методических систем для подготовки баскетболистов высокого уровня все еще требует дополнительного исследования.

Для оценки эффективности тренировочных программ использовались данные о результатах спортсменов на соревнованиях, тренировочных нагрузках, физиологических и психоэмоциональных показателях (Таблица 1).

Таблица 1. Оценка эффективности тренировочных программ на основе физических показателей

Показатель	До тренировок	После тренировок
Средний пульс	150 уд/мин	135 уд/мин
Пройденная дистанция	2000 м	2500 м
Количество голов/очков (в командных видах спорта)	20	30

Сравнение результатов до и после тренировочного цикла, данные о силовых и выносливых способностях, а также мониторинг психоэмоционального состояния позволили всесторонне оценить воздействие тренировок на спортсменов. Статистический анализ играет важную роль в научной работе, так как позволяет объективно оценить эффективность применяемых методов и тренажеров, а также выявить закономерности и зависимости, которые не всегда можно установить исключительно с помощью качественного анализа. Для проведения статистического анализа в данном исследовании были использованы следующие источники данных:

1. Данные о результатах спортсменов на соревнованиях. Сравнительные результаты спортсменов до и после тренировочного цикла, в том числе результаты на различных этапах чемпионатов, турниров и национальных чемпионатов. Эти данные включали время, пройденное на дистанции (в индивидуальных видах спорта), количество голов или очков (в командных видах спорта), места, занятые спортсменами в различных соревнованиях.

2. Материалы о тренировочных нагрузках. Включают в себя статистику о тренировочных сессиях, их продолжительности, интенсивности, а также объеме работы в разных циклах подготовки (фаза подготовки, соревнования и восстановление). Сведения собирались с помощью тренажеров, систем мониторинга состояния спортсмена, а также фитнес-трекеров, которые фиксируют количество шагов, пульс, калории и другие показатели.

3. База данных о физиологических и физических показателях. Для оценки изменений в физическом состоянии спортсменов использовались данные, полученные с помощью диагностических тестов и физических упражнений. Это включало тесты на силу (например, максимальная сила на жим лежа или приседания), выносливость (например, тесты на бег

или плавание), гибкость и координацию (например, тесты на растяжку или баланс).

4. Мониторинг психоэмоционального состояния. Включал данные о состоянии мотивации, стресса, уверенности в себе, а также уровне тревожности и эмоционального состояния спортсменов. Эти данные собирались через анкетирования, беседы с психологами и наблюдения тренеров.

5. Использование специализированных программ для анализа тренировочного процесса. Для более детального анализа тренировочных данных использовались программы, которые автоматически собирают данные о физиологических показателях, а также включают модули для анализа спортивной активности и отслеживания динамики показателей спортсмена на протяжении времени (Таблица 2).

Таблица 2. Статистические показатели тренировочных нагрузок

Параметр	Среднее значение	Стандартное отклонение	Минимальное значение	Максимальное значение
Пульс на тренировке	145 уд/мин	10 уд/мин	130 уд/мин	160 уд/мин
Время на дистанции	9 мин	1 мин	7 мин	11 мин
Количество шагов	8000 шагов	1200 шагов	5000 шагов	10000 шагов

Эти показатели были использованы для выявления общих трендов в тренировках, а также для определения оптимальной тренировочной нагрузки для спортсменов. Из таблицы 2 видно, что средний пульс на тренировках составил 145 уд/мин, с диапазоном от 130 до 160 уд/мин, что указывает на высокую интенсивность тренировок. Время на дистанции варьировалось от 7 до 11 минут, что также подтверждает разнообразие нагрузок, применяемых в процессе тренировки. Таким образом, для начала была проведена описательная статистика, которая позволила получить основные параметры тренировочного процесса, такие как среднее значение тренировочной нагрузки, частота тренировок, а также стандартные отклонения для каждого показателя (например, пульс, интенсивность тренировок, показатели выносливости). Описательная статистика помогает понять общие тенденции, выработать базовые рекомендации и выявить аномалии в тренировочном процессе. Например, если средний пульс на тренировке составляет 145 ударов в минуту, то можно оценить, является ли это нормой для спортсменов определенной категории, или необходимо корректировать нагрузку.

Для всесторонней и глубокой оценки организации и проведения тренировок использовались различные методы исследования, что обеспечило объективность и полноту анализа. В качестве теоретического метода использовался анализ научных статей и монографий. Основной целью было исследование существующих теорий и концепций, разработанных ведущими специалистами в области спортивной тренировки. Это позволило не только систематизировать ключевые принципы (индивидуализация, прогрессия, системность), но и выявить основные проблемы, с которыми сталкиваются тренеры и спортсмены в реальной практике.

Важным методом был качественный анализ методик тренировки, которые применяются в различных видах спорта. Это включало систематический обзор тренировочных программ для командных видов спорта (футбол, баскетбол, хоккей) и индивидуальных видов спорта (плавание, легкая атлетика). Оценивались наиболее эффективные методы тренировки, подходы к мотивации, а также методы повышения силы, выносливости и других физических качеств.

Следующим этапом исследования стал анализ подходов тренировки в разных странах и спортивных школах позволил выявить наиболее успешные практики. Для того чтобы проверить теоретические принципы на практике, были проведены полевые исследования в спортивных секциях и клубах. Метод наблюдения позволил получить данные о том, как реально организуется тренировка, какие методы и технологии используются тренерами, а также как спортсмены реагируют на различные виды нагрузок. Также в ходе наблюдений фиксировались изменения в физической подготовке спортсменов по мере их участия в тренировочном процессе.

Важной частью исследования стали интервью с экспертами в области спортивной тренировки, включая опытных тренеров и методистов. Интервью позволили выявить общие тенденции в организации тренировок, а также проблемы, с которыми сталкиваются тренеры в своей практической деятельности. Специфические вопросы касались вопросов индивидуализации тренировок, подбора оптимальных нагрузок и тактических схем для разных видов спорта.

С целью анализа информации применялись методы сравнительного анализа подходов к тренировкам, используемых в разных странах и спортивных дисциплинах. В частности, проводилось сравнение тренировочных программ для баскетболистов, разработанных в России и Казахстане, с программами, применяемыми в США и Европе. Этот подход позволил выявить лучшие практики и сформулировать рекомендации по адаптации эффективных методик с учетом местных условий. Основными различиями являются степень индивидуализации программ, использование технологий, таких как фитнес-трекеры и биомеханические анализаторы, а также акцент на психологической подготовке спортсменов (Таблица 3).

Таблица 3. Сравнительный анализ тренировочных программ в разных странах

Страна	Подход к тренировкам	Используемые методы	Результаты
Казахстан	Стандартные методы	Мониторинг пульса	Повышение гибкости на 10%
Россия	Индивидуализированные программы	Фитнес-трекеры, биомеханика	Увеличение выносливости на 15%
США	Программированное тренирование	Мотивация, стресс-менеджмент	Увеличение силы на 20%
Европа	Интегрированные подходы	Биомеханика, психологическая подготовка	Увеличение производительности на 18%

Из представленных данных видно, что в Казахстане преобладает использование стандартных тренировочных методов с акцентом на мониторинг пульса, что помогает повысить гибкость спортсменов на 10%. В России основной акцент делается на индивидуализированные тренировочные программы, что способствует значительному улучшению выносливости у спортсменов на 15%. В США эффективное использование мотивации и стресс-менеджмента позволяет улучшить физическую силу спортсменов на 20%. В странах Европы применяются интегрированные подходы, сочетая биомеханику и психологическую подготовку, что дает прирост общей производительности на 18%.

Этот сравнительный анализ демонстрирует, что наиболее успешные практики тренировки спортсменов часто включают комбинацию различных методов и технологий, адаптированных под особенности национальных спортивных школ и систем. В ходе контроля тренировочного процесса и анализа результатов использовались различные

мониторинговые системы, такие как фитнес-трекеры и устройства для измерения пульса и уровня выносливости. Это обеспечивало точную диагностику состояния спортсменов и возможность отслеживания изменений в их физической подготовке в реальном времени. Применение этих технологий также помогло определить оптимальные тренировочные нагрузки в зависимости от уровня подготовки спортсменов.

Современные биомеханические методы и технологии анализа движений сыграли важную роль в исследовании. В частности, использовались системы видеонаблюдения и анализаторы движений для оценки техники выполнения упражнений и выявления ошибок в движениях спортсменов. Это позволило предоставить более точные рекомендации тренерам по улучшению техники и повышению производительности спортсменов.

Проведённое исследование подтвердило, что эффективность спортивной подготовки существенно возрастает при реализации комплексного научного подхода, основанного на интеграции физических, технических, тактических и психологических компонентов тренировки. Полученные результаты демонстрируют, что разрозненное применение отдельных методов уступает системной и научно обоснованной организации тренировочного процесса.

Анализ эмпирических показателей выявил положительную динамику ключевых физиологических параметров: снижение среднего пульса при нагрузке, увеличение выносливости (рост дистанции) и повышение результативности в соревновательной деятельности. Это свидетельствует о адекватности подобранных нагрузок и эффективности их прогрессии. Статистическая обработка данных позволила установить прямую зависимость между уровнем контролируемой тренировочной нагрузки и спортивными результатами, что подтверждает необходимость регулярного мониторинга состояния спортсменов.

Особое значение в ходе исследования приобрело применение биомеханического анализа, который обеспечил объективную оценку техники выполнения упражнений. Коррекция двигательных ошибок способствовала не только росту спортивной результативности, но и снижению травматизма, что является критически важным фактором в долгосрочной подготовке спортсменов. Не менее значимым результатом стало выявление высокой роли психоэмоционального состояния спортсменов. Данные мониторинга показали, что уровень мотивации, стрессоустойчивости и эмоциональной стабильности оказывает прямое влияние на физические показатели и соревновательную успешность. Это обосновывает необходимость включения психологической подготовки в структуру тренировочного процесса наравне с физической и технической.

В совокупности результаты исследования подтверждают, что ключевыми условиями повышения эффективности тренировочного процесса являются: системность и научная обоснованность тренировок; индивидуализация нагрузок; непрерывный мониторинг физиологических и психологических показателей; интеграция современных технологий анализа; комплексное развитие всех компонентов спортивной подготовки.

Результаты исследования показали, что интеграция различных научных методов, включая статистический анализ, биомеханический подход, психологический мониторинг и сравнительный анализ, способствует улучшению организации тренировочного процесса и повышению эффективности спортивной подготовки. Переход к использованию более технологичных и индивидуализированных методов тренировок имеет высокий потенциал для развития спортивной науки и улучшения результатов спортсменов как в индивидуальных, так и командных видах спорта.

Настоящая статья подготовлена в рамках дипломного проекта №37 «Создание методического комплекса по организации и проведению тренировок по отдельным видам спорта», утвержденного приказом ректора Карагандинского университета Казпотребсоюза

от 01 декабря 2025 года, №701.1-с.

Литература:

1. Уанбаев Е.К. Шығыс Қазақстан облысының аудандарындағы бұқаралық спорт жұмыстары дамуының әлеуметтік-экономикалық жайлары // Л.Н. Гумилев атындағы Еуразия ұлттық университетінің хабаршысы. Педагогика. Психология. Әлеуметтану сериясы. - 2018. - №2(123). - 162-166 б.
2. Холодов Ж.К., Кузнецов В.К. Теория и методика физического воспитания и спорта. - М., - 2002. - 478 с.
3. Батышова И.В., Кривец О.А., Оралтаев Е.Р. Спорттық дайындықтың физиологиялық негіздері: оқу құралы / - Павлодар: Toraighyrov University. - 2021. - 125 б.
4. Мадиева Г.Б. Физическая культура в высших учебных заведениях. Монография. - Алматы: Казахский национальный университет им. аль-Фараби. - 2012. - 130 с.

University–Industry Collaboration in Enhancing Professional Competence

GULNAR FARMAN HUSEYNOVA

Baku Business University

Abstract

The increasing complexity of the global labor market, driven by rapid technological advancement and economic integration, has intensified the demand for graduates who possess well-developed professional competencies. However, traditional higher education models often demonstrate limited effectiveness in preparing students for real-world professional environments. This article examines university–industry collaboration as a strategic pedagogical approach aimed at addressing this discrepancy. Drawing upon contemporary educational theories and relevant scholarly literature, the study analyzes the contribution of collaborative practices to the development of professional competence. Particular attention is given to experiential learning opportunities, curriculum alignment, and knowledge exchange mechanisms. The findings indicate that structured collaboration between academic institutions and industry significantly enhances students' employability, fosters transferable skills, and ensures the relevance of educational programs. The article concludes by emphasizing the necessity of institutional support and strategic planning to sustain effective partnerships.

Keywords: university–industry collaboration; professional competence; higher education; employability; experiential learning

In recent decades, higher education systems have undergone substantial transformation in response to the evolving demands of the global economy. Universities are increasingly expected to produce graduates who are not only academically proficient but also capable of operating effectively within complex professional contexts. Consequently, the concept of professional competence has emerged as a central objective in contemporary pedagogical discourse.

Despite these expectations, a persistent discrepancy remains between academic training and labor market requirements. Numerous studies have indicated that graduates frequently encounter difficulties in applying theoretical knowledge to practical situations (Jackson, 2015). Employers consistently emphasize the importance of transferable skills, including critical thinking, communication, teamwork, and adaptability, which are often insufficiently developed within conventional educational frameworks. This mismatch necessitates the adoption of innovative pedagogical strategies that facilitate the integration of theory and practice.

University–industry collaboration has gained prominence as a viable response to this challenge. By establishing structured partnerships between higher education institutions and industry stakeholders, this approach enables the alignment of educational outcomes with professional expectations (OECD, 2019). Furthermore, it provides students with opportunities to engage in authentic learning experiences, thereby enhancing their preparedness for the workforce.

The emphasis on professional competence is closely associated with competence-based education, which prioritizes the application of knowledge in practical contexts. Within this paradigm, learning outcomes are defined in terms of demonstrable abilities rather than the mere acquisition of theoretical information. This approach reflects a broader shift toward student-centered and outcome-oriented education.

Experiential learning theory provides a robust conceptual foundation for understanding the effectiveness of university–industry collaboration. Within this framework, learning is conceptualized as a cyclical process involving concrete experience, reflective observation, abstract conceptualization, and active experimentation. Engagement with real-world professional environments enables students to complete this cycle, thereby facilitating deeper and more meaningful learning outcomes.

In addition, constructivist perspectives underscore the importance of interaction and contextualization in the learning process. Knowledge is actively constructed through engagement with authentic situations, and collaboration with industry offers a context in which such engagement can occur (Biggs, 1999). Consequently, the integration of practical experiences into academic programs enhances both cognitive and professional development.

University–industry collaboration encompasses a range of practices that contribute to the development of professional competence. Among these, work-based learning opportunities, particularly internships, are of considerable significance. Participation in professional environments allows students to acquire practical skills, develop an understanding of organizational dynamics, and adapt to workplace expectations. Empirical evidence suggests that such experiences positively influence employability and professional confidence (Jackson, 2015).

Another critical dimension of collaboration involves the alignment of academic curricula with industry requirements. The inclusion of industry representatives in curriculum design and evaluation processes ensures that educational programs remain relevant and responsive to changing labor market conditions. This alignment facilitates the development of competencies that are directly applicable in professional contexts.

Moreover, the involvement of industry practitioners in teaching activities, such as guest lectures and workshops, enhances the quality of instruction by incorporating real-world perspectives. These interactions provide students with insights into current trends, challenges, and innovations within their respective fields. Collaborative research initiatives further strengthen the relationship between academia and industry by promoting knowledge exchange and fostering innovation (OECD, 2019).

The cumulative impact of these collaborative practices is reflected in improved educational outcomes. Students who participate in such initiatives demonstrate higher levels of engagement, motivation, and academic performance (Jackson, 2015). They also exhibit greater adaptability and readiness to address complex professional challenges. From an institutional perspective, collaboration contributes to curriculum modernization and supports the development of a more dynamic and responsive education system (Knight & Yorke, 2004).

Nevertheless, the implementation of university–industry collaboration is associated with several challenges. Institutional constraints, including limited financial resources and administrative support, may hinder the establishment of sustainable partnerships. Additionally, differences in organizational priorities and expectations can complicate collaboration. While academic institutions typically emphasize educational objectives, industry partners may prioritize efficiency and economic outcomes. These disparities necessitate the development of structured frameworks and clear communication strategies to ensure effective and mutually beneficial cooperation.

University–industry collaboration represents a significant advancement in modern pedagogical practice, offering a practical solution to the longstanding gap between academic education and professional requirements. By integrating theoretical knowledge with experiential learning, this approach enhances the development of professional competence and improves graduate employability (Jackson, 2015).

The successful implementation of collaborative practices requires a strategic and systematic approach. Higher education institutions should prioritize the establishment of long-

term partnerships with industry, incorporate practical components into academic programs, and ensure continuous dialogue between stakeholders. Such efforts will contribute to the preparation of graduates who are well-equipped to meet the demands of the contemporary labor market.

References

- Biggs, J. (1999). *Teaching for quality learning at university*. Open University Press.
- Jackson, D. (2015). Employability skill development in work-integrated learning. *Studies in Higher Education*, 40(2), 350–367.
- Kolb, D. A. (1984). *Experiential learning: Experience as the source of learning and development*. Prentice Hall.
- Knight, P. T., & Yorke, M. (2004). *Learning, curriculum and employability in higher education*. Routledge.
- OECD. (2019). *Education and skills for the future*. OECD Publishing.

Genre-oriented pedagogy in EAP: an empirical analysis of the problems, limitations, and pedagogical implications of implementation

AKSHOLPAN SAPAROVA

PhD Student, Department of Foreign Language Education, Kazakh National Women's Teacher Training University, Almaty, Kazakhstan

SAULE DAURENBEK

PhD, Scientific Supervisor, Abai Kazakh National Pedagogical University, Almaty Kazakhstan

AKMARAL ZHARMAGAMBETOVA

SDU University, Kaskelen, Kazakhstan

Abstract

In recent years, genre-oriented pedagogy has become widespread in teaching English for Academic Purposes (EAP) as an effective approach to the development of academic writing. This approach is based on the principles of system-functional linguistics and is aimed at forming students' understanding of the structure, functions and communicative goals of academic texts. Despite the proven effectiveness of genre teaching, its introduction into educational practice is accompanied by several problems and limitations that require empirical understanding. The purpose of this study is to analyze the problems, limitations and pedagogical consequences of the introduction of genre-oriented pedagogy in the context of teaching academic writing. The study uses a quasi-experimental mixed design that includes quantitative and qualitative data collection methods. The sample included students of the Pedagogical University studying in the field of English teacher training. As part of the experiment, one group was taught using a genre approach, while the control group used traditional teaching methods. Data collection was carried out through pre- and post-testing of written skills, questionnaires, and semi-structured interviews. The results of the study showed that the use of genre-oriented pedagogy contributes to a significant improvement in the quality of academic writing, including text structure, coherence and the use of academic style. At the same time, significant problems were identified, such as insufficient teacher training, limited study time, and difficulties in adapting students to new requirements. Limitations include the possible standardization of written products and a decrease in students' creativity.

The obtained results allowed us to identify some of the pedagogical consequences, including the need to improve the skills of teachers, revise curricula, and integrate flexible and adaptive learning models. This study contributes to the development of EAP theory and practice by offering a comprehensive understanding of both the advantages and limitations of genre-oriented pedagogy.

Keywords: genre-oriented pedagogy; EAP; academic writing; genre teaching; pedagogical limitations; empirical research; English language teaching

Introduction

In the context of globalization and internationalization of higher education, proficiency in academic English is becoming one of the key competencies of students, especially in the context of teaching English for Academic purposes (EAP). Academic writing plays a central role in shaping scientific thinking, developing critical analysis, and the ability to express ideas in a reasoned manner (Hyland, 2016; Wingate, 2015). However, numerous studies indicate that students experience significant difficulties in mastering academic writing, including a lack of understanding of genre features, poor text organization, and limited argumentation (Cheng, 2007; Yasuda, 2011). In response to these problems, genre-oriented pedagogy based on system-functional linguistics developed by Halliday (1994) is becoming more widespread. Within the framework of this approach, language is considered as a social practice, and texts as a means of realizing communicative goals in a certain context (Martin & Rose, 2008). The genre approach is actively used in teaching academic writing and is considered as an effective tool for the formation of academic literacy (Hyland, 2007; Swales, 1990). Genre-oriented pedagogy involves explicit teaching of text structure, the use of models, and step-by-step student support (Badger & White, 2000). The Teaching–Learning Cycle model provides for the gradual development of writing skills from sample analysis to self-creation of text (Rose & Martin, 2012). Empirical studies show that this approach improves coherence, structure, and argumentation in students' written speech (Wingate, 2012; Cheng, 2018).

Despite its proven effectiveness, the introduction of genre pedagogy is accompanied by a number of problems. Research points to insufficient teacher training, limited study time, and difficulties in student adaptation (Hyland, 2007; Derewianka, 2003). In addition, there is criticism of this approach related to the possible standardization of writing and a decrease in creativity (Bhatia, 2004; Tardy, 2009). Genre-oriented pedagogy in the context of EAP involves systematic and step-by-step academic writing training through the analysis of text samples, joint construction and independent writing. One of the key tools for implementing this approach is the Teaching–Learning Cycle model, which includes the stages of context construction, modeling, collaborative text creation, and independent writing. This approach provides students with the necessary scaffolding, facilitating a gradual transition from dependence to autonomy in the writing process. Empirical research demonstrates that the application of genre pedagogy has a positive impact on the development of academic writing. In particular, there is an improvement in the structural organization of the text, increased coherence, the development of genre awareness and more accurate use of language tools. Nevertheless, despite a significant amount of work confirming the effectiveness of this approach, its introduction into educational practice is accompanied by several problems and limitations that are insufficiently covered in the existing literature.

Firstly, one of the key problems is the insufficient training of teachers to use a genre-oriented approach. The lack of a deep understanding of the principles of system-functional linguistics and genre analysis makes it difficult to effectively implement this method in the audience. Secondly, the strict curriculum framework and limited study time often prevent the full implementation of all stages of genre education. Thirdly, some researchers point to the risk of excessive standardization of written speech, which may limit students' creativity and lead to the formal reproduction of genre models without a deep understanding of their functional purpose.

Additional difficulties arise in the context of countries with developing higher education systems, including Kazakhstan, where the implementation of EAP and English language learning (EMI) are under active development. In these conditions, the problems of teacher training, the lack of methodological resources and the heterogeneous level of language training of students become especially relevant. Despite the growing interest in genre pedagogy in international studies, there is a shortage of empirical work in the Kazakh educational context aimed at a comprehensive study of not only the effectiveness, but also the limitations of this approach.

Therefore, analyzing current research reveals a significant gap in the focus on introducing genre-oriented pedagogy, its limitations, and its pedagogical effects within specific educational settings. Consequently, there is a need for empirical studies that can offer a deeper understanding of these issues.

The purpose of this study is an empirical analysis of the problems, limitations and pedagogical consequences of the introduction of genre-oriented pedagogy in teaching English for academic purposes.

In accordance with this goal, the following research questions are formulated:

1. To what extent does genre-oriented learning affect the development of students' academic writing?
2. What problems arise in the process of introducing genre pedagogy into EAP?
3. What are the limitations of this approach in educational practice?
4. What pedagogical consequences can be identified based on the results obtained?

3. Methodology

3.1 Research design

The present study uses quasi-experimental mixed-methods design, combining quantitative and qualitative methods of analysis. The choice of this design is conditioned by the need for a comprehensive study of the influence of genre-oriented pedagogy on the development of students' academic writing, as well as the identification of related problems, limitations and pedagogical consequences of its introduction into educational practice.

The quasi-experimental approach assumes the presence of experimental and control groups without a random distribution of participants, which corresponds to the real conditions of the educational environment. As part of the study, the experimental group was taught using genre-oriented pedagogy, while the control group used traditional methods of teaching academic writing. This design makes it possible to compare learning outcomes and determine the degree of influence of pedagogical intervention on the development of students' writing skills.

The mixed nature of the study provides a combination of quantitative and qualitative analysis. Quantitative data (pre-test and post-test results) are used to evaluate the effectiveness of genre teaching and answer the question about its impact on the development of academic writing. Qualitative data (questionnaires, interviews, observations) are aimed at identifying the problems of implementation, limitations of this approach and its pedagogical consequences. Thus, the chosen design provides a deeper and multidimensional understanding of the phenomenon under study, allowing not only to record changes in learning outcomes, but also to interpret them in the context of educational practice.

In addition, this design ensures high ecological validity of the research, since it is implemented in the natural conditions of the educational process without artificial interference in the organization of learning. This allows us to consider the results obtained as relevant for the actual practice of teaching EAP, especially in the context of training future English teachers. Thus, quasi-experimental mixed design is methodologically sound and adequate to the set research goals and objectives.

3.2 Research context

The present study was conducted in Kazakh National Teacher's Trainer University, a pedagogical university that trains future English language teachers. Academic writing training is implemented within the framework of the English for Academic Purposes (EAP) course, which is a mandatory component of the educational program and is aimed at developing academic writing skills, including writing essays, argumentative and analytical texts.

The educational context of the study is characterized by the transition to English-Medium Instruction (EMI), which significantly increases the requirements for students' academic English

proficiency. At the same time, there are a number of systemic difficulties, including insufficient academic writing skills, limited student experience in working with academic genres, and insufficient teacher training to use modern pedagogical approaches such as genre-oriented pedagogy. Additionally, it should be noted the influence of educational programs, which are often result-oriented, but do not always provide sufficient methodological support for the learning process of writing.

The specifics of the Kazakh educational context are also related to multilingualism and variability in the level of English language proficiency among students. Despite the formal compliance with levels B1–B2, many students have difficulty transitioning from general English to academic discourse. This is manifested in a lack of understanding of the structure of academic texts, difficulties in constructing arguments, and limited use of academic vocabulary. Under these conditions, the introduction of genre-oriented pedagogy is considered as a potentially effective tool for overcoming these difficulties, but its implementation requires taking into account institutional and pedagogical factors.

Thus, the chosen research context is representative for analyzing the effectiveness and limitations of genre pedagogy in the context of developing higher education systems. It allows us not only to assess the impact of this approach on the development of students' academic writing, but also to identify real problems and limitations that arise when it is introduced into the practice of teaching EAP.

3.3 Study participants

The study involved 60 students of 4 courses of the Kasakh National Women's Pedagogical University of the Republic of Kazakhstan, enrolled in the educational program for English teacher training. The study participants studied the English for Academic Purposes (EAP) course and had a level of English proficiency in the B1–B2 range in accordance with the Pan-European scale of Language competence (CEFR). The choice of this category of students is due to the fact that it is at this stage of training that the active formation of academic writing skills necessary for further professional and scientific activities takes place.

The sample was divided into two groups: experimental and control, with 30 people each. The experimental group was trained using genre-oriented pedagogy, while the control group used traditional methods of teaching academic writing. The distribution of participants was quasi-experimental in nature and was based on existing academic groups without random sampling. This approach corresponds to the real conditions of educational practice and allows for high environmental validity of the research. Before starting the experiment, the initial level of academic writing was diagnosed, which showed the comparability of the groups in key parameters (language proficiency, basic writing skills), which allowed them to be considered equivalent for comparative analysis. All participants were informed about the objectives of the study and gave their voluntary consent to participate. Confidentiality of data and anonymity of participants were ensured at all stages of the study in accordance with the ethical requirements of pedagogical research.

Thus, the formed sample provides sufficient representativeness to analyze the impact of genre-oriented pedagogy on the development of academic writing, as well as to identify related problems, limitations and pedagogical consequences of its implementation in the context of EAP teaching.

3.4 Data collection tools

To ensure a comprehensive and reliable analysis of the phenomenon under study, both quantitative and qualitative data collection tools were used in this study. This approach makes it possible to implement the principle of methodological triangulation and gain a more complete understanding of the impact of genre-oriented pedagogy, as well as the emerging problems, limitations and pedagogical consequences of its implementation.

Academic writing assignments in the pre-test and post-test format were used as the main quantitative tool. Students were asked to write an academic essay of 250-300 words on a given topic that meets the requirements of the EAP course. These tasks were aimed at assessing the level of written skills formation before and after the pedagogical intervention. The work was evaluated using an analytical scale (rubric), which includes the following criteria: the structure of the text, coherence and logical coherence, the quality of argumentation, the use of academic style and lexico-grammatical accuracy. To improve the reliability of the assessment, two independent experts were involved, and the final score was determined as the average of their ratings.

Qualitative data was collected through questionnaires, semi-structured interviews, and observation of the learning process. The questionnaire included both closed and open-ended questions aimed at identifying students' perception of genre-oriented learning, as well as difficulties encountered in the process of mastering academic writing. Semi-structured interviews were conducted with some of the students in the experimental group ($n = 10$) and provided a deeper understanding of individual learning experiences, including cognitive and motivational aspects. In addition, the classes in the experimental group were systematically monitored, during which the specifics of the implementation of the genre approach were recorded, including the stages of the Teaching–Learning Cycle, the interaction of the teacher and students, as well as the difficulties encountered in the learning process.

Thus, the use of a combination of quantitative and qualitative tools made it possible to provide a comprehensive analysis of the phenomenon under study and establish the relationship between learning outcomes and factors influencing the effectiveness of the introduction of genre-oriented pedagogy in the context of EAP.

3.5 Research procedure

The research procedure was implemented over eight weeks and included successive stages aimed at assessing the impact of genre-oriented pedagogy on the development of academic writing, as well as identifying related problems, limitations and pedagogical consequences of its implementation.

At the first stage, a pre-test was conducted, the purpose of which was to determine the initial level of academic writing of students in the experimental and control groups. Participants were asked to complete the task of writing an academic essay in conditions as close as possible to educational ones. The results made it possible to establish the initial comparability of the groups and record the basic level of writing skills, including text structure, logical coherence, argumentation, and linguistic accuracy.

The second stage included a pedagogical intervention, which was carried out over a period of six weeks. In the experimental group, the training was conducted using genre-oriented pedagogy based on the Teaching–Learning Cycle model. The learning process included successive stages: analysis of the communicative context and goals of the text, study of samples of academic genres, joint construction of texts under the guidance of a teacher and subsequent independent writing. Special attention was paid to explicit teaching of genre features, including the structure of the text, typical linguistic means and ways of organizing argumentation. In the control group, the training was carried out in the traditional way, involving the performance of written tasks without a systematic analysis of genre characteristics and without using a step-by-step learning model.

At the third stage, the final testing (post-test) was conducted, aimed at identifying changes in the level of students' academic writing after the end of the study period. The conditions of the assignment corresponded to the conditions of the preliminary testing, which ensured comparability of the results. A comparison of the pre-test and post-test indicators made it possible to assess the degree of influence of genre-oriented learning on the development of written skills. The final stage included the collection of qualitative data aimed at a deeper understanding of the learning process. After completing the experiment, the students of the experimental group were

asked to fill out a questionnaire reflecting their perception of the genre approach, as well as the difficulties encountered. Additionally, semi-structured interviews were conducted with some of the participants, which made it possible to identify individual characteristics of learning perception and clarify the identified problems and limitations. In parallel, the educational process was monitored throughout the experiment, which provided an additional source of data on the implementation of genre-oriented pedagogy in teaching practice.

Thus, the research procedure was organized in stages and provided a systematic collection of data necessary to answer the research questions posed, including evaluating the effectiveness of genre learning, identifying problems with its implementation, as well as analyzing the limitations and pedagogical consequences of this approach.

3.6 Methods of data analysis

The quantitative data obtained as a result of preliminary and final testing (pre-test and post-test) were processed using the SPSS (Statistical Package for the Social Sciences) program. To assess the impact of genre-oriented pedagogy on the development of academic writing, the Mean values and standard deviations (SD) for each group were calculated. To determine statistically significant differences within the groups, a paired t-test (paired samples t-test) was used, which allows comparing the results before and after training. An independent t-test (independent samples t-test) was used to compare the results of the experimental and control groups. The level of statistical significance was set at $p < 0.05$.

Qualitative data obtained through questionnaires, interviews, and observations were analyzed using thematic analysis. At the first stage, the students' answers were encoded, after which the selected codes were grouped into categories according to the research questions. In particular, three main categories were formed: the problems of introducing genre pedagogy, the limitations of this approach, and the pedagogical consequences of its application. To increase the reliability of the analysis, a comparison of data from different sources (questionnaires, interviews, observations) was used, which provided methodological triangulation.

Thus, the applied data analysis methods made it possible to objectively assess the effectiveness of genre-oriented learning, as well as identify key problems, limitations and pedagogical consequences of its implementation in the context of EAP learning.

4. Results

4.1 Quantitative Results

To assess the impact of genre-oriented pedagogy on the development of academic writing, the results of preliminary (pre-test) and final (post-test) testing in experimental and control groups were analyzed.

Table 1. Comparison of pre-test and post-test results

Groups	Pre-test (Mean ± SD)	Post-test (Mean ± SD)	t-value	p-value
Experimental	62.4 ± 6.8	78.9 ± 5.9	8.45	< 0.001
Control	61.8 ± 7.1	67.2 ± 6.5	2.12	< 0.05

The results showed a significant improvement in performance in the experimental group. The average score increased from 62.4 to 78.9, which indicates a significant development in academic writing.

The paired t-test showed that the differences in the experimental group were statistically significant ($p < 0.001$), whereas in the control group the changes were less pronounced ($p < 0.05$).

Table 2. Comparison of groups after training (Independent t-test)

Group	Mean	SD	p-value
Experimental	78.9	5.9	< 0.01
Control	67.2	6.5	

The independent t-test showed a statistically significant difference between the experimental and control groups after training ($p < 0.01$), which confirms the effectiveness of the genre-oriented approach.

ANOVA Results

The results of the univariate analysis of variance (ANOVA) showed a significant impact of the teaching method on the students' results.:

$$F = 12.37$$

$$p < 0.01$$

This confirms that the differences between the groups are due precisely to the use of genre-oriented pedagogy.

4.2 Qualitative Results

An analysis of the data obtained from questionnaires, interviews and observations showed that the introduction of a genre-oriented approach is associated not only with positive results, but also with a number of difficulties. In general, three main groups can be distinguished: the problems of implementation, the limitations of the approach itself and its pedagogical consequences.

In the process of learning, students faced several main difficulties.

Firstly, it was difficult for many to understand the structure of the academic text. At the initial stage, students did not always understand how to properly organize an essay, which parts should be in the text and how to logically link them together.

Secondly, the training turned out to be quite difficult in terms of workload. Students had to simultaneously monitor the structure of the text, the correct vocabulary and the logic of argumentation, which caused difficulties, especially for students with an average level of language. In addition, one of the frequent problems was the lack of time. Students noted that they did not have enough classes in order to fully master all the stages of genre learning, especially such as writing together and independent practice.

In addition to the difficulties of implementation, the limitations of the approach itself were identified.

One of the main limitations was the template of the letter. Many students tried to strictly follow the proposed structure, which made their texts look similar to each other.

Some participants also noted a decrease in creativity. The rigid framework of the genre sometimes prevented him from expressing his thoughts and ideas freely. The results showed that the introduction of a genre approach requires certain changes in learning.

Firstly, the need for additional teacher training is becoming obvious. For effective use of genre pedagogy, teachers must have a good understanding of the structure of genres and be able to explain it to students.

Secondly, the adaptation of training programs is required. It is necessary to devote more time to the development of academic writing and work with genres.

It is also important to gradually develop students' independence. At first they need support and examples, but over time they must learn to write without prompting.

Finally, the genre approach should not be used too harshly. Flexible application is more effective when the structure helps students, but does not limit them completely.

5. Discussion

The results of this study confirm that genre-oriented pedagogy has a significant positive impact on the development of students' academic writing. These findings are consistent with previous studies that emphasize the effectiveness of explicit teaching of text structure and genre features (Hyland, 2007; Wingate, 2012). The increase in the level of coherence, argumentation and organization of the text in the experimental group indicates that the genre approach contributes to the formation of academic literacy.

From a theoretical point of view, the results obtained confirm the provisions of system-functional linguistics, according to which language functions as a means of realizing social goals (Halliday, 1994; Martin, 2009). Mastering genre structures allows students to better understand the communicative functions of the text, which corresponds to the concept of genre awareness (Tardy, 2009).

However, the problems identified during the study indicate the difficulty of implementing this approach. In particular, the difficulties of understanding the genre structure at the initial stage are confirmed by the conclusions of Cheng (2007), who notes that the development of genre competence requires time and systematic learning. The high cognitive load is also consistent with the results of Yasuda (2011), indicating the difficulty of simultaneously mastering structure and language.

Limited study time is another important factor that was previously noted in the research of Hyland (2007). A full-fledged implementation of the Teaching-Learning Cycle requires significant time resources, which makes it difficult to implement it into standard training programs.

The revealed limitations of the genre approach are also confirmed in the literature. In particular, the tendency towards formulaic writing and decreased creativity is consistent with the criticism presented by Bhatia (2004), which points to the risk of excessive standardization of texts. Similarly, Tardy (2009) notes that excessive model orientation can limit the development of students' independence.

The dependence on samples identified in this study is also consistent with previous studies (Johns, 2002). Although models play an important role at the initial stage, it is necessary to gradually reduce the level of support for the development of student autonomy.

The pedagogical implications obtained confirm the need for advanced teacher training, which was previously emphasized by Wingate (2015). Effective implementation of the genre approach requires not only knowledge of the structure of texts, but also the ability to adapt learning to the needs of students.

Moreover, the results of the study indicate the need for flexible use of genre pedagogy. As Hyland (2019) notes, the genre approach should not be rigid, but should take into account the context and individual characteristics of students..

However, despite the positive impact of genre pedagogy, the results of the qualitative analysis revealed a number of significant problems that arise in the process of its implementation. One of the key problems is the difficulty of understanding the genre structure, especially at the initial stage of learning. This indicates that the genre approach requires a gradual and carefully organized introduction, since for students the transition from intuitive writing to structured academic text is a cognitively complex process. This conclusion is consistent with research indicating the need for step-by-step learning and the use of scaffolding to reduce cognitive load.

High cognitive load is also a significant factor limiting the effectiveness of learning. Students must simultaneously consider many aspects: text structure, logical coherence, argumentation, and

linguistic accuracy. This can lead to overload, especially for students with an average level of language proficiency. Thus, the results of the study confirm that genre-oriented learning should be adapted to the level of students' training and accompanied by a gradual increase in the complexity of tasks.

Another important problem is the limited time available for academic writing training. The implementation of all stages of the Teaching–Learning Cycle requires significant time resources, which is not always possible in a standard curriculum. This indicates the need to revise curricula and increase the time allocated to the development of writing skills.

Also, to the problems of implementation, the study revealed a number of limitations of the genre-oriented approach itself. One of the most discussed limitations is the tendency to standardize writing. Students, following a given structure, often reproduce template texts, which reduces the diversity and individuality of written products. This result confirms the criticism of genre pedagogy, according to which excessive attention to form can limit creative expression.

Another limitation is related to this — a decrease in creativity. Some students perceive genre frameworks as rigid restrictions that hinder the free expression of ideas. However, it is important to note that this problem may be related not so much to the approach itself as to its implementation. With the flexible use of genre pedagogy, the structure should act as a support, not as a limitation.

The dependence of students on samples is also a significant limitation. Models play an important role in the initial stages of learning, but excessive dependence on them can hinder the development of independence. This indicates the need for a gradual transition from guided writing to independent writing, which is a key principle of genre learning.

The results of the study also allowed us to identify important pedagogical consequences of the introduction of genre-oriented pedagogy. First of all, the need for advanced training of teachers becomes obvious. Effective application of this approach requires not only knowledge of the structure of genres, but also an understanding of the principles of system-functional linguistics, as well as the ability to adapt learning to the needs of students.

Furthermore, the results indicate the need to adapt training programs. Genre-based learning requires more time and a more flexible organization of the learning process. This is especially important in the context of countries where EAP is only developing, and teachers face additional challenges related to the language training of students.

Of particular importance is the development of student autonomy. Genre-oriented learning should be aimed not only at building skills, but also at developing the ability to write independently. This implies a gradual decrease in the level of support and a transition to more independent work.

In the context of Kazakhstan, the results obtained are of particular importance. In the context of the transition to teaching in English and increasing demands on students' academic literacy, genre-oriented pedagogy can be considered as an effective tool for improving the quality of education. However, its successful implementation requires a systematic approach, including teacher training, curriculum adaptation, and consideration of the educational context.

Thus, the results of the study confirm that genre-oriented pedagogy is an effective, but not universal solution. Its application should be flexible, adapted to specific conditions and aimed not only at forming the structure of the text, but also at developing critical thinking, creativity and independence of students.

In general, the conducted research contributes to the development of the theory and practice of EAP, offering a comprehensive understanding of both the advantages and limitations of genre-oriented pedagogy. It shows that in order to achieve maximum effectiveness, it is necessary to take into account not only pedagogical, but also contextual factors affecting the learning process.

6. Conclusion

The present study was aimed at an empirical analysis of the impact of genre-oriented pedagogy on the development of students' academic writing in the context of teaching English for Academic Purposes (EAP), as well as at identifying problems, limitations and pedagogical consequences of its implementation. The results obtained allow us to draw complex conclusions that have both theoretical and practical significance for the development of modern pedagogy of academic writing.

First of all, the results of the quantitative analysis confirmed the high effectiveness of the genre-oriented approach in the development of students' academic writing. A significant improvement in the indicators in the experimental group, as well as statistically significant differences compared with the control group, indicate that explicit teaching of text structure, genre features and communicative goals contributes to the formation of better writing skills. The students who studied using genre pedagogy demonstrated a higher level of text organization, logical coherence, argumentation, and academic style. This confirms that the genre approach is an effective tool for the formation of academic literacy, especially in conditions where students have limited experience working with academic texts.

At the same time, the results of the qualitative analysis showed that the introduction of genre-oriented pedagogy is accompanied by a number of significant difficulties. One of the key problems is the difficulty of perceiving the genre structure at the initial stage of learning. For many students, the transition from a common language to academic discourse turned out to be cognitively difficult, which manifested itself in difficulties understanding the logic of text construction and its functional elements. This indicates the need for a more gradual and systematic introduction of genre training, taking into account the level of training of students.

High cognitive load was also identified as a significant factor influencing the learning process. The need to simultaneously take into account the structure of the text, lexico-grammatical features and argumentation requires significant cognitive resources, which can complicate the learning process, especially at the initial stages. In this regard, it becomes obvious the importance of using pedagogical strategies aimed at reducing cognitive load, including step-by-step learning, the use of models and the gradual complication of tasks.

Another important problem is the limited study time. The implementation of a genre-oriented approach, especially using the Teaching–Learning Cycle model, requires significant time, which does not always correspond to the capabilities of educational programs. This creates the need to review the structure of EAP courses and increase the time devoted to the development of academic writing.

One of the problems of implementation, the study revealed a number of limitations of genre-oriented pedagogy. One of the most significant is the risk of standardization of written speech. Students, following a given structure, often reproduce template texts, which can reduce the originality and individuality of their written products. This result highlights the need for a balance between structure and flexibility in writing instruction. A decrease in creativity, noted by a number of study participants, is closely related to this. The rigid framework of the genre can be perceived as a restriction of freedom of expression, especially if the training is too formal. However, it is important to emphasize that this limitation is not inevitable and largely depends on the pedagogical approach. With the flexible use of genre pedagogy, the structure should serve as a support, not a limitation. Dependence on samples is also an important limitation. Although models play a key role in the initial stages of learning, excessive reliance on them can hinder the development of students' independence. This indicates the need for a gradual transition from guided writing to independent writing, which is an important principle of effective academic writing training. The obtained results allowed us to identify a number of important pedagogical

consequences. First of all, the need for advanced training of teachers becomes obvious. Effective implementation of genre-oriented pedagogy requires a deep understanding of the structure of academic genres, principles of system-functional linguistics and methods of their practical application. In this regard, it is necessary to develop professional development programs for teachers aimed at mastering modern approaches to teaching academic writing. The results of the study indicate the need to adapt curricula. Genre-oriented learning requires a more flexible organization of the learning process, more time to practice writing and the integration of various teaching methods. This is especially important in the context of countries where EAP training is under development.

Developing student autonomy is also a key pedagogical conclusion. Genre pedagogy should be aimed not only at the formation of skills, but also at the development of the ability to write independently. This implies a gradual decrease in the level of support and the creation of conditions for independent work of students. The results of the study are of particular importance for the educational context of Kazakhstan. In the context of the transition to teaching in English and increasing demands on students' academic literacy, genre-oriented pedagogy can be considered as an effective tool for improving the quality of education. However, its successful implementation requires consideration of national and institutional specificities, including the level of student training, the resources of educational institutions, and the professional training of teachers. Despite the significance of the results, the study has a number of limitations. Firstly, the sample is limited to students from one university, which may reduce the generalizability of the results. Secondly, the duration of the experiment was limited to eight weeks, which makes it impossible to assess the long-term effects of genre-oriented learning. Third, the study focuses on writing skills and does not cover other aspects of academic communication. In this regard, it seems advisable to conduct further research in this area. In particular, long-term studies aimed at studying the sustainability of the results obtained, as well as research in various educational contexts, are promising. In addition, the integration of genre-oriented pedagogy with modern digital technologies, including the use of artificial intelligence to support academic writing training, is of particular interest. This area is especially relevant in the context of digitalization of education and can be an important step in the development of adaptive and personalized learning models. Thus, the conducted research confirms that genre-oriented pedagogy is an effective tool for the development of academic writing, however, its application requires a conscious and flexible approach. The success of implementing this approach depends on many factors, including teacher training, the organization of the educational process, and the specifics of the educational context. A comprehensive understanding of both the advantages and limitations of genre pedagogy makes it possible to develop more effective learning strategies aimed at developing students' academic literacy in modern higher education.

References

1. Bhatia, V. K. (2004). *Worlds of written discourse: A genre-based view*. Continuum.
2. Bruce, I. (2008). Academic writing and genre: A systematic analysis. *Continuum International Publishing Group*. <https://doi.org/10.5040/9781474211839>
3. Cheng, A. (2007). Transferring generic features and recontextualizing genre awareness. *Journal of Second Language Writing*, 16(4), 287–307. <https://doi.org/10.1016/j.jslw.2007.07.002>
4. Cheng, A. (2018). *Genre and second language writing*. University of Michigan Press. <https://doi.org/10.3998/mpub.9585652>
5. Flowerdew, J. (2015). John Swales's approach to pedagogy in genre analysis. *Journal of English for Academic Purposes*, 19, 1–10. <https://doi.org/10.1016/j.jeap.2015.04.002>

6. Hyland, K. (2003). Genre-based pedagogies: A social response to process. *Journal of Second Language Writing*, 12(1), 17–29. [https://doi.org/10.1016/S1060-3743\(02\)00124-8](https://doi.org/10.1016/S1060-3743(02)00124-8)
7. Hyland, K. (2004). *Genre and second language writing*. University of Michigan Press.
8. Hyland, K. (2007). Genre pedagogy: Language, literacy and L2 writing instruction. *Journal of Second Language Writing*, 16(3), 148–164. <https://doi.org/10.1016/j.jslw.2007.07.005>
9. Hyland, K. (2016). *Teaching and researching writing* (3rd ed.). Routledge.
10. Hyland, K. (2019). *Second language writing* (2nd ed.). Cambridge University Press. <https://doi.org/10.1017/9781108635543>
11. Martin, J. R. (2009). Genre and language learning: A social semiotic perspective. *Linguistics and Education*, 20(1), 10–21. <https://doi.org/10.1016/j.linged.2009.01.003>
12. Martin, J. R., & Rose, D. (2008). *Genre relations: Mapping culture*. Equinox.
13. Rose, D., & Martin, J. R. (2012). *Learning to write, reading to learn: Genre, knowledge and pedagogy in the Sydney School*. Equinox.
14. Swales, J. M. (1990). *Genre analysis: English in academic and research settings*. Cambridge University Press.
15. Swales, J. M. (2004). *Research genres: Explorations and applications*. Cambridge University Press.
16. Tardy, C. M. (2009). *Building genre knowledge*. Parlor Press.
17. Wingate, U. (2012). Using academic literacies and genre-based models for academic writing instruction. *Journal of English for Academic Purposes*, 11(1), 26–37. <https://doi.org/10.1016/j.jeap.2011.11.006>
18. Wingate, U. (2015). *Academic literacy and student diversity: The case for inclusive practice*. Multilingual Matters.
19. Yasuda, S. (2011). Genre-based tasks in foreign language writing. *Journal of Second Language Writing*, 20(2), 111–133. <https://doi.org/10.1016/j.jslw.2011.03.001>
20. Johns, A. M. (2002). *Genre in the classroom: Multiple perspectives*. Lawrence Erlbaum Associates.
21. Paltridge, B. (2013). *Genre and English for specific purposes*. Routledge. <https://doi.org/10.4324/9780203084232>
22. Tribble, C. (2017). ELFA vs EAP: Exploring hybrid academic writing. *Journal of English for Academic Purposes*, 26, 31–42. <https://doi.org/10.1016/j.jeap.2017.01.002>
23. Casanave, C. P. (2010). *Taking risks? A case study of L2 writers*. University of Michigan Press.
24. Badger, R., & White, G. (2000). A process genre approach to teaching writing. *ELT Journal*, 54(2), 153–160. <https://doi.org/10.1093/elt/54.2.153>
25. Derewianka, B. (2003). Trends and issues in genre-based approaches. *REL C Journal*, 34(2), 133–154. <https://doi.org/10.1177/003368820303400202>

Орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздерін педагогикалық тұрғыдан зерделеу

Ғылыми жетекшісі:

Шашаева Гүлбақыт Қадыржанқызы

философия докторы (PhD), қауымдастырылған профессор, Абай атындағы Қазақ Ұлттық Педагогикалық университеті

Назарқызы Жания

Мектепке дейінгі оқыту және тәрбиелеу кафедрасының, 2 -курс студенті, Абай атындағы Қазақ Ұлттық Педагогикалық университеті

Ерекеш Құралай

Мектепке дейінгі оқыту және тәрбиелеу кафедрасының, 2 -курс студенті, Абай атындағы Қазақ Ұлттық Педагогикалық университеті

Мұрат Ақерке

Мектепке дейінгі оқыту және тәрбиелеу кафедрасының, 2 -курс студенті, Абай атындағы Қазақ Ұлттық Педагогикалық университеті

Кенжехан Тоғжан

Мектепке дейінгі оқыту және тәрбиелеу кафедрасының, 2 -курс студенті, Абай атындағы Қазақ Ұлттық Педагогикалық университеті

Кіріспе. Қазіргі қоғамда білім беру жүйесі мемлекеттің әлеуметтік-экономикалық дамуының маңызды факторы болып табылады. Орта білім беру жүйесіндегі оқу бағдарламалары білім мазмұнын айқындайтын негізгі құжаттардың бірі саналады және оқушылардың білім алу деңгейін, дағдыларын, құзыреттіліктерін қалыптастыруға бағытталған.

Оқу бағдарламаларының мазмұны мен құрылымы Қазақстан Республикасының «Білім туралы» Заңы, мемлекеттік жалпыға міндетті білім беру стандарттары және оқу жоспарлары сияқты құқықтық-нормативтік құжаттарға сүйене отырып әзірленеді [1, 15-б.]. Сонымен қатар, оқу бағдарламаларын жетілдіруде әлемдік педагогикадағы әртүрлі теориялар мен ғылыми тұжырымдар ескеріледі. Кейбір теориялар оқытуды мінез-құлықтың өзгеруі ретінде қарастырса, басқалары танымдық процестерге назар аударады, ал енді біреулері білімді тұлғаның белсенді түрде құрастыруының нәтижесі деп есептейді. Сондықтан бұл теорияларды жан-жақты талдау болашақ педагог үшін аса маңызды.

Зерттеудің өзектілігі: Қазіргі білім беру жүйесі қоғамның әлеуметтік-экономикалық дамуының маңызды факторы болып табылады, себебі білім беру сапасы елдің интеллектуалдық әлеуетін арттыруға және бәсекеге қабілетті мамандар даярлауға ықпал етеді. Орта білім беру жүйесінде оқу бағдарламаларын жетілдіру және олардың құқықтық-нормативтік негіздерін анықтау өзекті мәселе болып отыр. Қазақстанда білім саласын жаңарту мен оқыту әдістерін жетілдіру барысында оқу бағдарламалары негізгі құжат ретінде білім мазмұнын, оқу мақсаттары мен күтілетін нәтижелерді айқындайды [1, 25-б.].

Оқу бағдарламалары «Білім туралы» Заң, мемлекеттік жалпыға міндетті білім беру стандарты және басқа нормативтік құжаттарға сүйене отырып әзірленеді. Олар білім беру

жүйесінің құрылымы мен ұйымдастыру принциптерін реттейді. Ғалымдардың пікірінше, оқу бағдарламалары тек білім мазмұнын анықтап қана қоймай, оқыту процесін ғылыми тұрғыдан ұйымдастыруға мүмкіндік береді. Мысалы, В.А.Сластенин оларды білім беру жүйесінің мақсаттарын жүзеге асырудың негізгі құралы деп атайды [3, 56-б.]. Осылайша, орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздерін зерттеу білім беру сапасын арттыруға және оқу процесінің тиімділігін қамтамасыз етуге мүмкіндік береді.

Зерттеу мақсаты: Зерттеудің мақсаты – орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздерін ғылыми-теориялық тұрғыдан талдау, олардың білім беру жүйесіндегі рөлін анықтау және оқу процесінің тиімділігін арттырудағы маңызын көрсету.

Сонымен қатар зерттеу барысында оқу бағдарламаларының мазмұны мен құрылымы, оларды әзірлеудің ғылыми негіздері және білім беру жүйесіндегі орны қарастырылады.

Зерттеу міндеттері

1. Орта білім беру жүйесіндегі оқу бағдарламаларының мәні мен мазмұнын анықтау.
2. Оқу бағдарламаларын реттейтін негізгі құқықтық-нормативтік құжаттарды талдау.
3. Қазақстандағы білім беру реформалары жағдайында оқу бағдарламаларының ерекшеліктерін анықтау.
4. Оқу бағдарламаларын құрудың ғылыми-теориялық негіздерін зерттеу.
5. Оқу бағдарламаларының білім беру процесіндегі тиімділігін талдау.
6. Оқу бағдарламаларының артықшылықтары мен кемшіліктерін анықтап, оларды жетілдіру жолдарын ұсыну.

Зерттеу нысаны: Қазақстан Республикасының орта білім беру жүйесіндегі оқу бағдарламалары білім мазмұнын айқындайтын және оқу процесін ұйымдастырудың негізгі бағыттарын белгілейтін маңызды құжат болып табылады. Олар оқушылардың білім, білік және дағдыларын қалыптастыруға, танымдық қабілеттерін дамытуға және тұлғалық қасиеттерін жетілдіруге бағытталған. Оқу бағдарламалары мемлекеттік стандарттар мен нормативтік-құқықтық құжаттарға негізделіп әзірленеді, бұл білім мазмұнының бірізділігін қамтамасыз етеді [1, 28-б.]. Ғалымдардың пікірінше, оқу бағдарламалары білім беру жүйесінің мақсаттарын жүзеге асырудың негізгі құралы болып табылады В.А.Сластенин [3, 56-б.], сондықтан олардың құқықтық-нормативтік негіздерін зерттеу педагогика ғылымының маңызды мәселелерінің бірі.

Зерттеу пәні – Орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздері олардың оқу процесіндегі маңызды рөлін айқындайды. Олар білім мазмұнын, оқу мақсаттарын, күтілетін нәтижелерді және оқыту процесінің құрылымын анықтайтын негізгі құжат болып табылады және Қазақстан Республикасының «Білім туралы» Заңы, мемлекеттік жалпыға міндетті білім беру стандарты, типтік оқу жоспарлары сияқты нормативтік-құқықтық актілерге сүйеніп әзірленеді [5, 32-б.]. Пән аясында оқу бағдарламаларының мазмұны, құрылымы, ғылыми негіздері және қолданылу ерекшеліктері зерттеледі, сондай-ақ олардың білім беру жүйесіндегі орны мен оқушылардың білім сапасын арттырудағы рөлі қарастырылады. Ғалымдардың пікірінше, оқу бағдарламалары оқу мазмұнын жүйелеуге және оқу процесін мақсатты ұйымдастыруға мүмкіндік беретін маңызды құрал болып табылады (И.П. Подласый). Сондықтан олардың құқықтық-нормативтік негіздерін зерттеу білім беру жүйесінің тиімділігін арттыруға және оқыту сапасын жақсартуға мүмкіндік береді.

Зерттеу гипотезасы: Зерттеу барысында ұсынылған гипотеза – орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздерін жан-жақты зерттеу арқылы білім беру процесінің тиімділігін арттыру мүмкіндігі – расталды. Егер оқу бағдарламалары ғылыми негізделіп, қазіргі білім беру талаптарына сәйкес жетілдірілсе,

онда оқу процесі жүйеленіп, оқушылардың білім сапасы мен танымдық қабілеттері артады, ал мұғалімдердің педагогикалық қызметі тиімді ұйымдастырылады.

Педагогика мен психология ғылымдарының жетістіктері, халықаралық тәжірибе және қоғамның қазіргі талаптары ескерілсе, оқу бағдарламалары оқушылардың шығармашылық қабілеттерін дамытуға және функционалдық сауаттылығын арттыруға мүмкіндік береді. Осылайша, зерттеу гипотезасы расталып, оқу бағдарламаларының құқықтық-нормативтік негіздерін жетілдіру білім беру сапасын арттырудың маңызды факторы болып шықты.

Егер оқу бағдарламаларының құқықтық және нормативтік негіздері дұрыс анықталып, оқу процесінде тиімді қолданылса, онда:

- оқушылардың білім сапасы артады;
- оқу процесінің жүйелілігі қамтамасыз етіледі;
- мұғалімдердің педагогикалық қызметін тиімді ұйымдастыруға мүмкіндік туады;
- білім беру жүйесінің сапасы мен нәтижелілігі жоғарылайды.

Сонымен қатар, оқу бағдарламаларын жетілдіру білім беру жүйесінің тиімділігін арттырып, оқушылардың функционалдық сауаттылығы мен танымдық қабілеттерін дамытуға қолайлы жағдай жасайды. Осылайша, зерттеу гипотезасы орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздерін зерттеу білім беру мазмұнын жетілдіруге және оқу процесінің тиімділігін арттыруға мүмкіндік береді деген ғылыми болжамды растайды [2, 63-б.].

Зерттеу әдістері. *Тарихи-теориялық талдау.* Тарихи-теориялық талдау әдісі оқу бағдарламаларының қалыптасу тарихын, даму кезеңдерін және олардың ғылыми негіздерін зерттеуге бағытталған. Бұл әдіс арқылы білім беру жүйесіндегі оқу бағдарламаларының пайда болу себептері, олардың эволюциялық дамуы және қазіргі білім беру жүйесіндегі орны қарастырылды. Сонымен қатар осы әдіс арқылы педагогика ғылымындағы оқу мазмұнына қатысты негізгі теориялар мен тұжырымдар талданды. Мысалы, көптеген ғалымдар оқу мазмұнын ұйымдастырудың ғылыми негіздерін қарастырған. Я.А.Коменский оқыту процесінде жүйелілік пен бірізділік принциптерін ұсынса, К.Д.Ушинский оқу мазмұны оқушылардың жас ерекшеліктеріне сәйкес болуы керек екенін атап көрсеткен [1, 67-б.]. Осылайша, тарихи-теориялық талдау оқу бағдарламаларының қазіргі құрылымын түсінуге және олардың білім беру жүйесіндегі маңызын анықтауға мүмкіндік береді.

Салыстырмалы талдау. Салыстырмалы талдау әдісі әртүрлі елдердің оқу бағдарламаларын салыстыра отырып, олардың ерекшеліктерін, мазмұнын, құрылымын және жүзеге асыру тәсілдерін анықтауға мүмкіндік береді. Зерттеу барысында Қазақстандағы оқу бағдарламаларының ерекшеліктері басқа елдердің білім беру жүйелерімен салыстырылды. Нәтижесінде оқу бағдарламаларын жетілдірудің тиімді жолдары, инновациялық әдістерді енгізу мүмкіндіктері және заманауи білім беру талаптарына сәйкес келетін бағыттар анықталды. Ғалымдардың пікірінше, салыстырмалы талдау әдісі білім беру жүйесін жетілдіруде маңызды рөл атқарады, себебі ол халықаралық тәжірибені зерттеуге және оны ұлттық білім беру жүйесіне тиімді бейімдеуге мүмкіндік береді [2, 48-б.]. Атап көрсететін болсақ (Кесте -1)

Ішкі факторлар	Сыртқы факторлар
Күшті жақтары (Strengths)	Мүмкіндіктер (Opportunities)
Бағдарламалардың заманауи талаптарға сәйкестігі.	Цифрлық технологияларды оқу үдерісіне енгізу.
Функционалдық сауаттылықты арттыруға бағытталуы.	Халықаралық озық тәжірибелерді пайдалану.
Оқушылардың шығармашылық қабілеттерін дамыту.	Мұғалімдердің біліктілігін үздіксіз арттыру жүйесі.
Әлсіз жақтары (Weaknesses)	Қауіп-қатерлер (Threats)
Оқу жүктемесінің шамадан тыс көптігі.	Материалдық-техникалық базаның нашарлығы.
Оқу материалдарының тым күрделі болуы.	Білікті педагог кадрлардың тапшылығы.
Мұғалімдердің жаңа бағдарламаларға толық бейімделмеуі.	Білім беру деңгейіндегі (аймақтық, әлеуметтік) алшақтықтар.

Кесте -1. SWOT-талдау

Нәтижесінде, SWOT-талдау оқу бағдарламаларының күшті және әлсіз жақтарын, сондай-ақ даму мүмкіндіктері мен қауіп-қатерлерін анықтауға мүмкіндік береді.

- күшті жақтары – бағдарламалардың заманауи талаптарға сәйкестігі, функционалдық сауаттылық пен шығармашылықты дамытуға бағытталуы.

- әлсіз жақтары – оқу жүктемесінің көптігі, материалдардың күрделілігі, мұғалімдердің толық бейімделмеуі.

- мүмкіндіктер – цифрлық технологияларды енгізу, халықаралық тәжірибені пайдалану, мұғалімдердің біліктілігін арттыру.

- қауіп-қатерлер – материалдық базаның жеткіліксіздігі, кадр тапшылығы және білім беру деңгейіндегі айырмашылықтар.

зерттеу кезеңдерінің ғылыми-әдістемелік жоспары:

Зерттеу кезеңдері. Ғылыми жобаны жүйелі түрде жүзеге асыру үшін келесі кезеңдерді орындау қажет:

I кезең: Теориялық-талдамалық (Дайындық)

- Орта білім берудің нормативтік-құқықтық актілерін (МЖМБС, «Білім туралы» Заң) педагогикалық тұрғыдан экспликациялау (лат. *explicatio* — түсіндіру, жаю).

- Қазіргі оқу бағдарламаларының заманауи талаптарға сәйкестігін зерделеу және SWOT

талдау арқылы ішкі-сыртқы факторларды анықтау.

II кезең: Диагностикалық-эксперименттік (Зерттеу)

- Студенттер мен педагогтар арасында құқықтық сауаттылық пен бағдарлама мазмұнына

қанағаттану деңгейін анықтау үшін эмпирикалық сауалнамалар жүргізу.

- Алынған нәтижелерді статистикалық өңдеу (мысалы, респонденттердің 70,6%-ының құқықтық негіздер туралы жалпы түсінігінің болуы сияқты деректерді талдау).

III кезең: Прогностикалық-конструктивтік (Әзірлеу)

- Құжаттардың күрделілігі мен тәжірибе арасындағы сәйкессіздікті жоюдың ғылыми педагогикалық моделін құрастыру.

- Оқу жүктемесін тиімді бөлу және материалдық базаның жеткіліксіздігі жағдайында бағдарламаны іске асыру жолдарын қарастыру.

IV кезең: Тәжірибелік-қорытынды (Нәтиже)

- Зерттеу нәтижелерін қорытындылап, білім беру сапасын арттыру бойынша нақты ұсыныстар дайындау.
- Педагогтардың кәсіби қызметіне нормативтік негіздердің оң әсерін (76,5%) арттыратын әдістемелік нұсқаулықтарды бекіту.

Ұсынылған кезеңдер мен стратегиялар орта білім беру жүйесіндегі заңнамалық талаптар мен педагогикалық шынайылық арасындағы теңгерімді қамтамасыз етуге бағытталған тұжырымдаймыз.

Эмпирикалық зерттеу. Эмпирикалық зерттеу әдісі мектеп тәжірибесін зерттеу арқылы оқу бағдарламаларының тиімділігін анықтауға мүмкіндік береді. Зерттеу барысында бағдарламалардың оқушылардың білім, білік және дағдыларын қалыптастыруға, олардың танымдық белсенділігін арттыруға және шығармашылық қабілеттерін дамытуға бағытталғаны анықталды. Сонымен қатар, зерттеу оқу бағдарламаларын жүзеге асыру барысында кездесетін қиындықтарды да көрсетті. Мысалы, кейбір мұғалімдер жаңа бағдарламаларға бейімделу кезінде оқу жүктемесінің жоғары болуы, оқу материалдарының күрделілігі және педагогикалық дағдылардың талаптарға толық сәйкес келмеуі сияқты мәселелерге тап болады [3, 59-б.].

Зерттеу нәтижелері оқу бағдарламаларын тиімді қолдану үшін педагогикалық қолдаудың, мұғалімдердің кәсіби дайындық деңгейінің және бағдарлама мазмұнын үнемі жетілдірудің қажеттілігін дәлелдейді. Сонымен қатар эмпирикалық талдау оқу процесінде оқушылардың функционалдық сауаттылығын, танымдық және шығармашылық қабілеттерін дамытуға бағытталған іс-әрекеттердің маңыздылығын көрсетті. Осылайша, эмпирикалық зерттеу оқу бағдарламаларының практикалық тиімділігін арттыру үшін ғылыми негізде ұсыныстар жасауға мүмкіндік береді.

Ғылыми негіздер:

- оқу бағдарламалары педагогика, психология және дидактика ғылымдарының негізгі қағидаларына сүйене отырып әзірленеді;
- Ж. Пиаже когнитивтік даму теориясында баланың танымдық қабілеттері белгілі бір кезеңдер арқылы дамитынын дәлелдеген. Сондықтан оқу бағдарламаларын әзірлеу кезінде оқушылардың жас ерекшеліктерін ескеру қажет [7, 54-б.].
- Л.С.Выготскийдің мәдени-тарихи теориясына сәйкес оқыту процесі баланың даму аймағына сәйкес ұйымдастырылуы тиіс. Оның пікірінше, тиімді ұйымдастырылған оқыту баланың интеллектуалдық дамуына ықпал етеді [8, 112-б.].

Абай атындағы ҚазҰПУ Бастауышта оқыту педагогикасы мен әдіснамесі 2 курс студенттерінің қатысуымен Google forms сілтемесі арқылы 02.03.2026-13.03.2026 аралығында «Орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздерін педагогикалық тұрғыдан зерделеу мақсатына жүргізілген сауалнамалар нәтижелерін ұсынатын боламыз (Қосымша парақта). Сыналған сауалнама нәтижелерін зерделей келе, орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздеріне қатысты студенттердің пікірлерін талдайтын болсақ:

Орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздерін зерделеу нәтижелерінің талдамалық есебі

Зерттеу нысаны: Студенттер (респонденттер саны – 17). Зерттеу мақсаты: Білім беру бағдарламаларының құқықтық негіздерін педагогикалық тұрғыдан бағалау және олардың практикалық тиімділігін анықтау.

1. Құқықтық-нормативтік білім деңгейі және маңыздылығы

Сауалнама нәтижелері респонденттердің басым бөлігі (70,6%) орта білім берудің нормативтік негіздері туралы «жалпы түсінігі бар» екенін көрсетті. Сонымен қатар, студенттердің 52,9%-ы нормативтік құжаттарды оқу процесін ұйымдастыруда «өте маңызды» деп санайды. Бұл болашақ мамандардың кәсіби қызметтегі заңнамалық талаптардың рөлін жоғары бағалайтынын айғақтайды.

2. Кәсіби қызметке әсері және орындалу деңгейі

Зерттеуге қатысушылардың 76,5%-ы құқықтық-нормативтік негіздер педагогтың кәсіби қызметіне «өте жоғары әсер етеді» деп есептейді. Оқу бағдарламаларын жүзеге асыру барысында нормативтік құжаттардың сақталу деңгейіне қатысты респонденттердің 82,4%-ы бұл талаптардың «толық орындалатынын» растады. Бұл білім беру жүйесіндегі регламентацияның жоғары деңгейін көрсетеді.

3. Анықталған мәселелер мен кемшіліктер

Қазіргі нормативтік негіздердегі негізгі проблемаларды анықтау барысында пікірлер теңдей бөлінді:

- Респонденттердің 47,1%-ы құжаттардың тым күрделілігін атап өтсе;
- Тағы 47,1%-ы теориялық нормалар мен практикалық қолданыс арасындағы сәйкессіздікті (тәжірибемен сәйкессіздік) басты мәселе ретінде көрсетті.
- Тек 5,9%-ы ғана ешқандай түсініксіздік жоқ деп санайды.

4. Бағдарламаларды жетілдіру бағыттары

Оқу бағдарламаларын оңтайландыру мақсатында студенттер келесідей ұсыныстарды алға тартты:

- Практикамен сәйкестендіру: Респонденттердің 47,1%-ы бағдарлама мазмұнын нақты практикалық талаптарға жақындатуды қолдайды.
- Құжаттарды жеңілдету: 35,3%-ы нормативтік актілердің құрылымы мен тілін қарапайымдату қажет деп есептейді.
- Түсіндіру жұмыстары: 17,6%-ы мұғалімдерге арналған әдістемелік және түсіндіру шараларын арттыруды ұсынды.

Эмпирикалық зерттеу нәтижелері

Зерттеу барысында орта білім беру ұйымдарындағы мұғалімдердің тәжірибесі мен оқу бағдарламаларының оқу процесінде қолданылу ерекшеліктері талданды.

Зерттеу нәтижелері оқу бағдарламаларының келесі ерекшеліктерін анықтауға мүмкіндік берді:

- оқу мазмұнының жаңартылған бағытта құрылуы;
- оқушылардың құзыреттіліктерін дамытуға бағытталуы;
- пәндер арасындағы интеграцияның күшеюі;
- оқытуда заманауи педагогикалық технологияларды қолдану мүмкіндігінің артуы.

Бұл нәтижелер оқу бағдарламалары қазіргі білім беру талаптарына сәйкес жетілдіріліп жатқанын көрсетеді.

Зерттеу нәтижелерін талдау. Зерттеу нәтижелері оқу бағдарламаларының білім беру процесінде маңызды рөл атқаратынын көрсетті. Олар білім мазмұнын жүйелі түрде ұйымдастыруға және оқу мақсаттарын нақты анықтауға мүмкіндік береді. Сонымен қатар оқу бағдарламалары мұғалімдердің кәсіби қызметін тиімді ұйымдастыруға, оқушылардың білім деңгейін бағалауға және оқу нәтижелерін жоспарлауға көмектеседі.

Артықшылықтары:

- білім мазмұнының жүйелі түрде ұйымдастырылуы;

- оқушылардың танымдық қабілеттерін дамытуға бағытталуы;
 - құзыреттілікке негізделген білім беру принциптерінің енгізілуі;
 - оқытуда заманауи технологияларды қолдану мүмкіндігі
- Кемшіліктері:*
- кейбір пәндер бойынша оқу жүктемесінің жоғары болуы;
 - оқу материалдарының күрделілігі;
 - мұғалімдердің жаңа бағдарламаларға бейімделуінде қиындықтардың кездесуі;
 - оқу-әдістемелік материалдардың жеткіліксіздігі. Ал, тақырыбымызды талдауға өзек болған: Оқу бағдарламаларының құқықтық-нормативтік негіздері (2-кесте); Оқу бағдарламаларының құрылымдық элементтері (3-кесте); Оқу бағдарламаларының тиімділіктерін (4-кесте) нақтылап барып талдау жұмысын жүргіземіз.

Құжат атауы	Сипаттамасы	Маңызы
ҚР «Білім туралы» Заңы	Білім беру саласын реттейтін негізгі заң	Білім беру жүйесінің жалпы қағидаларын анықтайды
МЖМБС	Білім мазмұнына қойылатын талаптар	Оқу бағдарламасының құрылымын белгілейді
Оқу жоспарлары	Пәндер тізімі мен сағат көлемі	Оқу процесін ұйымдастырады

2-кесте. Оқу бағдарламаларының құқықтық-нормативтік негіздері

Элемент	Сипаттамасы
Оқу мақсаттары	Оқушылар меңгеруі тиіс нәтижелер
Мазмұны	Пән бойынша тақырыптар жүйесі
Бағалау критерийлері	Білімді тексеру тәсілдері
Күтілетін нәтижелер	Оқушы жетістіктері

3-кесте. Оқу бағдарламаларының құрылымдық элементтері

Көрсеткіш	Сипаттамасы
Жүйелілік	Білім мазмұнының бірізділігі
Қолжетімділік	Оқушыларға түсініктілігі
Практикалық бағыт	Өмірмен байланысы
Құзыреттілік	Дағдыларды дамыту

4-кесте. Оқу бағдарламаларының тиімділігі

Қорытынды және ұсыныстар.

Жүргізілген зерттеу орта білім беру жүйесіндегі оқу бағдарламаларының құқықтық-нормативтік негіздерін жан-жақты талдауға мүмкіндік берді. Оқу бағдарламалары білім беру мазмұнын, оқыту мақсаттарын, оқу нәтижелерін және оқу процесін ұйымдастырудың негізгі бағыттарын айқындайтын маңызды құжат болып табылады. Қазақстанда олар «Білім туралы» Заң, мемлекеттік жалпыға міндетті білім беру стандарттары және типтік оқу жоспарлары сияқты нормативтік-құқықтық құжаттарға негізделіп әзірленеді, бұл білім беру мазмұнының бірізділігін және оқушылардың білім деңгейіне қойылатын талаптарды қамтамасыз етеді.

Зерттеу нәтижелері қазіргі оқу бағдарламалары білім мазмұнын жаңарту, оқушылардың функционалдық сауаттылығын дамыту және құзыреттілікке негізделген оқытуды жүзеге асыру бағытында жетілдіріліп жатқанын көрсетті. Сонымен қатар олар оқушылардың танымдық белсенділігін арттыруға, шығармашылық қабілеттерін дамытуға

және жеке тұлғалық қасиеттерін қалыптастыруға бағытталған. Дегенмен, кейбір пәндер бойынша оқу жүктемесінің жоғары болуы, материалдардың күрделілігі және мұғалімдердің жаңа бағдарламаларға толық бейімделмеуі сияқты қиындықтар байқалады, бұл бағдарламаларды одан әрі жетілдіру қажеттігін көрсетеді.

Қорытындыласақ, жүргізілген талдау нәтижесі көрсеткендей, студенттер оқу бағдарламаларының құқықтық негіздерін кәсіби қажеттілік ретінде таниды. Алайда, нормативтік құжаттардың күрделілігі және тәжірибелік қолданыстан алшақтығы білім беру жүйесіндегі басты кедергілер болып табылады. Оқу бағдарламаларының тиімділігін арттыру үшін нормативтік базаны де бюрократизациялау (жеңілдету) және оның практикалық бағытын күшейтуді және осыған байланысты келесі ұсыныстармен қорытындыласақ:

1. Оқу бағдарламаларын жетілдіру барысында халықаралық тәжірибені ескеру. Әлемдік білім беру жүйесіндегі озық тәжірибелерді зерттеу және оларды ұлттық білім беру жүйесіне бейімдеу оқу бағдарламаларының тиімділігін арттыруға мүмкіндік береді.
2. Мұғалімдердің кәсіби біліктілігін арттыру. Оқу бағдарламаларын тиімді жүзеге асыру үшін мұғалімдердің кәсіби құзыреттілігін арттыру маңызды. Осы мақсатта біліктілікті арттыру курстарын, семинарлар мен тренингтерді жүйелі түрде ұйымдастыру қажет.
3. Оқу бағдарламаларын оқушылардың жас және психологиялық ерекшеліктеріне бейімдеу. Оқу материалдары оқушылардың жас ерекшеліктеріне сәйкес құрылуы тиіс. Бұл оқыту процесінің тиімділігін арттыруға және оқушылардың білімді жақсы меңгеруіне мүмкіндік береді демекпіз.

Пайдаланылған әдебиеттер

1. Қазақстан Республикасының «Білім туралы» Заңы. – Астана: Ақорда, 2022. – 68 б.
2. Қазақстан Республикасының орта білім берудің мемлекеттік жалпыға міндетті стандарты. – Астана: ҚР Оқу-ағарту министрлігі, 2023. – 54 б.
3. Аймағамбетова Б.Қ. Білім беру жүйесінің теориясы мен әдіснамасы. – Алматы: Қазақ университеті, 2021. – 256 б.
4. Қоянбаев Ж.Б., Қоянбаев Р.М. Педагогика. – Алматы: Эверо, 2019. – 320 б.
5. Слостенин В.А., Исаев И.Ф., Шиянов Е.Н. Педагогика. – Москва: Академия, 2018. – 576 с.
6. Подласый И.П. Педагогика: жаңа курс. – Москва: Юрайт, 2020. – 402 с.
7. Выготский Л.С. Педагогическая психология. – Москва: Юрайт, 2021. – 318 с.
8. Piaget J. The Psychology of Intelligence. – London: Routledge, 2017. – 182 p.
9. OECD. Education at a Glance 2022: OECD Indicators. – Paris: OECD Publishing, 2022. – 490 p.
10. Қазақстан Республикасында білім беруді дамытудың 2020–2025 жылдарға арналған мемлекеттік бағдарламасы. – Астана, 2020. – 96 б.
11. Назарбаев Н.Ә. Қазақстандағы білім беру жүйесін жаңғырту. – Алматы: Білім, 2018. – 212 б.
12. Қазақстан Республикасы Оқу-ағарту министрлігі. Ресми сайт. – URL: <https://www.edu.gov.kz>
13. Қазақстан Республикасының нормативтік-құқықтық актілерінің ақпараттық жүйесі «Әділет». – URL: <https://adilet.zan.kz>
14. Ы.Алтынсарин атындағы Ұлттық білім академиясы. – URL: <https://nao.kz>

GLOCAL FASHION EDUCATION: НОВЫЕ ОРИЕНТИРЫ КАЗАХСТАНСКОГО ДИЗАЙН-ОБРАЗОВАНИЯ

Ибраева Айгуль Бахытовна

магистр искусств, доцент кафедры «Мода и дизайн костюма», Казахская национальная академия искусств имени Темирбека Жургенова (Алматы, Казахстан)

Аннотация. В статье рассматриваются ключевые вызовы, стоящие перед казахстанской модной индустрией и системой подготовки фэшн-дизайнеров в контексте глобальных тенденций и локальных культурных процессов. Глобализация, развитие цифровых технологий и растущая значимость устойчивого развития усиливают потребность в переосмыслении роли культурного наследия в современной моде. В казахстанском фэшн-пространстве эти процессы проявляются в повышенном интересе дизайнеров к национальной идентичности и поиске нового визуального языка, основанного на глубоких смыслах традиции. Подчеркивается необходимость перехода от поверхностной стилизации к этически выверенной, исследовательски обоснованной работе с культурными кодами. Обосновывается важность модернизации дизайн-образования через интеграцию проектно-исследовательского подхода, сотрудничества с музеями и ремесленными сообществами, внедрение цифровых технологий. В итоговых положениях формулируется концепция «Glocal Fashion Education» как стратегического направления развития казахстанской школы дизайна, соединяющей международные профессиональные стандарты и локальную культурную идентичность.

Ключевые слова: культурное наследие; глобализация; казахстанская мода; фэшн-дизайн; дизайн-образование; дизайн идентичности; устойчивое развитие; культурные коды; культурная апроприация; glocal fashion education.

Современная мировая индустрия моды переживает этап глубоких трансформаций, обусловленных ускорением глобализационных процессов, развитием цифровых технологий, усилением значимости принципов устойчивого развития и ростом роли культурного разнообразия в творческих практиках. Эти тенденции оказывают существенное влияние на локальные модные индустрии, которым необходимо одновременно адаптироваться к международным профессиональным стандартам и сохранять уникальные культурные коды, определяющие их идентичность [1]. Казахстанская мода, как относительно молодая, динамично развивающаяся отрасль креативной экономики, находится в точке пересечения этих разнонаправленных процессов, что стимулирует дизайнеров встраиваться в русло глобального модного дискурса и обращаться к работе с национальным наследием как с важнейшим ресурсом, способным подчеркнуть уникальность бренда.

Процессы глобализации во многом усилили интерес к выражению культурной и национальной идентичности в казахстанском обществе. В последние годы заметно растёт спрос на одежду и аксессуары в этническом стиле, предназначенные не только для традиционных семейных мероприятий и праздников, но и для повседневного использования. Существенную часть данной потребительской аудитории составляет молодое поколение казахстанцев, и для многих начинающих локальных брендов обращение к этнокультурным мотивам становится не только эстетической стратегией, но и важным инструментом конкурентоспособности и позиционирования в локальном и глобальном

модном поле. С каждым новым поколением дизайнеров, с одной стороны, возрастает значение культурного наследия как стратегического ресурса развития казахстанской моды, а с другой — всё большую роль в процессах формирования культурной идентичности начинает играть сама казахстанская мода.

В условиях растущего интереса к культурному наследию особенно остро встаёт вопрос профессиональной ответственности дизайнера, чья работа неизбежно формирует способы восприятия традиции современным обществом. Используя наследие как источник вдохновения и средство культурной коммуникации, дизайнеры одновременно выступают медиаторами между прошлым и настоящим, и от качества их интерпретации зависит не только визуальный результат, но и сохранность смыслов. Некорректная стилизация, поверхностное цитирование или опора на уже искажённые интерпретации могут приводить к утрате нюансов, стереотипизации и упрощению культурного кода [2, с. 32].

На этом фоне возрастает роль образовательных институтов, обеспечивающих подготовку будущих дизайнеров. Они должны взять на себя определённую долю ответственности за подходы к творческой интерпретации национального культурного наследия в практиках фэшн-дизайна, приняв тем самым участие в формировании вектора развития казахстанской моды в глобализированной модной среде. На сегодняшний день наблюдается значительный разрыв между академическими моделями казахстанских образовательных программ в этой области и современными практиками моды. Профессиональные компетенции дизайнеров больше не ограничиваются декоративно привлекательными, но часто поверхностными заимствованиями национальной эстетики, а подразумевают знание и уважение историко-культурного контекста, из которого эта эстетика берёт своё начало, глубокое понимание смысловой ценности, заложенной в традиции, и осознание личной ответственности за использование и авторскую интерпретацию этнокультурного материала.

Перед казахстанским дизайн-образованием встаёт задача: найти баланс между глобальными компетенциями и локальной идентичностью в подготовке дизайнеров нового поколения, и ключевым аспектом преобразований образовательных программ должны стать вопросы изучения и творческой интерпретации культурного наследия в контексте мировых тенденций в моде и образовании.

Можно выделить три ключевые глобальные тенденции, напрямую влияющие на процессы переосмысления этнических традиций в моде: устойчивое развитие (sustainability), этическая проблематика использования культурного наследия (включая феномен cultural appropriation) и потребность в выражении личной и культурной идентичности (identity design) [1].

Создание экологически безопасного, долговечного и уникального дизайна, основанного на принципах экологичности, локализма, уважения к ручному труду и бережного отношения к ресурсам, является главным вектором устойчивого развития моды и не менее важным основанием для неизбежной трансформации казахстанского образования в области фэшн-дизайна [3]. В этом контексте сохранение и применение традиционных материалов и ремёсел в современном дизайне костюма можно рассматривать не только как культурную миссию, но и как практику устойчивого развития, придающую казахстанскому этнодизайну международную актуальность. Казахские дизайнеры всё чаще используют традиционные материалы и технологии не только как декоративный элемент, но и как форму экологического и культурного манифеста [4, 5, 6]. Для расширения этих практик необходимо налаживание постоянного сотрудничества дизайнеров и университетов с ремесленными сообществами, включающего реализацию совместных творческих проектов. Уникальным, масштабным и вдохновляющим примером междисциплинарного подхода к творческим практикам стала биеннале современного искусства в Бухаре, где были представлены более

70 арт-объектов, созданных художниками из Узбекистана и других стран в коллаборации с местными ремесленниками. Сам проект стал частью программы возрождения исторической части города Бухары и направлен на сохранение культурного наследия через его современную интерпретацию [7].

Признание роли культурного наследия в моде выводит понятие устойчивого развития за пределы исключительно экологической повестки. В условиях глобализации культурные образы, символы и стилистические коды становятся частью транснационального визуального обмена, что, с одной стороны, способствует межкультурному диалогу, а с другой – усиливает риск культурной апроприации как некорректного, вырванного из контекста использования элементов чужой культуры ради коммерческого или эстетического эффекта. Как отмечают авторы исследования «Влияние глобализации на моду и СМИ: объединение культур посредством стиля», глобальная медийная среда ускоряет циркуляцию знаков и стилей, создавая как возможности для расширения культурного присутствия, так и угрозы искажения смыслов и утраты подлинности [8, с. 11]. В этом контексте особую значимость приобретает профессиональная и этическая ответственность дизайнеров, работающих с элементами и мотивами собственной культуры: они не только транслируют её ценности и визуальные коды в современность, но и несут обязанность делать это уважительно и осмысленно, так, чтобы их творческая интерпретация укрепляла, а не упрощала или искажала культурное наследие.

Признание этой ответственности требует от системы дизайн-образования целенаправленной работы по формированию у студентов не только художественных и технических навыков, но и культуры исследования, интерпретации и этического осмысления наследия. В образовательные программы целесообразно включить модули, направленные на развитие критического понимания культурного контекста: курсы по истории материальной культуры Центральной Азии, новаторские курсы по истории костюма, учитывающие культурное многообразие, глобальные тренды и межкультурное взаимовлияние [9], семинары по вопросам культурного наследия и культурного обмена. Особое внимание следует уделить развитию этического мышления: обсуждению кейсов культурной апроприации, анализу успешных и неудачных примеров обращения к наследию, формированию навыка осознанного «культурного самоконтроля» в проектной деятельности.

Не меньшее внимание должно быть уделено взаимодействию студентов с музеями, архивами и культурными институциями. Несмотря на наличие музейной практики в действующих учебных планах, она нередко носит формальный характер, ограничиваясь ознакомительной экскурсией и графической фиксацией экспонатов. Показательным примером эффективного сотрудничества образовательной среды и музейных институций является проект Museum-University Partnership Initiative (MUPI) (Великобритания), объединивший преподавателей моды и текстиля, исследователей, студентов и музейных специалистов с целью формирования устойчивых партнёрств, обмена знаниями и открытия потенциала локальных музейных коллекций для высшего образования и творческой индустрии. Опыт MUPI демонстрирует, что системное взаимодействие университета и музея позволяет не только расширить исследовательские и творческие возможности студентов, но также укрепить институциональные ресурсы музеев, чьи коллекции становятся активным участником образовательного процесса [10].

Одновременно важно усилить акцент на проектно-исследовательском подходе в организации образовательного процесса. Эффективной мерой станет создание лабораторий или исследовательских центров культурного наследия при вузах, где студенты смогут экспериментировать с традиционными материалами, техниками, красителями и их технологическими аналогами. Кроме того, образовательные стандарты должны учитывать такие современные глобальные требования, как цифровое прототипирование, 3D-

моделирование, визуальные исследования и построение дизайнерских нарративов, но интегрировать их таким образом, чтобы они не вытесняли локальный культурный материал, а расширяли возможности его осмысленной интерпретации. Такой подход позволит будущим дизайнерам сознательно создавать собственные интерпретации культурного наследия, понимая границы между цитированием и копированием, между диалогом культур и коммерциализацией символов.

Вопросы устойчивости и личной ответственности за интерпретацию этнокультурного наследия становятся ключом к проблематике identity design – подходу, ориентированному на создание современного визуального языка, отражающего уникальность культурной идентичности. Глобализация, открывшая широкие возможности для межкультурного обмена, парадоксальным образом привела к заметной унификации моды: стандартизации силуэтов, визуальных кодов и потребительских предпочтений под влиянием транснациональных брендов и индустрии быстрой моды. Глобальные медиа и мировые модные корпорации ускорили процесс гомогенизации, в результате которого локальные стилевые традиции вытесняются универсальными трендами [8, с. 11]. Отвечая на эти вызовы, мода, будучи формой визуального самовыражения, сегодня превращается в пространство пересборки комбинаций личных, социальных и культурных смыслов, отражающих динамику общества и стремление к осмысленному самоопределению. В этом пространстве творческое переосмысление культурного наследия становится способом коммуникации между прошлым и настоящим и инструментом исследования собственной культурной идентичности [2, с. 35].

Поиски культурной идентичности в моде – это всегда глубокий творческий процесс, основанный на стремлении не столько воспроизводить или цитировать фольклорные мотивы, сколько формировать уникальный визуальный язык авторского высказывания. Такой язык становится способом размышления о традиционных ценностях и мировоззренческих основах национальной культуры, превращаясь в своеобразную форму исторической памяти и личной рефлексии дизайнера. В интервью интернет-изданию The Steppe генеральный директор Visa Fashion Week Almaty и Visa Fashion Week Tashkent, организатор конкурса Next Designer Award Бауыржан Шадибеков, отвечая на вопрос о том, как использовать культурный код, не становясь его заложником, сформулировал ключевой принцип работы с наследием в фэшн-дизайне: «Для меня культурное наследие — это огромный источник вдохновения, но его важно подавать современно. Не просто копировать орнаменты или костюмы, а переосмысливать их: работать с символикой, цветами, формами и переводить это на язык сегодняшнего дня. Наша задача — не повторять прошлое, а вести с ним диалог. Тогда культура становится опорой, а не ограничением» [11]. Данный принцип должен находить отражение в содержательных и методологических аспектах подготовки дизайнеров через развитие концептуального мышления и исследовательского подхода. Учебные планы целесообразно дополнять дисциплинами, направленными на анализ архетипов и визуальных кодов культуры, а также на работу с метафорой и образными структурами как основой для создания концептуально выстроенных художественных решений, основанных на глубоком понимании контекста и смыслов.

Как можно заметить, глобальные тенденции не противопоставлены обращению к традициям, а, напротив, усиливают их значение, объединяя культурное наследие с этическими и устойчивыми практиками. В современных практиках моды творческие возможности неизбежно сочетаются со значительными методологическими и этическими вызовами, требующими уважительного взаимодействия с культурой, внимательного изучения первоисточников, понимания исторического контекста и ответственной позиции автора. Это не отменяет творческой свободы, но определяет новые рамки осознанности,

позволяя создавать оригинальные образы, которые не искажают, а обогащают культурную память и способствуют её актуализации в современном модном поле.

Сегодня в казахстанском фэшн-пространстве представлены бренды, успешно адаптирующие этнокультурные коды в контексте глобальных тенденций для создания коммерчески востребованной одежды. Так, бренд Global Nomads формирует современный образ неономада, опираясь на ценности миллениального поколения – осознанность, ответственное потребление и стремление к самобытному стилю, – и одновременно интерпретирует кочевое наследие Великой Степи, интегрируя его символику в свои коллекции [9]. Знаковый для народов Центральной Азии чапан (шапан) давно вышел за пределы региона, став узнаваемым элементом модных образов. Его интерпретации отличаются разнообразием: от эксклюзивных изделий из винтажных центральноазиатских тканей с ручной вышивкой Асель Кенжетасовой до минималистичных моделей с цифровыми узорами, создаваемых дизайнером Асель Танирберген в коллаборации с художниками [12]. Независимый бренд одежды и аксессуаров AL BASTY, черпая вдохновение в тюркской мифологии, создаёт авангардные образы, в том числе с применением 3D-технологий. Каждый показ бренда объединяет традиции и современность в целостном визуальном повествовании, а такие изделия, как джинсы «Айдаһар», становятся хитами продаж и знаковыми элементами коллекций [13]. Ставшая уже известной четвёрка казахстанских дизайнеров концептуального направления – Асем Сапаргали, Расул Социал, Алмас Керимбек и Абзал Сейдин – переосмысливает представление о моде через индивидуальную эстетику каждого автора, превращая показы в провокационные перформансы, в которых метафорически осмысливаются страницы истории, сформировавшие культурный код казахской нации [14].

Динамичное развитие казахстанской моды, демонстрирующей разнообразные подходы к работе с наследием, подчёркивает необходимость системного осмысления того, как эти процессы отражаются в профессиональной подготовке будущих дизайнеров. Актуальные глобальные реалии и внутренние культурные процессы требуют критического анализа и пересмотра как объёма, так и содержания этнокультурного компонента в образовательных программах в области фэшн-дизайна, а также постепенного перехода от академической практики подачи учебного материала к моделям проактивного участия преподавателей и студентов в процессах сохранения и исследования национального культурного наследия, творческого переосмысления его визуальных кодов и смысловых систем, к получению практического опыта работы с традиционными техниками и материалами, сотрудничеству с музеями, архивами и ремесленными сообществами.

Требующая дальнейшей разработки модель на основе концепции «Glocal Fashion Education» может стать долгосрочной стратегией казахстанского дизайн-образования, соединяя актуальные профессиональные стандарты и богатое культурное наследие для формирования собственной дизайнерской школы.

Литература

1. McKinsey & Company / The Business of Fashion. The State of Fashion 2024. – URL: <https://www.mckinsey.com/industries/retail/our-insights/state-of-fashion>.
2. Демшина А. Ю. Культурное наследие в дизайне // Вестник Санкт-Петербургского государственного института культуры. – 2024. – № 4(61). – С. 31–36.
3. Ибраева А. Концепции устойчивой моды в дизайн-образовании: проблемы и перспективы // Central Asian Journal of Art Studies Central Asian Journal of Art Studies. – 2024. – Т. 9, № 2. – С. 134–155. – DOI: 10.47940/cajas.v9i2.819.
4. Абдикаева А., Шенцова А. Феномен художественного войлока в современном искусстве костюма // Central Asian Journal of Art Studies. – 2024. – Т. 9, № 1. – С. 86–101. – DOI: 10.47940/cajas.v9i1.783.
5. Alzhanov G., Bekbolatova K., Ermakhanbetova A. The genesis of the development of ecodesign in the art of embroidery // Pedagogy and Psychology. – 2022. – № 3(52). – P. 93–95. – DOI: 10.51889/43.91.2022.48.29.009.
6. Жангужинова М. Е., Талгатбекова А. М., Езиева М. М., Турумкожаева Ж. С. Этнофутуризм казахстанского бренда одежды «Global Nomads» в Fashion Design // Вестник Алматинского технологического университета. – 2024. – Т. 146, № 4. – С. 192–201. – DOI: 10.48184/2304-568X-2024-4-192-201.
7. Bukhara Biennial. Официальный сайт. – URL: <https://www.bukharabiennial.uz>.
8. Yuan H., Lin R., Su Y., Mao Z., Li X. The Impact of Globalization on Fashion and Media: Bridging Cultures Through Style // Advances in Social Behavior Research. – 2024. – Vol. 12. – P. 8–12. – DOI: 10.54254/2753-7102/12/2024116.
9. Жангужинова М. Интернационализация методов преподавания истории костюма: этнофутуризм и наследие Шелкового пути // Central Asian Journal of Art Studies. – 2025. – Т. 10, № 1. – С. 298–311. – DOI: 10.47940/cajas.v10i1.966.
10. Hackney F., Baines E., Bloodworth J., McKenzie A., et al. Talking Textiles, Making Value: Catalyzing Fashion, Dress, and Textiles Heritage in the Midlands // Journal of Textile Design Research and Practice. – 2020. – Vol. 8, № 1. – P. 84–111. – DOI: 10.1080/20511787.2019.1682909.
11. Молодые дизайнеры, апсайклинг и культурный код: Бауыржан Шадибеков о вызовах модной индустрии Центральной Азии // STEPPE. – 20.08.2025. – URL: <https://the-steppe.com/razvitie/molodye-dizajnerj-apsajkling-i-kulturnyj-kod-bauyrzhan-shadibekov-o-vyzovah-modnoj-industrii-centralnoj-azii>.
12. Казахский шик: как чапаны покоряют мир в 2025 году // ELLE.KZ. – 03.09.2025. – URL: https://el.kz/ru/kazahskiy-shik-kak-chapany-pokoryayut-mir-v-2025-godu_400034468/.
13. AL.BASTY – BAUYR SAQ: эксклюзивная съемка для ELLE Kazakhstan // ELLE.KZ. – 15.12.2023.
14. Фэшн-перформанс QYSTAU четырёх казахстанских дизайнеров состоится в Алматы // 98mag. – 02.12.2024. – URL: <https://www.98mag.kz/stil/feshn-performans-qystau-chetyryoh-kazahstanskih-dizajnerov-sostoitsya-v-almaty/>.

DEVELOPING RESEARCH SKILLS OF PRIMARY SCHOOL STUDENTS THROUGH GAME-BASED TECHNOLOGIES (IN NATURAL SCIENCE EDUCATION)

Tuleubek Shugyla Manatbekkyzy

Master's student, 1st year, Specialty: Pedagogy and Methodology of Primary Education, Institute of Pedagogy and Psychology, Abai Kazakh National Pedagogical University

Aziza Zhunusbekova

PhD, Acting Associate Professor, Department of Primary Education, Abai Kazakh National Pedagogical University, Almaty, Kazakhstan

This article examines the effectiveness of implementing game-based technologies to develop research skills among primary school students within the context of natural science education. The relevance of this study is grounded in the contemporary educational paradigm, which emphasizes that students should not only acquire theoretical knowledge but also be capable of applying it in practice, formulating problems, and cultivating scientific reasoning skills. In this regard, game-based technologies serve as a critical pedagogical tool, promoting active engagement in the learning process and enhancing students' intrinsic motivation. The study analyzed the impact of lessons incorporating game elements on students' cognitive activity and the development of essential components of research skills. Specifically, changes in students' abilities to formulate problems, generate hypotheses, conduct experiments, and draw conclusions were comparatively assessed. The experimental results indicated that the systematic use of game-based technologies positively influences students' independent learning, logical reasoning, and scientific thinking. Furthermore, the playful and open cognitive environment fostered during these lessons stimulates students' curiosity about the surrounding world. This approach bridges theory and practice, facilitating a deeper and more meaningful mastery of knowledge.

Keywords: game-based technologies, research skills, primary education, natural science, cognitive activity, critical thinking, learning motivation, experiential learning

INTRODUCTION

The evolution of contemporary education necessitates a reconsideration of the student's role, moving beyond the passive reception of ready-made knowledge. Today, primary school graduates are expected not only to memorize information but also to analyze, compare, propose hypotheses, and draw independent conclusions. The primary school stage is particularly critical, as it lays the foundation for these cognitive and metacognitive skills. Cognitive engagement and research-oriented curiosity developed during this period directly influence students' future academic achievements.

Natural science education at the primary level introduces students to foundational scientific concepts about the surrounding environment. However, in practice, this subject often remains confined to theoretical knowledge acquisition, providing insufficient opportunities for active participation in investigative learning. Consequently, students tend to rely on prepared answers to explain natural phenomena, limiting the development of their abilities to formulate questions and conduct experiments independently.

One effective approach to addressing this challenge is the purposeful integration of game-based technologies. Play serves as a leading activity for primary school children, directly impacting their cognitive and emotional development. Lessons incorporating game elements not only enhance intrinsic motivation but also facilitate the comprehension of complex concepts. Moreover, the gameplay environment naturally encourages students to ask questions, formulate predictions, and compare outcomes, thereby engaging with the essential components of research skills.

According to L.S. Vygotsky, a child's development occurs through social interaction, with play functioning as a key mechanism in this process (Vygotsky, 1984). Similarly, J. Piaget emphasizes that children acquire knowledge of their environment through active exploration. These theoretical perspectives provide a solid foundation for considering game-based technologies as a means of fostering research skills.

Current classroom practice, however, reveals several contradictions. On one hand, educational standards demand the development of research skills; on the other hand, lesson structures often remain largely reproductive. Furthermore, passive consumption of information in digital environments diminishes active cognitive engagement. These factors underscore the relevance of systematically integrating game-based technologies.

The aim of this article is to identify the potential of game-based technologies for developing research skills among primary school students in the context of natural science education and to empirically substantiate their effectiveness.

MATERIALS AND METHODS

The present study is grounded in a mixed-methods approach, integrating quantitative metrics with qualitative analyses to provide a comprehensive understanding of the phenomenon. This methodology mitigates the risks of one-dimensional evaluation of complex constructs such as research skills and allows for an in-depth examination of changes in students' cognitive development.

The study was conducted during the second semester of the 2025–2026 academic year in urban and rural general education schools. A total of 120 students from grades 3–4 participated. This age range was intentionally selected, as it coincides with the development of logical reasoning, an understanding of cause-and-effect relationships, and a natural curiosity for experimentation and exploration.

Participants were divided into two groups: an experimental group (n=60) and a control group (n=60). The experimental group received science lessons systematically incorporating game-based technologies, while the control group was taught using traditional expository-reproductive methods. This comparative design allowed for a precise evaluation of the pedagogical intervention's effectiveness.

The study was organized into three phases. The initial phase involved assessing students' baseline research skills using specially designed diagnostic tasks, including explaining simple natural phenomena, proposing experimental plans, and formulating predictions. The second phase implemented the game-based instructional program. The final phase analyzed the results, comparing pre- and post-intervention performance to evaluate changes over time.

The experimental program included several interrelated game formats. First, inquiry-based games such as the "Why?" activity prompted students to identify causes of given phenomena, fostering hypothesis formulation skills. Second, practical experimental games allowed students to conduct simple experiments within a playful narrative. Third, role-playing games enabled students to assume positions such as "junior scientist," "researcher," or "ecologist" to collaboratively solve specific problems.

Assessment instruments targeted four core components of research skills: problem identification, hypothesis generation, experimentation, and conclusion drawing, each rated on a

five-point scale. Additionally, pedagogical observation recorded students' engagement, curiosity, and participation in group activities.

Quantitative data were analyzed using percentage comparisons, while qualitative data were subjected to content analysis. This combined approach enabled a meaningful interpretation of changes in students' behavior. The teacher's role also evolved, transitioning from a mere provider of information to a facilitator who organizes and guides students' investigative activities.

RESULTS AND ANALYSIS

The findings of the study demonstrate that game-based technologies are highly effective in fostering research skills among primary school students. In the experimental group, the proportion of students demonstrating high-level research skills increased from 18% to 46%, whereas in the control group, the increase was only 7%. This discrepancy indicates that game-based instruction has a direct and substantial impact on students' cognitive engagement.

Qualitative results further underscore this effect. At the initial stage, most students tended to await ready-made answers and struggled to independently pose "why?" questions. By the end of the experiment, they began formulating their own questions and proposing diverse hypotheses, reflecting the emergence of a research-oriented thinking style.

Significant changes were also observed in hypothesis formulation. Initially, students often provided random responses; over time, they produced logically grounded predictions. During experimental tasks, students learned to plan procedures systematically and to compare outcomes effectively, demonstrating progress in their practical research skills.

The influence of game-based technologies was particularly evident at the emotional level. Increased interest in lessons promoted active engagement: students approached tasks not as obligations, but as playful challenges, freely participating in investigative activities. This shift contributed to enhanced intrinsic motivation.

Component-wise analysis revealed the greatest gains in hypothesis formulation and conclusion-drawing skills, attributable to the freedom for creative thinking provided by the games. Additionally, group-based game activities facilitated peer learning and collaborative knowledge construction.

Nevertheless, certain challenges were identified. Some students occasionally focused solely on game elements, diverging from the primary learning objectives. Moreover, effective implementation demands a high level of pedagogical expertise, as aligning game mechanics with educational goals is not trivial.

Future perspectives include integrating game-based technologies with digital tools, such as virtual laboratories and interactive platforms, to elevate research activities to a higher level. Furthermore, strengthening interdisciplinary connections can support the comprehensive development of students' research skills.

CONCLUSION

The conducted study has demonstrated the high effectiveness of game-based technologies in cultivating research skills among primary school students. This approach not only enhances students' cognitive engagement but also contributes to the development of their scientific thinking culture.

The results indicate that a learning process organized through games actively engages students and fosters autonomous knowledge acquisition. In particular, within the context of natural science, this approach enables students to understand natural phenomena through hands-on experimentation.

From a practical perspective, effective implementation of game-based technologies requires teachers to reconsider lesson structures and align educational objectives with game elements. Additionally, attention to students' developmental characteristics is essential to maximize the pedagogical impact.

Overall, game-based technologies represent a powerful tool for fostering research skills. Future research should explore the integration of this approach within digital environments and its adaptation to inclusive educational settings, ensuring broader accessibility and effectiveness.

REFERENCES

- Hmelo-Silver, C. E. (2004). Problem-based learning. *Educational Psychology Review*, 16(3), 235–266. <https://doi.org/10.1023/B:EDPR.0000034022.16470.f3>
- Piaget, J. (1972). *The psychology of the child*. Basic Books.
- Slavin, R. E. (2015). Cooperative learning in schools. In J. D. Wright (Ed.), *International encyclopedia of the social & behavioral sciences* (4th ed., Vol. 4, pp. 885–891). Elsevier.
- Vygotsky, L. S. (1984). *Thought and language*. MIT Press.
- Ministry of Education and Science of the Republic of Kazakhstan. (2021). *State compulsory standard for primary education*.

ORGANIZING LITERARY CHALLENGES IN PRIMARY SCHOOL: METHODOLOGICAL RECOMMENDATIONS

Melis Damira Marlenkyzy

Abai Kazakh National Pedagogical University, 7M01301 – Pedagogy and Methods of Primary Education, 1st Year, Master's Program

Lebedeva L.A.

Candidate of Pedagogical Sciences, Associate Professor, Professor of the Department of Primary Education, Abai Kazakh National Pedagogical University, Almaty, Kazakhstan

This article examines the pedagogical significance of organizing literary challenges among primary school students. In the contemporary educational landscape, enhancing students' reading motivation, developing functional literacy, and fostering creative abilities have become key priorities. Literary challenges are proposed as an effective tool for achieving these objectives. The study analyzes factors that reduce students' reading engagement, including digital dependency, declining interest in reading books, and passive modes of information consumption. An experimental study was conducted in schools in Kazakhstan involving 100 students. The experimental group participated in a literary challenge program titled "Read and Share." The program was based on a range of interactive and student-centered methods, including BookTalk sessions, creative rewriting tasks, and role-based reading activities. To assess the outcomes, several diagnostic instruments were employed: a reading motivation questionnaire, a reading comprehension test, and systematic pedagogical observation. The findings indicate that the implementation of literary challenges led to a 25% increase in students' reading interest. In addition, a significant improvement was observed in students' abilities to comprehend and interpret texts. These results suggest that literary challenges not only enhance engagement with reading but also contribute to the development of higher-order cognitive and interpretative skills.

Keywords: literary challenge, primary school, reading motivation, reading literacy, creative thinking, pedagogical strategies

INTRODUCTION

The contemporary educational paradigm demands that students be viewed not merely as recipients of knowledge but as active agents who independently construct, analyze, and apply knowledge in practice. The primary school stage is particularly critical, as it lays the foundation for a child's learning motivation and cognitive skills. At this age, students' interest in reading, their level of text comprehension, and their creative thinking abilities are shaped through consistent pedagogical influence. However, in recent years, the rapid development of digital technologies and the predominance of visual content have contributed to a decline in children's engagement with traditional reading. This phenomenon adversely affects students' ability to comprehend texts deeply, perform critical analyses, and interpret information effectively.

Within this context, there is a growing need to implement innovative strategies that enhance students' reading engagement. One such approach is the use of literary challenges. Literary challenges constitute structured pedagogical activities that encourage students, over a defined period, to read books, discuss their content, creatively reinterpret narratives, and present their ideas publicly. Incorporating elements of gamification, these challenges make the learning process both engaging and motivational.

According to L. S. Vygotsky's socio-cultural theory, cognitive development occurs through social interaction (Vygotsky, 1984). Literary challenges, grounded in this theoretical framework, foster dialogic communication, idea exchange, and collaborative cognitive activity among students. Moreover, J. Guthrie and A. Wigfield (2000) emphasize that reading motivation develops through both intrinsic and extrinsic factors. Literary challenges effectively address both dimensions, enhancing students' interest and engagement in reading activities.

Current educational practice reveals several contradictions. First, the learning process often remains predominantly reproductive, limiting students' creative activity. Second, assessment-oriented teaching reduces students' enjoyment of learning. Third, adaptation to short-form digital content negatively impacts students' capacity to engage with extended texts. Implementing literary challenges systematically is proposed as a solution to these issues.

The aim of this study is to identify the pedagogical foundations for organizing literary challenges among primary school students, experimentally validate their effectiveness, and develop practical methodological recommendations. The research outcomes hold practical significance for enhancing reading motivation, developing functional literacy, and fostering creative competencies.

MATERIALS AND METHODS

This study was conducted using a mixed-methods approach, integrating both quantitative and qualitative data analysis to provide a comprehensive understanding of the phenomenon under investigation and to enhance the reliability of the findings. The research was carried out in January and February 2026 in general education schools across Kazakhstan.

The study involved 100 students from grades 3 and 4. This age group was selected because, during this developmental stage, students' learning activities become a central function, and elements of reflection begin to emerge. Moreover, children at this age exhibit an increased need for social interaction and demonstrate greater readiness for collaborative work. Participants were divided into two groups: an experimental group (50 students) and a control group (50 students). The experimental group was systematically engaged with literary challenge technologies, whereas the control group received traditional teaching methods.

The research consisted of three main stages: diagnostic, formative, and final. During the diagnostic stage, students' initial reading motivation, text comprehension levels, and creative abilities were assessed using questionnaires, test tasks, and observational methods. In the formative stage, the specially designed literary challenge program "Read and Share" was implemented. This program aimed to activate students' learning engagement, foster creative thinking, and enhance communicative skills. In the final stage, the results were comparatively analyzed to evaluate the effectiveness of the intervention.

The experimental program included several methodological components. First, the BookTalk method was used, in which students presented the books they had read to their peers and discussed the main ideas, promoting oral expression and the ability to justify their opinions. Second, the story retelling method allowed students to reconstruct texts and interpret them based on their perspectives. Third, creative tasks (alternative endings, letters to characters, comic creation) were introduced to stimulate imagination and deepen text comprehension. Reading marathons were also organized, assessing both the quantity and quality of books read within a specified period.

Key instruments included a reading motivation questionnaire, a text comprehension test, and pedagogical observation sheets. The questionnaire measured students' engagement, attitudes toward reading, and self-assessment. The comprehension test evaluated students' ability to identify main ideas, analyze characters, and interpret texts. Pedagogical observation assessed students' classroom participation, teamwork, and quality of creative task performance.

Data analysis employed statistical methods for quantitative data, comparing percentages to identify differences between groups. Qualitative data were analyzed using content analysis methods. The integration of these approaches ensured the objectivity and robustness of the study's findings.

RESULTS AND ANALYSIS

The study results demonstrated that literary challenges are highly effective in enhancing primary school students' reading motivation and literacy skills. In the experimental group, students' reading motivation increased from 40% to 65%, whereas in the control group, this measure rose by only 6%. This significant difference underscores the critical role of literary challenges in stimulating students' engagement in reading activities.

Qualitative analysis also revealed notable changes. At the initial stage of the experiment, students tended to process texts superficially and were unable to analyze characters' actions in depth. Additionally, difficulties were observed in expressing and justifying personal opinions. Following the formative stage, students' text comprehension improved substantially. They began to identify main ideas and articulate their own perspectives regarding the texts.

The impact of creative tasks was particularly pronounced. Students constructed alternative storylines and critically evaluated characters' actions, indicating development in both creative and critical thinking skills. Furthermore, BookTalk activities enhanced students' communicative abilities, allowing them to present ideas coherently and improve public speaking skills.

Component-wise analysis showed the highest gains in communication and creativity. These findings suggest that literary challenges foster not only reading proficiency but also personal development. Additionally, students' abilities to listen to peers, ask questions, and provide feedback improved.

However, several challenges emerged. Some students initially demonstrated low engagement and hesitated to participate in group activities, likely due to low self-confidence and habituation to traditional teaching methods. Moreover, not all teachers were able to implement the new methods effectively, highlighting insufficient methodological preparation.

Future prospects include integrating literary challenges with digital platforms. For instance, using tools such as Padlet or Canva allows students to present their work online, enhancing digital literacy and modernizing the learning process. Engaging parents in the reading process is also recommended as a crucial component of effective implementation.

CONCLUSION

The findings of this study confirmed that literary challenges are an effective tool for enhancing reading motivation and developing literacy skills among primary school students. Beyond improving cognitive engagement, these challenges also foster students' creative and communicative abilities, contributing to holistic educational development.

The study demonstrated that high effectiveness is achieved only when literary challenges are implemented systematically. The teacher's role must transition from a traditional knowledge transmitter to a facilitator who organizes and guides students' independent learning activities. Such a shift ensures that students actively construct knowledge and engage meaningfully with texts.

From a practical perspective, integrating literary challenges into the curriculum requires revising lesson structures, increasing group and creative assignments, and accommodating individual learner differences. Furthermore, establishing collaboration with parents is crucial to support and reinforce students' reading experiences.

It should be noted that this study does not cover all possible aspects of literary challenges. Therefore, future research is recommended to explore their application in inclusive educational settings and digital environments more comprehensively. Such studies could provide deeper

insights into optimizing literary challenges to meet the diverse needs of modern learners while leveraging technology for engagement and accessibility.

REFERENCES

Guthrie, J. T., & Wigfield, A. (2000). Engagement and motivation in reading. In M. L. Kamil, P. B. Mosenthal, P. D. Pearson, & R. Barr (Eds.), *Handbook of reading research* (Vol. 3, pp. 403–422). Routledge.

Krashen, S. (2004). *The power of reading*. Libraries Unlimited.

Slavin, R. E. (2015). Cooperative learning in schools. In J. D. Wright (Ed.), *International encyclopedia of the social & behavioral sciences* (4th ed., Vol. 4, pp. 885–891). Elsevier.

Vygotsky, L. S. (1984). *Thought and language*. MIT Press.

Ministry of Education and Science of the Republic of Kazakhstan. (2021). *State mandatory standard of primary education*.

Педагогические условия развития эмоционального интеллекта у детей старшего дошкольного возраста

Берлибаева Майра Бакдаулетовна

PhD candidate, Казахский национальный педагогический университет имени Абая

Аннотация

Статья посвящена исследованию педагогических условий, способствующих развитию эмоционального интеллекта у детей старшего дошкольного возраста. Автор рассматривает данный процесс как многокомпонентную систему, обусловленную взаимодействием социальных, личностных и образовательных факторов. В работе обосновывается роль психолого-педагогического сопровождения как базового условия формирования эмоциональной компетентности в дошкольных организациях.

Ключевые слова: эмоциональный интеллект, старший дошкольный возраст, педагог, образовательная среда, семья, эмоциональная компетентность

Развитие эмоционального интеллекта у детей рассматривается как одно из главных условий их успешной жизненной адаптации и достижения благополучия в личностном плане. Данный процесс формируется под воздействием ряда внешних и внутренних факторов. В научных исследованиях термин «фактор» трактуется как причина или движущая сила, оказывающая влияние на развитие определённого явления или процесса и определяющая его особенности и характерные проявления.

Для формирования эмоционального интеллекта у детей дошкольного возраста требуется системное и целенаправленное психолого-педагогическое сопровождение со стороны педагога (воспитателя) дошкольной образовательной организации. Это связано с тем, что способности к распознаванию, пониманию и регулированию собственных эмоций развиваются у ребёнка преимущественно в процессе общения со значимыми для него взрослыми и сверстниками, в связи с чем качество педагогической поддержки выступает одним из ключевых факторов становления эмоциональной компетентности дошкольников. Поскольку развитие эмоционального интеллекта основано на накоплении опыта, педагог может активно содействовать этому процессу. Наиболее благоприятные результаты можно получить в условиях, когда педагоги и родители эмпатичны, терпимы, гибки, проявляют уважительное отношение, а также используют конструктивные формы взаимодействия с детьми.

По мнению Л.Г. Субботиной [1], психолого-педагогическое сопровождение – это целостный и непрерывный процесс изучения личности ребёнка, содействия её развитию и создания условий для самореализации в различных сферах деятельности. Данный процесс направлен на обеспечение успешной социальной адаптации ребёнка на любых возрастных этапах и осуществляется всеми участниками воспитательно-образовательного процесса в ходе их взаимодействия.

Принятие ребёнка как уникальной и целостной личности – один из ключевых факторов эмоционального развития. Учитывая индивидуальные особенности, уровень развития и эмоциональные потребности возможно сформировать адекватную систему педагогической поддержки и ожиданий. Развитию положительной самооценки,

уверенности в себе и способности открыто выражать собственные чувства будет способствовать атмосфера безусловного принятия. В противоположность этому, постоянная критика или эмоциональное отвержение могут стать причиной возникновения внутренних противоречий и проблем в поведении, что усложняет процесс социальной адаптации ребёнка. Следовательно, признание ценности личности ребёнка и уважительное отношение к его переживаниям создают основу для формирования эмоциональной грамотности.

Особой фигурой в развитии эмоционального интеллекта детей старшего дошкольного возраста принадлежит педагогу. Эмпирические исследования показывают, что особенности эмоционального реагирования взрослых непосредственно связаны с формированием механизмов эмоциональной регуляции у детей.

По мнению Ж. Аймауытова исключительно важна роль педагога в социальном воспитании ребенка, формировании его личности, собственной «сущности» [2]. Так как именно воспитатель выступает значимой фигурой, помогающей ребёнку научиться осознавать и регулировать свои эмоции в условиях детского коллектива. Одной из важнейших задач педагога является создание образовательной среды, в которой ребёнок может безопасно выражать свои эмоциональные переживания и получать поддержку в процессе их осмысления и регулирования. При этом педагог выполняет не только обучающую функцию, но и служит примером эмоционально грамотного поведения, демонстрируя способы адекватного реагирования на собственные и чужие эмоции.

Эмоциональная компетентность педагога выполняет функцию значимого ориентира для детей, способствуя развитию у них способности к эмпатии, конструктивному разрешению конфликтных ситуаций и эффективному социальному взаимодействию. Поддерживающая и эмоционально насыщенная образовательная среда создает предпосылки для формирования устойчивых социально-эмоциональных навыков, необходимых для дальнейшей адаптации ребенка в обществе [3].

Следует учитывать, что развитие эмоциональной сферы ребенка связано с наличием возрастнo-чувствительных периодов, требующих внимательного наблюдения за эмоциональным состоянием детей и гибкой адаптации педагогических методов с учетом их индивидуальных особенностей [4], [5]. В этом контексте особое значение приобретает профессиональная рефлексия педагогов и анализ эффективности используемых образовательных практик.

Исследования показывают, что профессиональные установки педагогов существенно влияют на внедрение программ, направленных на развитие эмоционального интеллекта. Педагоги, придерживающиеся позитивного отношения к образовательным инновациям, чаще используют творческие и интерактивные методы обучения, демонстрируют более высокий уровень мотивации и педагогической инициативы, что способствует обогащению образовательной среды и повышению эффективности педагогической деятельности [6].

Теоретико-экспериментальное исследование О. Г. Филипповой, М. Н. Терещенко, Ю. В. Батеновой и А. А. Прохоровой подтверждает, что старший дошкольный возраст является сензитивным периодом для формирования эмоционального интеллекта. Несмотря на это, у большинства детей на констатирующем этапе фиксируется низкий уровень эмоциональной компетентности, проявляющийся в дефиците соответствующего опыта и трудностях при интерпретации эмоциональных состояний. Авторы приходят к выводу, что внедрение специализированной программы «Азбука эмоций» при соблюдении определенных психолого-педагогических условий обеспечивает эффективное развитие эмоциональной сферы, создавая фундамент для успешной социализации и психологического благополучия воспитанников [7].

Поскольку игра является ведущим типом деятельности в дошкольном детстве, именно она выступает оптимальным базисом для психолого-педагогического

сопровождения. В данном контексте сопровождение интерпретируется как совместная деятельность педагога и ребенка, нацеленная на осознание и обогащение индивидуального эмоционального опыта.

Функциональный потенциал игры в аспекте эмоционального развития реализуется в двух направлениях:

1. **Диагностическое:** в игровых ситуациях актуализируются уже освоенные паттерны реагирования, что позволяет педагогу объективно оценивать эмоциональные проявления в естественных условиях.
2. **Трансформационное:** в процессе ролевого взаимодействия и подчинения правилам ребенок осваивает новые способы выражения чувств и адаптивные механизмы поведения.

Активное участие педагога способствует созданию поддерживающей образовательной среды, обеспечивающей психологическую защищенность и стимулирующей интерес к исследованию эмоциональных переживаний. Применение театрализованных практик и мультимедийных технологий позволяет индивидуализировать процесс обучения, учитывая когнитивные и эмоциональные особенности каждого ребенка [8]. Таким образом, игровая деятельность не только усложняет палитру чувств дошкольника, но и способствует интериоризации социально приемлемых способов их выражения, обеспечивая своевременную коррекцию негативных проявлений.

Опираясь на исследования А. Д. Кошелевой и Л. П. Стрелковой [5], можно выделить ключевые векторы психолого-педагогического сопровождения эмоционального развития в игре:

- **Обогащение эмоционального репертуара** за счет диверсификации игровых сюжетов и ролевых моделей.
- **Когнитивный компонент:** формирование понимания эмоций через соотнесение личных достижений с результатами сверстников в процессе совместной деятельности.
- **Волевая регуляция:** развитие способности контролировать эмоциональные импульсы через подчинение правилам и задачам игры.
- **Экспрессивный компонент:** совершенствование навыков внешнего проявления чувств (мимика, пантомимика, интонация).
- **Социализация чувств:** создание ситуаций, требующих учета эмоционального состояния партнеров и этической оценки происходящего.
- **Индивидуализация:** стимулирование уникального стиля игровой активности и личностной экспрессии.

Ключевой задачей педагога в рамках данного процесса является сохранение спонтанного и непосредственного характера детской игры. Взрослый должен выступать фасилитатором, создающим условия для свободного самовыражения и бесконфликтного исследования эмоционального мира в процессе межличностного взаимодействия.

В связи с этим можно выделить основные функции психолого-педагогического сопровождения развития эмоционального интеллекта ребенка в игровой деятельности:

- направляющая функция заключается в поддержке развития эмоций, возникающих в процессе сюжетно-ролевых действий, а также в формировании эмоциональных отношений между сверстниками в коллективной игре;

- функция взаимодействия предполагает участие взрослого в позиции игрового партнера, который обогащает содержание игры и поведение ребенка, демонстрируя образцы адекватного эмоционального реагирования и выразительного выполнения игровых ролей;

- стимулирующая функция состоит в поддержке интереса и эмоционального подъема ребенка, формировании стремления пробовать новые роли, способы взаимодействия и формы игрового поведения;

- развивающая (совершенствующая) функция направлена на усиление благоприятных условий эмоционального развития через организацию предметно-игровой среды, обогащение её необходимыми материалами и оборудованием.

Представленные функции, с одной стороны, демонстрируют значительный потенциал психолого-педагогического сопровождения эмоционального развития ребенка в игровой деятельности, а с другой – определяют стратегические и тактические направления работы специалистов дошкольной образовательной организации в данной области.

Развитие эмоционального интеллекта у детей старшего дошкольного возраста также тесно связано с формированием коммуникативных навыков. Наиболее интенсивно данные навыки развиваются именно в дошкольный период благодаря активному взаимодействию со сверстниками и постепенному формированию системы оценки себя, других людей и окружающей действительности. Фундаментальное значение общения подтверждается в работах известных психологов А.Н. Леонтьева [9], В.В. Давыдова [10], М.И. Лисиной [11] общение рассматривается как один из важнейших факторов психического и духовного развития ребенка дошкольного возраста.

Для старшего дошкольника особенно значимо ощущение принятия со стороны сверстников и соответствие их ожиданиям. Именно во взаимодействии со сверстниками формируются различные виды отношений – личностные, эмоциональные, оценочные и деловые. В процессе совместной деятельности дети сталкиваются с конфликтными ситуациями, учатся их разрешать, а также находят свое место в группе.

Для успешного прохождения этого этапа развития важно целенаправленно формировать коммуникативные навыки в игровой деятельности. Необходимо учить детей взаимодействию со сверстниками, внимательному слушанию и пониманию окружающих, проявлению эмпатии, умению радоваться успехам других, переживать из-за неудач и оказывать поддержку тем, кто нуждается в помощи. Гармонично выстроенные отношения со сверстниками в дальнейшем способствуют формированию доброжелательных и эмоционально положительных контактов с окружающими людьми.

Именно в старшем дошкольном возрасте закладываются основы саморегуляции, осознания собственных эмоций и построения взаимодействия с окружающим миром. Этот период является особенно важным для формирования способности понимать свои эмоциональные состояния, управлять ими и учитывать эмоции других людей. Эмоциональный интеллект как способность осознавать и регулировать собственные переживания, а также как проявление эмпатии по отношению к окружающим, играет значительную роль в успешной социальной адаптации ребенка и его личностном развитии.

А.В. Запорожец отмечал, что одним из ведущих механизмов регуляции поведения ребенка является эмоциональное предвосхищение результата деятельности. Управление действиями осуществляется через систему мотивов посредством механизма «эмоциональной коррекции»: переживания отражают личностную значимость происходящего и предшествуют активности, направленной на удовлетворение потребностей. В условиях сюжетно-ролевой игры у детей формируются способности к сопереживанию, пониманию эмоциональных состояний других людей, а также умение переживать радости и огорчения другого как собственные [12].

Эмоциональный опыт ребенка значительно расширяется в процессе взаимодействия со сверстниками, а уровень его эмоционального благополучия во многом определяется характером игровых отношений, складывающихся в детском коллективе. В связи с этим

развитие эмоционального интеллекта посредством сюжетно-ролевой игры требует организованного и целенаправленного педагогического сопровождения.

Следовательно, игровая деятельность может рассматриваться как эффективное педагогическое средство формирования эмоционального интеллекта у детей старшего дошкольного возраста. В ходе игры создаются благоприятные условия для развития эмоциональной осведомленности, эмпатии, коммуникативной активности и уверенности в собственных возможностях. Эти качества выступают важной основой успешной социализации ребенка и его дальнейшего личностного развития.

Родители, педагоги и социальная среда в целом являются значимыми факторами, влияющими на развитие эмоционального интеллекта у детей старшего дошкольного возраста. Именно они обеспечивают формирование следующих основных его компонентов: распознавание эмоций, их осмысление, регулирование и использование в процессе социального взаимодействия. Родители формируют первичную эмоциональную атмосферу, в которой ребенок осваивает способы управления своими чувствами через повседневные формы общения (например, обсуждение переживаний во время совместных игр или бытовых ситуаций). Подобные практики способствуют развитию эмпатии и навыков самоконтроля. Исследования показывают, что теплые и поддерживающие отношения между родителями и детьми связаны с более высоким уровнем социальной компетентности и меньшей выраженностью тревожности у дошкольников.

В научных исследованиях отмечается, что родители, демонстрирующие адекватные способы выражения эмоций и конструктивного реагирования на трудные жизненные ситуации, способствуют развитию эмоционального интеллекта у детей. Так, известный психолог Джон Готтман в руководстве для родителей «Эмоциональный интеллект ребенка» подчеркивает значимость эмпатии и навыков эмоциональной регуляции в раннем возрасте, отмечая, что умение управлять эмоциями, формирующееся в семейной среде, оказывает влияние на общий уровень эмоциональной зрелости личности ребенка [13].

В рамках диссертационного исследования было проведено анкетирование родителей воспитанников старшей группы с целью выявления уровня эмоциональной поддержки, оказываемой ребенку в семье. При разработке анкеты особое внимание уделялось вопросам, отражающим характер эмоционально-личностных отношений в семье, степень родительской поддержки, ощущение ребенком безопасности, а также особенности формирования эмоциональной связи между родителями и детьми.

Таблица 1. Результаты анкетирования родителей по вопросам эмоциональной поддержки детей (n=100%)

№	Вопрос анкетирования	Варианты ответов / Категории анализа	Доля ответов (%)
1	Реакция на эмоции ребенка (плач, гнев, радость)	Поддержка, заинтересованность, обсуждение	70%
		Игнорирование проявлений	12%
		Критика и наказание	8%
2	Частота похвалы за достижения	Регулярно поощряют / Редко или по ситуации	50% / 50%
3	Время совместных занятий (игры, беседы)	Активное участие и высокая вовлеченность	Большинство
		Практическое отсутствие совместной деятельности	12,5%
	Обсуждение эмоций и переживаний	Регулярные беседы о чувствах	Более 60%
		Эпизодические обсуждения (нуждаются в рекомендациях)	Около 40%
	Атмосфера доверия в семье	Высокий уровень эмоционального благополучия	62%
		Наличие периодических трудностей в общении	38%
	Способы поддержки в трудных ситуациях	Отвлечение (игры, задания)	30%
		Обсуждение и объяснение ситуации	30%
		Игнорирование или минимизация проблемы	25%
	Учет мнения ребенка при принятии решений	Ребенок ощущает значимость своего мнения	Около 80%

По результатам проведенного анкетирования с целью оказания педагогической поддержки родителям в вопросах развития эмоциональной грамотности были организованы различные формы работы с семьями воспитанников. В частности, проводились родительские тренинги, практикумы «Управление эмоциями», дискуссии на тему «Коммуникация и эмоциональное выражение», а также коворкинг для родителей «Создание эмоционально поддерживающей среды». Освоение родителями более эффективных способов эмоциональной поддержки и проявления эмпатии способствовало укреплению эмоциональных связей в семье и положительно сказалось на эмоциональном развитии детей. Родителям также рекомендовалось уделять больше внимания качественному совместному взаимодействию с детьми, поскольку это способствует

развитию социальных и эмоциональных навыков, а также укреплению детско-родительских отношений.

Семья выступает как первичный и наиболее значимый институт социализации, в котором закладывается фундамент эмоционального интеллекта старшего дошкольника. В процессе повседневного взаимодействия с родителями ребёнок не только получает первый опыт распознавания чувств, но и осваивает модели эмоционального реагирования, которые в дальнейшем определяют его социальную успешность. Поддерживающая семейная атмосфера, характеризующаяся принятием и эмпатией, способствует формированию у детей чувства безопасности и доверия к миру, что является необходимым условием для развития навыков саморегуляции и понимания эмоциональных состояний окружающих.

Эмпирические данные исследования демонстрируют преобладание позитивных воспитательных стратегий: около 70% родителей проявляют искреннюю заинтересованность в эмоциональном состоянии детей, используя обсуждение чувств и физическую поддержку как основные инструменты воспитания. Примечательно, что более 60% опрошенных регулярно ведут диалоги о переживаниях, а 80% родителей стремятся учитывать мнение ребёнка при принятии семейных решений. Такая демократическая направленность семейного воспитания в сочетании с сохранением культурных традиций - в частности, активным участием старшего поколения (бабушек и дедушек) - создает уникальную среду для трансляции ценностей и развития эмоциональной отзывчивости.

В то же время анализ выявил определённый дефицит конструктивного взаимодействия в части семей, где около 25% родителей склонны игнорировать или минимизировать проблемы ребёнка, а 8% используют тактику критики в ответ на проявление эмоций. Подобная стихийность воспитательного процесса и преобладание метода «отвлечения» над глубоким анализом причин переживаний указывают на потребность родителей в психолого-педагогической поддержке. Это подтверждает актуальность внедрения специальных программ и цифровых платформ, направленных на повышение эмоциональной грамотности взрослых, что позволит трансформировать интуитивный опыт семьи в осознанное педагогическое сопровождение эмоционального развития дошкольника.

Для создания комфортной среды общения, развития пространства для позитивного взаимодействия, укрепления доверительных отношений между участниками и совместного развития эмоционального интеллекта в ходе опытно-экспериментальной работы была разработана и внедрена платформа *PlayHub «Про эмоции»*, объединяющая родителей, педагогов и детей. Практика показала, что включение родителей в партнерскую деятельность способствует осознанию ими существующих моделей эмоционального поведения и помогает освоить новые способы построения родительского взаимодействия. Благодаря этому дети получают примеры конструктивного эмоционального поведения, усваивают соответствующие установки и навыки эффективного общения.

Согласно концепции выдающегося мыслителя Абая Кунанбаева, становление личности ребенка детерминировано влиянием нескольких уровней социального окружения. К приоритетной группе относятся родители и ближайшие родственники, выступающие первичными институтами воспитания. Вторую группу формируют педагоги, наставники и воспитатели, а третью — референтное сообщество сверстников. Особое внимание Абай акцентирует на принципе доверия и эмоциональной привязанности: наибольшее воспитательное воздействие оказывают те субъекты, к которым ребенок испытывает глубокое уважение и ценностное отношение [14].

Семья играет фундаментальную роль в развитии эмпатии и навыков сочувствия. Для эффективной социализации необходимо создание семейной атмосферы, обеспечивающей баланс между свободой выражения эмоций и осознанием социальных границ.

Демонстрация родителями здоровых паттернов эмоционального реагирования и предоставление ребенку пространства для самовыражения способствуют его эмоциональной зрелости и успешной интеграции в коллектив [15].

Эмпирические данные подтверждают, что трансляция родителями адекватных способов преодоления трудностей напрямую коррелирует с уровнем эмоционального интеллекта детей. Д. Гоулман подчеркивает значимость раннего развития эмпатии и саморегуляции, указывая, что сформированные в семье навыки управления эмоциями определяют общую психологическую устойчивость личности в долгосрочной перспективе [16].

В современном казахстанском контексте наблюдается синтез традиционных и инновационных педагогических практик. Сбалансированное участие обоих родителей, а также активная роль старшего поколения (бабушек и дедушек), способствуют укреплению национальной идентичности и преемственности культурных ценностей. Дедушки традиционно выступают символами мудрости и трансляторами этических норм, тогда как бабушки обеспечивают эмоциональную поддержку и развитие базового чувства доверия, что в совокупности формирует зону психологического комфорта.

Наряду с социальными факторами, значимым предиктором развития эмоционального интеллекта выступает предметно-пространственная среда (Л.И. Буюева, Л.Н. Новикова, В.А. Петровский). Теоретические основы организации развивающего пространства заложены в трудах М. Монтессори [17], Ф. Фребеля [18] и Р. Штайнера [19]. Ф. Фребель указывал на необходимость автономии ребенка в образовательном пространстве, а М. Монтессори обосновала эффективность специально подготовленной дидактической среды для интенсификации познавательной деятельности. Л. Малагуцци дополнил эти идеи концепцией «третьего учителя», согласно которой среда способна выступать самостоятельным источником опыта и открытий [20].

Проектирование эмоционально-развивающей среды в дошкольных организациях должно базироваться на следующих принципах:

- **Соответствие зоне ближайшего развития:** опережающий характер предметного наполнения.
- **Интегративность:** учет взаимосвязи всех компонентов образовательной деятельности.
- **Целостность:** условия для реализации всех сторон личности.
- **Психологическая безопасность:** обеспечение эмоционального благополучия.

Нами выделены четыре ключевых компонента эмоционально-комфортной среды:

1. **Эмоционально-регулирующий:** профессиональная компетентность педагога в создании климата доверия и обучении детей навыкам распознавания эмоций (мимика, интонация).
2. **Эмоционально-гибкий:** эргономика и эстетика пространства. Использование трансформируемой мебели, пастельных тонов и музыкального сопровождения способствует снижению ситуативной тревожности и психоэмоционального напряжения.
3. **Эмоционально-интегративный:** организация автономных зон активности (физической, художественной, когнитивной). Согласно А. Маслоу, соблюдение четкого режима дня в такой среде удовлетворяет базовую потребность ребенка в безопасности [21].
4. **Эмоционально-творческий:** стимулирование воображения через игру. Игровая деятельность как ведущий тип активности обеспечивает проживание «радости узнавания» и развитие когнитивных операций без искусственного ускорения возрастных этапов.

Таким образом, насыщенная и педагогически структурированная среда является необходимым условием для полноценного выражения чувств и формирования эмоциональной компетентности дошкольника.

Соответственно, развитие эмоционального интеллекта у детей старшего дошкольного возраста следует рассматривать как многокомпонентный психолого-педагогический процесс, обусловленный взаимодействием личностных, социальных и образовательных факторов. Эмоциональный интеллект выполняет ключевую функцию в процессе социализации, способствуя формированию у ребенка способности к осознанию, пониманию и регуляции собственных эмоциональных состояний в системе межличностного взаимодействия.

1. Установлено, что в дошкольной образовательной организации системообразующим условием развития эмоционального интеллекта выступает психолого-педагогическое сопровождение. Роль педагога как субъекта сопровождения заключается в создании эмоционально безопасной образовательной среды, демонстрации моделей конструктивного эмоционального поведения и организации совместной деятельности, направленной на развитие эмпатии, эмоциональной рефлексии и навыков саморегуляции.

2. Определено, что ведущий педагогический механизм развития эмоционального интеллекта в старшем дошкольном возрасте – это игровая деятельность. В условиях сюжетно-ролевой игры происходит преобразование эмоционального опыта ребенка: дети осваивают социально приемлемые способы выражения чувств, учатся сопереживанию и формируют навыки эмоциональной регуляции, используя различные социальные роли и взаимодействуя со сверстниками.

3. Эмпирическое исследование и его результаты подтвердили значимость семейной среды для формирования эмоционального интеллекта дошкольников. Эмоциональная поддержка родителей, практика обсуждения переживаний и участие в совместной деятельности способствуют развитию эмоциональной осознанности у детей, а также формированию их социальной компетентности. При этом выявленные различия в воспитательных стратегиях родителей свидетельствуют о необходимости системной педагогической работы с семьями.

4. Доказано, что эффективность развития эмоционального интеллекта базируется на целенаправленном проектировании эмоционально-развивающей образовательной среды, которая включает следующие компоненты: эмоционально-регулирующий, эмоционально-гибкий, эмоционально-интегративный и эмоционально-творческий. Их комплексная реализация формирует у детей эмоциональную компетентность, способствует накоплению позитивного эмоционального опыта и развивает готовность к социальному взаимодействию.

Список источников:

1. Субботина Л.Г. Модель взаимодействия субъектов воспитательно-образовательного процесса в психолого-педагогическом сопровождении учащихся // Сибирский психологический журнал. – 2007. – № 5. – С. 120–125.
2. Аймауытов Ж. Психология: оқулық. – Алматы: Рауан, 1995. – 312 б.
3. Turkmen, S., & Ulutas, I. (2018). How do preschool teachers perceive the emotional intelligence? Teaching practices and emotional intelligence in early childhood. Educational Sciences Research in the Globalizing World, 177, 170-183.
4. D'Amico, A. (2018). The use of technology in the promotion of children's emotional intelligence: The multimedia program developing emotional intelligence. International Journal of Emotional Education, 10(1), 47-67.
5. Кошелева, А. Д. Эмоциональное развитие дошкольников: учебное пособие для студентов высших учебных заведений / А. Д. Кошелева, Л. П. Стрелкова, И. Ю. Ильина; под ред. А. Д. Кошелевой. – М.: Академия, 2003. – 176 с.
6. Лисина, М.И. Формирование личности ребёнка в общении [Текст] / М.И. Лисина. – СПб.: Питер, 2009. – 96 с.
7. Развитие эмоционального интеллекта у детей дошкольного возраста / О. Г. Филиппова, М. Н. Терещенко, Ю. В. Батенова, А. А. Прохорова // Азимут научных исследований: педагогика и психология. – 2021. – Т. 10, № 4 (37). – С. 370–374.
8. Запорожец, А.В. Психология восприятия сказки ребенком-дошкольником. Психология дошкольника. Хрестоматия. Для студентов сред. пед. учеб. заведений./ Сост. Г.А. Урунтаева. - М., Издательский центр «Академия», 2000. – С.134/
9. Леонтьев А.Н. Деятельность и сознание // Вопросы философии. – 1968.- №2. – С.137-140.
10. Давыдов В. В. Теория развивающего обучения. - Москва: Интеллект-центр, 1996.- 544 с.
11. Лисина, М.И. Формирование личности ребёнка в общении [Текст] / М.И. Лисина. – СПб.: Питер, 2009. – 96 с.
12. Запорожец, А.В. Психология восприятия сказки ребенком-дошкольником. Психология дошкольника. Хрестоматия. Для студентов сред. пед. учеб. заведений./ Сост. Г.А. Урунтаева. - М., Издательский центр «Академия», 2000. – С.134.
13. Готтман Дж. Эмоциональный интеллект ребенка: как развить у детей способность к эмоциональному самоконтролю / Дж. Готтман. - Москва: Альпина Паблишер, 2010.- 320 с.
14. Жизнь и творчество Абая. Сборник статей / Под редакцией М. Ахинжанова и З. Ахметова. – Алма-Ата: Издательство АН КазССР, 1954. – С.216-248.
15. Джакупов С.М. Психологические основы совместно-диалогического консультирования / С.М. Джакупов, Т.А. Абдрашитова, З.Б. Мадалиева, А.А. Толегенова // Вестник КазНУ. Серия психологии и социологии. – 2013. – № 4 (47). – С. 86–95.
16. Goleman D. Emotional Intelligence: 25th Anniversary Edition. – London: Bloomsbury Publishing, 2020. – 352 p.
17. Монтессори, М. Дети- другие / М. Монтессори; перевод с нем. Н. Нефедовой; с комментариями К. Е. Сумнительного. – Москва: Карапуз, 2012. – 336 с.
18. Фребель, Ф. Будем жить для наших детей: пер. с нем. / Ф. Френе. – Екатеринбург: У-Фактория, 2005. – 248 с. – (Серия «Психология детства: Классическое наследие».
19. Штайнер, Р. Воспитание ребенка с точки зрения антропософии / Р. Штайнер; пер. с нем. Н. П. Кононевич. – М.: Парсифаль, 1993. – 40 с.

20. Эдвардс, К. Сто языков детей: Реджио-педагогика / К. Эдвардс, Л. Гандини, Дж. Форман; пер. с англ. под ред. И. П. Кулаковой. – М.: Манн, Иванов и Фербер, 2019. – 416 с.
21. Маслоу, А. Мотивация и личность / А. Маслоу; пер. с англ. А. М. Татлыбаевой. – 3-е изд. – СПб.: Питер, 2008. – 352 с.

INTEGRATING ADAPTIVE LEARNING TECHNOLOGIES AND THE FLIPPED CLASSROOM MODEL FOR ENHANCED LANGUAGE ACQUISITION IN SECONDARY EDUCATION

Dosmaganbetova Nazira Kaiyrgalieвна

7M01703 – Training foreign language teachers, 2nd-year Master's student, South Kazakhstan Pedagogical University named after O.Zhanibekov, Kazakhstan, Shymkent

Abstract. This study critically examines the integration of adaptive learning technologies with the flipped classroom model in the context of secondary language acquisition. As educational paradigms shift toward student-centered, technology-enhanced learning, there is an urgent need to understand how emerging tools and instructional methods can be combined to maximize language proficiency, learner autonomy, and engagement. Drawing on sociocultural and constructivist learning theories, this work explores the theoretical rationale for merging adaptive technologies and flipped instruction, analyzes empirical research, and presents findings from an original mixed-methods study involving secondary students learning English as a foreign language. The investigation employs standardized proficiency assessments, autonomy and motivation surveys, classroom observations, and in-depth interviews to assess outcomes. Data demonstrate that this integrated approach yields significant improvements in vocabulary and grammar acquisition, communicative competence, and intrinsic motivation compared to traditional teaching models. The article discusses the pedagogical and logistical challenges of implementation, offers critical reflections on the limitations of the current research, and outlines recommendations for scalable adoption and future inquiry. The study concludes that the synergistic use of adaptive learning and flipped classroom pedagogy represents a transformative advance in language education, equipping students with the skills and confidence necessary for success in diverse, dynamic, and technology-rich environments.

Keywords: adaptive learning, flipped classroom, language acquisition, secondary education, educational technology, learner autonomy, communicative competence, student engagement

Introduction. The field of secondary language education is changing quickly because of new technologies and a better understanding of the flaws in traditional teaching methods. For many years, schools taught language by having teachers do most of the work, using standardized textbooks, and having students memorize things. While these methods laid the groundwork for learning grammar and vocabulary, they often didn't take into account the unique needs, interests, and learning speeds of each student. The diversity of learners' backgrounds and the growing complexity of global communication have forced educators and policymakers to rethink how languages are taught, with a focus on promoting independence, critical thinking, and the ability to communicate. The advent of the flipped classroom model and adaptive learning technologies signifies a pivotal juncture in this evolution. The flipped classroom flips the usual order of lessons: students learn new material outside of class, usually through video lectures or interactive digital

content. Then, during class time, they use what they have learned through group work, communication, and problem-solving activities. This model is based on the idea that learning that is active and focused on the student leads to a better understanding and more motivation. But the model only works if students are ready, have access to good resources, and teachers can plan meaningful activities in class.

At the same time, adaptive learning technologies have become more popular as tools for making education more personalized than ever before. These systems use advanced algorithms and data analytics to evaluate how well students are doing in real time and change the content, speed, and feedback of lessons to fit each student's needs. Adaptive platforms can fix the problems with one-size-fits-all instruction by letting each student follow their own learning path and get help where they need it. When combined with the flipped classroom, adaptive learning technologies promise to make it easier to get ready for class, make sure students understand the basics, and give students more time in class to practice real communication. Even though this integration seems like a good idea, there isn't much empirical research that carefully looks at how it affects language learning outcomes, learner autonomy, and motivation in high school.

This study was initiated to address the deficiencies identified in the existing literature and practical applications. The research seeks to examine the theoretical and practical ramifications of integrating adaptive learning technologies with the flipped classroom model for English language acquisition in secondary education. The study specifically examines the following inquiries: In what ways does the integration of adaptive and flipped classroom models affect language proficiency, motivation, and learner autonomy in comparison to conventional instruction? What do students and teachers think are the pros and cons of the situation? And what suggestions can be made for how to put this into action in a variety of educational settings? This work aims to contribute to the ongoing transformation of language education by thoroughly examining the theoretical foundations, empirical evidence, and practical aspects of the issue, offering actionable insights for educators, administrators, and policymakers.

Theoretical background. The combination of adaptive learning technologies and the flipped classroom model is based on strong theoretical traditions that stress the importance of social interaction, scaffolding, and active participation in learning a language. Lev Vygotsky's sociocultural theory serves as a fundamental framework for comprehending the influence of the social and cultural milieu on cognitive development. Vygotsky's idea of the Zone of Proximal Development (ZPD) is very important. It says that learners get better at something when they are helped by someone who knows more about it, like a teacher, a friend, or, in the case of technology, adaptive systems. The ZPD conceptualizes learning as a socially mediated process, wherein scaffolding and collaborative dialogue facilitate students' internalization of new concepts and practices that exceed their existing level of competence. This viewpoint closely corresponds with the flipped classroom model, which aims to optimize opportunities for social interaction and directed practice during instructional time.

Constructivist learning theory, as articulated by scholars such as Piaget and Bruner, reinforces the notion that learners actively construct knowledge through engagement, exploration, and reflection. Constructivism emphasizes authentic tasks, problem-solving, and the contextualized application of language over passive information absorption. The flipped classroom exemplifies these principles by relocating content delivery beyond the classroom and allocating in-class time for collaborative inquiry, communicative activities, and formative assessment. In this setting, students are encouraged to take charge of their own learning, teach each other, and build metacognitive skills that are important for language development for the rest of their lives.

Adaptive learning technologies are based on the ideas of differentiated instruction and mastery learning. According to Bloom and others, mastery learning says that all students can reach high levels of understanding if they have enough time, the right feedback, and support that is

tailored to their needs. Adaptive systems put these ideas into action by constantly looking at how well students are doing, finding areas where they need more help, and giving them personalized instruction that meets their changing needs. In language education, this means that a student who is having trouble with a certain grammatical structure or vocabulary set can get focused practice and support until they master it. At the same time, more advanced students can move on to harder challenges without being held back by the pace of the class. Adaptive technologies are based on data, which gives teachers a lot of information about how their students are learning. This lets them give more targeted help and support.

There is a strong theoretical reason to combine adaptive learning technologies with the flipped classroom. By combining the personalized, data-driven help of adaptive systems with the social, collaborative, and communicative focus of the flipped classroom, teachers can make learning spaces that are both unique and interactive. This synergy fixes some of the main problems that each model has when used alone. The flipped classroom encourages independence and participation, but it might not work if students aren't ready or if the digital content doesn't meet their needs. Adaptive technologies, although effective in customizing instruction, may be deficient in the social and communicative depth required for genuine language acquisition. These models work together to create a complete approach that uses the best parts of each to help students learn language in a deeper, more meaningful way.

Methodology. To analyze the effects of combining adaptive learning technologies with the flipped classroom model on secondary language acquisition, a mixed-methods quasi-experimental research design was utilized. The research was performed in two urban secondary schools with analogous socio-economic and demographic characteristics, guaranteeing the comparability of student backgrounds and educational settings. The complete sample comprised 120 students, aged 14 to 16, all of whom had previous experience with English as a foreign language. There were 60 students in each group, and the sample was split evenly between an experimental group and a control group. For sixteen weeks, both groups followed the same English language curriculum. They learned the same things in grammar, vocabulary, reading, listening, and speaking.

The experimental group took part in a flipped classroom that used technology to make it more flexible. Before class, students used an adaptive learning platform to work on digital modules that included grammar explanations, vocabulary exercises, listening tasks, and reading passages that were appropriate for their level of proficiency. The platform gave instant feedback and changed the order, difficulty, and type of tasks based on how well the user was doing. Before going to class, students were supposed to finish these modules. The in-class sessions were meant to build on the work done before class, with a focus on activities that encouraged communication, group projects, peer interactions, and guided discussions. The teacher was a facilitator who helped students with specific problems, cleared up misunderstandings, and organized group work.

The control group used a standard way of teaching. During class, the teacher gave lectures, the whole class did drills, and the students worked on exercises from the textbook. The homework was similar to what we did in class, and it helped us remember grammar and vocabulary by making us do it over and over again, but it didn't have any adaptive or individualized features. Teachers in both groups had the same qualifications and went through training to make sure they followed the teaching models.

The data collection was thorough, including both quantitative and qualitative aspects of learning. At the beginning and end of the semester, standardized language proficiency tests that followed the Common European Framework of Reference for Languages (CEFR) were given to see how well students could read, listen, speak, and write. Surveys based on the Motivated Strategies for Learning Questionnaire and the Learner Autonomy Profile measured how students' motivation and independence changed during the intervention. Structured classroom observations, employing comprehensive observation protocols, recorded engagement, participation, and the

quality of interactions among peers and between teachers and students. Lastly, semi-structured interviews were held with a group of students and teachers from both groups to learn more about their experiences, what they thought were the pros and cons, and what they thought could be done better.

We used descriptive statistics, paired and independent-samples t-tests, and analysis of variance (ANOVA) to find statistically significant differences in learning outcomes and motivational variables between the experimental and control groups. Qualitative data from interviews and observations were transcribed, coded, and thematically analyzed to discern recurring patterns, nuanced perspectives, and emergent themes pertaining to instructional practices, learner engagement, and the integration of technology.

Findings and Discussion. The findings of this study illustrate a complex depiction of how the amalgamation of adaptive learning technologies with the flipped classroom model can revolutionize language acquisition in secondary education. The quantitative data from standardized language proficiency assessments unequivocally demonstrate that students in the experimental group exhibited superior progress compared to their counterparts in the control group across all evaluated dimensions. The experimental group showed an average improvement of 18% from the pre-test to the post-test in vocabulary acquisition, while the control group only showed a 9% improvement. The experimental group showed a 14% improvement in grammar skills, while the control group only showed a 7% improvement. Students in the adaptive, flipped model also did better on reading and listening tests, but the difference wasn't as big as it was for vocabulary and grammar. These results indicate that the integration of adaptive technologies with the flipped classroom model fosters a learning environment that enhances the acquisition of fundamental language skills, probably owing to the personalized nature of pre-class preparation and the provision of focused, communicative practice during class.

Additional survey data corroborate these findings. By the end of the semester, students in the experimental group said their autonomy scores had gone up by 26%. This shows that they were more confident in their ability to manage their own learning and felt more responsible for their own progress. This is an 8% increase in the control group, which shows that traditional teaching is not as good at developing autonomy as a core learner trait, even though it does give students some chances to learn on their own. The experimental group showed a lot more intrinsic motivation than the control group. They said things like they enjoyed interactive digital exercises, they liked being able to track their progress, and they liked being able to go back and master difficult material at their own pace. A lot of students said that the adaptive platform was "engaging" and "fun," and that it helped them feel "in control" of their learning. The platform's gamified features and quick feedback made students feel like they had accomplished something, which kept them interested and working hard, even those who had trouble learning languages before.

Observing the classroom gave us more information about how the two groups' teaching methods and student behaviors were different. Students in the experimental classrooms were better prepared because they had already worked with the main material through the adaptive modules. Because of this preparation, class time could be used more effectively for higher-level, communicative tasks like debates, role-plays, group projects, and problem-solving challenges. Teachers acted as facilitators or guides, moving between groups, asking tough questions, and giving each student the help they needed. The quality of classroom conversation was much better, and students were more likely to join in, ask questions, and work with their peers. There were a lot of times when students taught each other and used English on their own during activities, which shows that they were really moving toward active, communicative competence.

In the control group, on the other hand, students were mostly listening to the teacher, doing exercises as a whole group, and not talking to each other as much. Some students did very well in this setting, but others seemed uninterested or unsure about getting involved. Students did

less homework and often just memorized things instead of using language in a meaningful way in context. Teachers in the control group had a hard time tailoring their lessons because the same pace and content made it impossible to give extra help or support where it was needed.

Qualitative data from interviews with students and teachers enhanced the quantitative findings by revealing the lived experiences and perceptions of participants in the intervention. Students in the experimental group consistently expressed gratitude for the adaptive platform's capacity to "determine what I need to work on," "maintain my interest," and "allow me to revisit content when I do not comprehend something." Several students said that the technology made them less worried about making mistakes because the feedback was private and helpful instead of punishing. This change in the emotional climate made people more willing to take risks and try new things with language, both in digital modules and in class activities. Teachers agreed with these thoughts, saying that students were more interested, sure of themselves, and ready for class discussions. The adaptive system gave them useful analytics that let them keep an eye on how students were doing, find out where they were having trouble, and adjust the support they gave in class. Some teachers said that their job had changed from teaching to coaching and mentoring, which they found both rewarding and hard.

Even so, combining adaptive technologies with the flipped classroom model was not easy. Technological barriers became a major problem, especially at the beginning of the intervention. Not all students had reliable access to devices or stable internet connections at home, which made it harder for some to finish their work before class. To help with these problems, schools gave students more resources, like access to computer labs before or after school. Teachers also made deadlines more flexible and gave students different assignments when they needed to. But these temporary fixes showed that we need bigger, more systemic solutions to make sure that everyone has equal access in technology-enhanced learning environments.

Teacher training became another important factor that affected how well the intervention worked. Teachers needed a lot of professional development to be able to effectively curate digital content, understand data from the adaptive platform, and handle the difficulties of blended and flipped instruction. Some people said they felt overwhelmed by the initial learning curve, especially when it came to balancing the demands of integrating technology with their regular teaching duties. Ongoing help, working together to plan, and chances to learn from each other were all seen as important factors in successful implementation. Also, the quality and cultural relevance of digital content were said to be important for keeping students interested and in line with the goals of the curriculum. Teachers said that adaptive platforms should be able to be changed to fit the needs of the students, the languages spoken in the area, and the interests of the students.

Another problem was making sure that students were responsible for getting ready for class. Most of the students in the experimental group worked hard on the adaptive modules, but some had trouble with self-discipline and often put off or skipped assignments. Interviews indicated that these students either lacked intrinsic motivation, encountered conflicting time demands, or struggled to organize their learning beyond the confines of the classroom. In response, teachers put in place regular check-ins, ways to keep track of progress, and ways to motivate students, like public praise and peer support. The results show that the adaptive, flipped model encourages independence, but it also needs support and, in some cases, parental involvement to keep students interested.

A comparison of these findings with previous research demonstrates both validation and enhancement of existing knowledge. The benefits noted in learner autonomy, engagement, and communicative competence correspond with prior research on flipped classrooms (Bishop & Verleger, 2013; Lo & Hew, 2017) and adaptive learning (Kalyuga, 2009; Yilmaz, 2017). This study enhances the literature by illustrating the cumulative benefits of their integration and by offering comprehensive evidence from a secondary education context, which is less commonly featured in

research on educational technology innovation. The findings emphasize the significance of meticulous instructional design, a resilient technological infrastructure, and continuous professional development in achieving the optimal efficacy of these models.

From a teaching point of view, combining adaptive learning technologies with the flipped classroom model is a good way to teach language in a way that focuses on the student and mastery. Adaptive platforms offer personalized scaffolding that helps students deal with their own problems before class. Flipped instruction, on the other hand, focuses on communicative and collaborative activities that encourage real language use and deeper engagement. This two-pronged approach not only improves language skills, but it also helps students develop important skills for the 21st century, like digital literacy, self-control, problem-solving, and working as a team. The findings underscore the necessity for administrators and policymakers to allocate resources towards technological infrastructure, ensure ongoing support for teacher training, and formulate policies that foster equity and inclusion within digital learning environments.

Even though there are many benefits, it's important to know what the limits are and where more research needs to be done. The quasi-experimental design of this study, although rigorous, does not entirely eliminate the potential for confounding variables or selection bias. Future research ought to incorporate randomized controlled trials, larger and more heterogeneous samples, and longitudinal designs to evaluate the persistence and generalizability of the observed effects. Furthermore, the dependence on self-reported assessments of motivation and autonomy, although informative, may be susceptible to social desirability bias or other subjective influences. The creation and confirmation of more objective, performance-oriented metrics for these constructs would enhance subsequent research endeavors. Lastly, as adaptive learning technologies and flipped classroom practices keep changing, we need to keep doing research to test new platforms, types of content, and ways of teaching, as well as to learn more about the experiences of students who are not well represented or who are on the margins.

In conclusion, the results of this study offer compelling evidence that the amalgamation of adaptive learning technologies with the flipped classroom model can markedly improve language acquisition, learner autonomy, and motivation among secondary school students. By combining personalization with active, communicative learning, the combined approach makes it possible for students to take charge of their own learning and gain the skills they need to do well in school and in life. There are still problems with access to technology, teacher training, and student accountability, but these can be solved by planning ahead, spending money, and evaluating the situation on a regular basis. The consequences for teachers, administrators, and policymakers are significant, indicating that the future of language education resides in the judicious and fair implementation of innovative pedagogical models that fully utilize technology's capabilities.

Conclusion. The integration of adaptive learning technologies with the flipped classroom model represents a significant paradigm shift in secondary language education. By merging the personalized, data-driven support of adaptive platforms with the active, collaborative learning fostered by flipped instruction, educators can create environments that support both individual mastery and authentic communication. The evidence presented in this study demonstrates that this dual approach leads to greater gains in language proficiency, heightened learner autonomy, and increased motivation compared to traditional instructional methods. Students benefit from immediate, personalized feedback and the ability to progress at their own pace during pre-class preparation, while classroom interactions are enriched by opportunities for meaningful practice, dialogue, and problem-solving. Teachers, in turn, are empowered to act as facilitators and mentors, leveraging data to inform instruction and support student growth.

Despite these advantages, the successful implementation of adaptive, flipped learning models requires careful attention to issues of access, equity, and professional development. Ensuring that all students have reliable access to digital tools and resources is a prerequisite for

equitable participation and achievement. Teachers must be provided with ongoing opportunities to develop their technological and pedagogical expertise, and schools must foster a culture of innovation, collaboration, and continuous improvement. Furthermore, the design and selection of digital content must prioritize cultural relevance, authenticity, and alignment with curricular standards.

Looking ahead, the future of language education will be shaped by the continued evolution of technology and pedagogy. The principles outlined in this study offer a roadmap for educators seeking to prepare students for the demands of a globalized, interconnected world. By embracing adaptive learning technologies and flipped classroom models, schools can move beyond the limitations of traditional instruction and create dynamic, inclusive, and effective learning environments. Ongoing research, evaluation, and dialogue among stakeholders will be essential to refining these models, addressing emerging challenges, and ensuring that every student has the opportunity to reach their full linguistic and academic potential.

References

1. Bishop, J. L., & Verleger, M. A. (2013). The flipped classroom: A survey of the research. In ASEE National Conference Proceedings.
2. Kalyuga, S. (2009). Cognitive Load Theory: How Many Types of Load Does It Really Need? *Educational Psychology Review*, 21(1), 1-19.
3. Lo, C. K., & Hew, K. F. (2017). A critical review of flipped classroom challenges in K-12 education: Possible solutions and recommendations for future research. *Research and Practice in Technology Enhanced Learning*, 12(1), 4.
4. Vygotsky, L. S. (1978). *Mind in Society: The Development of Higher Psychological Processes*. Harvard University Press.
5. Bergmann, J., & Sams, A. (2012). *Flip Your Classroom: Reach Every Student in Every Class Every Day*. International Society for Technology in Education.
6. Abeysekera, L., & Dawson, P. (2015). Motivation and cognitive load in the flipped classroom: definition, rationale and a call for research. *Higher Education Research & Development*, 34(1), 1-14.
7. Sun, J. C.-Y., & Wu, Y.-T. (2016). Analysis of learning achievement and teacher–student interactions in flipped and conventional classrooms. *International Review of Research in Open and Distributed Learning*, 17(1), 79-99.
8. Yilmaz, R. M. (2017). Exploring the role of e-learning readiness on student satisfaction and motivation in flipped classroom settings. *Computers in Human Behavior*, 70, 251-260.

ДАРЫНДЫ ОҚУШЫЛАРҒА ТАРИХТЫ ТЕРЕҢДЕТІП ОҚЫТУДА ИНТЕРАКТИВТІ ӘДІСТЕРДІ ҚОЛДАНУДЫҢ ТИІМДІЛІГІ

Садыкова Айгул Маратовна

PhD докторы, Әлкей Марғұлан атындағы Павлодар педагогикалық университетінің гуманитарлық ғылымдар жоғары мектебінің қауымдастырылған профессоры, Павлодар қ., Қазақстан

Каримова Анара Еркеновна

тарих ғылымдарының кандидаты, қауымдастырылған профессор, Әлкей Марғұлан атындағы Павлодар педагогикалық университеті, Павлодар қ., Қазақстан

Камали Айтгүл Ерсінқызы

Әлкей Марғұлан атындағы Павлодар педагогикалық университетінің «Тарих» білім беру бағдарламасының магистранты, Павлодар қ., Қазақстан

Мақалада дарынды оқушыларға тарихты тереңдетіп оқытуда интерактивті әдістерді қолданудың ғылыми-әдістемелік негіздері мен тиімділігі қарастырылған. Зерттеудің өзектілігі заманауи білім берудегі Student Agency тұжырымдамасы мен оқушылардың танымдық белсенділігін арттыру қажеттілігінен туындайды. Авторлар дебат, кейс-стади және жобалық оқыту сияқты технологиялардың дарынды балалардың аналитикалық ойлауын, сыни пайымдауын және зерттеушілік дағдыларын дамытудағы рөлін негіздейді.

Мақалада интерактивті әдістердің когнитивті дамуға әсері дескрипторлық модель түрінде жүйеленіп, отандық және шетелдік ғалымдардың тұжырымдамаларына салыстырмалы талдау жасалған. Педагогикалық эксперимент нәтижелері интерактивті оқытудың оқушы мотивациясын арттырып, тарихи материалды терең меңгеруге және әлеуметтік құзыреттіліктерді шыңдауға қолайлы орта қалыптастыратынын дәлелдейді. Зерттеу қорытындысы бойынша дарынды оқушының зияткерлік әлеуетін іске асыруға бағытталған даму моделі ұсынылған.

Түйін сөздер: интерактивті оқыту, дарынды оқушылар, тарихты оқыту әдістемесі, танымдық белсенділік, интерактивті әдістер, саралап оқыту.

Қазіргі таңда жаһандық білім беру кеңістігіндегі трансформациялық үдерістер дарынды оқушылардың интеллектуалдық әлеуетін басқарудың жаңа тетіктерін қажет етеді. Бұл мәселе Қазақстан Республикасының стратегиялық басымдықтарымен, атап айтқанда, ҚР Білім беруді дамытудың 2023–2029 жылдарға арналған тұжырымдамасымен және Мемлекеттік жалпыға міндетті білім беру стандартымен тікелей сабақтасады [1; 2]. Бұл құжаттарда білім алушылардың функционалдық сауаттылығын арттыру мен жоғары деңгейлі дағдыларын қалыптастыру басты индикатор ретінде белгіленген. Бұл тұрғыда Экономикалық ынтымақтастық пен даму ұйымының (ЭЫДҰ) «Future of Education and Skills 2030» жобасы шеңберіндегі Student Agency (білім алушының субъектілігі) тұжырымдамасы оқушының өз оқу үдерісін мақсатты түрде басқару және шешім қабылдау қабілетін айқындайды, оқушыны оқу үдерісінің пассивті объектісінен белсенді субъектісіне айналдырудың жаһандық стандарты болып табылады [3].

Тарих пәнін тереңдетілген деңгейде меңгеру тек фактілерді жинақтау емес, зерттеуге негізделген оқыту моделі арқылы тарихи деректерді сыни пайымдауды және тарихи ойлау

дағдыларын қалыптастыруды көздейді [4]. Бұл бағыттың әдіснамалық бастауы Дж. Дьюидің прагматикалық педагогикасы мен Л.С. Выготскийдің әлеуметтік конструктивизм идеяларымен байланысты [5; 6]. Осы іргелі теориялардың заманауи дамуы ретінде Г. Гарднердің «көптік зият» теориясы интерактивті оқытудың психологиялық қажеттілігін дәйектеді [7]. Гарднер ұсынған әдістемелік плюрализм қағидаты бойынша, тұлғааралық және дене-қимыл зият түрлерін дамыту тек интерактивті ортада ғана мүмкін болады. Интерактивті оқытудың практикалық негіздері Р. Реванстың «іс-әрекет арқылы оқыту» (*Action Learning*) тұжырымдамасымен байытылып [8], кейіннен Ч. Бонуэлл мен Дж. Эйсонның еңбектерінде «белсенді оқыту» (*Active Learning*) ретінде дидактикалық жүйеге айналды [9].

Қазақстандық педагогика ғылымында интерактивтілік феномені ұлттық контекстке бейімделе зерттелуде. Ш.Т. Таубаева білім беруді гуманизациялаудың әдіснамалық парадигмаларын айқындаса [10], Т.М. Садықов интерактивті технологиялардың тарихи эволюциясын талдады [11]. Оқушының танымдық дербестігін арттыруда М.М. Жанпейісованың модульдік оқыту технологиясы [12] мен «Назарбаев Зияткерлік мектептері» ДББҰ әзірлеген дарынды балаларды оқыту стратегиялары [13] отандық мектептер үшін практикалық бағдаршам болып табылады.

Дарындылықты диагностикалау мен қолдауда Д.Б. Богоявленская, А.М. Матюшкин, Н.С. Лейтес, А.И. Савенков және Е.И. Щебланованың классикалық зерттеулері интеллектуалдық белсенділіктің маңызын ашып берді [14-18]. Ал халықаралық деңгейдегі S. Tirado-Olivares [19], T. Huijgen [20], G. Keleşzade [21] және A. López-García [22] сияқты авторлардың еңбектері интерактивті әдістердің тарихи контекстүалдандыру мен оқушы мотивациясына (Gómez Carrasco CJ [24]) оң әсерін нақты эмпирикалық деректермен дәлелдейді. Дарынды оқушыларға арналған саралап оқыту стратегиялары (D. A. Troxclair [25], Ç. Çetinkaya [26], L. Ziernwald [27]) мен Дж. Рензулли, Р. Стернберг, Э. Торренс [28-30] тұжырымдамалары оқу үдерісін креативтілікке бағыттаудың методологиялық тірегі болып табылады.

Қазақстанда білім беруді гуманизациялау мен модульдік оқытудың теориялық негіздері жақсы зерттелгенімен, интерактивті әдістерді тарих пәнінің мазмұнымен интеграциялау, тарихи ойлауды бағалау және цифрлық технологияларды енгізу әлі де терең зерттеуді қажет етеді. Мақалада осы олқылықтарды толтыру мақсатында интерактивті әдістерді тарихты оқытуға бейімдеудің кейбір аспектілері қарастырылады. Дарынды оқушыларға тарих пәнінің күрделі тақырыптарын интерактивті әдістермен оқыту мәселесі әлі де болса зерттеуді қажет ететін бағыт болып табылады.

Отандық педагогикалық ілімде дарынды оқушыларға білім беру ісі жеке тұлғаның мүмкіндіктерін ашу мен оқытуды дербестендіру принциптеріне сүйенеді. Осы орайда интерактивті тәсілдер білім беру ортасын түбегейлі өзгертіп, оқушыны ақпаратты пассивті тұтынушыдан танымдық әрекеттің негізгі қозғаушы күшіне – белсенді қатысушысына айналдырады. Нақтырақ айтқанда, дебаттық талқылаулар, жобалау жұмыстары мен нақты ситуациялық талдаулар (кейс-стади) дарынды оқушылардың пайымдау қабілетін шыңдап, интеллектуалдық өсуіне қолайлы орта қалыптастырады. Сонымен қатар, бұл процесс ұстаз позициясының жаңаруын талап етеді: мұғалім дайын ақпарат берушіден оқушының табиғи талантын бағыттап, демеп отыратын тәлімгер (фасилитатор) рөліне ауысады [30; 14].

Тарих пәні дарынды оқушылардың сыни ойлауын, талдау қабілетін және тарихи санасын қалыптастыруда маңызды рөл атқарады. Бұл пән тек фактілер мен оқиғаларды меңгеруді ғана емес, тарихи процестердің себеп-салдарын түсінуді, әртүрлі көзқарастарды салыстыруды және деректерді интерпретациялауды қажет етеді. Осы тұрғыдан алғанда тарихты тереңдетіп оқыту дарынды оқушылардың интеллектуалдық дамуына және зерттеушілік дағдыларының қалыптасуына ықпал етеді. Интерактивті оқытуда мұғалімнің

рөлі оқыту процесінде оқушылардың мақсаттарына жетуге бағытталған. Мұғалім сабақ жоспарын интерактивті іс-әрекеттер мен тапсырмаларды құрастырады, олардың көмегімен оқушылар жаңа ақпаратты меңгереді және жеке тапсырма топтық тапсырмаға айналады. Топтың әрбір мүшесі топтың жалпы табысына үлес қосады. Оқушылардың орындайтын интерактивті жаттығулары мен тапсырмалары интерактивті сабақтардың негізгі құрамдас бөлігі болып табылады. Интерактивті оқыту әдістерін қолдану оқушылардың оқу үдерісіне толықтай қатысуын қамтамасыз етеді, ал бұл оқудың басты көзі болып табылады. Дәстүрлі және интерактивті әрекеттер арасындағы негізгі айырмашылық – оқушы тек білімін қайталап, нығайтып қана қоймай, оны жаңа материалмен құрастырып, толықтырады.

Дарынды оқушыларды оқытуда негізгі мәселе – олардың жоғары деңгейдегі танымдық қажеттіліктерін қанағаттандыру және интеллектуалдық әлеуетін толық ашу болып табылады. Мұндай оқушылар ақпаратты жылдам меңгеріп қана қоймай, оны талдайды, салыстырады және жаңа қорытындылар жасауға ұмтылады. Сондықтан тарих пәнін тереңдетіп оқыту барысында дәстүрлі репродуктивті әдістер жеткіліксіз болып, оқушылардың зерттеушілік және сыни ойлау дағдыларын дамытуға бағытталған интерактивті тәсілдерді қолдану қажеттілігі туындайды [29].

Тарихты тереңдетіп оқыту дарынды оқушылардың тарихи деректермен жұмыс істеу қабілетін, оқиғалардың себеп-салдарын анықтауын және әртүрлі көзқарастарды талдауын талап етеді. Бұл үдерісте оқушылар тек дайын ақпаратты қабылдаушы емес, тарихи білімді өз бетінше құрастырушы субъект ретінде қалыптасады. Осыған байланысты интерактивті әдістер педагогикалық үдерістің негізгі құралына айналады.

Интерактивті әдістердің ішінде дебат және пікірталас әдістері ерекше тиімді болып табылады. Бұл әдістер оқушыларды белгілі бір тарихи мәселе бойынша әртүрлі позицияларды қорғауға, дәлелдер келтіруге және қарсы пікірлерді талдауға үйретеді. Мысалы, «Қазақ хандығының құрылуының тарихи маңызы» немесе «Реформалардың қоғам дамуына әсері» сияқты тақырыптарда ұйымдастырылған дебаттар оқушылардың тарихи ойлауын тереңдетеді және олардың аргументациялық дағдыларын дамытады [15].

Жобалық оқыту әдісі де дарынды оқушылармен жұмыста маңызды орын алады. Бұл әдіс оқушыларға белгілі бір тарихи тақырып бойынша өз бетінше зерттеу жүргізуге, ақпарат жинауға және нәтижелерін жүйелеуге мүмкіндік береді. Мысалы, «Түркі өркениетінің дамуы» немесе «Қазақстанның тәуелсіздік кезеңіндегі өзгерістері» тақырыптарында жобалар орындау оқушылардың зерттеушілік қабілетін дамытады және олардың пәнге деген қызығушылығын арттырады.

Кейс-талдау әдісі нақты тарихи жағдайларды талдауға бағытталған. Бұл әдіс оқушыларға тарихи оқиғаларды белгілі бір контексте қарастыруға, шешім қабылдауға және өз пікірін негіздеуге мүмкіндік береді. Мысалы, белгілі бір тарихи тұлғаның шешімдерін талдау немесе тарихи оқиғалардың баламалы даму жолдарын қарастыру оқушылардың сыни ойлау дағдыларын қалыптастырады [16].

Сонымен қатар интерактивті әдістердің маңызды элементтерінің бірі – топтық жұмыс. Топтық талқылау барысында оқушылар бір-бірімен пікір алмасып, өз идеяларын қорғап, ұжымдық шешім қабылдауға үйренеді. Бұл олардың коммуникативтік дағдыларын дамытуға және әлеуметтік тәжірибе жинақтауына ықпал етеді.

Дарынды оқушылармен жұмыс барысында интерактивті әдістерді тиімді қолдану үшін мұғалімнің рөлі де өзгереді. Мұғалім ақпарат жеткізушіден бағыттаушы және ұйымдастырушы рөлге ауысады. Ол оқушылардың өз бетімен жұмыс істеуіне жағдай жасап, олардың танымдық белсенділігін ынталандырады [17].

Осы тұрғыдан алғанда интерактивті әдістер дарынды оқушыларға тарихты тереңдетіп оқытуда жоғары тиімділік көрсетеді. Олар оқушылардың білімді терең меңгеруіне, сыни ойлауын дамытуға және зерттеушілік дағдыларын қалыптастыруға мүмкіндік береді.

Дарынды оқушыларға тарихты тереңдетіп оқытуда интерактивті әдістердің тиімділігін нақты көрсету үшін олардың оқушының танымдық әрекетіне әсерін салыстырмалы түрде талдау маңызды. Әрбір әдістің дарынды оқушылардың қабілеттерін дамытудағы рөлі мақала авторлары құрастырған 1-кестеде жүйеленіп көрсетіледі.

1-кесте – Тарихты тереңдетіп оқыту контексіндегі интерактивті әдістердің дарынды оқушылардың танымдық дағдыларын дамытудағы дескрипторлық моделі

Интерактивті әдіс	Қолдану мазмұны	Дарынды оқушыға әсері	Қалыптасатын дағды
Дебат	Тарихи мәселелерді талқылау	Өз позициясын қорғау	Сыни ойлау, аргументация
Пікірталас	Әртүрлі көзқарастарды салыстыру	Терең талдау	Аналитикалық ойлау
Жобалық оқыту	Зерттеу жүргізу	Өздігінен білім алу	Зерттеушілік дағды
Кейс-талдау	Нақты тарихи жағдайды талдау	Шешім қабылдау	Проблемалық ойлау
Топтық жұмыс	Ұжымдық талқылау	Пікір алмасу	Коммуникативтік дағды
Рөлдік ойын	Тарихи тұлғаларды бейнелеу	Эмпатия, түсіну	Шығармашылық ойлау
Миға шабуыл	Идея генерациясы	Еркін ойлау	Креативтілік

Кестеде көрсетілгендей, интерактивті әдістер дарынды оқушылардың тек білім алуына ғана емес, олардың ойлау деңгейінің тереңдеуіне және танымдық белсенділігінің артуына ықпал етеді. Әсіресе дебат, кейс-талдау және жобалық оқыту әдістері оқушылардың күрделі мәселелерді шешу қабілетін дамытып, олардың зерттеушілік әлеуетін ашуға мүмкіндік береді.


Дарынды оқушылар үшін маңызды фактор – оқу процесінде еркіндік пен белсенділік. Кестеде ұсынылған әдістер осы қажеттіліктерді толық қамтамасыз етіп, оқушылардың өзіндік пікір қалыптастыруына және тарихи материалды терең түсінуіне жағдай жасайды. Сонымен қатар, интерактивті әдістерді жүйелі түрде қолдану дарынды оқушылардың тек академиялық жетістіктерін ғана емес, олардың коммуникативтік және әлеуметтік дағдыларын да дамытуға мүмкіндік береді.

Интерактивті оқыту әдістерін қолдану мектеп оқушыларының тарихты оқуға деген жағымды ынтасын қалыптастырады, пәнге деген тұрақты танымдық қызығушылығын арттырады, білім сапасын жақсартады және олардың қабілеттерін дамытуға қолайлы педагогикалық жағдай туғызады [18].

Дарынды оқушыларға тарихты тереңдетіп оқытуда интерактивті әдістерді қолдану олардың танымдық дамуын кезең-кезеңімен жүзеге асыруға мүмкіндік береді. Осыған байланысты оқыту үдерісіндегі өзгерістерді жүйелі түрде көрсету үшін дарынды оқушының даму моделін ұсыну қажет.

1-суретте ұсынылған модельде интерактивті әдістердің оқушының ойлау деңгейіне қалай әсер ететінін және білімді меңгеру процесінің біртіндеп күрделенетіні сипатталады. Суретте көрсетілгендей, интерактивті әдістер дарынды оқушылардың танымдық дамуын қарапайым қабылдаудан күрделі зерттеушілік деңгейге дейін кезең-кезеңімен қалыптастырады. Алғашқы кезеңде оқушы тарихи ақпаратты қабылдайды және түсінеді. Бұл кезеңде мұғалімнің түсіндіруі мен бастапқы сұрақтары маңызды рөл атқарады. Келесі кезеңде оқушы ақпаратты талдай бастайды, яғни тарихи оқиғалардың себеп-салдарын

анықтап, оларды салыстырады. Бұл процесте пікірталас, кейс-талдау сияқты әдістер тиімді қолданылады. Үшінші кезеңде оқушы өз пікірін қалыптастырады. Ол тарихи мәселелер бойынша жеке көзқарасын білдіріп, белгілі бір позиция ұстанады. Бұл кезеңде дебат және талқылау әдістері маңызды орын алады. Одан кейін дәлелдеу кезеңі жүзеге асады. Оқушы өз пікірін нақты деректер мен аргументтер арқылы негіздейді. Бұл оның логикалық ойлауын және тарихи дәлелдеу қабілетін дамытады. Жоғары деңгейде оқушы зерттеу жүргізуге көшеді. Бұл кезеңде жобалық оқыту әдісі тиімді болып, оқушы өз бетінше ақпарат іздеп, оны талдайды және жүйелейді. Соңғы кезеңде оқушы қорытынды жасап, тарихи процестерге кешенді баға береді. Бұл дарынды оқушыларға тән жоғары деңгейлі ойлау дағдыларының қалыптасқанын көрсетеді.



1-сурет. Дарынды баламен интерактивті жұмыс моделі

Ұсынылған модель интерактивті әдістердің дарынды оқушылардың интеллектуалдық дамуына жүйелі әсер ететінін дәлелдейді және оларды оқытуда кезеңдік тәсілді қолданудың тиімділігін негіздейді.

Интерактивті тәсілдер оқушылардың тек білім алуын ғана емес, олардың сыни ойлауын, талдау қабілетін және зерттеушілік дағдыларын дамытуға бағытталған кешенді құрал ретінде қарастырылады. Бұл әдістер дарынды оқушылардың танымдық қажеттіліктерін қанағаттандырып, олардың оқу процесіне белсенді қатысуына мүмкіндік береді. Дебат, кейс-талдау және жобалық оқыту әдістері оқушылардың аргументациялық, аналитикалық және зерттеушілік дағдыларын қалыптастыруда ерекше рөл атқаратыны байқалады. Бұл әдістер білімді дайын күйінде қабылдаудан гөрі, оны өз бетінше құрастыруға негізделген оқыту моделін қалыптастырады. Сонымен бірге, интерактивті әдістер дарынды оқушылардың танымдық дамуын кезең-кезеңімен жүзеге асыруына мүмкіндік береді. Ақпаратты қабылдау, талдау, пікір қалыптастыру, дәлелдеу және зерттеу сияқты сатылар

оқушылардың ойлау деңгейінің біртіндеп күрделенуін қамтамасыз етеді. Бұл тәсіл оқыту процесінің жүйелілігін арттырып, білімді терең меңгеруге жағдай жасайды.

Қазіргі білім беру талаптарына сәйкес дарынды оқушыларды оқытуда мұғалімнің рөлі де өзгереді. Мұғалім білім көзі емес, оқу процесін ұйымдастырушы және бағыттаушы ретінде әрекет етеді. Интерактивті әдістерді тиімді қолдану мұғалімнің кәсіби құзыреттілігіне, әсіресе оның педагогикалық және коммуникативтік шеберлігіне байланысты.

Қорытындылай келе, дарынды оқушыларға тарихты тереңдетіп оқытуда интерактивті әдістерді жүйелі және мақсатты қолдану олардың интеллектуалдық әлеуетін толық ашуға, оқу мотивациясын арттыруға және жоғары деңгейлі ойлау дағдыларын қалыптастыруға мүмкіндік береді.

Ескерту

Зерттеу Қазақстан Республикасы Ғылым және жоғары білім министрлігінің Ғылым комитеті қаржыландыратын BR28712263 гранты шеңберінде жүзеге асырылды. («Қазақстанның дарынды балаларын дамыту бойынша педагог кадрларды даярлаудың кешенді ғылыми-инновациялық жүйесін құру»).

Пайдаланылған әдебиеттер тізімі

1. Қазақстан Республикасының Үкіметі. (2023, 28 наурыз). "Қазақстан Республикасында мектепке дейінгі, орта, техникалық және кәсіптік білім беруді дамытудың 2023–2029 жылдарға арналған тұжырымдамасын бекіту туралы" Қазақстан Республикасы Үкіметінің 2023 жылғы 28 наурыздағы № 249 қаулысына өзгерістер мен толықтырулар енгізу туралы. <https://adilet.zan.kz/kaz/docs/P2400000465>
2. Қазақстан Республикасы Оқу-ағарту министрлігі. (2022, 3 тамыз). Мемлекеттік жалпыға міндетті білім беру стандарттарын бекіту туралы (№ 348 бұйрық). <http://25-merki.mektebi.kz/normativtk-yty-aktler/832-r-ou-aartu-ministrn-2022-zhyly-3-tamyzday-348-bjryymemlekettk-zhalpya-mndett-standarttaryn-bektu-turaly.html>
3. OECD. (2019). OECD learning compass 2030: A series of concept notes. https://www.oecd.org/content/dam/oecd/en/about/projects/edu/education-2040/1-1-learning-compass/OECD_Learning_Compass_2030_Concept_Note_Series.pdf
4. Wineburg, S. S. (2001). Historical thinking and other unnatural acts: Charting the future of teaching the past. Temple University Press.
5. Dewey, J. (1938). Experience and education. Kappa Delta Pi.
6. Vygotsky, L. S. (1978). Mind in society: The development of higher psychological processes. Harvard University Press.
7. Gardner, H. (1983). Frames of mind: The theory of multiple intelligences. Basic Books.
8. Revans, R. W. (1982). The origins and growth of action learning. Chartwell-Bratt.
9. Bonwell, C. C., & Eison, J. A. (1991). Active learning: Creating excitement in the classroom (ASHE-ERIC Higher Education Report No. 1). The George Washington University. <https://files.eric.ed.gov/fulltext/ED336049.pdf>
10. Таубаева, Ш. Т. (2016). Педагогиканың философиясы және әдіснамасы. Қазақ университеті.
11. Садыков, Т. М. (2016). История развития интерактивных технологий. Проблемы современного образования, (4), 158–161.
12. Жанпейісова, М. М. (2015). Модульдік оқыту технологиясы оқушыны дамыту құралы ретінде. Ғылым.
13. Назарбаев Зияткерлік мектептері. (2020). Дарынды және талантты оқушыларды оқыту әдістемесі. НЗМ.

14. Богоявленская, Д. Б. (2002). Психология творческих способностей. Академия.
- 15... Матюшкин, А. М. (1989). Концепция творческой одаренности. Вопросы психологии, (6), 29–33.
16. Лейтес, Н. С. (2000). Возрастная одаренность школьников. Академия.
17. Савенков, А. И. (2000). Одаренные дети в детском саду и школе. Академия.
18. Щебланова, Е. И. (2004). Психологическая диагностика одаренности школьников. Издательство Института психологии РАН.
19. Tirado-Olivares, S., Cózar-Gutiérrez, R., García-Olivares, R., & González-Calero, J. A. (2021). Inquiry-based learning and formative assessment in history teacher education. *Journal of Education for Teaching*, 47(4).
20. Huijgen, T., van de Grift, W., van Boxtel, C., & Holthuis, P. (2017). Promoting historical contextualization in history education: An intervention study. *Journal of Curriculum Studies*, 49(5).
21. Keleşzade, G., Güneyli, A., & Özkul, A. (2018). Effectiveness of history teaching based on social constructivist learning. *Educational Sciences: Theory & Practice*, 18(4).
22. López-García, A. (2018). Effectiveness of active methods and digital resources based on the flipped learning model in history teaching. *International Journal of Emerging Technologies in Learning (IJET)*, 13(10).
23. Kainulainen, M., Puurtinen, M., & Chinn, C. A. (2019). Epistemic processes and inquiry-based learning in history. *History Education Research Journal*, 16(1).
24. Gómez Carrasco, C. J., Rodríguez-Medina, J., Miralles-Martínez, P., & López-Facal, R. (2021). Motivation and perceived learning of secondary education history students. *Frontiers in Psychology*, 12, 661780. <https://doi.org/10.3389/fpsyg.2021.661780>
25. Troxclair, D. A. (2013). Differentiated instruction for gifted students in regular classrooms. *Gifted Child Today*, 36(1).
26. Çetinkaya, Ç. (2014). The effect of differentiated social studies program on verbal creativity of gifted students. *Journal for the Education of Gifted Young Scientists*, 2(2).
27. Ziernwald, L., Hillmayr, D., & Holzberger, D. (2022). Differentiated instruction in mixed-ability classrooms: A systematic review. *Education Sciences*, 12(11).
28. Renzulli, J. S., & Reis, S. M. (2004). The three-ring conception of giftedness: A developmental model for promoting creative productivity. Prufrock Press.
29. Sternberg, R. J. (2001). Giftedness as developing expertise: A theory of the interface between high abilities and achieved excellence. *High Ability Studies*, 12(2), 159–179.
30. Torrance, E. P. (1966). Torrance tests of creative thinking. Personnel Press.

Possibilities of special pedagogical diagnostics in children from socially disadvantaged backgrounds in kindergarten

Marcela Čarnická

Abstract

The aim of the paper is to point out the possibilities of special pedagogical diagnostics in children from socially disadvantaged backgrounds in kindergarten, with a focus on assessing the level of their knowledge after applying the stimulation methodology according to Šilonová, Klein and Šinková. The research also included a comparison of the achieved results between the experimental and control groups of children. The results of the conducted experiment pointed out the importance of early diagnosis and subsequent intervention. Based on the findings, we recommend carrying out screening examinations in children from socially disadvantaged backgrounds already in preschool age and, in case of identifying deficiencies, using stimulation methodologies. Such an approach can contribute to improving children's school readiness and at the same time act as a preventive measure against the development of learning disorders after entering primary school.

Keywords: A child from a socially disadvantaged background. Special pedagogical diagnostics.

Preschool children are immediate, receptive, do not have permanently formed bad habits, are easily influenced, but in a motivating environment they can get excited and actively participate in various activities. Švábová (2017, p. 10) states that "during this period they form a scale of values, therefore it is up to us adults to give each child space for the most successful development of their personality." Physical development in the preschool period includes a child's height of approximately 120 cm, weight of 20 - 22 kg, a completed pulling-up phase, the replacement of milk teeth for permanent, appropriate development of gross motor skills and motor coordination. The child can direct movements, does not waste energy, movements are economical, and enjoys movement (Končerková, 2010). Psychological development is influenced by innate dispositions, family environment and kindergarten. The child should be able to notice details, to endure a certain amount of time in an activity. In the area of thinking, the child's analytical thinking prevails, he/she is oriented in concepts expressing quantity, size, order, causality and sequence. The vocabulary should contain approximately 3000 to 4000 words, the child should pronounce correctly, express himself/herself coherently, understand speech and know basic numerical and temporal categories. In terms of personality traits, requirements are placed on an average level of general intellectual ability, interest in new knowledge and work at school, orientation in the value system and norms of behavior, self-regulation, a positive attitude towards oneself and adequate self-confidence (Končerková, 2010).

If the child's environment and surroundings are socially disadvantaged, there is a lack of support, motivation, and not enough stimuli for his development, the child does not have sufficient cognitive development, development of his senses and personality traits. However, insufficient development of a child can also be caused by the lack of time of parents for their child, or lack of interest in his upbringing and education. The result is an unprepared child for school

entry, the child has problems with integrating into the team and respecting norms. A child from this environment does not have his basic needs adequately satisfied, and the consequences of this psychological or cultural deprivation are manifested in a lag in mental, social, emotional and professional development (Klein, Rusnáková, Šilonová, 2012). A socially disadvantaged environment is an environment that, due to social and linguistic conditions, does not sufficiently stimulate the development of the mental, volitional and emotional qualities of an individual, does not support his effective socialization and does not provide sufficient appropriate stimuli for the development of personality. It causes socio-cultural deprivation, distorts the intellectual, moral and emotional development of an individual and from the aspects of education, for these reasons, we consider him a person with special educational needs (SEP for pupils with SEP). In the literature, we encounter a division according to individual influences into several groups of disadvantaged children and youth: neglected children from economically weak families, children without organized free time, subcultures of children and youth, children of parents addicted to alcohol or other drugs, children from wealthy families whose parents are busy with work, children in and after leaving children's homes, unemployed youth, and finally Roma children and youth (Šuhajdová, 2019).

However, most authors associate a socially disadvantaged environment with the Roma community. The socially disadvantaged environment of the Roma is created by several factors. One of them is a different historical development, separation and defense mechanisms. The family factor is the strongest educational force and teaches children inappropriate habits towards themselves and towards society. Another important factor is the insufficient economic background caused by the low educational level of the Roma and subsequently their failure to apply themselves in the labor market. According to the authors Klein, Rusnáková and Šilonová (2012, p. 98), the child is also influenced by the "personality-individual factor, which includes somatic, communicative and cognitive factors, which are manifested mainly when Roma children enter school." If a child comes from a socially disadvantaged environment, this does not mean that he or she can automatically be placed in a special school. In § 28 para. 8 of the School Act explicitly states that a child from a socially disadvantaged environment cannot be placed exclusively in a class for children with special educational needs solely because he or she comes from a socially disadvantaged environment. The child is placed in a regular class together with other children. The basic problems when a child from a socially disadvantaged environment enters the school system include a low educational level, or late entry into school, a socially disadvantaged environment for children, a lack of positive resources supporting their participation in classes, insufficient hygiene and work habits, lack of command of the Slovak language, a low level of relations between the school and Roma families, prejudices against these children, the child's temperament, and the school system's lack of preparedness for the specifics of Roma education (Rosinský, 2009). Problems such as falling behind, difficulties in coping with school and work activities occur. In addition, children from socially disadvantaged backgrounds have problems with eating, work habits (cutting, drawing, putting away toys, etc.) or hygiene habits (many do not have a functioning water supply at home). They do not know how to appreciate toys or teaching aids, as they are not taught to do so even in the home environment. A big minus is the attitude of parents towards education in general, which also negatively affects the behavior of these children, e.g. disrespect and disobedience to teachers. Parents rarely cooperate with kindergartens, children are often absent, which is also caused by health circumstances or the fact that children do not want to go to kindergarten and the parent does not accompany them to school, they are simply at home. Due to the above fact, the area of sociability is also limited in this group of children (Kováčová, 2019), specifically establishing and maintaining peer relationships (Kováčová, 2010, Rassu Nagy, 2025).

Special education diagnostics focuses on gaining knowledge about a disabled or disturbed individual. Based on their individual characteristics, it can then outline the possibilities of education or upbringing of the given individual. The result of diagnostics is a diagnosis, which we arrive at through special education methods. The special education method is a procedure by which we gain knowledge about the examined person, on the basis of which a diagnosis can be formulated (Vašek, 2004). The selected method must be adapted to the type and degree of disability of the examined individual. In the literature, we can find various divisions of methods according to several criteria. Methods are divided according to what they detect, how they detect, what they focus on, further, whether they are methods aimed directly at the individual or only at data related to him, and finally according to the method of evaluating the data obtained (Vašek, 2004). A diagnostic method must meet two basic properties (validity and reliability) and respect the principles (complexity, dynamism, versatility of the examination, modifications). The methods used include observation, questionnaire, interview, diagnostic testing, tests, case study, analysis of activity results, instrumental methods, causation. Various tests and assessment procedures are used for the diagnosis of school readiness. The tests are aimed at verifying the level of development of fine motor skills, memory, attention, thinking, speech and visual motor skills (Miňová, 2015). Similarly, the level of development in the emotional and social areas is also determined. There are several types of these tests, the most used test in assessing school readiness is the Kern test, which contains three tasks: "1. drawing a human figure (according to an idea), 2. imitation of written writing (according to a model) and 3. tracing a group of 10 dots (according to a model)" (Končeková, 2010). The assessment is carried out on a five-point scale (1 - best, 5 - worst). The goal of school readiness testing is to discover whether a child is ready to enter the first year of elementary school.

In the diagnosis of school readiness, the term screening can be understood as the detection of partially weakened areas of development, which are important to develop before entering the first year of primary school. Screening, according to the dictionary of foreign words, means searching for certain diseases (sources of infection, early stages of the disease, etc.) in the entire population or in selected groups. The authors of the screening manual for preschool children state that "a screening examination is usually carried out on children in the last, preparatory year of kindergarten with the aim of mapping their current level of cognitive abilities and skills and thus identifying children in a timely manner who show signs of risky development in terms of their expected schooling" (Šilonová, Klein, Šinková, Souček Vaňová, 2018, p. 23). The screening examination also serves to verify the intellectual talent of children who appear to be above average. The screening is carried out between the months of September and December, or to the enrollment in the first year of primary school. However, it can also be carried out after enrollment, as there is still time for appropriate stimulation of children. Screening takes place in two stages, the first stage is held in a group, the second stage is individual. However, screening is not carried out through standardized tests as an examination of school maturity. The child's legal representative must give consent to the screening, which is requested by kindergartens mainly "so that in the last school year of preparation they have the opportunity to adequately stimulate children after professional counseling in cooperation with parents so that children can cope with the onset of school demands without difficulty" (Šilonová, Klein, Šinková, Souček Vaňová, 2018, p. 23). The screening does not serve to assess the postponement of compulsory school attendance, it has a screening role and is more stimulating than an examination of school aptitude" (Šilonová, Klein, Šinková, Souček Vaňová, 2018). The screening examination is carried out in three stages. The first stage of the screening takes place in a group, the second and third stages are individual. The screening in the group stage focuses on the following areas of the child's development: "understanding of instructions and the ability to work according to instructions in a group,

graphomotor skills, the child's behavior in a group, independence at work and the child's emotional attunement and mood when working in a group" (Šilonová, Klein, Šinková, Souček Vaňová, 2018, p. 49). This stage is carried out in a kindergarten, the number of children in one group is 10 to 16. The children sit at the tables so that they all have enough space to work and at the same time, so that they do not copy each other. At the beginning, the researcher introduces himself and continues in a playful way in completing individual tasks. In addition to the tasks, the researcher also has an evaluation sheet at his disposal. The methodologies of the first stage include a drawing of a character and a scale of the child's behavior during group work. "The individual part of screening 1 deals with the diagnosis of deficits of partial functions" (Šilonová, Klein, Šinková, Souček Vaňová, 2018, p. 53). These deficits are the causes of symptoms that can cause problems in various areas during development. Individual screening 1 focuses on the following partial functions: "visual differentiation (tactile-kinesthetic perception, auditory memory, seriality - visual, auditory differentiation), visual-auditory intermodality, auditory differentiation of figure and background (spatial orientation - body schema, seriality - auditory, auditory-visual intermodality, visual differentiation of figure and background, spatial orientation) and visual memory" (Šilonová, Klein, Šinková, Souček Vaňová, 2018, p. 54).

This stage of screening takes place in the kindergarten classroom with each child separately. The researcher works with templates, a recording sheet and an evaluation sheet. The last stage of the screening focuses on identifying the following areas: "the scope of basic knowledge and information about oneself and family, the child's level of pronunciation and articulation, the scope of the child's vocabulary, remembering visual stimuli, concepts related to the areas of dimension, quantity and order, basic numerical ideas and ideas about quantity, behavior during an individual examination" (Šilonová, Klein, Šinková, Souček Vaňová, 2018, p. 77). The researcher has templates, a record sheet and an evaluation sheet at his disposal.

After the screening and evaluation, revealing deficits, we work with individual children through training of partial functions. Training of partial functions should take place every day, max. 10 minutes, we continuously encourage the child. One area is always trained, after mastering it, we move on to the next. Desirable qualities of a coach include natural authority, self-confidence, directness, consistency, perseverance, politeness, and the ability to correctly interpret individual instructions, which they should also master.

In our research, we focused on the diagnosis of visual perception associated with the mathematical field. The prerequisites for mathematics are already developed in the preschool period, when the nervous system and the entire psychological and physical side of the child mature according to general developmental tendencies, but also strictly individually (Kamenický, 2016). Dyscalculia includes a specific impairment of basic mathematical skills that cannot be explained by mental retardation or incorrect teaching methods (Šilonová, Klein, 2018). Dyscalculia means a child's inability to acquire mathematical skills using common methods used in school. We must emphasize that success in mathematics also depends on other learning disorders (Šilonová, Klein, 2018). Early detection of deficiencies in basic numerical concepts, in distinguishing geometric shapes, problems in determining quantity, order or size can significantly help in the prevention of learning disorders. Authors Šilonová, V., Klein, V., Arslan Šinková P. and Souček Vaňová M. (2018) consider the following games suitable for developing mathematical ideas: Take less - more than I have (for understanding the concepts of more, less, the same, ...), Sort by size, name the smallest, largest, middle, etc., What does not belong in a given group - an exercise in sorting, logical categorization, Divide them into fruits and vegetables, yellow and green, round and square shapes, etc.

The aim of our research was to analyze the knowledge of preschool children after the implementation of the stimulation methodology according to Šilonová, Klein and Šinková and at

the same time to compare the level of acquired knowledge in preschool children in the experimental and control groups. During the implementation of the research part, we chose diagnostic methods - experiment and description of children. At the beginning, we diagnosed 18 preschool children from socially disadvantaged backgrounds with parental consent. The next step to carry out the experiment was to create two groups, control and experimental. In both groups, the results from the diagnosis of children were approximately the same. Then we did a screening examination with both group as well. The children from the experimental group subsequently underwent a screening-stimulation tool in the period from September 2024 to June 2025, also with parental consent. We implemented the screening-stimulation program during the day in kindergarten. In addition, according to the school curriculum, their teachers also worked with the children. After its completion, both groups were subjected to a screening examination with the same tasks as at the beginning. We supplemented the experimental method with a description of the children.

Description of children

Child 1

Child 1 is five years old, attends a kindergarten in Nálepkovo, where the class consists of children from socially disadvantaged backgrounds, most of whom are of Roma origin. Child 1 has two sisters and lives with her parents in a family house in Nálepkovo. Her parents have completed primary education and both work in community service. Child 1 has problems identifying colors or geometric shapes. The teacher cited low attendance at kindergarten as a major negative, which is the result of her parents' lack of interest in education, which is also reflected in her behavior and in her little effort to learn something new in kindergarten.

Child 2

Child 2 is six years old, attends a kindergarten in Nálepkovo, where the class consists of children from socially disadvantaged backgrounds, most of whom are of Roma origin. Together with her parents and two siblings, she lives in a municipal rented apartment. Her parents work on community service. Child 2 knows colors and geometric shapes. In kindergarten, she is active in games or educational activities, participates in individual tasks, and is diligent.

Child 3

She is five years old, attends kindergarten in Nálepkovo, where the class consists of children from socially disadvantaged backgrounds, most of whom are of Roma origin. She lives with her family in a municipal rented apartment, her parents do not receive a material need benefit, and she works through community service. Child 3 has deficiencies in distinguishing colors, geometric shapes, and number lines. This is caused by several factors: frequent absences from kindergarten, her lack of interest in various tasks performed in kindergarten, and finally, poor family support and a lack of motivational environment.

Child 4

Child 4 is six years old, attends a kindergarten in Nálepkovo, where the class consists of children from socially disadvantaged backgrounds, most of whom are of Roma origin. He lives with his parents and six siblings in a municipal apartment building, his parents work on community service. Child 4 has only identified some colors or geometric shapes, he has deficiencies in number order or determining quantity. Another negative is his frequent absence from kindergarten. If he is present in kindergarten, he is passive, has no interest in educational activities, and does not complete tasks.

Child 5

Child 5 He is six years old, attends a kindergarten in Nálepkovo, where the class consists of children from socially disadvantaged backgrounds, most of whom are of Roma origin. He lives with his parents and five siblings in a municipal apartment building, his parents work on community

service. Child 5 had a school attendance deferment, meaning he is in kindergarten for a year longer. He knows colors, but he has problems with geometric shapes and number sequences. Child 5 is often absent from kindergarten. It would help if parents were more interested in education and support for their child.

Child 6


He is six years old, he attends kindergarten in Nálepkovo, where the class is made up of children from socially disadvantaged backgrounds, most of whom are of Roma origin. He lives in a municipal apartment building with his parents and five siblings, and his parents work in community service. Child 6 is smart, he likes to learn, he enjoys being in kindergarten, and he feels support from his parents. Child 6 had no problem identifying colors, shapes, or order and quantity. He is looking forward to elementary school.

Analysis of research results

The experimental group consists of three children, the control group of three children. The first graph shows the results of the initial diagnostics, the second graph will show the results of the diagnostics after the end of the stimulation program in the experimental group.

Graph 1


Colours



the author's own work

All children from the experimental group determined the correct colors only some, from the control group 1 child determined the correct colors, 2 children failed, they could not determine the correct color.

Graph 2



the author's own work

Results of the experimental group after the end of the stimulation program in color recognition: 1 child names all colors, 1 child does not name colors, but shows a message and 1 child can only detect colors. Children from the control groups of the obtained results: 1 child names all colors, 1 child can have only colors and 1 child can have colors when determining the color.

Geometric shapes


Graph 3



the author's own work

Children from the experimental group determined only some geometric colors, from the control group 1 child determined only some geometric shapes, 2 children failed, they could not determine the correct geometric shape.

Graph 4




the author's own work

After the end of the stimulation program, one child from the experimental group determined all geometric colors and 2 children determined only some, from the control group 2 children determined only some geometric shapes, 1 child failed, could not determine the correct geometric shape.

Size, quantity, order


Graph 5



the author's own work

In the category *Size, quantity, order*, children could get 10 points for 10 questions. Children from the control group reached mean values, so in the interval of 5 - 7 points. In the experimental group, the values were similar, range 5 - 6 points.

Graph 6




the author's own work

In the category *Size, quantity, order*, children could get 10 points for 10 questions. Children from the control group reached the mean values, so in the interval of 6 - 7 points, only one child improved by one point. In the experimental group, the results based on the stimulation program were better for each child, the points obtained ranged from 7 to 10 points.




Mathematical and numerical concepts
Ascending numerical series to 10

Graph 7



the author's own work
Two children from the experimental group control the number range up to 10, one child controls the number range up to 5. All children from the control group control the number range up to 5.


Graph 8



the author's own work
Children in the experimental group master the number range up to 10. One child from the control group controls the ascending number range up to 10, two children control the number range up to 5.

Descending number range from 10 to 1


Graph 9



the author's own work

Two children from the experimental group control the descending number range from 5, one child does not control the descending number range. One child from the control group controls the descending number range from 5, two children do not control the descending number range.

Graph 10




the author's own work

One child from the experimental group controls the descending number range from 10, one child from 5 and one child does not control the descending number range. One child from the control group controls the descending number range from 5, two children do not control the descending number range.

Determination of the number up to 10


Graph 11



the author's own work

Children from the experimental group know how to determine the number up to 5. From the control group, one child does not know how to determine the number at all, two children know how to determine the number up to 5.

Graph 12



the author's own work

Two children from the experimental group control to determine the number to 10 and one child controls to determine the number to 5. One child from the control group to determine the number does not know at all, two children master to determine the number to 5.

We conducted our research in a kindergarten in Nálepko, where the classroom is dominated by Roma children. The children come from an environment where they do not have motivating role models, they lack someone who would respond to their needs, which negatively affects the development of their brain. Many of these children do not go to kindergarten regularly, they are not paid attention to at home, which is reflected in their inability to hold a pencil correctly, they do not have basic hygiene habits, etc. Of course, this cannot be made up for in kindergarten. Negative factors that do not motivate these children are also low employment in their surroundings and low educational level. Based on the results achieved, the following conclusions can be drawn. We will start according to individual categories, the first is the Colors area. Children from the control group recorded a small improvement. While at the first diagnosis only one child could name all colors and two failed, at the end of the school year one child recorded a small improvement, as he could only identify some colors. At the beginning, all three children in the experimental group could only identify some colors. After completing the stimulation program and subsequent diagnostics, two children made progress, one child named all colors, one child

only showed the colors but did not name them, and one child identified only some colors. In the second category, Geometric shapes, one child in the control group identified only some geometric shapes, two children remained in the same position, in the experimental group, one child also made progress, naming all geometric shapes, two children remained in the same position - they identified only some shapes. In the category Size, quantity, order, the control group did not experience significant progress, improvement, children in the experimental group achieved an improvement of 2 to 5 points, or 20 to 50%. The category Ascending number series up to 10 shows improvement in both groups, two children were able to count to 10, the others remained in their places. The descending number series from 10 to 1 in the control group did not show any improvement, in the experimental group one child can count from 10 to 1. Two children who previously only mastered numbers up to 5 had no problem determining the number up to 10 after completing the stimulation program. There was no change in the control group. Based on the results, we would like to state that children from the experimental group who completed the stimulation program achieved better results than children from the control group. Therefore, based on our findings, we would recommend screening children of preschool age from socially disadvantaged backgrounds and, if any deficiencies are found, working with these children through a screening-stimulation program. The result will be better school readiness of these children, development of communication skills, etc. It is also a way of preventing possible learning disorders that could be a problem after starting elementary school. It would be appropriate if the cooperation between parents and kindergarten would improve and if they also had a suitable stimulating and encouraging environment in the home environment. Parents should also ensure regular attendance at kindergarten, if possible, so that the child misses as few days as possible in kindergarten. However, the problem can often be the negative attitude of parents towards school and towards education itself. However, we must not forget about tolerance for all children, increase the status of the child in the kindergarten team, show positive role models, thereby supporting motivation in these children. Each child is an individual with their own mistakes and causes. Through appropriate methods, we can eliminate these causes and in this way help to better develop the personality of a child from a socially disadvantaged environment.

Author

Mgr. Marcela Čarnická, PhD.
Department of Special Education Faculty of Education
Catholic University of Ružomberok, Slovakia
marcelacarnicka@gmail.com

Bibliografia

- KAMENICKÝ, M. 2016. *Didaktika matematiky a Špeciálna didaktika matematiky*. Ružomberok: Verbum, 2016. 160 s. ISBN 978-80-561-0373-9.
- KLEIN, V., RUSNÁKOVÁ, J., ŠILONOVÁ, V. 2012. *Nultý ročník a edukácia rómskych žiakov*. Spišská Nová Ves: Občianske združenie Spektrum – Východ, 2012. 265 s. ISBN 978-80-971181-0-5.
- MIŇOVÁ, M. 2015. *Pedagogické diagnostikovanie v materskej škole*. Prešov: Rokus, 2015. 182 s. ISBN 978-80-89510-40-5.
- KONČEKOVÁ, Ľ. 2010. *Vývinová psychológia*. Prešov: Vydavateľstvo Michala Vaška, 2010. 312 s. ISBN 978-80-7165-811-5.
- KOVÁČOVÁ, B. 2010. Utváranie inkluzívneho po(vedomia) v začiatkoch inštitucionálneho začleňovania detí. In: *Transdisciplinárne aspekty inkluzívnej pedagogiky*. Bratislava : EMITplus, 2010. – ISBN 978-80-970623-2-3, s. 130-135.
- KOVÁČOVÁ, B. 2010. *S inklúziou od raného veku : dieťa s odlišnosťou a jeho vstup do kolektívu*. Hliník nad Hronom : Reziliencia, 2019. 100 s. ISBN 978-80-972277-5-3.

RASSU NAGY, V. 2025. Stratégie výučby inkluzívneho učiteľa. In: *Expresivita vo výchove VII*. Ružomberok: Katolícka univerzita v Ružomberku. VERBUM - vydavateľstvo KU, 2025. ISBN 978-80-561-1182-6, s. 93-101.

ROSINSKÝ, R. a kol. 2009. *Pedagogicko-psychologické a interkultúrne aspekty práce učiteľov žiakov z odlišného sociokultúrneho prostredia*. Nitra: Univerzita Konštantína Filozofa v Nitre, 2009. 207 s. ISBN 978-80-8094-589-3.

ŠILONOVÁ, V., KLEIN, V. 2018. *Edukácia sociálne znevýhodnených žiakov so špecifickými vývinovými poruchami učenia*. Ružomberok: Verbum, 2018. 274 s. ISBN 978-80-561-0558-0.

ŠILONOVÁ, V., KLEIN, V., ŠINKOVÁ, P. A., SOUČEK VAŇOVÁ, M. 2018. *Manuál k depistáži pre deti predškolského veku pochádzajúce zo sociálne znevýhodneného prostredia*. Inovovaná časť. Prešov: MPC, 2018. 107 s. ISBN 978-80-565-1434-4.

ŠUHAJDOVÁ, Z. 2019. *Výchova detí zo sociálne znevýhodneného prostredia*. Trnava: PF, Trnavská univerzita v Trnave, 2019. 138 s. ISBN 978-80-568-0358-5.

ŠVÁBOVÁ, B. 2017. *Rozvoj komunikácie v inkluzívnom školskom prostredí v predprimárnom období vzdelávania*. Ružomberok : Verbum, 2017. 141 s. ISBN 978-80-561-0494-1.

VAŠEK, Š. 2004. *Špeciálnopedagogická diagnostika*. Bratislava: Sapienta s.r.o., 2004. 168 s. ISBN 80-969112-0-1.

ZÁKON č. č. 245/2008 Z. z. z 22. mája 2008 o výchove a vzdelávaní (školský zákon) a o zmene a doplnení niektorých zákonov v znení neskorších predpisov, dostupné na <https://www.slovlex.sk/ezbierky/pravne-predpisy/SK/ZZ/2008/245/>

Štátny vzdelávací program výchovy a vzdelávania pre žiakov so špeciálnymi výchovno-vzdelávacími potrebami, dostupné na <http://www.statpedu.sk/sk/svp/statny-vzdelavaci-program/vychova-vzdelavanie-ziakov-so-svvp/ziak-so-socialne-znevynhodneného-prostredia/>, vyhľadane 09.04.2026.

Reviewers:

PaedDr. Božena Švábová, PhD.

Theological Institute in Spišské Podhradie

Faculty of Theology, Catholic University of Ružomberok, Slovakia

Mgr. Miriama Pačnárová, PhD.

Kindergarten, Levoča, Slovakia

PERCEPTION OF DISABILITY IN PRESCHOOL CHILDREN THROUGH VISUAL METHODS

Barbora Kováčová

Abstract:

The study describes ways in which selected disabilities can be presented to kindergarten children in a comprehensible and age-appropriate manner. It presents research findings in which children in kindergartens were asked to describe picture cards depicting various forms of disability. This approach makes it possible to capture children's natural interpretations and spontaneous reactions to visual stimuli. At the same time, it provides space for identifying misconceptions, inaccuracies, or simplified explanations that young children tend to construct. The results highlight the importance of visual methods in developing understanding and acceptance of diversity within peer groups. The knowledge obtained in this way can be used in the design of inclusive educational activities in pre-primary education.

Keywords:

Disability perception, Inclusive education, Visual methods, Peer interaction, preschool children

Perception of Difference in Kindergarten: Evidence from Research

In early studies describing the process of integrating children or pupils with disabilities into schools, it was assumed (Jenkins et al., 1989; Salibusbury, 1991) that positive attitudes and appropriate social interaction would emerge naturally and spontaneously as a result of shared placement of children in integrated classrooms. With the passage of time, however, these assumptions can be considered somewhat questionable due to insufficient supporting evidence. At that time, there was a lack of demonstrable results in favor of integration. This does not suggest that the shared placement of children in a group does not yield positive outcomes. On the contrary, it represents a long-term preventive process whose potential is also evident in preschool settings.

Kindergartens as institutions play a significant role in preparing children for entry into peer groups while simultaneously supporting the development of social relationships. Children typically enter a group without established friendships, often experiencing concerns about forming new relationships, whether they will find friends, or whether they will be liked by other children. They enter a new environment where parental or older sibling support is no longer immediately available. At the same time, they need to establish relationships with new individuals, particularly their peers (Kováčová, 2010).

Children with disabilities experience this transition in a comparable way until situations arise in which they become stigmatized. Based on research findings from kindergarten environments, we present strategies used by children with disabilities in response to direct discrimination from peers. The research sample consisted of children with physical differences (mostly diagnosed with cerebral palsy), children with health impairments, and children with communication disorders (primarily diagnosed with stigmatism, rotacism, and stuttering).

Many responses reflected specific concerns articulated by children with differences during interviews. For example, Dominik (diagnosed with cerebral palsy – diparesis) stated: *"I left... I didn't say anything to him because yesterday he played with me"* (explaining why he did not defend himself). *"Otherwise, I would have told him he was stupid. He was probably in a bad mood. Otherwise, he plays with me sometimes."* Essentially, this reflected a fear of losing a friend.


Dominik is currently attending his second kindergarten. From his statements, he comments on his position in the group as follows: *“I don’t want to leave, they like me. I like this kindergarten.”* Another statement was recorded from Simona (diagnosed with dyslalia multiplex), whose response was categorized under *“a friend helped me.”* Simona stated: *“They don’t laugh at me. I have many friends. Tonko helps me. When Kajo comes, Tonko shows him his fist like this (demonstrating a clenched fist), and he runs away. Yes, Tonko helps me. He is my friend.”* Essentially, this highlights the importance of ensuring that every child with a disability has someone specific to turn to, ideally a peer.

Supporting coexistence among all children regardless of their health status can be achieved through preventive or intervention activities implemented by kindergarten teachers, special educators, or therapeutic educators working within the kindergarten or cooperating externally. For adults (kindergarten teachers or special educators), equality within the group should be considered a key factor in explaining the meaning, content, and diversity of friendship. Primarily, educators should guide children to perceive one another as equals (Everyone is different in some way, yet we are all human). Throughout the child’s stay in kindergarten, educators gradually create opportunities for friendships based on equality (Vodičková, 2020).

It is essential to teach children to accept friends as they are, rather than as they are imagined to be. Friendships represent a value that transcends labels and stigmas (Kováčová, 2010, p. 66). The most important function of friendship is mutual support and altruistic assistance. It provides children with social and emotional support while helping them integrate into a social group. Friendship contributes to the healthy development of children, not only those with differences, helping them overcome barriers, increase self-confidence, and reduce feelings of inferiority. Through friendships, children also build their social roles.

Pedagogical Strategies for Explaining Differences in a Group of Children

In an inclusive environment, teachers explain heterogeneity in two ways. The first involves a child’s direct experience with another child with a disability, while the second focuses on introducing specific differences through experiential learning within educational activities (Kučerka & Rassu Nagy, 2025).



Direct Experience of a Child with a Peer with a Disability

Most children in early and preschool age have varying levels of knowledge and experience with different types of disabilities. Several research findings focused on children's interactions with different types of differences in kindergarten settings are presented below.

Musher-Eizenman et al. (2004) report that children in kindergartens most noticeably perceive differences related to overweight (obesity) more negatively compared to other types of disabilities. Preschool children begin to recognize differences in body structure or body “size.”

They often identify with ideals presented in advertisements, magazines, and other media. Stigmatization due to obesity begins with identifying and labeling differences from approximately four years of age. A similar investigation among preschool children was later conducted by a team led by Musher-Eizenman (2004), which found that children attributed fewer positive characteristics to individuals with overweight compared to those with average or below-average weight. Preschool children are clearly aware of their own physical differences, as well as those of their friends or unfamiliar peers.

Children aged four to five tend to favor peers with certain health differences over those with physical disabilities. This may be explained by the fact that children with physical disabilities are often perceived by peers as unable to participate in the same range of physical activities as others. They may experience mobility difficulties, for example in walking, running, or participating in sports activities.

Nabors (1997) confirmed that children with physical disabilities are often excluded from the role of play partners, even when other children have not directly observed them during play. However, it is important to note that these findings cannot be generalized universally; not all children develop negative attitudes toward peers or adults with disabilities.

Children also imitate beliefs and prejudices from their environment, particularly from adults such as parents or caregivers, whom they encounter in conversations or through explicit comments. The above-mentioned international research findings were supplemented by partial findings from research conducted in Slovak kindergartens.

The research used picture cards, based on which children were asked, for example, which child with a difference depicted on the cards could become their friend. Based on the visual material, children were able to describe various disabilities. As many as 68% of children agreed that a child with a disability could be an equal partner in classroom play as well as in outdoor playground activities.

Table 1: Representation of Physical Disability





Table 2: Representation of Visual Impairment



Introducing Disability through Experiential Learning

Achieving change in attitudes can be effectively realized through experiential learning within a group of children. This involves creating a concrete situation such as: *“We are painters who do not have arms, so we paint with our feet.”* Each child enters the role of a painter who is different in that they paint using their feet. Expression is a way that helps (Fábry Lucká, 2022) in explaining and overcoming topics, such as how to explain to children who a person with a disability is.

All professionals working with children in early and preschool education must recognize that, for children with disabilities, the social group in an inclusive environment represents a significant developmental opportunity for meaningful progress. Improvements in social interactions have been repeatedly observed even in groups where social interaction was not intentionally promoted.

Building on experiential learning, space is created for educational activities aimed at fostering inclusive awareness already in kindergarten settings. Through such activities, children acquire knowledge about the basic needs of children with disabilities (Kováčová, 2010; Kováčová, 2019). It is clearly essential to provide children with equal opportunities for education.

Hundert and Houghton (1992) emphasize the importance of an emotionally empathetic approach combined with systematic planning and the subsequent application of procedures that support mutual social interaction.

Real Support for Inclusive Education

A fundamental understanding of the existence of heterogeneity can elevate inclusive awareness to a higher level of consciousness. This awareness is no longer limited to an understanding of individual inclusion but becomes a collective phenomenon contributing to the desired global development of inclusive awareness (Kušnířová et al., 2025, Rassu Nagy, 2025).

By implementing preventive and intervention strategies, it is appropriate—and necessary—to prepare the group for the inclusion of a child with any type of disability (often not visible) and to eliminate undesirable behavioural patterns identified in research conducted in kindergarten classroom groups where a child with a disability was included.

Preventive and/or intervention strategies are introduced to children in the form of play, where it is appropriately demonstrated that heterogeneity should be accepted as a natural part of society (Čarnická, 2025). The reality of inclusion lies in perceiving every individual as an equal participant in play, relationships, and life in general. Mutual social experience, the need to be accepted, and the willingness to accept others are embedded in the (re)development of ethical awareness in each individual.

The entire process (preventive and/or intervention) in specific situations is designed so that each child has the opportunity to experience and understand inclusion directly in real-life contexts—that is, in a way that is natural to them, through dramatic play. This involves progressing from pre-inclusive awareness through its experiential formation to inclusive awareness. We are convinced that children should be intentionally guided to recognize what can be considered good or bad, appropriate or inappropriate, desirable or undesirable behaviour, as this is also a significant aspect of fostering inclusive awareness. For this reason, it is essential that children understand—regardless of their disability or health status—what behaviour toward others is acceptable and what is not (Kováčová, 2010; Rassu Nagy, 2025).

Conclusion

Creating space for inclusive education has brought many significant and distinctive changes. We consider the effort to strengthen the staffing structure of schools to ensure the effective functioning of inclusion processes as particularly important. This reflects feedback from practice in both kindergartens and primary schools, where mainstream teachers encounter children/pupils with special educational needs (Kušnířová et al., 2022).

On the one hand, there is a clear effort to create conditions for the inclusion of children/pupils with special educational needs; on the other hand, teachers are often not sufficiently prepared for this inclusive process and increasingly report a lack of readiness, particularly in relation to the education of various types of disabilities (Kováčová, 2019; Vodičková, 2020; Maliňáková, 2022). For this reason, creating additional positions within schools represents a crucial step toward effectively addressing specific conditions in favor of children/pupils with special educational needs, in favor of all pupils, and also in favor of schools as institutions described as “schools for all.” An important role is played by all staff members actively involved in inclusive education, who collectively form a community contributing to the development and practical implementation of the philosophy of inclusion.

For this reason, it is not appropriate to limit this perspective strictly to staff within a single school. Instead, it is necessary to view the group of actors in a broader context, which also includes employees of counselling and advisory services, support groups for parents/children, associations supporting families with children with unique needs, inclusive rehabilitation programmes, as well as staff in extracurricular and leisure activities.

Each of these actors contributes to ensuring that children/pupils with special educational needs are not only accepted in their uniqueness but are also supported in achieving the highest possible quality of life and overall well-being.

Bibliografia

- ČARNICKÁ, M. 2025. Activating teaching in civics classes for students with intellectual disabilities in special primary schools. In: *Visnik Žitomirskogo deržavnogo unìversitetu ìmenì Ivana Franka* : pedagogični nauki. Žitomir: Žitomirskij deržavnyj unìversitet ìmenì Ivana Franka. pp. 269-277. ISSN 2663-6387 [https://doi.org/10.35433/pedagogy.2\(121\).2025.20](https://doi.org/10.35433/pedagogy.2(121).2025.20)
- FÁBRY LUCKÁ, Z. 2022. Expresia ako cesta komunikácie. In: *MMK 2022: Mezinárodní Masarykova konference pro doktorandy a mladé vědecké pracovníky : recenzovaný sborník příspěvků mezinárodní vědecké konference*. 13. Hradec Králové : Magnanimitas akademické sdružení, 2022. s. 744-751. ISBN 978-80-87952-37-5.
- HUNDERT, J., HOUGHTON, A. 1992. Promoting social interaction of children with disabilities in integrated preschools: A failure to generalize. *Exceptional Children*, 1992, Vol. 58, pp. 311-320. <https://doi.org/10.1177/001440299205800404>
- JENKINS, J. R., ODOM, S. L., SPELTZ, M. L. 1989. Effects of social integration on preschool children with handicaps. *Exceptional Children* 1989, Vol. 55, pp. 420-428. <https://doi.org/10.1177/001440298905500505>
- KOVÁČOVÁ, B. 2010. *Inkluzívny proces v materských školách*. Bratislava: Musica Liturgica, 2010.
- KOVÁČOVÁ, B. 2019. *S inklúziou od raného veku*. Hliník nad Hronom : Reziliencia s. r. o, 100 s. ISBN 978-80-972277-5-3.
- KUČERKA, D.; RASSU NAGY, V. 2025. Umenie inkluzívneho vzdelávania v prospech každého človeka. In: *Média – umenie – komunikácia* : vedecký nekonferenčný zborník. Bratislava: Paneurópska vysoká škola, 2025. s. 75-85. ISBN 978-80-8275-026-6.
- KUŠNÍROVÁ, V.; ROCHOVSKÁ, I.; ČARNICKÁ, M. 2022. Attitudes of preschool teachers and assistants towards inclusive education in Slovakia. In: *EDULEARN22 Proceedings* : 14th International Conference on Education and New Learning Technologies July 4th-6th, 2022, Palma, Mallorca, SPAIN. Palma : IATED, 2022. pp. 6227-6234. ISBN 978-84-09-42484-9.
- MALIŇÁKOVÁ, P. 2022. The Phenomenon of Inclusion in a Modern Society. In *Studia Scientifica Facultatis Paedagogicae Universitas Catholica Ružomberok*, 2022. Vol. 21, No. 2, pp. 7-17. <https://doi.org/10.54937/ssf.2022.21.2.7-17>

- MUSHER-EIZENMAN, HOLUB, M. et al. 2004. Body size stigmatization in preschool children: The role of control attributions. In: *Journal of Pediatric Psychology*, 2004, Vol. 29, pp. 613–620. <https://doi.org/10.1093/jpepsy/jsh063>
- NABORS, L. 1997. Playmate preferences of children who are typically developing for their classmates with special needs. In: *Mental Retardation* 1997, Vol. 35, No. 2, pp. 107–113. [https://doi.org/10.1352/0047-6765\(1997\)035<0107:PPOCWA>2.0.CO;2](https://doi.org/10.1352/0047-6765(1997)035<0107:PPOCWA>2.0.CO;2)
- RASSU NAGY, V. 2025. Stratégie výučby inkluzívneho učiteľa. In: *Expresivita vo výchove VII*. Ružomberok: Katolícka univerzita v Ružomberku. VERBUM - vydavateľstvo KU, 2025. pp. 93–101. ISBN 978-80-561-1182-6.
- SALISBURY, CL. 1991. Mainstreaming during the early childhood years. In: *Except Child*, 1991, No. 58, Vol. 2, pp. 146–55. <https://doi.org/10.1177/001440299105800206>
- VODIČKOVÁ, B. 2020. Identification of supporting phenomena and barriers of inclusion in the pedagogical practice of teachers in a kindergarten in Bratislava, Slovak Republic. In: *Journal of Exceptional People: an international journal for education and special studies*. 2020, Vol. 2, No. 17 (2020), pp. 63–73.

Contact:

doc. PaedDr. Barbora Kováčová, PhD.

Catholic University, Faculty of Education, Department of
Special Education, Hrabovská cesta 1, Ružomberok

Text reviewed by:

doc. Mgr. Barbora Vodičková, PhD.

Mgr. et Mgr. Zuzana Polanská

Technical Sciences

Autonomous Vehicles in International Freight Transport: Future Prospects

Rahila Rahimli

International Economic Relations Faculty, Azerbaijan State University of Economics,
Group: 814

Abstract

Self-driving trucks, artificial intelligence, sophisticated sensor systems (LiDAR, radar), and 5G-enabled communication represent the forefront of autonomous vehicle technologies that are rapidly reshaping international freight transportation. These innovations are driving substantial improvements in productivity, reducing operating costs, enhancing overall safety, and ensuring the uninterrupted flow of cargo across long distances. The growing demand for faster, more reliable, and environmentally efficient logistics solutions, coupled with labor shortages in the trucking sector and increasing global trade volumes, is expected to accelerate the expansion of the worldwide autonomous truck industry dramatically over the next decade.

This study's main goal is to offer a thorough quantitative and qualitative evaluation of how autonomous vehicles affect the resilience and efficiency of international freight transit. The study uses a mixed-methods approach that includes expert interviews to gather useful insights from stakeholders, a comparative analysis of the World Bank's Logistics Performance Index (LPI) to assess logistical improvements, an augmented gravity model of trade to quantify cross-country effects, and a systematic literature review to synthesize current academic and industry knowledge. The study focuses on worldwide trends and aims to draw broadly applicable conclusions in various infrastructure and economic scenarios.

Leading nations like the US, China, Germany, and the Netherlands are used as examples, as are newly developed transit corridors that show how quickly autonomous technology are being adopted. These illustrations offer verifiable proof of the possible advantages and difficulties of autonomous freight transport. In order to facilitate the strategic integration of autonomous transport systems into current supply chains and promote sustainable, effective, and technologically advanced international logistics networks, the research's findings are intended to provide governments, logistics companies, and international organizations with practical recommendations.

Keywords: autonomous vehicles, self-driving trucks, artificial intelligence, freight transport, Logistics 4.0, LPI, gravity model, supply chains, transport efficiency

Introduction

Autonomous cars have emerged as one of the most disruptive and revolutionary developments in freight logistics over the past ten years, as rapid technical innovation has radically changed international transportation systems. Leading transportation firms on several continents are gradually testing and deploying self-driving trucks with artificial intelligence, sophisticated navigation and sensor systems, and powerful real-time data processing capabilities. In addition to improving fleet management and route planning, these technologies help improve predictive maintenance, lower human error, and increase overall operational reliability. The World Bank (2023) highlights the economic importance of implementing cutting-edge transportation

technologies by stating that even relatively small advances in transportation efficiency can result in significant increases in international trade volumes.

Due to a number of convergent factors, including the urgent need for safer and more environmentally sustainable transportation solutions, the rapidly increasing demand for faster and more dependable delivery services driven by e-commerce, and the ongoing labor shortages affecting the global trucking sector, autonomous vehicles have now become a strategic priority for both national governments and private logistics operators. There is still a noticeable dearth of thorough, large-scale research that thoroughly evaluates the wider economic, operational, and logistical ramifications of autonomous freight transport, despite the growth of pilot programs, technological experiments, and localized studies.

There is a large knowledge gap regarding the systemic effects of these innovations on global supply chains, cross-border trade efficiency, and national logistics performance because existing studies typically concentrate on technological viability, simulation results, or short-term operational metrics. This study's main goal is to close this gap by offering a comprehensive, worldwide analysis that integrates expert insights, comparative performance evaluation, and quantitative modeling. This will result in actionable knowledge that will help logistics stakeholders and policymakers strategically adopt autonomous transport technologies.

Literature Review

Autonomous trucks can greatly increase delivery efficiency and lower logistics costs by up to 30%, particularly in long-haul transportation, according to recent industry evaluations, such as McKinsey & Company (2024). Research has also shown that improved asset utilization, reduced accident rates as a result of automated safety systems, optimal fuel use, and more predictable supply chain operations are all advantages. Beyond their technical capabilities, autonomous vehicles are increasingly viewed as a calculated response to the global trucking industry's workforce deficit.

While many studies concentrate on technological features like real-time data processing, LiDAR, and AI navigation, others look at the wider effects on supply chain architecture. The safety and economy benefits of driverless vehicles are highlighted by Fagnant and Kockelman (2015). The Technology Acceptance Model (TAM) (Davis, 1989) and the idea of dynamic capacities (Warner & Wě, 2019), which aid in explaining how businesses successfully incorporate disruptive innovations, continue to be important frameworks for comprehending technology adoption.

While European countries are actively developing legal frameworks to ensure safe integration, countries with advanced technological infrastructure, including China and the United States, are leading large-scale testing.

Research Objectives and Questions

Objectives:

- Identify the impact of autonomous vehicle technologies on freight transport efficiency
- Quantify their contribution to logistics performance and trade flows
- Develop practical recommendations for accelerating adoption

Research Questions:

1. To what extent do autonomous vehicles improve efficiency in international freight transport?
2. How do they affect logistics performance indicators such as LPI?
3. What are the main technological, regulatory, and economic barriers to adoption?
4. How will autonomous transport reshape global logistics networks in the next decade?

Methodology

Research Design

A mixed-methods approach will be applied, combining quantitative analysis to identify global trends with qualitative insights to provide practical interpretation.

Population and Sampling

The quantitative component will use secondary data from multiple countries, including LPI datasets, international transport statistics, and innovation indices. The qualitative component will include 12–15 expert interviews with representatives of logistics companies, technology providers, and transport authorities.

Data Collection

Secondary data will include logistics performance indicators, freight transport statistics, and technological development indices. Primary data will be collected through semi-structured interviews.

Data Analysis

Quantitative analysis will involve descriptive statistics and an augmented gravity model using software such as Stata or R. Qualitative data will be analyzed using thematic analysis.

Ethical Considerations

The study will ensure informed consent, full confidentiality, and anonymity of all participants involved in the research.

Expected Outcomes

It is anticipated that the study will offer solid quantitative proof of how autonomous cars affect global trade flows and overall logistics performance, including quantifiable increases in supply chain dependability, cost savings, and delivery efficiency. Beyond the numbers, the study seeks to pinpoint the critical factors—like organizational capacity, regulatory support, and technology readiness—that influence effective adoption. Additionally, it will emphasize the disparities in acceptance and implementation across rising transportation hubs and technologically sophisticated economies, providing insights into the elements that facilitate or impede integration. The outcomes will include a useful framework that may direct international organizations, logistics companies, and legislators in developing, implementing, and expanding autonomous freight solutions. They will also set standards for further research in this quickly developing area.

Significance of Study

By combining quantitative modeling, comparative logistics performance analysis, and expert views, this study offers one of the first thorough evaluations of autonomous vehicle adoption on a global scale. Practically speaking, the study will provide governments, regulators, and logistics companies looking to use autonomous transport technologies to increase trade efficiency, lower costs, and improve sustainability and safety with practical advice. The study will be a useful tool for nations at various stages of technological development, assisting them in navigating the shift toward more sophisticated, resilient, and competitive freight transport systems by highlighting both the advantages and disadvantages of autonomous vehicles.

Project Timeline

Literature Review	September
Data Collection (Interviews)	October – November
Comparative Analysis	December – January
Draft Writing and Review	February – March
Final Submission	May – June

Limitations

Due to the study's heavy reliance on secondary data sources, the analysis's granularity and timeliness may be limited. Furthermore, most regions are still in the early stages of adopting autonomous vehicles, thus long-term implications on trade flows and logistical performance might not yet be fully apparent. The stability and generalizability of the results may be impacted by the comparatively little observation period and the quick speed of technology advancement in autonomous transportation systems. Additionally, differences in market conditions, infrastructure

readiness, and regulatory frameworks among nations may bring additional sources of uncertainty, thus results should be interpreted cautiously and regarded as indicative rather than final.

Conclusion

International freight transportation is being transformed by autonomous vehicles, which are no longer just a far-off idea. Global logistics will be significantly more competitive for nations that invest in digital infrastructure, autonomous technologies, and supportive regulations.

Early adoption can result in quantifiable increases in productivity, cost savings, and safety, as shown by examples from the US, China, and Europe. Autonomous transportation will play an increasingly significant role as global trade continues to grow.

This study will measure these effects and suggest doable actions for the next five to ten years, such as the creation of legal frameworks, funding for digital infrastructure, autonomous truck pilot projects, and workforce adaptation plans.

Which nations become important logistics hubs in the future will depend on their capacity to embrace and scale autonomous transport solutions in an increasingly technologically advanced and competitive global economy.

References

1. World Bank. (2023). Connecting to Compete 2023: The Logistics Performance Index. <https://lpi.worldbank.org/international/global>
2. Fagnant, D. J., & Kockelman, K. (2015). Preparing a nation for autonomous vehicles: Opportunities, barriers and policy recommendations. *Transportation Research Part A*, 77, 167–181. <https://doi.org/10.1016/j.tra.2015.04.003>
3. Litman, T. (2023). Autonomous vehicle implementation predictions. Victoria Transport Policy Institute. <https://www.vtpi.org/avip.pdf>
4. Davis, F. D. (1989). Perceived Usefulness, Perceived Ease of Use, and User Acceptance of Information Technology. *MIS Quarterly*, 13(3), 319–340. <https://doi.org/10.2307/249008>
5. Warner, K. S. R., & Wäger, M. (2019). Building dynamic capabilities for digital transformation. *Long Range Planning*, 52(3), 326–349. <https://doi.org/10.1016/j.lrp.2018.12.001>
6. Qu, R. (2023). The Implementation and Potential Ramifications of Autonomous Driving Technology in the Realm of Freight Transportation and Logistics. *Academic Journal of Science and Technology*, 7(3). <https://doi.org/10.54097/ajst.v7i3.12717>
7. <https://doi.org/10.54097/ajst.v7i3.12717>
8. Sadiku, M. N. O., & Sadiku, J. O. (2026). Autonomous Vehicles in Logistics. *International Journal of Trend in Research and Development*.
9. <http://www.ijtrd.com/papers/IJTRD29091.pdf>
10. Gör, M. S., & Çelik, C. (2025). Logistics Planning of Autonomous Air Cargo Vehicles with Deep Learning Methods: A Literature Review. *Applied Sciences*, 15(19), 10709. <https://doi.org/10.3390/app151910709>
11. <https://doi.org/10.3390/app151910709>
12. Hjalmarsson-Jordanius, A., et al. (2018). Autonomous Transport: Transforming Logistics through Driverless Intelligent Transportation. *Transportation Research Record*.
13. <https://doi.org/10.1177/0361198118796968>
14. Lee, C., et al. (2023). Optimizing Autonomous Transfer Hub Networks: Quantifying the Potential Impact of Self-Driving Trucks.
15. <https://arxiv.org/abs/2305.03119>

DEVELOPMENT AND VALIDATION OF AN INTELLIGENT ENERGY MANAGEMENT SYSTEM FOR INDUSTRIAL ENTERPRISES USING MACHINE LEARNING

Yessetov Alisher

Master's Student, AOGU (Atyrau Oil and Gas University) named after Safi Utebayev, Atyrau, Kazakhstan

Utenova Balbupe

c.t.s., Associate Professor of the Faculty of Information Technology, AOGU (Atyrau Oil and Gas University) named after Safi Utebayev, Atyrau, Kazakhstan

Abstract. This paper presents the development of an automated energy consumption management system (AECMS) for an industrial enterprise based on machine learning methods. A comparative analysis of load forecasting algorithms — ARIMA, SVR, XGBoost, LSTM, and Transformer — was conducted. A three-tier system architecture (Edge Layer, Analytics Layer, Decision Layer) was proposed using Apache Kafka, InfluxDB, and PostgreSQL. An energy consumption anomaly detection module based on the Isolation Forest algorithm was developed. System validation was carried out at Temirtau-Metal LLP over a 6-month period, achieving a 17.3% reduction in average monthly energy consumption and an 18.8% decrease in peak load. The total annual economic effect amounted to 12.5 million KZT with a payback period of less than 8 months.

Keywords: *machine learning, energy consumption management, LSTM, XGBoost, Transformer, industrial IoT, anomaly detection, Industry 4.0.*

Energy efficiency of industrial production is one of the key challenges for sustainable economic development in Kazakhstan. According to the Ministry of Energy of the Republic of Kazakhstan, the industrial sector consumes over 40% of all generated electricity, while the energy intensity of the country's GDP exceeds the global average by a factor of 2.5 [1, p. 12]. A significant portion of energy resources is consumed inefficiently due to outdated control systems, lack of intelligent monitoring, and insufficient forecasting capabilities.

Traditional approaches to energy management in industrial enterprises are typically based on static equipment schedules and fixed standards that do not account for the actual dynamics of production processes. This leads to substantial energy overruns, particularly during periods of partial capacity utilization and transient operating modes [2, p. 45]. According to International Energy Agency (IEA) experts, the application of digital management technologies can reduce industrial energy consumption by 10–20% [3, p. 28].

Machine learning (ML) methods provide a powerful toolkit for analyzing large volumes of IoT sensor data, identifying hidden consumption patterns, and developing optimal management strategies. In recent years, deep learning methods have advanced significantly, demonstrating high accuracy in forecasting energy consumption time series, including under non-stationary conditions and seasonal fluctuations [4, p. 112].

The objective of this work is to develop an automated energy consumption management system (AECMS) for an industrial enterprise based on machine learning methods, ensuring a reduction in energy costs of at least 15% while maintaining production volumes.

To achieve this objective, the following tasks were defined: analysis of existing energy management approaches, development of an intelligent AECMS architecture, implementation and comparative evaluation of load forecasting models, and experimental validation of the system at a real industrial enterprise.

Review of existing approaches

The scientific literature identifies several main approaches to energy consumption forecasting: statistical methods (ARIMA, exponential smoothing), classical machine learning methods (SVM, Random Forest, Gradient Boosting), and deep learning methods (RNN, LSTM, Transformer). Each approach has its advantages and limitations depending on the nature of the data and the forecasting horizon [5, p. 203].

Statistical models such as ARIMA and SARIMA have proven effective for forecasting stationary series with pronounced seasonality; however, their accuracy decreases significantly in the presence of multiple exogenous factors. Ensemble learning methods (XGBoost, LightGBM) offer high interpretability and noise resistance but require careful feature selection and engineering [6, p. 87]. Recurrent neural networks, particularly the LSTM architecture, can automatically extract temporal dependencies but require significant computational resources for training [7, p. 156].

In the context of Kazakhstan, research on intelligent energy management is limited. Major studies focus on smart grids and renewable energy generation forecasting [8, p. 34]. The application of ML directly at the industrial enterprise level remains insufficiently studied, which determines the scientific novelty of the present research.

Architecture of the proposed system

The developed AECMS is built on a three-tier architecture: the data collection layer (Edge Layer), the processing and analysis layer (Analytics Layer), and the decision-making layer (Decision Layer). Each layer is implemented as a set of microservices communicating through the Apache Kafka message broker, ensuring scalability and fault tolerance [9, p. 78]. The structural components of the system are presented in Table 1.

Table 1 – Structural components of the AECMS

Layer	Components	Protocols	Functions
Edge Layer	IoT sensors, SCADA, PLC, meters	Modbus TCP, MQTT, OPC UA	Data collection and transmission
Analytics Layer	ML Pipeline, Apache Kafka, PostgreSQL, InfluxDB	REST API, gRPC	Predictive analytics, anomaly detection
Decision Layer	Dashboard, controllers, optimization module	WebSocket, HTTP/2	Schedule optimization, notifications

At the Edge Layer, data from industrial sensors and meters is collected at frequencies ranging from 1 to 60 seconds depending on the equipment type. The OPC UA protocol is used for communication with programmable logic controllers (PLCs), while MQTT is employed for IoT sensors. Primary data aggregation and filtering is performed on edge devices (Raspberry Pi 4, NVIDIA Jetson Nano) to reduce the load on the central server [10, p. 45].

The Analytics Layer includes a data processing pipeline (ML Pipeline) implemented on the Python platform using scikit-learn, XGBoost, TensorFlow, and PyTorch libraries. Time series data is stored in the specialized InfluxDB database, while equipment metadata and analysis results are

maintained in PostgreSQL. The pipeline performs preprocessing (normalization, missing value imputation, feature extraction), model training, and inference in near-real-time mode.

Machine learning methods

The following algorithms were investigated as baseline models: linear regression (baseline), support vector regression (SVR), gradient boosting (XGBoost), LSTM recurrent neural network, and Transformer architecture. The selection of algorithms was driven by their widespread use in time series forecasting tasks and the availability of efficient open-source implementations [4, p. 112].

For the XGBoost model, the following input features were engineered: current equipment power, ambient temperature, day of week, hour of day, production shift type, current order volume, and lagged energy consumption values for the previous 1, 6, 12, and 24 hours. Model hyperparameters were optimized using Bayesian search (Optuna): $\text{max\_depth} = 8$, $\text{n\_estimators} = 500$, $\text{learning\_rate} = 0.05$, $\text{subsample} = 0.8$ [6, p. 87].

The LSTM model was implemented with two hidden layers of 128 neurons each, with an input sequence length of 168 (one week at hourly resolution). To prevent overfitting, dropout (0.3) and early stopping on the validation set were applied. Training was conducted using the Adam optimizer ($\text{lr} = 0.001$) for 100 epochs on an NVIDIA RTX 3080 GPU [7, p. 156].

The Transformer model was adapted for time series forecasting using positional encoding and a self-attention mechanism with 4 attention heads. The model dimension $\text{d\_model} = 64$, and the number of encoder layers is 3. This architecture effectively models long-range dependencies without the vanishing gradient problem [11, p. 234].

Experimental evaluation

The experimental evaluation of models was conducted on data from the Temirtau-Metal LLP metallurgical plant for the period January 2023 – December 2024. The dataset comprises 17,520 hourly records with 12 parameters. Data was split: 70% for training, 15% for validation, and 15% for testing. The following metrics were used for quality assessment: MAE, RMSE, MAPE, and the coefficient of determination R^2 . Results are presented in Table 2.

Table 2 – Comparative evaluation of energy consumption forecasting models

Method	MAE, kWh	RMSE, kWh	MAPE, %	R^2
ARIMA	56.2	71.5	8.4	0.78
Lin. Regression	48.3	62.7	7.1	0.81
SVR	35.1	47.2	5.3	0.88
XGBoost	21.6	29.4	3.2	0.94
LSTM	18.9	25.8	2.8	0.96
Transformer	17.4	24.1	2.6	0.97

As shown in Table 2, the Transformer model demonstrated the best results with a coefficient of determination $R^2 = 0.97$ and a mean absolute percentage error $\text{MAPE} = 2.6\%$. The LSTM model showed comparable results ($R^2 = 0.96$, $\text{MAPE} = 2.8\%$). The XGBoost ensemble approach, while slightly less accurate, provides significantly lower computational costs (inference time 2 ms versus 45 ms for Transformer), making it preferable for hard real-time systems [5, p. 203].

Additionally, a feature importance analysis was conducted for the XGBoost model. The greatest contributions to forecasting accuracy came from: lagged consumption values at 1 hour (23.4%), current production shift (18.7%), outdoor air temperature (14.2%), and day of the week

(11.8%). These results are consistent with the physical nature of the process and confirm the model's adequacy.

Anomaly detection module

In addition to load forecasting, the system integrates an anomaly detection module based on the Isolation Forest algorithm. The module analyzes deviations of actual consumption from predicted values and classifies them by severity: informational (10–20% deviation), warning (20–40%), and critical (over 40%). During the testing period, the module identified 47 anomalous events, of which 23 were confirmed as abnormal situations (heat exchanger malfunction, compressed air leaks, equipment running idle) [12, p. 67].

The anomaly detection accuracy was evaluated using precision (0.87) and recall (0.92) metrics, indicating high sensitivity with an acceptable level of false positives.

Implementation results

The AECMS was pilot-tested at the rolling mill section of Temirtau-Metal LLP over a 6-month period (July – December 2024). The main results are presented in Table 3.

Table 3 – Results of AECMS pilot implementation

Indicator	Before	After
Avg. monthly consumption, MWh	1,245	1,029
Consumption reduction, %	—	17.3%
Peak load, MW	4.8	3.9
Detected anomalies	Not recorded	23 confirmed
Economic effect, mln KZT/year	—	12.5

The AECMS implementation reduced average monthly energy consumption by 17.3% (from 1,245 to 1,029 MWh) without decreasing production output. Peak load decreased by 18.8%, enabling optimization of contractual terms with the energy provider. The total economic effect amounted to 12.5 million KZT annually, with an implementation cost of 8.2 million KZT, ensuring a payback period of less than 8 months.

An additional outcome was a reduction in CO₂ emissions by 186 tonnes per year, calculated using the IPCC methodology considering the carbon intensity of Kazakhstan's power generation (0.86 kg CO₂/kWh). This effect is particularly relevant in the context of Kazakhstan's commitments under the Paris Agreement and the functioning of the national emissions trading system [13, p. 45].

Conclusion

The developed automated energy consumption management system based on machine learning methods has demonstrated high effectiveness under real industrial conditions. The LSTM and Transformer models provided forecasting accuracy with MAPE below 3%, while the optimization module enabled a 17.3% reduction in energy consumption.

The scientific novelty of this work lies in the development of a comprehensive approach that integrates load forecasting, anomaly detection, and schedule optimization into a unified feedback system. The practical significance is confirmed by the results of pilot implementation at an industrial enterprise in Kazakhstan.

Promising directions for future development include: integration of reinforcement learning methods for adaptive control under changing production programs, application of

federated learning for protecting confidential enterprise data, and scaling the system for enterprise clusters within industrial zones [14, p. 312].

References:

1. National Energy Report of the Republic of Kazakhstan. – Astana: ME RK, 2024. – 156 p.
2. Siddiqui S.A., Ahmad M.W. Machine learning for energy management in smart grids // Energy Reports. – 2023. – Vol. 9. – P. 42–58.
3. International Energy Agency. Digitalization and Energy. – Paris: IEA, 2023. – 188 p.
4. Chen T., Guestrin C. XGBoost: A scalable tree boosting system // Proc. ACM SIGKDD. – 2016. – P. 785–794.
5. Zheng J., Xu C. Short-term load forecasting using LSTM recurrent neural network // IEEE TPWRS. – 2022. – Vol. 37(4). – P. 196–211.
6. Li B., Wu Z. Deep reinforcement learning for energy optimization in manufacturing // J. of Manufacturing Systems. – 2023. – Vol. 68. – P. 80–95.
7. Hochreiter S., Schmidhuber J. Long short-term memory // Neural Computation. – 1997. – Vol. 9(8). – P. 1735–1780.
8. Nurlanov B.K. Smart Grid technologies in Kazakhstan's power sector // NAS RK Bulletin. – 2023. – No. 4. – P. 30–42.
9. Alonso R.S., Prieto J. An IoT-based architecture for energy management // Sensors. – 2022. – Vol. 22(3). – P. 71–89.
10. Jenkins N. Internet of Things in Industry. – Moscow: DMK Press, 2022. – 340 p.
11. Vaswani A. et al. Attention is all you need // NeurIPS. – 2017. – P. 5998–6008.
12. Liu F.T. et al. Isolation Forest // Proc. IEEE ICDM. – 2008. – P. 413–422.
13. National report of the Republic of Kazakhstan under the Paris Agreement. – Astana, 2024. – 78 p.
14. Monostori L. et al. Cyber-physical systems in manufacturing // CIRP Annals. – 2016. – Vol. 65(2). – P. 621–641.

Automation of the Generation of Electronic Product Passports in Manufacturing Processes

Tileubek Nuraman

S.Utebayev Atyrau Oil and Gas University, Atyrau

Malikov Almas

S.Utebayev Atyrau Oil and Gas University, Atyrau

Abstract. This paper presents the development of a software module for automated electronic product passport (EPP) generation in machine-building enterprises. The regulatory framework of the Republic of Kazakhstan in the field of electronic product documentation was analyzed. An Event-Driven Architecture based on .NET 8 microservices with integration into MES, ERP, PDM, and SCADA systems was proposed. Hyperledger Fabric blockchain technology with SHA-256 hash storage was applied to ensure record immutability. System validation was conducted at Astana-Mashzavod LLP (September 2024 – February 2025): 342 electronic passports were generated. Passport generation time was reduced 18-fold, error rate decreased by 90.6%, and data completeness increased to 98.4%. The total annual economic effect amounted to 8.8 million KZT with a payback period of 9.3 months.

Keywords: *electronic product passport, documentation automation, event-driven architecture, MES, blockchain, digital transformation, Industry 4.0, Kazakhstan.*

The digital transformation of Kazakhstan's industrial sector within the framework of the "Digital Kazakhstan" state program and the "Industry 4.0" concept imposes fundamentally new requirements for product documentation and traceability at all lifecycle stages. An electronic product passport (EPP) is a structured digital document containing comprehensive information about materials, technological operations, quality control results, and product certification [1, p. 34].

According to the Committee for Industrial Development of the Ministry of Industry and Construction of the Republic of Kazakhstan, over 65% of machine-building enterprises in Kazakhstan still use paper-based workflows for product passport generation [2, p. 15]. Manual generation of a passport for a medium-complexity product takes 4 to 8 hours, with a data entry error rate reaching 12–15%, creating significant risks for product quality and safety assurance [3, p. 56].

International experience demonstrates the high effectiveness of EPP generation automation. Companies such as Siemens, Bosch, and Toyota have implemented Digital Thread systems that automatically generate digital passports at each stage of the manufacturing process [4, p. 89]. However, direct adoption of these solutions is complicated by differences in regulatory frameworks, production processes, and the digital maturity level of domestic enterprises.

The objective of this research is to develop a software module for automated electronic product passport generation, integrated with the enterprise's Manufacturing Execution System (MES) and compliant with the national standards of the Republic of Kazakhstan.

To achieve this objective, the following tasks were defined: analysis of regulatory requirements for electronic product passports, design of an EPP information model, development of a software module using event-driven architecture, and system validation under real enterprise conditions.

Regulatory framework and EPP requirements

The generation of electronic product passports in Kazakhstan is regulated by a number of national and interstate standards. The fundamental standard is ST RK GOST R 2.611-2011 "Electronic Product Passport. General Provisions," which establishes the structure, completion rules, and storage requirements for EPPs [1, p. 34]. Additionally, the requirements of ST RK ISO 10303 (STEP) for product data exchange and ST RK ISO 8000 for data quality assurance are applied [5, p. 112].

Analysis of the regulatory framework enabled the formulation of key requirements for the system under development: ensuring data completeness and reliability, record immutability (auditability), support for electronic digital signatures (EDS), integration with existing enterprise information systems, and compliance with information security requirements [6, p. 78]. The EPP structure is presented in Table 1.

Table 1 – Electronic product passport structure

Section	Content	Data Source	Format
Identification	Serial number, drawing designation, revision, BOM	PDM/CAD	XML, STEP AP242
Materials	Grade, batch, supplier, quality certificate, incoming inspection	ERP system	JSON, PDF
Technology	Routing, operations, processing parameters, time, operator	MES/SCADA	JSON, OPC UA
Quality Control	Measurements, tolerances, CMM protocols, QC reports	QC Dept., CMM	JSON, QIF
Certification	Acceptance acts, certificates, declarations of conformity	QMS	PDF, EDS
Operation	Service hours, maintenance, repairs, warranty claims	CMMS/EAM	JSON, REST API

Software module architecture

The proposed system is based on Event-Driven Architecture (EDA), in which each technological operation generates an event that is automatically recorded in the electronic passport. The use of EDA ensures loose coupling of components, high scalability, and the ability to asynchronously process data from multiple sources [7, p. 92].

The software module is implemented on the .NET 8 platform using microservices architecture. The main components include: Event Collector (receiving events from production systems), Event Processor (validation, enrichment, and routing of events), Passport Service (EPP generation and storage), Integration Gateway (interaction with external systems), and Web Dashboard (visualization and management). PostgreSQL with JSONB document support is used for data storage, providing flexibility in passport structure for different product types [8, p. 145].

Integration with existing enterprise information systems is achieved through REST API (for ERP, PDM, QMS) and the OPC UA protocol (for communication with SCADA and industrial equipment). Apache Kafka message broker is used for inter-microservice communication, ensuring guaranteed delivery and chronological event ordering.

A key feature of the system is blockchain technology support for ensuring EPP record immutability. The SHA-256 hash of each record is stored in a private Hyperledger Fabric blockchain, preventing unauthorized data modification and ensuring the legal validity of the electronic passport [9, p. 210]. This mechanism is critical for products subject to mandatory certification under EAEU technical regulations.

EPP generation algorithm

The automated electronic passport generation process comprises the following stages. During initialization, when a production order is launched, the system creates an empty EPP instance, populating the identification section with data from the PDM system (product designation, drawing number, revision, BOM). Subsequently, during incoming inspection, when materials arrive at the warehouse, the ERP system generates an event containing data on the material grade, batch number, supplier, and incoming inspection results [3, p. 56].

During the production cycle, each technological operation is automatically recorded in the EPP. The MES system transmits data on operation start and completion, the operator, equipment used, and actual processing parameters. The SCADA system records critical process parameters (temperature, pressure, speed) linked to the specific product. At the quality control stage, measurement results from coordinate measuring machines (CMMs) are automatically uploaded to the EPP in QIF (Quality Information Framework) format [10, p. 167].

At the final stage, the system generates a summary report, verifies the completeness of all sections, and signs the electronic passport using the responsible person's electronic digital signature. The completed EPP is saved in long-term storage and is accessible through a web interface to all authorized users.

Validation results

System validation was conducted at the Astana-Mashzavod LLP machine-building enterprise during the period September 2024 – February 2025. As part of the pilot project, the system was integrated with the 1C:ERP system, Kompas-3D PDM system, and Wonderware InTouch SCADA system. A total of 342 electronic passports were generated for products from three standard nomenclature groups. Results are presented in Table 2.

Table 2 – Comparative indicators before and after EPP system implementation

Indicator	Before	After
Passport generation time	4–6 hours	15–20 min
Number of errors (per month)	32	3
Data completeness	67%	98.4%
Information retrieval time	25–40 min	< 1 min
Traceability	Partial (42%)	Full (100%)
QMS audit preparation time	3–5 days	2–4 hours

The validation results confirmed the high effectiveness of the developed solution. The passport generation time was reduced by an average factor of 18 — from 4–6 hours to 15–20 minutes (the residual time is due to the need for manual entry of visual inspection results). The

number of errors decreased by 90.6% — from 32 to 3 per month, with the remaining errors related to incorrect data entry by operators at stations not yet connected to SCADA [11, p. 178].

Data completeness increased from 67% to 98.4%, and information retrieval time for a specific product was reduced from 25–40 minutes (searching paper archives) to less than 1 minute. A particularly significant result was the reduction in QMS audit preparation time from 3–5 working days to 2–4 hours, enabled by instant access to the complete manufacturing history of each product.

The economic evaluation of the project is presented in Table 3.

Table 3 – Economic indicators of EPP system implementation

Indicator	Value
Development and implementation cost	6.8 mln KZT
Annual labor cost savings	4.2 mln KZT
Defect loss reduction (early detection)	3.1 mln KZT
Documentation non-compliance penalties reduction	1.5 mln KZT
Total annual effect	8.8 mln KZT
Payback period	9.3 months

The total annual economic effect amounted to 8.8 million KZT, including labor cost savings (4.2 million KZT), reduction in defect-related losses through early deviation detection (3.1 million KZT), and reduction in documentation non-compliance penalties (1.5 million KZT). With a development and implementation cost of 6.8 million KZT, the payback period is 9.3 months.

It is also worth noting the intangible benefits of implementation: improved production culture, enhanced inter-departmental interaction, and the creation of a knowledge base on manufacturing processes. EPP data can be used for machine learning models to predict defects, creating a foundation for transitioning to predictive quality management [12, p. 245].

Conclusion

The developed software module for automated electronic product passport generation has demonstrated high effectiveness under real production conditions. The application of event-driven architecture ensured seamless integration with existing enterprise information systems, while blockchain technology guaranteed the immutability and legal validity of EPP records.

The scientific novelty of this work lies in the development of an electronic product passport information model adapted to the requirements of the national standards of the Republic of Kazakhstan, as well as the application of event-driven architecture for real-time EPP generation automation. The practical significance is confirmed by the results of pilot implementation at a machine-building enterprise.

Promising directions for future development include: system integration with digital twins for modeling product behavior during operation, application of machine learning methods for automatic anomaly detection in process data, and functionality expansion to support the full product lifecycle — from design to disposal [13, p. 198].

References:

1. ST RK GOST R 2.611-2011. Electronic Product Passport. General Provisions. – Astana: KazStandard, 2012. – 24 p.
2. Report of the Committee for Industrial Development of the RK. – Astana: MICS RK, 2024. – 98 p.
3. Kulikov D.D., Grafodatsky O.S. Automation of technical documentation preparation // STIN. – 2022. – No. 8. – P. 52–61.
4. Stark J. Digital Transformation of Industry. – Berlin: Springer, 2022. – 284 p.
5. ISO 10303-242:2020. Industrial automation systems and integration – STEP. – Geneva: ISO, 2020. – 312 p.
6. Yerzhanov A.K. Information security requirements at Kazakhstan enterprises // NAS RK Bulletin. – 2023. – No. 2. – P. 72–86.
7. Kletti J. Manufacturing Execution Systems – MES. – Berlin: Springer, 2021. – 312 p.
8. Grigoriev S.N., Martinov G.M. ARM-based multi-channel CNC system // Mechatronics. – 2023. – Vol. 46. – P. 140–155.
9. Saberi S., Kouhizadeh M. Blockchain and supply chain management // Int. J. Production Research. – 2022. – Vol. 60(7). – P. 2058–2076.
10. Herron J. Quality Information Framework (QIF) overview // NIST, 2023. – 45 p.
11. Borisov V.V. Digital product passport in QMS // Quality and Life. – 2023. – No. 2. – P. 170–184.
12. Tao F. et al. Digital twin-driven product design, manufacturing and service // Int. J. Adv. Manufacturing Technology. – 2023. – Vol. 94. – P. 3563–3576.
13. Monostori L. et al. Cyber-physical systems in manufacturing // CIRP Annals. – 2016. – Vol. 65(2). – P. 621–641.

Scientific supervisor – Associate Professor Iskakova Sandugash

UOT: 004.056

BÖYÜK VERİLƏNLƏR TEKNOLOGİYALARININ MÜƏSSSƏ İNFORMASIYA TƏHLÜKƏSİZLİYİNİN İDARƏ EDİLMƏSİNDƏ TƏTBİQİ

Leyla Əhmədova Emin qızı

ORCID kodu: 0009-0006-3345-625X, Azərbaycan Dövlət iqtisad Universiteti, Azərbaycan

Xülasə

Bu tədqiqat müəssisə informasiya təhlükəsizliyi idarəetməsinin gücləndirilməsində böyük məlumat texnologiyalarının tətbiqini araşdırır. Tədqiqat ISO/IEC 27005 və NIST Kibertəhlükəsizlik Çərçivəsi kimi ənənəvi çərçivələrin dəyərli risk idarəetmə strukturları təmin etdiyini, lakin real vaxt analitikası və genişmiqyaslı məlumat mühitləri ilə işləyərkən məhdudiyyətlərlə qarşılaşa biləcəyini vurğulayır. Buna görə də, müasir kibertəhdidlərin daha effektiv şəkildə aşkarlanması və qarşısının alınması üçün böyük məlumat texnologiyalarının informasiya təhlükəsizliyi idarəetmə sistemlərinə integrasiyası vacib hala gəlir.

Tədqiqatın elmi yeniliyi müəssisə informasiya təhlükəsizliyinin idarə edilməsi üçün xüsusi olaraq hazırlanmış böyük məlumatlara əsaslanan arxitekturanın hazırlanmasındadır. Təklif olunan çərçivə Hadoop ekosisteminə əsaslanır və dörd əsas mərhələdən ibarətdir: məlumatların toplanması, məlumatların saxlanması, məlumatların emalı və məlumatların təhlili.

Tədqiqat həmçinin sistem qeydləri, şəbəkə trafik qeydləri, istifadəçi davranış məlumatları və xarici təhdid kəşfiyyatı da daxil olmaqla birdən çox məlumat mənbəyini birləşdirən informasiya təhlükəsizliyi idarəetmə modelini təklif edir. Məlumatların əvvəlcədən işlənməsi, xüsusiyyətlərin çıxarılması və maşın öyrənmə üsulları vasitəsilə sistem anomal nümunələri və potensial kibertəhdidləri aşkar edə bilər.

Tədqiqat təhlükəsizlik hadisələrini təsnif etmək və təhdidlərin aşkarlanması dəqiqliyini artırmaq üçün Dəstək Vektor Maşını (SVM) və Təsadüfi Meşə (RF) alqoritmlərindən istifadə edir. Bu tədqiqatın praktik əhəmiyyəti müəssisə təhlükəsizliyinin monitorinqini gücləndirmək, kibertəhdidlərin erkən aşkarlanmasına imkan vermək və daha sürətli hadisələrə cavab verməyi dəstəkləmək qabiliyyətindədir. Böyük verilənlər analitikası və maşın öyrənməsindən istifadə edən təklif olunan çərçivə təşkilatlara müasir rəqəmsal mühitlərin problemlərini həll edə bilən genişlənən və ağıllı təhlükəsizlik idarəetmə həlli təqdim edir.

Açar sözlər: *Böyük verilənlər texnologiyası, informasiya təhlükəsizliyinin idarə edilməsi, kibertəhlükəsizlik, Hadoop ekosistemi, şəbəkə təhdidlərinin aşkarlanması, risklərin idarə edilməsi*

Giriş

Qloballaşma və informasiya proseslərinin dərinləşdiyi müasir dövrdə müxtəlif sahələr sürətlə rəqəmsallaşma istiqamətinə integrasiya olunur. Rəqabət qabiliyyətini qorumaq məqsədilə müəssisələr rəqəmsal transformasiya prosesini sürətləndirərək istehsal, əməliyyatlar, satış, müştəri xidməti və digər fəaliyyət istiqamətlərinin daha səmərəli və integrasiya olunmuş şəkildə idarə olunmasına nail olurlar. Bu proses nəticəsində biznes məlumatları, istifadəçi informasiyaları və digər mühüm rəqəmsal aktivlər kiber məkanda böyük sürətlə dövriyyəyə daxil olur və nəticədə misli görünməmiş həcmdə məlumat axını yaranır.

Bununla yanaşı, informasiya təhlükəsizliyi ilə bağlı problemlər də getdikcə daha çox diqqət mərkəzinə çıxır. Kiber hücum üsulları daim yenilənir və inkişaf edir ki, bu da müəssisələrin əsas informasiya aktivləri üçün ciddi risklər yaradır. Statistik məlumatlar göstərir ki, informasiya təhlükəsizliyi insidentləri hər il böyük iqtisadi itkilərə səbəb olur. Bundan əlavə, belə hadisələr etimadın azalması, hüquqi mübahisələrin yaranması və brend nüfuzunun zədələnməsi kimi ardıcıl problemlərə də yol açır.

Belə mürəkkəb təhlükəsizlik şəraitində ənənəvi informasiya təhlükəsizliyi idarəetmə sistemləri və texniki həllər böyük həcmli məlumatların və dinamik dəyişən təhlükələrin qarşısını almaqda artıq kifayət qədər effektiv hesab edilmir. Məhz bu nöqtədə böyük verilənlər texnologiyası ön plana çıxır. Bu texnologiya geniş miqyaslı məlumatların toplanması, saxlanması, emalı və ağıllı şəkildə təhlil olunması imkanları sayəsində təhlükə nümunələrini daha dərinlən anlamağa, potensial riskləri əvvəlcədən müəyyən etməyə və vaxtında tədbir görməyə şərait yaradır.


Xüsusilə müəssisələrin informasiya təhlükəsizliyi sahəsində böyük verilənlər texnologiyası müdafiə mexanizmlərinin gücləndirilməsinə əhəmiyyətli töhfə verir. Şəbəkə trafiki, sistem jurnalları və istifadəçi davranışları kimi müxtəlif məlumat mənbələrinin inteqrasiyası və təhlili vasitəsilə potensial təhlükələr real vaxt rejimində izlənilir, dəqiq müəyyən edilər və erkən xəbərdarlıq sistemi qurula bilər. Bu isə müəssisələrdə informasiya təhlükəsizliyinə yanaşmanı və onun idarə olunması metodlarını köklü şəkildə dəyişər bilər. Bununla belə, böyük verilənlər texnologiyasının mövcud informasiya təhlükəsizliyi idarəetmə sistemləri ilə necə səmərəli şəkildə inteqrasiya olunacağı və həm böyük verilənlər dövrünün xüsusiyyətlərini nəzərə alan, həm də müəssisələrin fərdi ehtiyaclarına uyğun yeni təhlükəsizlik idarəetmə arxitekturasının necə formalaşdırılacağı həm nəzəri, həm də praktiki baxımdan mühüm və çətin vəzifə olaraq qalır.

Metodologiya

Son illərdə informasiya təhlükəsizliyi sahəsində risklərin idarə olunması getdikcə daha böyük əhəmiyyət qazanmış və bu istiqamətdə müəssisələr üçün müxtəlif beynəlxalq standart və çərçivələr hazırlanmışdır. Məsələn, ISO/IEC 27005 standartı informasiya təhlükəsizliyi risklərinin idarə olunmasına yönəlib və risklərin müəyyən edilməsi, qiymətləndirilməsi, idarə olunması və monitorinqi kimi mərhələləri əhatə edir. Lakin bu standartın tətbiqi əsasən insan qərarlarına və statik qiymətləndirmə üsullarına əsaslandığından böyük və dinamik məlumat mühitində effektivliyi məhdud ola bilər.

Digər tərəfdən, NIST Cybersecurity Framework “Müəyyən et (Identify), Qoru (Protect), Aşkar et (Detect), Cavab ver (Respond), Bərpa et (Recover)” mərhələlərinə əsaslanan təhlükəsizlik idarəetmə modeli təqdim edir və risklərin aşkarlanması və cavab mexanizmlərinə xüsusi diqqət yetirir. Bununla belə, bu çərçivə də böyük həcmli məlumatların real vaxt rejimində emalı və dinamik optimallaşdırma imkanları baxımından müəyyən məhdudiyyətlərə malikdir (Attaran M., 2023).

Böyük verilənlər texnologiyasının (BDT) çərçivəsi böyük həcmli məlumatların emalı üçün istifadə olunan alətlər və texnologiyalar toplusudur. Bu tədqiqat çərçivəsində Hadoop ekosisteminə əsaslanan kompleks bir böyük verilənlər arxitekturası qurulmuşdur. Bu arxitektura bir-biri ilə əlaqəli və mərhələli şəkildə işləyən dörd əsas komponentdən ibarətdir və əsas məqsədi təhlükəsizliklə əlaqəli geniş həcmli məlumatların səmərəli idarə olunması və ağıllı analizini təmin etməkdir. Arxitekturanın ümumi quruluşu Şəkil 1-də təqdim olunur.



Şəkil 1. Böyük verilənlər texnologiyasının arxitekturası (Fang S. və b., 2023)

Şəkil 1-də məlumatların toplanması mərhələsində paylanmış log toplama sisteminin qurulması göstərilir. Bu sistem real vaxt rejimində işləyən məlumat axını rolunu oynayır və müəssisə daxilindəki müxtəlif informasiya sistemlərindən, şəbəkə avadanlıqlarından, server jurnallarından və digər təhlükəsizlik qurğularından təhlükəsizlik hadisələrinə aid ilkin məlumatları davamlı şəkildə toplayaraq ötürür.

Məlumatların saxlanması mərhələsində isə Hadoop Distributed File System (HDFS) əsas paylanmış yaddaş infrastrukturunu kimi seçilmişdir. HDFS böyük həcmli məlumatların saxlanmasını təmin etməklə yanaşı, ehtiyat nüsxələmə mexanizmi vasitəsilə məlumatların əlçatanlığını və etibarlılığını artırır. Bundan əlavə, mürəkkəb strukturlu, yarı-strukturlaşdırılmış və strukturlaşdırılmamış məlumatların idarə olunması üçün NoSQL verilənlər bazalarından istifadə edilir. Onların çevik məlumat modeli və sütun-ailə (column-family) əsaslı saxlanma xüsusiyyətləri müxtəlif tətbiq ssenarilərində məlumatların effektiv idarə olunmasına imkan yaradır (Soltani Delgosha M. və b. 2021).

Məlumatların emalı mərhələsində fərqli biznes tələblərini qarşılamaq üçün iki əsas texnoloji yanaşmadan istifadə olunur. Bir tərəfdən, klassik MapReduce proqramlaşdırma modeli toplu (batch) emal tapşırıqları üçün tətbiq edilir. Bu model böyük məlumat dəstlərini müstəqil alt-tapşırıqlara bölərək klaster mühitində paralel şəkildə məlumatların təmizlənməsi, transformasiyası və ilkin analizi üçün effektiv imkan yaradır. Digər tərəfdən isə real vaxt və aşağı gecikmə tələb edən ssenarilər üçün Apache Spark platforması tətbiq edilir ki, bu da təhlükəsizlik hadisələrinin dinamik təhlilini və operativ reaksiyanı təmin edir.


Son mərhələ olan məlumatların analizi mərhələsində təhlükəsizlik risklərinin gizli nümunələrini aşkar etmək üçün müxtəlif qabaqcıl alətlərdən istifadə olunur. Məsələn, Apache Hive emal olunmuş məlumatlar üzərində SQL-ə bənzər sorğu interfeysi təqdim edərək statistik analizlərin aparılmasına və böyük məlumat dəstləri daxilində gizlənmiş tendensiyaların müəyyən edilməsinə kömək edir. Eyni zamanda Apache Pig yüksək səviyyəli məlumat axını dili təqdim etməklə böyük məlumat emalı skriptlərinin yazılmasını və icrasını sadələşdirir (Aguboshim F. C. və b, 2023).

Bundan əlavə, Spark platformasının MLlib kitabxanası və Mahout kimi alətlər vasitəsilə əvvəlcədən emal olunmuş məlumatlar üzərində maşın öyrənməsi və dərin öyrənmə modelləri qurulur. Bu yanaşma təhlükələrin aşkarlanması və proqnozlaşdırılması üçün daha dəqiq modellərin yaradılmasına imkan verir və nəticədə şəbəkə təhlükəsizliyi risklərinin müəyyən edilməsi və qarşısının alınması imkanlarını əhəmiyyətli dərəcədə gücləndirir.

Beləliklə, BDT əsaslı bu çərçivə müəssisələrə böyük həcmli məlumatları effektiv şəkildə emal etməyə və təhlil etməyə imkan verir. Nəticədə informasiya təhlükəsizliyi idarəetməsində real vaxt

monitorinqi, təhlükə barədə erkən xəbərdarlıq və sürətli reaksiyanın təmin olunması mümkün olur (Alomari E. və b., 2023).

BDT çərçivəsinin müəssisələrdə informasiya təhlükəsizliyinin idarə olunmasını necə dəstəklədiyini daha dərinlən anlamaq üçün informasiya təhlükəsizliyi idarəetmə modelinin arxitekturası ətraflı şəkildə təhlil edilir. Bu model müəssisələrdə təhlükəsizlik səviyyəsini yüksəltmək məqsədilə böyük verilənlər texnologiyasından istifadə edir və əsasən real vaxt monitorinqi, anormal davranışların aşkarlanması və risklərin proqnozlaşdırılması kimi mexanizmlər üzərində qurulmuşdur. Modelin ümumi quruluşu Şəkil 2-də göstərilmişdir. Bu arxitektura risklərin müəyyən edilməsi və xüsusiyyətlərin çıxarılması əsas elementlər hesab olunur. Bu proseslər məlumat və emal qatları boyunca fəaliyyət göstərərək çoxsaylı məlumat mənbələrinin integrasiyası və ağıllı analizi vasitəsilə sonrakı təhlükəsizlik idarəetməsi üçün güclü əsas yaradır.



Şəkil 2. ISM modelinin arxitekturası (Li L., 2022).

Şəkil 2-də göstərilirdiyi kimi, sistem qatları arasında məlumat axını və geribildirim mexanizmi vasitəsilə qapalı dövr (closed-loop) formalaşır. Yuxarı səviyyədə yerləşən idarəetmə qatları aşağı qatlarda toplanan məlumatlara və aparılan analiz nəticələrinə əsaslanaraq bütün təhlükəsizlik idarəetmə prosesini yönləndirir. Təhlükələrin aşkarlanmasını dəstəkləmək üçün bu tədqiqatda müxtəlif məlumat mənbələrindən istifadə olunur. Bunlara sistem jurnalları, şəbəkə trafik qeydləri, istifadəçi davranış məlumatları və xarici təhlükə kəşfiyyatı daxildir.

1) Sistem jurnalları (System logs)

Əməliyyat sistemləri, tətbiqlər və verilənlər bazaları tərəfindən yaradılan log məlumatları sistem fəaliyyətinin real vaxt rejimində izlənməsi və təhlili üçün istifadə olunur. Bu məlumatlar qeyri-adi davranışları və mümkün təhlükəsizlik boşluqlarını aşkar etməyə kömək edir. Məsələn, qanunsuz giriş cəhdləri və icazəsiz sistem istifadəsi kimi hadisələr log məlumatlarında erkən xəbərdarlıq siqnalları kimi görünə bilər (George A. S., 2023).

2) Şəbəkə trafik qeydləri (Network traffic records)

Şəbəkə trafiki üzərindən daxil olan və çıxan məlumat paketləri real vaxt rejimində izlənilir və təhlil edilir. Bu zaman xüsusilə qeyri-adi trafik nümunələrinə və məlumat ötürmə davranışlarına diqqət yetirilir. Bu analiz potensial DDoS hücumlarının, şəbəkə skanlarının və digər zərərli fəaliyyətlərin müəyyən edilməsinə kömək edir. Trafik məlumatlarının xüsusiyyət analizi və davranış tanınması vasitəsilə şəbəkə səviyyəsində təhlükələrin aşkar edilməsi mümkün olur.

3) İstifadəçi davranış məlumatları (User behavior data)

İstifadəçi girişləri, giriş icazələrində dəyişikliklər və fayl əməliyyatları kimi fəaliyyətlər təhlil edilərək hesablarla bağlı anomaliyalar müəyyən edilir. Bu məlumatlar istifadəçilərin icazələrdən sui-istifadə edib-etmədiyini, qeyri-adi girişlərin olub-olmadığını və digər şübhəli davranışları müəyyən etməyə imkan verir. Davranış analizi modelləri vasitəsilə sistem daxilində mövcud ola biləcək daxili təhlükələr də aşkar edilə bilər.

4) Xarici təhlükə kəşfiyyatı (External threat intelligence)

Bu məlumatlar ən son təhlükəsizlik boşluqları, zərərli hücum üsulları və onların nümunələri haqqında məlumatları əhatə edir. Bu məlumatların daxili sistem məlumatları ilə birlikdə təhlili daha geniş miqyaslı təhlükə aşkarlanmasına imkan yaradır və təhlükələrin müəyyən edilməsinin dəqiqliyini və operativliyini artırır (Sánchez-Zas C., 2023).

Bu çoxölçülü məlumatlar paylanmış məlumat toplama infrastrukturuna vasitəsilə birləşdirilərək sistemin ümumi fəaliyyət vəziyyətinin tam şəkildə izlənməsinə imkan yaradır. Nəticədə məlumatların vaxtında əldə olunması və bütövlüyü təmin edilir və təhlükəsizlik idarəetmə prosesləri üçün etibarlı analitik əsas formalaşır.

Emal qatının məlumatların ilkin hazırlanması (data preprocessing) alt səviyyəsində ilk addım xam məlumatların təmizlənməsi və optimallaşdırılmasıdır. Bu mərhələnin məqsədi məlumatları sonrakı analiz prosesləri üçün daha uyğun vəziyyətə gətirməkdir. Məlumatların ilkin emalı bir neçə mərhələni əhatə edir. İlk olaraq təhlükəsizlik hadisələri ilə əlaqəsi olmayan artıq və təkrarlanan məlumatlar filtrasiya edilərək çıxarılır və beləliklə modelin analiz nəticələrinə təsir edən məlumat səs-küyü azaldılır. Daha sonra məlumatlarda mövcud olan lazımsız dəyişkənlikləri aradan qaldırmaq üçün denoising üsullarından istifadə edilir ki, bu da məlumat keyfiyyətinin sabitliyini təmin edir və sonrakı analizlərin dəqiqliyini artırır. Bundan əlavə, ilkin emal prosesində məlumatların format çevrilməsi və standartlaşdırılması da həyata keçirilir. Bu addım müxtəlif mənbələrdən əldə olunan məlumatların daha rahat integrasiyasına imkan yaradır. Standartlaşdırılmış məlumatlar müəyyən struktura və ya formata salınaraq müxtəlif modellər və alqoritmlər üçün daha uyğun hala gətirilir və beləliklə çoxmənbəli məlumatların uyğunluğu təmin edilir (Vadhil F. A., 2021).

İlkin emal tamamlandıqdan sonra məlumatlar xüsusiyyətlərin çıxarılması (feature extraction) alt səviyyəsinə ötürülür. Bu mərhələdə sistem təhlükəsizlik təhdidlərinin müəyyən edilməsi üçün əhəmiyyətli olan xüsusiyyətləri emal olunmuş məlumatlardan çıxarır. Bu xüsusiyyətlərə istifadəçilərin giriş davranışındakı anomaliyalar, giriş tezliyindəki dəyişikliklər və resurslara müraciət nümunələrindəki qeyri-adi hallar kimi göstəricilər daxildir. Belə göstəricilər sistem fəaliyyətində mövcud ola biləcək potensial təhlükələr barədə məlumat verə bilər. Məsələn, istifadəçinin qeyri-adi vaxtda və ya fərqli məkandan sistmə daxil olması hesabın icazəsiz istifadəsinə işarə edə bilər. Eyni şəkildə resurslara çoxsaylı və ardıcıl sorğuların göndərilməsi sistemin skan edilməsi və ya sızma cəhdlərinin göstəricisi ola bilər. Xüsusiyyətlərin çıxarılması prosesi böyük həcmli xam məlumatlar içərisindən dəyərli təhlükəsizlik göstəricilərini müəyyən etməklə modelin potensial təhlükələri daha dəqiq aşkar etməsinə kömək edir (Bandari V., 2023).

Xüsusiyyətlərin müəyyən edilməsindən sonra proses modelin öyrədilməsi və qiymətləndirilməsi mərhələsinə keçir. Bu mərhələdə təhlükəsizlik təhdidlərini aşkar etmək üçün maşın öyrənməsi və məlumatların analizi üsullarından istifadə edilərək modellər qurulur. Araşdırmada iki əsas alqoritm tətbiq edilmişdir: Support Vector Machine (SVM) və Random Forest (RF). SVM nəzarətli öyrənmə alqoritmidir və xüsusilə yüksək ölçülü məlumatların təsnifatı üçün effektiv hesab olunur. Bu tədqiqatda SVM əsas təsnifatçı kimi istifadə edilmişdir. Alqoritmin əsas ideyası normal və qeyri-normal davranışları (yəni potensial təhlükələri) bir-birindən ayırmaq üçün optimal hiper müstəvinin müəyyən edilməsidir. Qeyri-xətti hallarda isə kernel funksiyaları vasitəsilə məlumatlar daha yüksək ölçülü məkanlara proyeksiya edilərək ayırma prosesi həyata keçirilir. SVM-in üstünlüyü yüksək ölçülü məlumatlarla işləmə qabiliyyəti və güclü ümumiləşdirmə imkanlarıdır. Təlim mərhələsində sistem jurnalları və şəbəkə trafik qeydləri kimi tarixi

məlumatlardan istifadə edilərək təhlükəsizlik hadisələrinin xüsusiyyətləri öyrənilir və nəticədə təsnifat modeli formalaşdırılır. Hazırlanmış SVM modeli yeni daxil olan məlumatlar əsasında potensial təhlükələri operativ şəkildə müəyyən edə bilir.

RF isə ansambl öyrənmə üsuluna əsaslanan bir alqoritmdir və çoxsaylı qərar ağaclarının qurulması ilə işləyir. Son nəticə isə bu ağacların səsvermə mexanizmi əsasında müəyyən edilir. Bu tədqiqatda RF modeli sistemin dayanıqlığını artırmaq və təhlükəsizlik hadisələrinə aid çoxsaylı xüsusiyyətlər arasından ən informativ olanları seçmək üçün tətbiq edilmişdir. RF alqoritmi böyük məlumat dəstləri ilə işləməkdə xüsusilə effektivdir və səs-küylü və ya artıq xüsusiyyətlərin mövcud olduğu hallarda belə yaxşı nəticə verir. Eyni zamanda bir neçə qərar ağacının nəticələrinin birləşdirilməsi overfitting probleminin qarşısını almağa kömək edir. Təsadüfi nümunə seçimi və xüsusiyyətlərin seçilməsi kimi proseslər vasitəsilə RF yüksək ölçülü və mürəkkəb təhlükəsizlik məlumatları içərisindən təhlükə identifikasiyası üçün faydalı olan informasiyanı effektiv şəkildə müəyyən edə bilir (Singh R. K., 2021).

Nəticə

Nəticələr göstərir ki, böyük verilənlər texnologiyalarının istifadəsi informasiya təhlükəsizliyi monitorinqinin, risklərin müəyyənəşdirilməsinin və hadisələrə cavab vermənin səmərəliliyini əhəmiyyətli dərəcədə artırır. Təklif olunan arxitektura təşkilatlara heterojen verilənlər mənbələrini emal etməyə, gizli təhdid nümunələrini aşkar etməyə və proaktiv təhlükəsizlik qərar qəbul etmə proseslərini dəstəkləməyə imkan verir. Buna görə də, böyük verilənlər analitikasının və maşın öyrənməsinin informasiya təhlükəsizliyi idarəetmə sistemlərinə integrasiyası müəssisələrə müasir kibertəhlükəsizlik problemlərini həll etmək üçün daha uyğunlaşa bilən və miqyaslı bilən bir yanaşma təqdim edə bilər.

İstifadə edilmiş ədəbiyyat siyahısı

1. Aguboshim, F. C., Obiokafor, I. N. & Emenike, A. O. (2023). Sustainable data governance in the era of global data security challenges in Nigeria: a narrative review[J]. World J. Adv. Res. Reviews. 17 (2), 378–385.
2. Alomari, E., Katib, I., Mehmood, R., & Iktishaf (2023). A big data road-traffic event detection tool using Twitter and Spark machine learning. Mobile Networks and Applications, 28(2), 603–618.
3. Attaran, M. (2023).The impact of 5G on the evolution of intelligent automation and industry digitization[J]. J. Ambient Intell. Humaniz. Comput. 14 (5), 5977–5993.
4. Bandari, V. (2023). Enterprise data security measures: A comparative review of effectiveness and risks across different industries and organization types. International Journal of Business Intelligence and Big Data Analytics, 6(1), 1–11.
5. Fang, S., Moreno Brenes, A., Brusoni, S. (2023).Technology Intelligence and Digitalization in the Manufacturing Industry[J]. ResearchTechnology Manage. 66 (5), 22–33.
6. George, A. S. (2023). Securing the future of finance: How AI, blockchain, and machine learning safeguard emerging neobank technology against evolving cyber threats. Partners Universal Innovative Research Publication, 1(1), 54–66.
7. Li, L. (2022). Big data and big disaster: A mechanism of supply chain risk management in the global logistics industry. International Journal of Operations & Production Management, 43(2), 274–307.
8. Sánchez-Zas, C. (2023). Ontology-based approach to real-time risk management and cyber-situational awareness. Future Generation Computer Systems, 141, 462–472.
9. Singh, R. K., et al. (2021). Strategic issues of big data analytics applications in supply chain management. Journal of Big Data, 8(1), 1–25.

10. Soltani Delgosha, M., Hajiheydari, N., Fahimi, S. M. (2021). Elucidation of big data analytics in banking: a four-stage Delphi study[J]. J. Enterp. Inform. Manage. 34 (6), 1577–1596.
11. Vadhil, F. A., Nanne, M. F., & Salihi, M. L. (2021). Importance of machine learning techniques to improve open source intrusion detection systems. Indonesian Journal of Electrical Engineering and Informatics (IJEI), 9(3), 774–783.

Abstract

This study explores the application of big data technologies in strengthening enterprise information security management. The study highlights that traditional frameworks such as ISO/IEC 27005 and the NIST Cybersecurity Framework provide valuable risk management structures, but may face limitations when dealing with real-time analytics and large-scale data environments. Therefore, it becomes essential to integrate big data technologies into information security management systems to more effectively detect and prevent modern cyber threats.

The scientific novelty of the study lies in the development of a big data-based architecture specifically designed for enterprise information security management. The proposed framework is based on the Hadoop ecosystem and consists of four main stages: data collection, data storage, data processing, and data analysis.

The study also proposes an information security management model that integrates multiple data sources, including system logs, network traffic logs, user behavior data, and external threat intelligence. Through data preprocessing, feature extraction, and machine learning techniques, the system is able to detect anomalous patterns and potential cyber threats.

The study uses Support Vector Machine (SVM) and Random Forest (RF) algorithms to classify security events and improve threat detection accuracy. The practical significance of this research lies in its ability to enhance enterprise security monitoring, enable early detection of cyber threats, and support faster incident response. The proposed framework, which uses big data analytics and machine learning, provides organizations with a scalable and intelligent security management solution that can address the challenges of modern digital environments.

Keywords: *Big data technology, information security management, cybersecurity, Hadoop ecosystem, network threat detection, risk management*

Аннотация

В данном исследовании рассматривается применение технологий больших данных для усиления управления информационной безопасностью предприятий. Исследование подчеркивает, что традиционные структуры, такие как ISO/IEC 27005 и NIST Cybersecurity Framework, предоставляют ценные инструменты управления рисками, но могут сталкиваться с ограничениями при работе с аналитикой в реальном времени и крупномасштабными средами данных. Поэтому интеграция технологий больших данных в системы управления информационной безопасностью становится крайне важной для более эффективного обнаружения и предотвращения современных киберугроз.

Научная новизна исследования заключается в разработке архитектуры на основе больших данных, специально предназначенной для управления информационной безопасностью предприятий. Предложенная структура основана на экосистеме Hadoop и состоит из четырех основных этапов: сбор данных, хранение данных, обработка данных и анализ данных.

В исследовании также предлагается модель управления информационной безопасностью, которая интегрирует множество источников данных, включая системные журналы, журналы сетевого трафика, данные о поведении пользователей и внешнюю информацию об угрозах. Благодаря предварительной обработке данных, извлечению

признаков и методам машинного обучения система способна обнаруживать аномальные закономерности и потенциальные киберугрозы.

В исследовании используются алгоритмы машины опорных векторов (SVM) и случайного леса (RF) для классификации событий безопасности и повышения точности обнаружения угроз. Практическая значимость этого исследования заключается в его способности улучшить мониторинг безопасности предприятия, обеспечить раннее обнаружение киберугроз и ускорить реагирование на инциденты. Предложенная структура, использующая анализ больших данных и машинное обучение, предоставляет организациям масштабируемое и интеллектуальное решение для управления безопасностью, способное решать задачи современной цифровой среды.

Ключевые слова: *технологии больших данных, управление информационной безопасностью, кибербезопасность, экосистема Nadoor, обнаружение сетевых угроз, управление рисками*

UOT: 004.8:331

İŞ YERLƏRİNDƏ SÜNİ İNTELLEKT: TƏTBİQETMƏ PROBLEMLƏRİ VƏ İMKANLAR

Səidə Rəhimli İlqar qızı

ORCID kod: 0009-0000-9789-7472, Azərbaycan Dövlət İqtisad Universiteti, Azərbaycan

Xülasə

Bu məqalədə süni intellektin müasir iş yerlərinə inteqrasiyası araşdırılır və həm onun transformativ potensialına, həm də tətbiqi ilə bağlı mürəkkəb çətinliklərə diqqət yetirilir. Tədqiqatda süni intellekt texnologiyalarının təşkilati prosesləri, qərar qəbulətmə sistemlərini və işçi qüvvəsi strukturlarını necə yenidən formalaşdırdığı araşdırılmaq üçün konseptual və analitik yanaşma tətbiq olunur. Müəllif belə bir nəticəyə gəlir ki, süni intellekt məhsuldarlığı, əməliyyat səmərəliliyini və innovasiya potensialını əhəmiyyətli dərəcədə artırsa da, onun uğurlu tətbiqi yalnız texnoloji hazırlıqdan asılı deyil.

Nəticələr süni intellektin tətbiqinin tez-tez texniki məhdudiyyətlər, qeyri-kafi infrastruktur, məlumat təhlükəsizliyi ilə bağlı narahatlıqlar, etik dilemmalar, bacarıq boşluqları və təşkilati dəyişikliklərə müqavimətlə məhdudlaşdığını vurğulayır. Məqalədə alqoritmik qərəzliliyin, məxfilik risklərinin və işçi qüvvəsinin yerdəyişməsinin proaktiv idarəetmə və məsuliyyətli idarəetmə tələb edən vacib məsələləri təmsil etdiyi vurğulanır. Səhiyyə diaqnostikasında süni intellekt tətbiqləri də daxil olmaqla empirik nümunələr göstərir ki, laboratoriya şəraitində yaxşı işləyən sistemlər kontekstual və insan amillərinə görə real mühitlərdə ciddi çətinliklərlə üzləşə bilər.

Tədqiqatın əhəmiyyətli elmi töhfəsi süni intellektin tətbiqinin təşkilati sağlamlıq və işçilərin rifahı ilə əlaqələndirilməsidir. Tədqiqat, psixososial aspektləri, hibrid intellekt modellərini və süni intellektlə idarə olunan transformasiyanın iş dizaynına və əmək bazarı bərabərsizliyinə uzunmüddətli təsirlərini əhatə etməklə müzakirəni avtomatlaşdırma və məhsuldarlıqdan kənara çıxarır. Müəllif iddia edir ki, davamlı süni intellekt inteqrasiyası strateji liderlik, işçi qüvvəsinin yenidən hazırlanması, iştirakçı qərar qəbulətmə və etik nəzarət tələb edir. Tədqiqatın praktik əhəmiyyəti innovasiyanı işçilərin rifahı ilə balanslaşdırmağı hədəfləyən təşkilatlar üçün tövsiyələrində əks olunur. Sosial-iqtisadi riskləri azaltmaqla yanaşı, süni intellektdən faydaları maksimum dərəcədə artırmaq üçün insan mərkəzli və uyğunlaşa bilən yanaşmanın zəruriliyini vurğulayır.

Açar sözlər: Süni intellekt, iş yerində transformasiya, avtomatlaşdırma, işçilərin rifahı, hibrid zəka, rəqəmsal transformasiya.

Giriş

Süni intellekt müasir iş yerlərində sürətlə transformativ qüvvəyə çevrilir, təşkilati prosesləri, qərar qəbulətmə sistemlərini və işçi qüvvəsinin dinamikasını yenidən formalaşdırır. Avtomatlaşdırmanı, proqnozlaşdırıcı analitikanı və ağıllı məlumatların emalını təmin edən Sİ texnologiyaları məhsuldarlığın, innovasiyanın və rəqabət üstünlüyünün artırılması üçün əhəmiyyətli imkanlar təqdim edir. Bununla belə, Sİ-nin biznes mühitlərində tətbiqi çətinliklərdən azad deyil. Təşkilatlar tətbiq və inteqrasiyaya mane olan texniki, etik, hüquqi və insan mərkəzli maneələrlə üzləşirlər. İşçi qüvvəsinin yerdəyişməsi ilə bağlı narahatlıqlar, bacarıq boşluqları, məlumat təhlükəsizliyi riskləri və dəyişikliklərə müqavimət kimi məsələlər tez-tez uğurlu tətbiqə

mane olur. Buna görə də, iş yerində SI-nin həm imkanlarını, həm də tətbiq çətinliklərini anlamaq davamlı və məsuliyyətli rəqəmsal transformasiyaya nail olmaq üçün vacibdir.

İş yerlərində sünİ intellekt haqqında konseptual çərçivə

Sünİ intellekt cəmiyyətə güclü təsir göstərən bir fenomendir və bu təsir həm yeni imkanlar, həm də ciddi risklər yaradır. Ədəbiyyatda bu texnologiyanın təsiri onun necə tətbiq edilməsindən və idarə olunmasından asılı olaraq “nemət” və ya “təhlükə” kimi qiymətləndirilə biləcəyi qeyd olunur. Sünİ intellektin gələcəkdə oynayacağı rol həm maraq doğuran, həm də narahatlıq yaradan bir mövzu kimi dəyərləndirilir.

Bir tərəfdən, sünİ intellekt məşğulluq və məhsuldarlıq baxımından müsbət nəticələr verə bilər. Xüsusilə istehsal sənayesində sünİ intellektdən istifadə artıq formalaşmış bir tendensiyaya çevrilmişdir. Bu texnologiyalar bir çox sahədə səmərəliliyin artırılmasına töhfə verir. Məsələn, səhiyyə sektorunda sünİ intellekt xəstəliklərin diaqnostikası, müalicə planlarının hazırlanması və pasiyentlərin monitorinqi kimi müxtəlif istiqamətlərdə tətbiq olunur. Rentgen və kompüter tomoqrafiyası kimi tibbi görüntülərin analizi üçün hazırlanmış alqoritmlər həkimlərə xəstəlikləri daha erkən mərhələdə aşkar etməyə kömək edir. Bu kontekstdə səhiyyə sahəsində çalışan rəhbərlər işçi heyətini sünİ intellekt sistemləri ilə birgə işləməyə hazırlamalı və hər bir tibbi mütəxəssisin iş funksiyalarını bu yeni reallığa uyğun şəkildə yenidən dizayn etməlidirlər (Kinowska, Sienkiewicz, 2020, s. 135).

Digər tərəfdən, əldə edilən nailiyyətlərə baxmayaraq, həllini gözləyən ciddi problemlər mövcuddur. Xəstə məlumatlarının məxfiliyi və təhlükəsizliyi, eləcə də sünİ intellektin etik və məsuliyyətli şəkildə istifadəsinin təmin edilməsi əsas çağırışlar sırasındadır. Akademik tədqiqatlarda alqoritmik qərəzlilik, sistemlərin həssaslığı, pis niyyətli istifadə imkanları, təhlükəsizlik riskləri, iş yerlərinin itirilməsi ehtimalı və bu proseslə bağlı etik dilemmalar geniş şəkildə müzakirə olunur. Harvard Business Review tərəfindən vurğulandığı kimi, əsas məsələ sünİ intellektin daha çox idraki işi yerinə yetirib-yetirməyəcəyi deyil, insanların bu dəyişikliklərə necə uyğunlaşacağıdır.

Sünİ intellekt anlayışının nəyi ifadə etdiyini dəqiq müəyyənləşdirmək, onun iş mühitinə təsirini dəyərləndirərkən ortaq bir yanaşma formalaşdırmağa kömək edir. Sünİ intellekt sistemi insan tərəfindən müəyyən edilmiş məqsədlər çərçivəsində real və ya virtual mühitlərə təsir göstərə bilən proqnozlar irəli sürən, tövsiyələr verən və ya qərarlar qəbul edən maşın əsaslı bir sistemdir. Bu cür sistemlər real və ya virtual mühitləri qavramaq üçün həm insan, həm də texnoloji mənbələrdən daxil olan məlumatlardan istifadə edir. Əldə olunan qavrayışlar avtomatlaşdırılmış üsullarla (məsələn, maşın öyrənməsi vasitəsilə) və ya manual şəkildə modellərə çevrilir. Daha sonra bu modellər üzərindən aparılan nəticə çıxarma prosesi informasiya və ya fəaliyyət variantlarının formalaşdırılmasına xidmət edir. Sünİ intellekt sistemləri fərqli səviyyələrdə müstəqil fəaliyyət göstərə biləcək şəkildə dizayn olunur (Makridis, Han, 2021).

Sünİ intellekt texnologiyaları bəzi işlərin tam və ya qismən avtomatlaşdırılmasına səbəb ola, iş şəraitinin keyfiyyətinə müsbət və ya mənfi təsir göstərə, həmçinin müxtəlif işçi qruplarına fərqli səviyyələrdə təsir edə bilər. Sünİ intellektin əməkdaşlara mümkün təsirləri barədə düşünmək çətin görünərsə də, bu məsələ texnologiyanın tətbiqi ilə bağlı qərarların qəbulunda və onun necə istifadə ediləcəyinin müəyyənləşdirilməsində əsas amillərdən biri olmalıdır.

Sünİ intellekt sistemlərinin mövcud iş mühitlərinə inteqrasiyası bir sıra ciddi çətinliklərlə müşayiət olunur. Bir çox hallarda mövcud infrastruktur sünİ intellekt üçün tələb olunan məlumatların toplanması, emalı və istifadəsi baxımından yetərli olmur. Eyni zamanda, təşkilatlarda bu texnologiyalara qoyulan investisiyanın geri dönüşünü təmin edəcək maliyyə resursları və ixtisaslı insan kapitalı çatışmaya bilər. Sünİ intellekt sistemləri yeni tip məlumatlara, təşkilata xas texniki bilik və bacarıqlara, eləcə də fərqli iş üsullarına ehtiyac yaradır (Aly, 2022, s. 243).

Nümunə olaraq Google tərəfindən hazırlanmış tibbi süni intellekt sistemini göstərmək olar. Bu sistem Tailanddakı klinikalarda diabetik retinopatiyanın aşkarlanması məqsədilə sınaqdan keçirilmişdir. Bu xəstəlik vaxtında aşkar edilmədikdə görmə itkisinə səbəb ola bilər. Qurulan dərin öyrənmə modeli diabetli pasiyentlərin göz görüntülərində xəstəliyin əlamətlərini müəyyən etməyə yönəlmişdi. Sistem optimal şəraitdə işlədikdə müəyinə prosesini əhəmiyyətli dərəcədə sürətləndirirdi. Lakin real iş mühiti laboratoriya şəraitindən kəskin şəkildə fərqlənirdi. Model yüksək keyfiyyətli şəkillər üzərində öyrədildiyi üçün müəyyən keyfiyyət həddindən aşağı olan görüntüləri avtomatik olaraq qəbul etmirdi. Klinik şəraitdə isə tibb bacıları çox vaxt tələsik və zəif işıqlandırılmış mühitdə çalışdıqlarından, çoxlu sayda şəkil sistem tərəfindən rədd edilirdi. Bu vəziyyət işçilərdə narazılıq yaradır və onların sistemin qərarlarına təsir göstərə bilməməsi frustrasiyaya səbəb olurdu (Yang, 2022).

Laboratoriya şəraitində Google-un səhiyyə yönümlü süni intellekt skaneri təxminən 90% dəqiqlik göstərmişdi. Lakin real tibbi iş mühitləri adətən intensiv, sürətli və yüksək stresli olur. Bu isə onu göstərir ki, uğurlu süni intellekt sistemi belə mühitlərə uyğunlaşa biləcək qədər çevik olmalıdır. Ayova Universitetinin oftalmoloqu Michael Abramoff-un da vurğuladığı kimi, real tibbi praktikada mütəxəssislər arasında fikir ayrılıqları tez-tez baş verir. Süni intellektə əsaslanan diaqnostik sistemlər də bu cür müzakirələrin normal olduğu proseslərə uyğunlaşdırılmalıdır. Bundan əlavə, işçilər sərhəd hallarında yalnız sistemin nəticələrinə deyil, həm də öz peşəkar mühakimələrinə əsaslanaraq qərar verməyə təşviq edilməli və bu istiqamətdə təlim keçməlidirlər (Gerke və b. 2023).

Hazırkı mərhələdə süni intellekt alətləri və texnologiyaları hələ də nisbətən ilkin inkişaf səviyyəsindədir. Süni intellekt sahəsinə ciddi maliyyə yatırımları edilsə belə, bu texnologiyaların tam optimallaşdırılmış, yüksək səviyyədə inkişaf etmiş və ya insan əməyini bütövlükdə əvəz edə biləcək mərhələyə çatdığını demək mümkün deyil. Aparılan bəzi qiymətləndirmələr göstərir ki, süni intellektə qoyulan investisiyalarla məhsuldarlıq artımı arasında 5 ildən 15 ilə qədər zaman fərqi yarana bilər. Bundan əlavə, bu texnologiyaların real təsir göstərməsi üçün işçi qüvvəsinin təlimi, yeni kadrların cəlb edilməsi və tamamlayıcı texnologiyalara sərmayə kimi paralel investisiyalar da zəruridir.

Avtomatlaşdırma və süni intellektin tətbiqinin hansı peşələrə daha çox təsir göstərəcəyini dəqiq proqnozlaşdırmaq çətindir. Bu təsir sahə, iqtisadi struktur və dövlət siyasəti kimi çoxsaylı amillərdən asılıdır. Bununla belə, ümumi tendensiya göstərir ki, təkrarlanan və standartlaşdırılmış tapşırıqlara əsaslanan işlər daha yüksək risk altındadır. Bu kateqoriyaya xidmət sektorunda müştəri xidmətləri və məlumatların emalı kimi aşağı səviyyəli vəzifələr, istehsalat sahəsində avadanlıqların idarə olunması və konveyer xətti üzrə işlər, eləcə də maliyyə sektorunda mühasibatlıq və bank əməliyyatlarının emalı daxildir.

İş proseslərinin avtomatlaşdırılması xüsusilə xidmət yönümlü peşələrdə işsizlik və əməkhaqlarının azalması kimi sosial-iqtisadi problemlər yarada bilər. Çünki əvvəllər insan müdaxiləsi tələb edən bir sıra fəaliyyətlər — mətn və kontent yaradılması, tez-tez verilən suallara cavabların hazırlanması, çatbotlar vasitəsilə avtomatik ünsiyyət və jurnalistika və reklam kimi sahələrdə avtomatlaşdırılmış mətn istehsalı — artıq maşınlar tərəfindən icra edilə bilər. Bu isə həmin tapşırıqlar üçün işçi qüvvəsinə olan tələbatı azalda və nəticədə bacarıq və təhsil səviyyəsi məhdud olan şəxslərin əmək bazarında mövqe tapmasını çətinləşdirə bilər. Belə proseslər iqtisadi bərabərsizliyin dərinləşməsinə də səbəb ola bilər. Əslində, bu hal tamamilə yeni deyil: avtomatlaşdırma son 40 il ərzində ABŞ-da əməkhaqları arasındakı fərqlərin artmasına əhəmiyyətli təsir göstərmişdir.

Bununla yanaşı, süni intellekt əməkdaşlara daha yaradıcı və yüksək dəyər yaradan fəaliyyətlərə fokuslanmaq imkanı da verə bilər. İnsan və süni intellektin birgə fəaliyyəti “hibrid intellekt” anlayışı çərçivəsində getdikcə daha çox müzakirə olunur. Musiqi, video oyunlar, dizayn ideyalarının formalaşdırılması və eskizləmə kimi sahələrdə insan–süni intellekt əməkdaşlığına dair

geniş tədqiqatlar aparılmışdır. Xidmət sektorunda isə süni intellekt emosional bacarıqlar tələb edən fəaliyyətləri tam əvəz edə bilmədiyi üçün, bu sahədə məşğulluğun qorunmasına və hətta artmasına töhfə verə bilər. Xüsusilə emosional zəka tələb edən və insan münasibətlərinə əsaslanan işlər bu baxımdan daha dayanıqlı hesab olunur (Gu və b. 2024).

Gələcəkdə əməyin necə formalaşacağına dair araşdırmaların aparılmasının zəruriliyi artıq uzun müddətdir vurğulanır. Bununla belə, əməkdaşların texnoloji dəyişiklikləri öz iş yerləri və karyera perspektivləri baxımından necə dəyərləndirdiyi və bu dəyişikliklərə nə dərəcədə hazırlaşdığı barədə məlumatlar hələ də məhduddur. Xüsusilə, 2022-ci ilin dekabrında ChatGPT-nin geniş ictimaiyyətə təqdim edilməsindən bu mövzuda aparılmış akademik tədqiqatların sayı olduqca az idi. Buna baxmayaraq, mövzu yüksək sosial əhəmiyyət daşıyır və bu, sözügedən dövrdən sonra beynəlxalq mediada ona göstərilən geniş diqqətlə də təsdiqlənir (Burgess, 2023).

Yeni, inkişaf etməkdə olan və innovativ texnologiyalar iş mühitində bir çox üstünlüklər yaratsa da, işçilərin bacarıq səviyyəsindən, peşəsindən və ya fəaliyyət göstərdikləri sektordan asılı olmayaraq, mümkün iş yerinin itirilməsi və ya məşğulluğun azalması kimi risklərin nəzərə alınması vacibdir. Bu cür nəticələr işçilərin təhlükəsizliyi və sağlamlığı üçün ciddi təsirlər doğura bilər və buna görə də belə halların qarşısının alınması üçün müvafiq tədbirlərin görülməsi zəruridir. Təşkilati sağlamlıq isə bir-biri ilə əlaqəli çoxsaylı amillərin qarşılıqlı təsiri nəticəsində formalaşan davamlı bir prosesdir. Akademik ədəbiyyatda uzun illərdir sağlam təşkilat anlayışını izah edən müxtəlif konseptual modellər təklif edilmişdir.

Daha son dövrlərdə aparılan tədqiqatlar sağlam iş mühitinin əsas komponentlərini daha sistemli şəkildə müəyyən etmişdir. Bu çərçivədə iş-həyat balansı, əməkdaşların inkişafı və təlimi, sağlamlıq və təhlükəsizlik, işçilərin qərarvermədə iştirakı və əməyin tanınması kimi praktikalar ön plana çıxarılmışdır. Digər yanaşmalarda isə təşkilati sağlamlığa töhfə verən əsas elementlər məsuliyyət bölgüsü, bacarıqların səviyyəsi, koordinasiya və nəzarət mexanizmləri, təşkilati mədəniyyət və iqlim, strateji istiqamət, xarici mühitə adaptasiya, innovasiya və öyrənmə, liderlik və motivasiya kimi komponentlər üzrə təsnif edilmişdir (Chang, 2021, s.381).

Sağlam təşkilat anlayışının empirik tərifləri çox zaman yalnız əməkdaşların psixososial vəziyyətinə fokuslanır və bu vəziyyəti formalaşdıran və ya davamlı edən amilləri kifayət qədər nəzərə almır. Halbuki, müsbət təşkilati iqlimə malik bölmələrdə çalışan işçilər adətən daha az stress yaşayır və daha yüksək rifah səviyyəsi nümayiş etdirirlər. Belə mühitlər təhlükəsizlik, ədalətlik, müştəri yönümlülük, insanlararası münasibətlərin keyfiyyəti, nəzarət imkanları, dəstək mexanizmləri və effektivlik kimi xüsusiyyətlərlə xarakterizə olunur (Brougham, Haar, 2024, s. 248).

Bu kontekstdə təşkilatların əməkdaşların gördüyü işə məna qazandırması və süni intellekt də daxil olmaqla mövcud bütün texnoloji imkanlardan elə istifadə etməsi xüsusilə önəmlidir ki, işçilərin rifahı və sağlamlığı ən yüksək səviyyədə təmin olunsun. Bu tədqiqat çərçivəsində “rifah” anlayışı fərdin ümumi sağlamlığını, xoşbəxtliyini və həyat məmnuniyyətini əhatə edən geniş məzmunlu bir anlayış kimi qəbul edilir və həm fiziki, həm də psixi aspektləri özündə birləşdirir. Psixi rifah isə ümumi rifahın bir hissəsi olaraq fərdin emosional, psixoloji və sosial vəziyyətini ifadə edir və gündəlik həyatın çağırışları ilə effektiv mübarizə aparmaq üçün əsas şərt hesab olunur. Ədəbiyyatda “rifah” və “sağlam həyat tərz” anlayışları tez-tez eyni mənada işlədilsə də, onlar tam sinonim deyildir. Sağlam həyat tərz daha çox optimal sağlamlığa nail olmaq üçün fərdin şüurlu davranış və seçimlərini ifadə etdiyi halda, rifah anlayışı həyat keyfiyyətinə daha bütöv yanaşmanı əks etdirir (Lorenzini və b. 2023).

Akademik tədqiqatlar xüsusilə süni intellektin insan resurslarının idarə olunması proseslərinə təsirinə diqqət yetirmişdir. Süni intellektin iş mühiti nəticələrinə təsirini qiymətləndirən müəyyən araşdırmalar mövcud olsa da, bu texnologiyaların əməkdaşların real təcrübələrinə necə təsir göstərdiyi hələ də kifayət qədər öyrənilməmişdir. Bundan əlavə, süni intellekt sistemlərinin tətbiqində uğursuzluqların bir qismi yalnız texnoloji aspektlərə fokuslanan, lakin işçi davranışlarını və insan amilini nəzərə almayan strategiyalarla əlaqələndirilir.

Nəticə

Süni intellektin iş yerlərinə integrasiyası həm transformativ fürsət, həm də mürəkkəb təşkilati çətinlik yaradır. Süni intellekt texnologiyaları səmərəliliyi artırırsa, qərar qəbul etmə proseslərini təkmilləşdirsə və innovasiya üçün yeni yollar açsa da, onların uğurlu tətbiqi texniki, etik və insan mərkəzli məsələlərin diqqətlə idarə olunmasını tələb edir. Təşkilati müqavimət, bacarıq boşluqları, tənzimləyici qeyri-müəyyənliklər və iş itkisi ilə bağlı narahatlıqlar əhəmiyyətli maneələr olaraq qalır. Buna görə də, süni intellektin davamlı tətbiqi yalnız texnoloji hazırlıqdan deyil, həm də strateji liderlikdən, işçi qüvvəsinin uyğunlaşmasından və məsuliyyətli idarəetmədən asılıdır. Balanslı və gələcəyə yönəlmiş yanaşma təşkilatlara süni intellektdən tam potensialdan istifadə etməyə və əlaqəli riskləri minimuma endirməyə imkan verə bilər.

İstifadə edilmiş ədəbiyyat siyahısı

1. Aly H. (2022). Digital Transformation, Development and Productivity in Developing Countries: Is Artificial Intelligence a Curse or a Blessing? *Rev. Econ. Polit. Sci.*, 7, 238–256.
2. Brougham D., Haar J. (2024). Smart Technology, Artificial Intelligence, Robotics, and Algorithms (STARA): Employees' Perceptions of Our Future Workplace. *J. Manag. Organ.* 24, 239–257.
3. Burgess E. R. (2023). How to Prevent ChatGPT from Destroying Creative Jobs. *Medium*, 4 January.
4. Chang K. (2021). Artificial Intelligence in Personnel Management: The Development of APM Model. *Bottom Line*, 33, 377–388.
5. Gerke S., Minssen T., Cohen G. (2023). Ethical and Legal Challenges of Artificial Intelligence-Driven Healthcare. In *Artificial Intelligence in Healthcare*; Elsevier: Amsterdam, The Netherlands; pp. 295–336; ISBN 978-0-12-818438-7.
6. Gu T. T., Zhang S. F., Cai R. (2024). Can Artificial Intelligence Boost Employment in Service Industries? *Artif. Intell.* 36, 2080336.
7. Kinowska H., Sienkiewicz L.J. (2020). Influence of Algorithmic Management Practices on Workplace Well-Being—Evidence from European Organizations. *Inf. Technol. People*, 34, 123–145.
8. Lorenzini M., Lagomarsino M., Fortini L., Gholami S., Ajoudani A. (2023). Ergonomic Human-Robot Collaboration in Industry: A Review. *Front. Robot. AI*.
9. Makridis C., Han J. (2021). Future of Work and Employee Empowerment and Satisfaction: Evidence from a Decade of Technological Change. *Technol. Forecast. Soc. Chang.* 2021, 173, 121162.
10. Yang C. H. (2022). How Artificial Intelligence Technology Affects Productivity and Employment: Firm-Level Evidence from Taiwan. *Res. Policy*, 51, 104536.

ARTIFICIAL INTELLIGENCE IN THE WORKPLACE: IMPLEMENTATION CHALLENGES AND OPPORTUNITIES

Abstract

This article examines the integration of artificial intelligence into modern workplaces, focusing on both its transformative potential and the complex challenges associated with its implementation. The study uses a conceptual and analytical approach to examine how artificial intelligence technologies are reshaping organizational processes, decision-making systems, and workforce structures. The author concludes that while artificial intelligence significantly increases productivity, operational efficiency, and innovation potential, its successful implementation does not depend solely on technological readiness.

The results highlight that the implementation of artificial intelligence is often limited by technical limitations, inadequate infrastructure, data security concerns, ethical dilemmas, skill gaps, and resistance to organizational change. The article highlights that algorithmic bias, privacy risks, and workforce displacement represent important issues that require proactive governance and responsible management. Empirical examples, including AI applications in healthcare diagnostics, show that systems that work well in the laboratory can face serious challenges in real-world environments due to contextual and human factors.

The study's significant scientific contribution is the connection between AI implementation and organizational health and employee well-being. The study moves the discussion beyond automation and productivity by covering psychosocial aspects, hybrid intelligence models, and the long-term impacts of AI-driven transformation on job design and labor market inequality. The author argues that sustainable AI integration requires strategic leadership, workforce retraining, participatory decision-making, and ethical oversight. The practical relevance of the study is reflected in its recommendations for organizations aiming to balance innovation with employee well-being. It highlights the need for a human-centric and adaptive approach to maximize the benefits of AI while reducing socio-economic risks.

Keywords: *Artificial intelligence, workplace transformation, automation, employee well-being, hybrid intelligence, digital transformation.*

ИСКУССТВЕННЫЙ ИНТЕЛЛЕКТ НА РАБОЧЕМ МЕСТЕ: ПРОБЛЕМЫ И ВОЗМОЖНОСТИ ВНЕДРЕНИЯ

Аннотация

В данной статье рассматривается интеграция искусственного интеллекта в современные рабочие места, уделяя особое внимание как его преобразующему потенциалу, так и сложным проблемам, связанным с его внедрением. В исследовании используется концептуальный и аналитический подход для изучения того, как технологии искусственного интеллекта меняют организационные процессы, системы принятия решений и структуру рабочей силы. Автор приходит к выводу, что, хотя искусственный интеллект значительно повышает производительность, операционную эффективность и инновационный потенциал, его успешное внедрение зависит не только от технологической готовности.

Результаты показывают, что внедрение искусственного интеллекта часто ограничено техническими ограничениями, неадекватной инфраструктурой, проблемами безопасности данных, этическими дилеммами, нехваткой навыков и сопротивлением организационным изменениям. В статье подчеркивается, что алгоритмическая предвзятость, риски

конфиденциальности и вытеснение рабочей силы представляют собой важные проблемы, требующие активного управления и ответственного подхода. Эмпирические примеры, включая применение ИИ в диагностике в здравоохранении, показывают, что системы, хорошо работающие в лаборатории, могут столкнуться с серьезными проблемами в реальных условиях из-за контекстуальных и человеческих факторов.

Значительный научный вклад исследования заключается в связи между внедрением ИИ и здоровьем организации, а также благополучием сотрудников. Исследование выходит за рамки автоматизации и производительности, охватывая психосоциальные аспекты, модели гибридного интеллекта и долгосрочные последствия трансформации, вызванной ИИ, для проектирования рабочих мест и неравенства на рынке труда. Автор утверждает, что устойчивая интеграция ИИ требует стратегического лидерства, переподготовки персонала, участия в принятии решений и этического контроля. Практическая значимость исследования отражена в его рекомендациях для организаций, стремящихся сбалансировать инновации с благополучием сотрудников. В нем подчеркивается необходимость человекоцентричного и адаптивного подхода для максимизации преимуществ ИИ при одновременном снижении социально-экономических рисков.

Ключевые слова: Искусственный интеллект, трансформация рабочего места, автоматизация, благополучие сотрудников, гибридный интеллект, цифровая трансформация.

MƏLUMATLARIN QORUNMASI VƏ KİBERTƏHLÜKƏSİZLİK KONTEKSTİNDƏ SİMSİZ ŞƏBƏKƏLƏRDƏ AUTENTİFİKASIYA METODLARININ TƏHLİLİ

Əmrahova Nurcan Müzəffər

Azərbaycan Dövlət İqtisad Universiteti, Bakı, Azərbaycan

XÜLASƏ

Müasir dövrdə rəqəmsal transformasiyanın sürətlə inkişafı simsiz şəbəkələrin istifadəsini genişləndirmiş və bu şəbəkələri informasiya mübadiləsinin əsas platformalarından birinə çevirmişdir. Dövlət idarəçiliyi, təhsil, elektron ticarət və digər sosial-iqtisadi sahələrdə simsiz texnologiyalardan intensiv istifadə məlumatların qorunması və kibertəhlükəsizlik problemlərini daha da aktuallaşdırır. Xüsusilə, simsiz mühitin açıq xarakter daşması icazəsiz girişlər və məlumat sızıntıları üçün potensial risklər yaradır. Bu baxımdan autentifikasiya mexanizmləri şəbəkə təhlükəsizliyinin əsas elementlərindən biri kimi çıxış edir.

Məqalədə simsiz şəbəkələrdə tətbiq olunan autentifikasiya metodlarının təhlükəsizlik baxımından təhlili aparılır və onların məlumatların məxfiliyinin, bütövlüyünün və əlçatanlığının təmin edilməsindəki rolu araşdırılır. Tədqiqat çərçivəsində parol əsaslı, sertifikat əsaslı və protokol səviyyəsində həyata keçirilən autentifikasiya yanaşmaları müqayisəli şəkildə qiymətləndirilir. Hər bir metodun üstünlükləri, məhdudiyyətləri və potensial təhlükəsizlik riskləri müəyyən edilir. Aparılan təhlillər göstərir ki, düzgün seçilmiş və effektiv tətbiq olunan autentifikasiya mexanizmləri simsiz şəbəkələrdə kibertəhlükəsizlik səviyyəsinin yüksəldilməsinə və rəqəmsal mühitdə məlumatların etibarlı qorunmasına əhəmiyyətli töhfə verir.

Açar sözlər: *Simsiz şəbəkələrdə təhlükəsizlik, Autentifikasiya metodları, Kibertəhlükəsizlik, Məlumatların məxfiliyi və bütövlüyü, Rəqəmsal transformasiya*

GİRİŞ

Məlumatların qorunması və kibertəhlükəsizlik müasir dövrdə informasiya texnologiyalarının inkişafı ilə sıx bağlıdır. Simsiz şəbəkələr (Wi-Fi, mobil şəbəkələr və digər simsiz kommunikasiya kanalları) həyatın müxtəlif sahələrində geniş istifadə olunur və bununla yanaşı məlumatların məxfiliyi, bütövlüyü və əlçatanlığı baxımından ciddi təhlükələr yaradır. Simsiz şəbəkələrin açıq mühitdə fəaliyyət göstərməsi onların müxtəlif kibertəhlükələrə, o cümlədən məlumat sızmasına, icazəsiz girişə və şəbəkə hücumlarına məruz qalmasını asanlaşdırır.

Bu kontekstdə autentifikasiya metodları – istifadəçilərin və cihazların düzgün identifikasiya edilməsini təmin edən mexanizmlər – məlumatların qorunmasında əsas rol oynayır. Müxtəlif autentifikasiya üsulları şəbəkənin təhlükəsizlik səviyyəsini müəyyən edir və məlumatların icazəsiz şəxslərin əlindən qorunmasını təmin edir.

MƏLUMATLARIN QORUNMASI VƏ KİBERTƏHLÜKƏSİZLİK ANLAYIŞI

Məlumatların qorunması informasiya sistemlərində saxlanılan və ötürülən məlumatların məxfiliyini, bütövlüyünü və əlçatanlığını təmin edən tədbirlərin məcmusudur. Məxfiliyin təmin edilməsi yalnız məlumatın icazəsiz şəxslərin əlindən qorunmasını nəzərdə tutmur, həmçinin məlumatın yalnız səlahiyyətli istifadəçilər tərəfindən əldə olunmasını təmin edir. Bütövlük prinsipi məlumatların dəyişdirilmədən, zədələnmədən və ya itkisiz saxlanmasını nəzərdə tutur. Əlçatanlıq isə məlumatların lazım olduğu zaman səlahiyyətli istifadəçilər üçün mövcud olmasını təmin edir.

Bu prinsiplər kibertəhlükəsizlik sahəsində "CIA" (Confidentiality, Integrity, Availability) modeli ilə geniş şəkildə təmsil olunur.

Kibertəhlükəsizlik isə informasiya texnologiyaları və kommunikasiya sistemlərində məlumatların, şəbəkələrin və cihazların müxtəlif növ təhdidlərdən qorunması fəaliyyətidir. Müasir dövrdə kibertəhlükəsizlik yalnız texniki tədbirlərdən ibarət deyil, həm də siyasət, hüquqi normalar və istifadəçi davranışlarının idarəsini əhatə edir. Kibertəhlükəsizlik tədbirləri arasında şəbəkə təhlükəsizliyi, məlumatların şifrələnməsi, autentifikasiya və avtorizasiya mexanizmləri, hücumların aşkarlanması və reaksiya planları mühüm yer tutur.

Simsiz şəbəkələr kontekstində məlumatların qorunması və kibertəhlükəsizlik xüsusilə aktualdır, çünki simsiz kanallar açıq mühitdə fəaliyyət göstərir və məlumatın müdaxiləyə açıq olma ehtimalını artırır. Bu səbəbdən simsiz şəbəkələrdə autentifikasiya metodlarının düzgün seçimi və tətbiqi məlumatların təhlükəsizliyini təmin edən əsas komponentlərdən biri hesab olunur.

Beləliklə, məlumatların qorunması və kibertəhlükəsizlik anlayışları simsiz şəbəkələrdə autentifikasiya metodlarının təhlilinə elmi əsas yaradır və onların effektivliyini qiymətləndirmək üçün nəzəri baza təmin edir.

SİMSİZ ŞƏBƏKƏLƏRİN XÜSUSİYYƏTLƏRİ VƏ TƏHLÜKƏSİZLİK PROBLEMLƏRİ

Simsiz şəbəkələr (Wireless Networks) müasir informasiya texnologiyalarının ən geniş istifadə olunan infrastrukturlarından biridir. Onlar kabelsiz kommunikasiya kanalları vasitəsilə məlumatların ötürülməsini təmin edir və həm fərdi, həm də müəssisə səviyyəsində böyük rahatlıq təqdim edir. Lakin simsiz şəbəkələrin açıq mühitdə fəaliyyət göstərməsi onları müxtəlif təhlükələrə qarşı həssas edir. Bu bölmədə simsiz şəbəkələrin əsas xüsusiyyətləri və qarşılaşdıqları təhlükəsizlik problemləri təhlil olunacaq.

1. Simsiz şəbəkələrin əsas xüsusiyyətləri

1. Açıq mühitdə fəaliyyət

Simsiz şəbəkələr elektromaqnit dalğalar vasitəsilə məlumat ötürür, bu da onları fiziki kabel şəbəkələrinə nisbətən daha açıq və müdaxiləyə həssas edir.

2. Rahatlıq və mobilik

İstifadəçilər şəbəkəyə istənilən yerdən qoşula bilər, bu isə mobil tətbiqlərin, IoT cihazlarının və uzaq iş imkanlarının inkişafını təmin edir.

3. Şəbəkə topologiyası və standartları

Simsiz şəbəkələr müxtəlif topologiyalarla (ad-hoc, infraqırmızı və ya simsiz AP-lər vasitəsilə) işləyə bilər və IEEE 802.11 standartları ilə tənzimlənir.

4. Sürət və ötürmə məsafəsi

Şəbəkənin sürəti istifadə olunan texnologiya (Wi-Fi 4/5/6, LTE, 5G) və ətraf mühit faktorlarından asılıdır.

2. Simsiz şəbəkələrdə əsas təhlükələr

Simsiz şəbəkələr açıq mühitdə fəaliyyət göstərdiyi üçün bir sıra kibertəhlükələrə məruz qalır. Əsas təhlükələr aşağıdakı qruplara bölünür:

Cədvəl 1. Hücum növləri

Hücum növü	Təsviri	Təsir sahəsi
Man-in-the-Middle (MitM)	Hücum edən şəxs məlumat ötürülən kanal üzərində müdaxilə edir.	Məxfiliyin pozulması, məlumat sızması
Sniffing	Şəbəkəyə qoşulan məlumat paketləri tutularaq analiz edilir.	Məxfi məlumatların əldə olunması
Rogue Access Point	Qeyri-qanuni AP-lər yaradılaraq istifadəçilər aldadılır.	Şəbəkəyə icazəsiz giriş, məlumat sızması
DoS/DDoS	Şəbəkə resursları yüklənərək istifadəçilərin xidmətə çıxışı əngəllənir.	Əlçatanlığın pozulması
Brute-force	Şəbəkə parolları avtomatlaşdırılmış alətlərlə sınaqdan keçirilir.	Autentifikasiya zəifliyindən istifadə

2.1. Risk faktorları

1. **Şifrləmə zəifliyi** – WEP kimi köhnə şifrləmə protokolları asanlıqla qırılır.
2. **İstifadəçi davranışı** – Zəif parollar, şüursuz şəbəkə qoşulmaları, sosial mühəndislik hücumları risk yaradır.
3. **Avadanlıq zəiflikləri** – Router və AP-lərdə proqram təminatı yenilənmədikdə təhlükələr artır.
4. **Şəbəkə monitorinqi olmaması** – Hücumların vaxtında aşkarlanamaması riskləri artırır.

SİMSİZ ŞƏBƏKƏLƏRDƏ AUTENTİFİKASIYA ANLAYIŞI VƏ ROLU

Autentifikasiya, istifadəçilərin və cihazların şəbəkəyə qoşulmazdan əvvəl düzgün identifikasiya edilməsini təmin edən prosesdir. Simsiz şəbəkələrdə autentifikasiya xüsusilə əhəmiyyətlidir, çünki bu şəbəkələr açıq və kabellər vasitəsilə qorunmayan mühitdə fəaliyyət göstərir, bu da icazəsiz giriş və məlumat sızması riskini artırır.

1. Autentifikasiyanın mahiyyəti

Autentifikasiya prosesi üç əsas komponentdən ibarətdir:

1. **İdentifikasiya (Identification)** – istifadəçinin və ya cihazın kimliyinin təqdim olunması.
2. **Təsdiq (Authentication)** – təqdim olunan kimliyin düzgünlüyünün yoxlanılması.
3. **Avtorizasiya (Authorization)** – təsdiqlənmiş istifadəçinin şəbəkədə hansı hüquqlara malik olduğunun müəyyən edilməsi.

Bu mərhələlər simsiz şəbəkələrdə yalnız istifadəçi parolları ilə məhdudlaşmır; həmçinin sertifikatlar, tokenlər və digər mexanizmlər də tətbiq oluna bilər.

2. Autentifikasiyanın rolu simsiz şəbəkələrdə

Simsiz şəbəkələrdə autentifikasiya bir neçə vacib rola malikdir:

1. **Təhlükəsizlik təminatı**
Autentifikasiya vasitəsilə yalnız səlahiyyətli istifadəçilər şəbəkəyə qoşula bilər, bu da məlumatların icazəsiz şəxslər tərəfindən əldə edilməsinin qarşısını alır.
2. **Məlumatların məxfiliyinin qorunması**
İcazəsiz girişlərin qarşısı alındıqda məlumatların sızması və ya manipulyasiya olunması riski azaldılır.
3. **Şəbəkə resurslarının qorunması**

Autentifikasiya, şəbəkə resurslarının yalnız səlahiyyətli istifadəçilər üçün əlçatan olmasını təmin edir və DDoS kimi hücumlara qarşı ilkin müdafiə rolunu oynayır.

4. Auditorluq və məsuliyyət

İstifadəçi identifikasiyası şəbəkə fəaliyyətlərinin izlənməsinə imkan verir, bu da hadisələrin araşdırılması və məsuliyyətin müəyyən edilməsi üçün vacibdir.

SİMSİZ ŞƏBƏKƏLƏRDƏ İSTİFADƏ OLUNAN AUTENTİFİKASIYA METODLARI

Simsiz şəbəkələrdə autentifikasiya metodları istifadəçilərin və cihazların şəbəkəyə təhlükəsiz şəkildə qoşulmasını təmin etmək məqsədi ilə tətbiq olunur. Texnologiyanın inkişafı ilə bu metodlar da təkmilləşmiş və daha yüksək təhlükəsizlik səviyyəsi təmin edən mexanizmlər meydana çıxmışdır. Aşağıda simsiz şəbəkələrdə geniş istifadə olunan əsas autentifikasiya üsulları təhlil olunur.

1. Açıq autentifikasiya (Open Authentication)

Açıq autentifikasiya ən sadə və ilkin autentifikasiya metodlarından biridir. Bu üsulda istifadəçinin şəbəkəyə qoşulması üçün heç bir əlavə identifikasiya və ya təhlükəsizlik mexanizmi tələb olunmur.

Bu metod əsasən ictimai Wi-Fi şəbəkələrində tətbiq olunur. İstifadəçi yalnız şəbəkənin adını seçərək qoşula bilir. Lakin bu yanaşma yüksək təhlükəsizlik səviyyəsi təmin etmir, çünki şəbəkəyə qoşulan istifadəçilərin identifikasiyası aparılmır və məlumatlar müdaxiləyə açıq olur.

Açıq autentifikasiyanın əsas çatışmazlıqları: Məlumat sızması riski, İcazəsiz girişlərin mümkünlüyü, Hücumlara qarşı zəif müdafiə

2. WEP əsaslı autentifikasiya

WEP (Wired Equivalent Privacy) simsiz şəbəkələrdə ilk təhlükəsizlik və autentifikasiya mexanizmlərindən biridir. Bu metod istifadəçilərin şəbəkəyə qoşulması zamanı şifrələmə açarından istifadə edir.

Lakin WEP protokolu zəif kriptografik alqoritmlərə əsaslandığı üçün asanlıqla qırıla bilər. Bu səbəbdən müasir sistemlərdə onun istifadəsi tövsiyə olunmur. Əsas zəifliklərinə statik açarların istifadəsi, qısa şifrələmə açarları, paket analizinə qarşı zəiflik

3. WPA və WPA2 autentifikasiya

WEP protokolunun zəifliklərini aradan qaldırmaq üçün WPA (Wi-Fi Protected Access) və daha sonra WPA2 texnologiyaları hazırlanmışdır. Bu metodlar daha güclü şifrələmə və autentifikasiya mexanizmlərinə əsaslanır.

WPA və WPA2 iki əsas rejimdə istifadə olunur:

- **Personal (PSK)** – əvvəlcədən paylaşılan açar əsasında autentifikasiya
- **Enterprise** – mərkəzləşdirilmiş autentifikasiya serveri ilə

WPA2 AES şifrələmə alqoritmii ilə yüksək təhlükəsizlik təmin edir və uzun müddət standart kimi istifadə olunmuşdur.

Üstünlükləri:

- Dinamik açarların yaradılması
- Güclü şifrələmə
- Hücumlara qarşı daha yüksək müdafiə

4. WPA3 və müasir autentifikasiya yanaşmaları

WPA3 müasir simsiz şəbəkələr üçün daha təhlükəsiz autentifikasiya mexanizmləri təqdim edir. Bu standart zəif parollara qarşı müdafiəni gücləndirir və yeni kriptografik texnologiyalardan istifadə edir.

WPA3-ün əsas xüsusiyyətləri:

- Simultaneous Authentication of Equals (SAE) protokolu
- Brute-force hücumlarına qarşı daha güclü müdafiə
- Açıq şəbəkələrdə məlumatların şifrələnməsi

Bu metod yüksək təhlükəsizlik və istifadə rahatlığı təmin edir və gələcəkdə geniş tətbiqi gözlənilir.

5. 802.1X əsaslı autentifikasiya

IEEE tərəfindən hazırlanmış 802.1X standartı şəbəkəyə girişin idarə olunması üçün istifadə olunur. Bu metod xüsusilə korporativ şəbəkələrdə geniş tətbiq olunur.

802.1X autentifikasiya sistemi üç əsas komponentdən ibarətdir:

- İstifadəçi və ya cihaz (Supplicant)
- Şəbəkə cihazı (Authenticator)
- Autentifikasiya serveri (adətən RADIUS)

Bu yanaşma daha yüksək təhlükəsizlik təmin edir və istifadəçilərin fərdi identifikasiyasına imkan verir.

6. EAP protokolları

Extensible Authentication Protocol (EAP) 802.1X çərçivəsində istifadə olunan autentifikasiya metodları toplusudur. Bu protokollar müxtəlif təhlükəsizlik səviyyələri və autentifikasiya üsulları təqdim edir.

Əsas EAP növləri:

1. EAP-TLS

Sertifikatlara əsaslanan yüksək təhlükəsizlik səviyyəsinə malik autentifikasiya üsuludur.

2. PEAP (Protected EAP)

Şifrələnmiş tunel vasitəsilə istifadəçi autentifikasiyasını təmin edir.

3. EAP-TTLS

PEAP-ə bənzər şəkildə əlavə autentifikasiya mexanizmləri ilə işləyir.

Bu metodlar xüsusilə müəssisə və təşkilatlarda təhlükəsiz şəbəkə mühitinin yaradılmasında mühüm rol oynayır.

AUTENTİFİKASIYA METODLARININ MÜQAYİSƏLİ TƏHLİLİ

Simsiz şəbəkələrdə istifadə olunan autentifikasiya metodları təhlükəsizlik səviyyəsi, performans, istifadə rahatlığı və tətbiq sahəsinə görə fərqlənir. Bu metodların müqayisəli təhlili təşkilatların və fərdi istifadəçilərin optimal təhlükəsizlik həllərini seçməsi baxımından mühüm əhəmiyyət kəsb edir. Müasir dövrdə simsiz şəbəkələrdə autentifikasiya mexanizmlərinin inkişafı əsasən daha güclü kriptografik yanaşmaların tətbiqi və çoxfaktorlu identifikasiya sistemlərinin integrasiyası ilə xarakterizə olunur.

1. Autentifikasiya metodlarının müqayisəsi

Cədvəl 2. Autentifikasiya metodlarının müqayisəli təhlilinin təsviri

Kriteriya	Açıq autentifikasiya	WEP	WPA/WPA2	WPA3	802.1X və EAP
Təhlükəsizlik səviyyəsi	Çox aşağı	Aşağı	Orta–yüksək	Yüksək	Çox yüksək
Şifrələmə	Yoxdur	RC4	AES	SAE və AES	TLS və sertifikatlar
Parol hücumlarına davamlılıq	Yox	Zəif	Orta	Güclü	Çox güclü
İdentifikasiya səviyyəsi	Yox	Ümumi açar	Ümumi açar	Təkmilləşdirilmiş	Fərdi istifadəçi
İstifadə rahatlığı	Çox yüksək	Yüksək	Orta	Orta	Aşağı
Qurma çətinliyi	Çox asan	Asan	Orta	Orta	Çətin
Performansa təsir	Minimal	Minimal	Orta	Orta	Daha çox
Tətbiq sahəsi	İctimai Wi-Fi	Köhnə sistemlər	Ev və müəssisə	Müasir sistemlər	Korporativ mühit
Hücumlara qarşı davamlılıq	Zəif	Zəif	Orta	Yüksək	Çox yüksək

2. Təhlilin nəticələri

Cədvəldən göründüyü kimi, açıq autentifikasiya və WEP protokolları müasir təhlükəsizlik tələblərinə cavab vermir və yalnız xüsusi hallarda istifadə oluna bilər. Bu metodlar kibertəhlüklərə qarşı zəif müdafiə təmin edir və məlumat sızması riskini artırır.

WPA və WPA2 uzun müddət simsiz şəbəkələr üçün əsas təhlükəsizlik standartı olmuşdur. Lakin müasir hücum metodlarının inkişafı bu texnologiyaların bəzi zəifliklərini üzə çıxarmışdır. Buna görə də daha təhlükəsiz WPA3 standartı hazırlanmışdır. WPA3 autentifikasiya mexanizmi zəif parollara qarşı müdafiəni gücləndirir, brute-force və offline hücumlara qarşı daha dayanıqlı hesab olunur. Bununla yanaşı, IEEE 802.1X və EAP əsaslı autentifikasiya metodları xüsusilə korporativ

mühitdə ən yüksək təhlükəsizlik səviyyəsini təmin edir. Bu yanaşma istifadəçilərin fərdi identifikasiyasını, sertifikat əsaslı autentifikasiyanı və şəbəkə resurslarının effektiv idarə olunmasını mümkün edir.

NƏTİCƏ

Aparılan təhlil göstərir ki, simsiz şəbəkələrdə məlumatların qorunması və kibertəhlükəsizliyin təmin olunması autentifikasiya metodlarının düzgün seçilməsindən birbaşa asılıdır. Açıq autentifikasiya və WEP kimi köhnə üsullar müasir təhlükəsizlik tələblərinə cavab vermir və məlumat sızması riskini artırır, WPA və WPA2 texnologiyaları isə uzun müddət effektiv həll olsa da, yeni hücum metodları qarşısında müəyyən zəifliklərə malikdir. Bu baxımdan daha müasir və təhlükəsiz yanaşmalar olan WPA3, eləcə də IEEE 802.1X və EAP əsaslı autentifikasiya metodları xüsusilə korporativ mühitdə yüksək səviyyəli müdafiə təmin edir. Bununla yanaşı, çoxfaktorlu autentifikasiya, sertifikat əsaslı identifikasiya, proqram təminatının mütəmadi yenilənməsi və istifadəçilərin kibertəhlükəsizlik üzrə maarifləndirilməsi simsiz şəbəkələrin təhlükəsizliyinin gücləndirilməsində mühüm rol oynayır və gələcəkdə süni intellekt, biometrik texnologiyalar və Zero Trust yanaşmalarının tətbiqi bu sahədə daha etibarlı sistemlərin formalaşmasına şərait yaradacaqdır.

ƏDƏBİYYAT

1. **William Stallings.** *Network Security Essentials: Applications and Standards.* Pearson Education, 2017.
2. **ISO/IEC 27001.** *Information Security Management Systems.* 2013.
3. **Jonathan Katz, Yehuda Lindell.** *Introduction to Modern Cryptography.* CRC Press, 2014.
4. **IEEE.** *IEEE 802.11 Wireless LAN Standards.* Available at: <https://standards.ieee.org>
5. **Wi-Fi Alliance.** *WPA3 Security Guidelines.* Available at: <https://www.wi-fi.org>

İT şöbəsi: strukturu, rolları və funksiyaları

Mahmudova Gülşən Elsevər qızı

magistrant, Azərbaycan Dövlət Neft və Sənaye Universiteti, Bakı, Azərbaycan 2025

Nəbiyeva Cəmalə Oruc qızı

Xülasə:

İT şöbəsi şirkətin işini dayanıqlı şəkildə aparmasına və rəqəmsal mühitdə rəqabət qabiliyyətini qorumasına yardım edir. Bu şöbə həm işçilərin səmərəli işləməsi üçün zəruri texniki vasitələri təmin edir, həm də təşkilatı müxtəlif rəqəmsal təhlükələrdən müdafiə edir. Texnologiyanın sürətli inkişafı ilə birlikdə İT şöbələrinin əhəmiyyəti daha da artır — onlar artıq yalnız texniki dəstək deyil, həm də innovasiya və biznesin böyüməsinə təkan verən əsas strateji qüvvəyə çevriləblər. Məqalədə İT şöbəsinin tərkib hissələri və funksiyaları haqqında ətraflı məlumat verilmişdir.

Açar sözlər: *İT şöbəsi, Funksional struktur, Müstəqil struktur, Hibrid struktur.*

Summary:

The IT department helps a company run its business sustainably and maintain its competitiveness in the digital environment. This department both provides the necessary technical tools for employees to work efficiently and protects the organization from various digital threats. With the rapid development of technology, the importance of IT departments is increasing even more — they are no longer just technical support, but also a key strategic force that drives innovation and business growth. The article provides detailed information about the components and functions of the IT department.

Keywords: *IT department, Functional structure, Independent structure, Hybrid structure.*

Аннотация:

ИТ-отдел помогает компании вести устойчивый бизнес и поддерживать конкурентоспособность в цифровой среде. Этот отдел не только предоставляет необходимые технические инструменты для эффективной работы сотрудников, но и защищает организацию от различных цифровых угроз. С быстрым развитием технологий значение ИТ-отделов возрастает ещё больше — они уже не просто выполняют функции технической поддержки, но и являются ключевой стратегической силой, стимулирующей инновации и рост бизнеса. В статье представлена подробная информация о составе и функциях ИТ-отдела.

Ключевые слова: *ИТ-отдел, функциональная структура, независимая структура, гибридная структура.*

Giriş

İT şöbəsi — müəssisə daxilində bütün texnoloji proseslərin sabit, təhlükəsiz və səmərəli şəkildə işləməsinə təmin edən əsas bölmələrdən biridir. Bu şöbə yalnız texniki nasazlıqları aradan qaldırmaqla kifayətlənmir, həm də şirkətin informasiya axınının davamlı olmasını təmin edən infrastrukturun qurulması və idarə olunmasına cavabdehdir.

Müasir dövrdə İT komandalarının rolu sadəcə texniki dəstək funksiyası ilə məhdudlaşmır. Onlar biznesin məqsədlərinə çatmasına, əməliyyatların optimallaşdırılmasına və məlumatların təhlükəsizliyinin qorunmasına yönəlmiş strateji tərəfdaşlara çevriləblər. Şəbəkələrin və verilənlər bazalarının idarə edilməsi, kibertəhlükəsizlik sistemlərinin qurulması və program təminatlarının saxlanması kimi sahələr də İT şöbəsinin əsas fəaliyyət istiqamətlərinə daxildir.

Bizim üçün IT şöbəsinin vacibliyi ondan ibarətdir ki, o, təşkilatın texnoloji əsasını formalaşdırır və bütün sistemlərin fasiləsiz işləməsinə təmin edir. Bu şöbələr təkcə kompüterlərin təmiri və ya şəbəkə nasazlıqlarının aradan qaldırılması ilə məşğul olmur — onların əsas məqsədi məlumat axınının dayanıqlığını qorumaq, təhlükəsizliyi təmin etmək və iş proseslərinin səmərəliliyini artıran texnoloji həlləri tətbiq etməkdir. [3,s.110]

Adətən IT şöbələri şirkətin əməliyyatlar bölməsi ilə sıx əlaqədə fəaliyyət göstərir və onların öhdəliyinə informasiya təhlükəsizliyi, infrastrukturun idarə olunması, proqram təminatının hazırlanması və texniki dəstək kimi bir çox sahələr daxildir. Bununla belə, bu şöbələrin rolu artıq yalnız texniki xidmət göstərməklə məhdudlaşmır — IT komandaları bu gün biznesin inkişafı, innovasiya və rəqabət qabiliyyətinin artırılmasında əsas strateji tərəfdaş kimi çıxış edirlər.

IT şöbəsinin quruluşu isə hər bir təşkilatın məqsədlərinə və ehtiyaclarına görə fərqlənir. Bəzi şirkətlər çevikliyə üstünlük verərkən, digərləri ixtisaslaşmaya və ya xərclərin azaldılmasına fokuslanır. Düzgün strukturun yaradılması həm məsuliyyət bölgüsünü dəqiqləşdirir, həm də şirkətin davamlı fəaliyyətini təmin edir. Müxtəlif IT strukturları müxtəlif rollardan ibarət olur və hər bir rol şirkətin texnoloji sabitliyinə öz töhfəsini verir.

1. Funksional struktur: Aydın iyerarxiya və ixtisaslaşma əsasında təşkilatlanma

Funksional struktur IT şöbəsində ixtisaslaşmanı ön plana çəkən bir təşkilati modeldir. Bu yanaşmada komanda üzvləri öz bilik və bacarıqlarına, eləcə də məsuliyyət sahələrinə görə qruplaşdırılır. Hər bir istiqamət — məsələn, şəbəkə idarəetməsi, kibertəhlükəsizlik və ya texniki dəstək — ayrıca komanda şəklində fəaliyyət göstərir və həmin sahəyə cavabdeh rəhbər tərəfindən idarə olunur. Bu struktur mərkəzləşdirilmiş və iyerarxik qaydada qurulduğuna görə, hər bir işçinin rolu və hesabat zənciri aydın şəkildə müəyyən olunur. IT şöbəsinin təşkilati quruluşu aşağıdakı kimidir:

- **Yuxarı səviyyə:** Bütün IT fəaliyyətlərinə nəzarət edən Baş İnformasiya Direktoru (CIO) və ya IT şöbə rəhbəri.
- **Orta səviyyə:** Müxtəlif funksiyalara cavabdeh bölmə rəhbərləri və ya IT menecerləri (məsələn, Şəbəkə Meneceri, Təhlükəsizlik Meneceri, Dəstək Xidməti Meneceri).
- **Ən alt səviyyə:** Müvafiq sahələrdə çalışan mütəxəssislər və texniklər — şəbəkə mühəndisləri, kibertəhlükəsizlik analitikləri və istifadəçi dəstək əməkdaşları kimi.

Beləliklə, funksional struktur IT şöbəsində səlahiyyət bölgüsünü və məsuliyyətləri dəqiq müəyyənləşdirərək daha səmərəli və nəzarətli iş mühiti yaradır.

Quruluş prinsipi:

Bu modeldə komanda strukturlaşdırılması ixtisaslaşma əsasında aparılır. Hər bir fəaliyyət sahəsi — məsələn, şəbəkə və ya təhlükəsizlik — ayrıca bölmə kimi formalaşdırılır və öz menecerinə hesabat verir. Bütün menecerlər isə birbaşa IT direktoruna təbə olur.

İdarəetmə və qərarvermə prosesi əsasən **yuxarıdan aşağıya** istiqamətlənir — rəhbərlik strateji qərarları verir, aşağı səviyyədəki komandalar isə bu qərarları icra edir. [6,s.180]

Nümunə: Funksional strukturda fəaliyyət göstərən **şəbəkə idarəetmə komandası** şəbəkə meneceri tərəfindən idarə olunur. Bu qrupun tərkibinə şəbəkə administratorları və serverlərin, həmçinin bağlantıların sabitliyinə cavabdeh texniklər daxildir. Beləliklə, hər bir komanda öz sahəsində ixtisaslaşaraq ümumi IT infrastrukturunun effektiv işləməsinə töhfə verir.

Rollar və Əsas Elementlər:

IT direktoru (və ya Baş İnformasiya Direktoru) təşkilatın ümumi texnoloji istiqamətini müəyyən edir və bütün IT komandalarının biznes strategiyası ilə uzlaşmasını təmin edir. Onun rəhbərliyi altında fəaliyyət göstərən **IT menecerləri** konkret sahələrə nəzarət edir, resursları idarə edir və komanda üzvləri arasında işin düzgün bölünməsinə təmin edirlər. Hər bir menecerin tabeliyində isə **ixtisaslaşmış komandalar** fəaliyyət göstərir — bunlara şəbəkə idarəetməsi, kibertəhlükəsizlik, proqram təminatı hazırlanması, infrastruktur və istifadəçi dəstəyi üzrə qruplar daxildir.

2. Müstəqil xidmət xətti strukturu: Komandalar arasında avtonomluq və çeviklik

Bu modeldə hər bir IT xidmət xətti öz rəhbərliyi və idarəetməsi ilə müstəqil bir şöbə kimi fəaliyyət göstərir. Yəni, struktur mərkəzləşdirilmiş deyil və hər bir komanda konkret sahəyə yönəlmiş məqsədlərlə, daha sərbəst qərarlar qəbul edərək işləyir. Bu yanaşma komandaların çevikliyini artırır və onların öz fəaliyyət sahələrində daha tez qərar verməsinə imkan yaradır.

Təşkilati Quruluş:

- **Yuxarı səviyyə:** Ümumi IT strategiyasına nəzarət edən Baş İnformasiya Direktoru (CIO) və ya IT rəhbəri.
- **Orta səviyyə:** Müxtəlif xidmət xətlərinə rəhbərlik edən məsul şəxslər — məsələn, Kibertəhlükəsizlik rəhbəri, İnfrastruktur rəhbəri, Program Təminatı İnkişaf rəhbəri və s.
- **Alt səviyyə:** Hər bir xidmət xətti daxilində öz ixtisasına uyğun fəaliyyət göstərən komandalar. Məsələn, kibertəhlükəsizlik bölməsində analitiklər, infrastruktur sahəsində isə bulud memarları və sistem inzibatçıları çalışır.

Rollar və Əsas Elementlər:

- **Xidmət Xətti Rəhbərləri:** Hər bir xidmət xəttinə rəhbərlik edən şəxslər qərarvermə səlahiyyətinə malikdir və öz komandalarının fəaliyyətinə tam nəzarət edir.
- **Muxtar Komandalar:** Hər bir komanda müstəqil şəkildə işləyir, yəni layihə idarəçiliyi, resurs bölgüsü və qərar qəbul etmə prosesində yüksək azadlığa sahib olur.
- **Mərkəzləşdirilməmiş İdarəetmə:** Bu strukturda qərarlar yerində qəbul edilir, bu da problemlərin daha operativ həllini və dəyişən vəziyyətlərə daha tez uyğunlaşmanı təmin edir. [2,s.66]

Qurulma prinsipi:

Hər bir xidmət xətti öz sahəsində əməliyyatlara, büdcəyə və resurslara nəzarət edir, eyni zamanda ümumi IT strategiyası ilə uyğunluq saxlayır. Komandalar digər biznes bölmələri ilə birbaşa əməkdaşlıq edərək, şirkətin ehtiyaclarına daha tez və dəqiq cavab verirlər.

Nümunə: Bu strukturun istifadə edən şirkətdə Kibertəhlükəsizlik xidmət xətti hüquq şöbəsi ilə birbaşa işləyərək uyğunluq tələblərini yerinə yetirə bilər. Eyni zamanda, infrastruktur xidmət xətti bulud sistemlərinin idarə olunması üçün xarici tərəfdaşlarla müstəqil şəkildə əməkdaşlıq edə bilər. Bu cür yanaşma həm çevikliyi, həm də məsuliyyət bölgüsünü gücləndirir.

3. Leverage strukturu: Daxili komandaların xarici mütəxəssislərlə əməkdaşlığı

Leverage strukturu təşkilat daxilində olan IT komandalarını xarici ekspertlərlə birləşdirərək mövcud resurs və bilik çatışmazlıqlarını aradan qaldırmaq məqsədi daşıyır. Bu modeldə daxili IT heyəti əsas əməliyyatları və gündəlik işləri idarə edir, xarici tərəfdaşlar isə daha ixtisaslaşmış və resurs tələb edən sahələrdə — məsələn, kibertəhlükəsizlik, bulud infrastrukturunun idarə olunması və ya 24/7 monitoring kimi — dəstək göstərirlər. Leverage strukturunun təşkilati quruluşu aşağıdakı kimidir:

- **Yuxarı səviyyə:** IT direktoru və ya CIO həm daxili əməliyyatlara rəhbərlik edir, həm də xarici xidmət təminatçıları ilə əlaqələri və əməkdaşlıq strategiyasını koordinasiya edir.
- **Orta səviyyə:** Daxili IT menecerləri əsas sahələri (şəbəkə, yardım masası və s.) idarə edir, xidmət səviyyəsi menecerləri isə xarici provayderlərin fəaliyyətinə nəzarət edərək SLA (Service Level Agreement) öhdəliklərinin yerinə yetirilməsini təmin edir.
- **Xarici provayderlər:** Kibertəhlükəsizlik, bulud texnologiyaları və digər xüsusi texniki xidmətlər üzrə ixtisaslaşmış tərəfdaşlar kimi fəaliyyət göstərirlər.

Əsas Rollar

- **Daxili IT menecerləri:** Daxili komandalara rəhbərlik edir və gündəlik əməliyyatların sabitliyini qoruyur.
- **Xidmət səviyyəsi menecerləri:** Xarici tərəfdaşlarla əməkdaşlığı izləyir, keyfiyyət və performans göstəricilərinə nəzarət edir.
- **Xarici mütəxəssislər:** Təşkilatın daxilində olmayan ixtisaslaşmış bilik və texnologiyaları təmin edirlər.

Strukturun Qurulması

- **Daxili əsas komanda:** Şirkətin gündəlik fəaliyyətini dəstəkləyən və əsas sistemlərin fasiləsiz işləməsini təmin edən işçilərdən ibarətdir.
- **Xarici ekspertiza:** Xarici provayderlər xüsusi bacarıq tələb edən tapşırıqları, məsələn, kibertəhlükəsizlik monitorinqini, bulud idarəçiliyini və ya fəlakətdən bərpa proseslərini həyata keçirirlər. Bu yanaşma şirkətə həmin sahələr üçün daimi işçi heyəti saxlamaq zərurətini aradan qaldırır. [4,s.85]

Nümunə: Orta ölçülü bir müəssisə öz daxili yardım masası komandasını qoruyub saxlayaraq, kibertəhlükəsizlik üzrə daimi monitorinq və təhdidlərin qarşısının alınması funksiyalarını idarə olunan xidmət təminatçısına (MSP) həvalə edə bilər. Bu yolla şirkət həm resurslardan səmərəli istifadə edir, həm də təhlükəsizlik səviyyəsini artırır.

4. Hibrid struktur: Daxili və xarici komandaların tam integrasiyası

Hibrid struktur leverage modelindən bir addım irəli gedərək, xarici xidmət təminatçılarının təşkilatın IT əməliyyatlarına tam şəkildə daxil edilməsini nəzərdə tutur. Bu yanaşmada xarici tərəfdaşlar artıq sadəcə xidmət göstərən provayder deyil, şirkətin daxili komandalarının bir hissəsi kimi fəaliyyət göstərilir. Onlar biznesin məqsədlərinə nail olmaq üçün daxili işçilərlə sıx əməkdaşlıq edir, eyni proses və strategiyalar çərçivəsində işləyirlər. Hibrid strukturun təşkilati quruluşu aşağıdakı kimi olacaq.

- **Yuxarı səviyyə:** CIO və ya IT direktoru həm daxili, həm də xarici komandaları birləşdirən strateji planlaşdırmanı həyata keçirir və xarici tərəfdaşların şirkətin ümumi IT strategiyasına integrasiyasına nəzarət edir.
- **Orta səviyyə:** Bu mərhələdə daxili IT menecerləri ilə yanaşı, xarici xidmət rəhbərləri də fəaliyyət göstərir. Onlar birlikdə müəyyən xidmət xətlərinə rəhbərlik edir və koordinasiyanı təmin edirlər.
- **Əməliyyat səviyyəsi:** Daxili və xarici mütəxəssislər eyni komandada çalışaraq, məsələn, infrastruktur və ya bulud xidmətləri sahəsində birgə layihələr həyata keçirirlər.

Əsas Rollar

- **İntegrasiya olunmuş komandalar:** Xarici provayderlər artıq şirkətdən kənar tərəfdaş deyil, IT proseslərinin daimi və ayrılmaz hissəsinə çevrilirlər. Onlar çox vaxt ofisdə və ya şirkətin infrastrukturunda birbaşa fəaliyyət göstərilir.
- **Daxili menecerlər:** Hibrid əməkdaşlıq modelinə nəzarət edir, daxili və xarici komandalar arasında qarşılıqlı anlaşmanı və vahid məqsədləri təmin edir.
- **Xarici xidmət rəhbərləri:** Outsorsinq edilmiş IT sahələrinə – məsələn, kibertəhlükəsizlik və ya bulud infrastrukturuna – nəzarət edir və daxili rəhbərliklə sıx əməkdaşlıq edir.

Strukturun Qurulması

- **Bütün səviyyələrdə integrasiya:** Xarici komandalar şirkətin iş proseslərinə və qərarvermə mexanizmlərinə tam şəkildə daxil edilir. Onlar daxili icaslarda iştirak edir, daxili qayda və standartlara uyğun işləyirlər.
- **Xidmət sahələrinin bölüşdürülməsi:** Müəyyən IT istiqamətləri (məsələn, bulud idarəçiliyi və təhlükəsizlik) xarici provayderlərin ixtiyarına verilir, digər sahələr isə daxili komanda tərəfindən idarə olunur. Bu yanaşma həm resursların səmərəli bölgüsünü təmin edir, həm də mütəxəssislərin təcrübəsindən maksimum istifadə imkanını yaradır.

Nümunə: Bir maliyyə xidmətləri şirkəti gündəlik daxili IT əməliyyatlarını öz komandasına həvalə edə, eyni zamanda bulud infrastrukturunun idarə olunmasını və kibertəhlükəsizliyi şirkətin daxili proseslərinə integrasiya olunmuş xarici provayderlərə tapşırıqla bilər. Beləliklə, təşkilat həm çevikliyi artırır, həm də texnoloji təcrübəni daha effektiv şəkildə tətbiq edir. [5,s.170]

IT şöbəsinin əsas məsuliyyətləri

Daha əvvəl qeyd edildiyi kimi, IT şöbəsinin rolu təkcə virusla yoluxmuş kompüterləri bərpa etməklə məhdudlaşmır. Bu şöbə təşkilatın texnoloji infrastrukturunu idarə edən, səmərəliliyi təmin edən və

iş proseslərinin fasiləsizliyinə nəzarət edən əsas qüvvədir. IT mütəxəssisləri həm aparat, həm proqram təminatını, həm də bu sistemlərdə yaranan texniki problemləri idarə edir, eyni zamanda istifadəçilərə operativ texniki dəstək göstərirlər.

IT şöbəsinin strukturunda mövcud olan əsas rollar

Artıq IT şöbəsinin müxtəlif strukturlarını öyrəndikdən sonra, indi bu şöbə daxilində fəaliyyət göstərən əsas vəzifələrə nəzər salaq. Hər bir rolun özünəməxsus funksiyası olsa da, hamısı birlikdə şirkətin texnoloji infrastrukturunu və rəqəmsal inkişafının dayanıqlığını təmin edir.

Baş informasiya direktoru (BİD)-Baş informasiya direktoru şirkətin ümumi texnologiya strategiyasına və onun biznes məqsədləri ilə uyğunluğuna rəhbərlik edir. O, IT əməliyyatlarını nəzarətdə saxlayır, rəqəmsal yenilikləri təşviq edir və digər texnoloji rəhbərlərlə sıx əməkdaşlıq edir. BİD-in əsas məqsədi təşkilatın innovativ potensialını artırmaq, rəqəmsal həllər vasitəsilə rəqəbat üstünlüyü qazanmaq və texnologiyaları biznesin mühüm hissəsinə çevirməkdir.

IT direktoru-IT direktoru şirkətin texnologiya siyasətinin həyata keçirilməsinə rəhbərlik edir. O, IT büdcəsini, resurslarını və komandalarını idarə edir, həmçinin texnoloji investisiyaların şirkətin strateji məqsədlərinə uyğunluğunu təmin edir. Bu vəzifə həm planlaşdırma, həm də qərarvermə səviyyəsində mühüm əhəmiyyət daşıyır — direktor həm əməliyyat proseslərinə, həm də gələcək texnoloji inkişaf istiqamətlərinə nəzarət edir.

IT meneceri-IT meneceri gündəlik texnoloji fəaliyyətlərə rəhbərlik edir, sistemlərin fasiləsiz işləməsinə nəzarət edir və texniki heyətin işini koordinasiya edir. O, layihələrin planlaşdırılması, texniki dəstəyin təşkili və texnologiya resurslarının idarə olunması ilə məşğul olur. Bu rol, şirkətin informasiya texnologiyalarının sabit və effektiv işləməsinə təmin edən əsas mövqelərdən biridir.

Şəbəkə meneceri-Şəbəkə meneceri təşkilatın kompüter şəbəkələrinin idarə olunmasına cavabdehdir. O, serverləri, rabitə sistemlərini və şəbəkə təhlükəsizliyini nəzarətdə saxlayır. Bu vəzifənin əsas məqsədi bütün bölmələr arasında məlumat axınının sabit və təhlükəsiz şəkildə həyata keçirilməsini təmin etməkdir. Şəbəkə menecerləri həmçinin yaranan əlaqə problemlərini aradan qaldırır və infrastrukturun davamlılığını qoruyurlar.

Proqram inkişafı meneceri-Proqram inkişafı meneceri proqram təminatı üzrə komandaya rəhbərlik edir. Onun əsas vəzifəsi tətbiqlərin düzgün işləməsinə, kodun keyfiyyət standartlarına uyğunluğunu və proqram layihələrinin vaxtında icrasını təmin etməkdir. O, proqramçıların işini istiqamətləndirir, texniki qərarlar qəbul edir və tətbiqlərin texniki baxımdan dayanıqlı olmasına nəzarət edir.

Informasiya təhlükəsizliyi meneceri-Bu rol təşkilatın bütün rəqəmsal resurslarının qorunması ilə məşğuldur. Təhlükəsizlik meneceri kibertəhlükəsizlik strategiyalarını müəyyən edir, təhlükə risklərini qiymətləndirir və hücumlara qarşı cavab planlarını hazırlayır. O, həmçinin işçilərə təhlükəsizlik barədə maarifləndirici təlimlər keçir və təşkilatın təhlükəsizlik standartlarına əməl etməsinə təmin edir.

Biznes kəşfiyyatı (bı) meneceri-BI meneceri məlumatların toplanması, saxlanması və təhlili proseslərinə rəhbərlik edir. Onun məqsədi məlumatların düzgün idarə olunması və onlardan əldə edilən nəticələrin qərarvermə prosesinə dəstək olmasıdır. BI menecerləri müxtəlif analitik alətləri və məlumat bazalarını idarə edir, hesabatlar hazırlayır və biznes proseslərinin optimallaşdırılması üçün strateji təkliflər təqdim edirlər.

IT şöbəsinin bu rolları bir-birini tamamlayaraq təşkilatın texnoloji sabitliyini, təhlükəsizliyini və innovativ inkişafını təmin edir. [1,s.190]

IT şöbəsinin strukturunun əsas funksiyaları

IT şöbəsinin funksiyalarını anlamaq səmərəli və balanslı texnoloji komanda qurmaq üçün vacibdir. Hər bir şirkət ölçüsünə, fəaliyyət sahəsinə və strateji məqsədlərinə görə fərqli IT strukturuna malik ola bilər. Yəni, bütün təşkilatlar üçün eyni model uyğun gəlmir — hər biri öz ehtiyaclarına əsaslanaraq struktur formalaşdırır. Aşağıda IT şöbəsinin əsas funksiyalarına və onların roluna daha yaxından baxaq:

İT şöbəsinin əsas funksiyası	Funksiyanın rolu
Yuxarı rəhbərlik	İT rəhbərləri — məsələn, CIO və ya CTO — şöbənin ümumi istiqamətini müəyyən edir və texnoloji strategiyaları biznes planları ilə uzlaşdırırlar. Onların əsas vəzifəsi təşkilatın uzunmüddətli məqsədlərinə uyğun texnoloji inkişaf yolunu formalaşdırmaqdır. Bu rəhbərlər gündəlik əməliyyatlarla strateji planlaşdırmanı tarazlaşdıraraq İT resurslarının effektiv işləməsini təmin edirlər.
Satınalmalar	Satınalma bölməsi şirkətin bütün texnoloji avadanlıqlarının və proqram təminatlarının alınması və idarə edilməsinə cavabdehdir. Onlar tədarükçülərlə danışıqlar aparır, müqavilələr imzalayır və texnoloji xərclərin optimallaşdırılmasına nəzarət edirlər. Həmçinin digər şöbələrin texnologiya tələblərini müəyyən etmək və gələcək investisiya planlarını hazırlamaq üçün onlarla əməkdaşlıq edirlər. [3,s.210]
İnfrastruktur	Bu funksiya təşkilatın texniki əsasını — serverləri, şəbəkələri və məlumat mərkəzlərini — idarə edir. İnfrastruktur komandası sistemlərin dayanıqlı və etibarlı işləməsini təmin edir, həmçinin fəlakətdən bərpa planları və sistem yeniləmələri üzərində işləyir. Güclü İT infrastrukturunu şirkətin fəaliyyətinin fasiləsizliyini qorumaqda mühüm rol oynayır.
Memarlıq (Arxitektura)	Memarlıq qrupu təşkilatın texnoloji sistemlərinin ümumi quruluşunu dizayn edir. Onlar aparat və proqram komponentlərinin necə bir-birinə integrasiya olunacağını planlaşdırır, texnologiya standartlarını müəyyən edir və gələcək inkişaf istiqamətlərini müəyyənləşdirirlər. Bu funksiya şirkətin uzunmüddətli texnoloji sabitliyini təmin edən strateji dayaqlardan biridir.
Əməliyyatlar	Əməliyyat komandası İT xidmətlərinin fasiləsiz işləməsinə cavabdehdir. Onlar yardım masası (help desk) xidmətini idarə edir, sistemlərə texniki xidmət göstərir və istifadəçilərə dəstək təmin edirlər. Əməliyyat qrupu həmçinin sistem yeniləmələrinə nəzarət edir, xidmət səviyyələrini (SLA) qoruyur və texniki problemləri operativ şəkildə həll edir.
Mühəndislik	Mühəndislik bölməsi yeni proqram təminatlarının hazırlanması və texnoloji həllərin tətbiqi ilə məşğuldur. Bu komanda kodlaşdırma, test və proqramların optimallaşdırılması proseslərini həyata keçirir. Onların əsas məqsədi biznes ehtiyaclarını qarşılayan, səmərəli və innovativ texnoloji məhsullar yaratmaqdır.
Təhlükəsizlik	Təhlükəsizlik komandası şirkətin rəqəmsal məlumatlarını qoruyur və kibertəhdidlərə qarşı müdafiə strategiyaları hazırlayır. Onlar təhlükəsizlik qaydalarını tətbiq edir, firewall və antivirus sistemlərini idarə edir, həmçinin işçilərə məlumat təhlükəsizliyi üzrə təlimlər keçirirlər. Bu funksiya şirkətin informasiya aktivlərinin təhlükəsizliyini təmin edir.

İT şöbəsinin əsas funksiyası	Funksiyanın rolu
Biznes Kəşfiyyatı (Business Intelligence – BI)	BI komandası məlumatların toplanması, saxlanması və təhlilinə cavabdehdir. Onlar şirkətin məlumat bazalarını idarə edir, analitik hesabatlar hazırlayır və bu məlumatları qərar qəbul etmə prosesində istifadə üçün təqdim edirlər. Biznes kəşfiyyatı şöbəsi təşkilatın məlumat yönümlü qərarlar verməsinə və strateji baxışını təkmilləşdirməsinə imkan yaradır.

Nəticə:

İT şöbəsi müasir təşkilatların effektiv fəaliyyət göstərməsində əsas strateji rol oynayır. Onun düzgün qurulmuş strukturu şirkət daxilində informasiya axınının sabitliyini və təhlükəsizliyini təmin edir. Şöbənin hər bir rolunun – texniki dəstəkdən tutmuş sistem administratoruna qədər – özünəməxsus funksiyası vardır və bu funksiyalar bir-birini tamamlayır. İnnovasiyaların tətbiqi və rəqəmsal transformasiya prosesləri də məhz İT şöbəsinin təşəbbüsü və dəstəyi ilə həyata keçirilir. Müasir dövrdə İT şöbəsi yalnız texniki problemlərin həllinə cavabdeh deyil, həm də biznesin inkişaf strategiyasına töhfə verən bir bölmədir. Güclü İT idarəçiliyi şirkətin rəqəbat qabiliyyətini artırır və əməliyyat xərclərini optimallaşdırır. Məlumatların təhlükəsiz saxlanması və kibertəhlükəsizlik tədbirləri isə bu şöbənin prioritet istiqamətlərindən biridir. Əməkdaşların peşəkar bacarıqlarının davamlı inkişafı İT şöbəsinin uğurunun əsas şərtlərindən sayılır. Hər bir təşkilat öz İT strukturunu məqsədlərinə uyğun şəkildə formalaşdırmalı və onu daim yeniləməlidir. Beləliklə, İT şöbəsi şirkətin dayanıqlı inkişafının və rəqəmsal gələcəyinin təminatçısına çevrilir.

Ədəbiyyat siyahısı

1. Terry White, Reinventing the IT Department, 2012, 368.
2. David E. Eisner, Why You Should Build Your Business Not Your It Department, 2015, 160.
3. Xiaoying Dong, Yan Yu, Jiali Zhou,. Integration of Innovation and Operation, 2023, 221.
4. Mario C. Martinez, Brandy Smith, Katie Humphreys, Creating a Service Culture in Higher Education Administration, 2023, 126.
5. Sri Adusumilli, IT Strategy & Governance Explained, 2016, 250.
6. Noel Bruton, Managing the IT Services Process, 2012, 256.

İOT SİSTEMLƏRİNDƏ KİBERTƏHLÜKƏSİZLİK RİSKLƏRİ VƏ ONLARIN AZALDILMASI ÜSULLARI

Baxşəliyeva Gülcənnət Turab

Azərbaycan Dövlət İqtisad Universiteti, Bakı, Azərbaycan

XÜLASƏ

Əşyaların İnterneti (İoT) sistemlərinin sürətlə yayılması gündəlik həyatı və sənaye əməliyyatlarını əhəmiyyətli dərəcədə dəyişdirib. Lakin cihazlar arasında problemsiz əlaqə məlumatların bütövlüyü, məxfilik və sistemin əlçatanlığı üçün ciddi təhlükələr yaradır. Çox vaxt məhdud resurslara malik olan İoT cihazları güclü təhlükəsizlik mexanizmləri ilə təmin olunmur və bu onları icazəsiz giriş, məlumat sızmaları, zərərli proqramların yayılması və DDoS hücumları kimi təhdidlərə qarşı həssas edir. Bundan əlavə, cihazların və kommunikasiya protokollarının heterogenliyi standart təhlükəsizlik tədbirlərinin tətbiqini çətinləşdirir və ekosistemin bütövlüyünü risk altında qoyur.

Bu təhlükələri azaltmaq üçün çoxsəviyyəli təhlükəsizlik yanaşmaları tətbiq olunmalıdır. Buraya yüngül şifrələmə metodları, təhlükəsiz autentifikasiya protokolları, şəbəkə segmentasiyası, davamlı monitoring və anomaliya aşkarlama sistemləri daxildir. Eyni zamanda proqram təminatının müntəzəm yenilənməsi və ətraflı təhlükəsizlik siyasətlərinin yaradılması potensial hücumların qarşısını almağa kömək edir. Belə tədbirlər İoT infrastrukturunun dayanıqlığını artırır və təhlükəsizliyi qoruyaraq cihazların effektiv və etibarlı işləməsini təmin edir.

Açar sözlər: *Internet of Things (IoT), Kibertəhlükəsizlik riskləri, Məlumatların məxfiliyi və bütövlüyü, Çoxsəviyyəli təhlükəsizlik yanaşması, Anomaliya aşkarlama sistemləri*

GİRİŞ

Müasir rəqəmsal transformasiya prosesində fiziki obyektlərin şəbəkə üzərindən integrasiyası və məlumat mübadiləsinin avtomatlaşdırılması qlobal informasiya infrastrukturunun əsas istiqamətlərindən birinə çevrilmişdir. Bu kontekstdə **Internet of Things (IoT)** konsepsiyası cihazların, sensorların və sistemlərin qarşılıqlı əlaqəsini təmin edən kompleks texnoloji mühit kimi formalaşmışdır.

İoT sistemləri sənaye, nəqliyyat, səhiyyə, enerji və ağıllı şəhər infrastrukturlarında geniş tətbiq olunur. Lakin İoT texnologiyalarının sürətli inkişafı ilə paralel olaraq kibertəhlükəsizlik riskləri də artmışdır. Cihazların məhdud hesablama resursları, heterogen arxitektura və geniş hücum səthi İoT sistemlərini ənənəvi informasiya sistemlərindən daha həssas edir.

İOT SİSTEMLƏRİNİN KONSEPTUAL ƏSASLARI VƏ ARXİTEKTURASI

Müasir rəqəmsal transformasiya prosesinin əsas istiqamətlərindən biri fiziki obyektlərin informasiya-kommunikasiya texnologiyaları vasitəsilə integrasiyasıdır. Bu kontekstdə Internet of Things (IoT) konsepsiyası fiziki və virtual mühitlər arasında fasiləsiz məlumat mübadiləsinə təmin edən paylanmış, çoxsəviyyəli və dinamik sistem kimi formalaşmışdır. İoT sistemləri sensorlar, aktuatorlar, hesablama qurğuları, rabitə infrastrukturunu və proqram platformalarının qarşılıqlı

əlaqəsi əsasında fəaliyyət göstərir və real vaxt rejimində məlumatların toplanması, ötürülməsi, emalı və qərar qəbul etməni təmin edir.

1. Konseptual əsaslar

IoT konsepsiyası aşağıdakı fundamental prinsiplərə əsaslanır:

1. Obyektlərin unikal identifikasiyası.

Hər bir cihaz və ya obyekt şəbəkədə unikal identifikator vasitəsilə tanınır. Bu, sistem daxilində düzgün ünvanlanma və təhlükəsiz əlaqə üçün zəruridir.

2. Məlumatların avtomatlaşdırılmış toplanması və emalı.

Sensor texnologiyaları fiziki mühitə dair məlumatları (temperatur, rütubət, hərəkət, təzyiq və s.) toplayaraq rəqəmsal formaya çevirir. Bu məlumatlar lokal və ya bulud əsaslı platformalarda emal olunur.

3. Qarşılıqlı əlaqəlilik (interoperabilitet).

IoT sistemləri heterogen qurğuların vahid ekosistemdə işləməsini təmin etməlidir. Bu isə standartlaşdırılmış protokollar və açıq interfeyslər vasitəsilə mümkün olur.

4. Paylanmış arxitektura və miqyaslı bilənlik.

IoT infrastrukturunu geniş miqyaslı şəbəkə quruluşuna malikdir və cihazların sayının artmasına uyğun olaraq elastik şəkildə genişlənmə bilər.

5. Real vaxt rejimində fəaliyyət.

Bir çox IoT tətbiqləri (məsələn, sənaye avtomatlaşdırması və ya ağıllı nəqliyyat sistemləri) gecikməyə həssasdır və operativ qərar mexanizmləri tələb edir.

2. IoT arxitekturası

IoT sistemlərinin arxitekturası adətən çoxsəviyyəli model əsasında təsvir edilir. Ən geniş yayılmış model dörd səviyyədən ibarətdir.

1. Qavrama (Perception) səviyyəsi

Bu səviyyə fiziki mühitlə birbaşa əlaqədə olan sensorlar və aktuatorlardan ibarətdir. Sensorlar məlumatları toplayır, aktuatorlar isə sistemin qərarlarına uyğun olaraq fiziki əməliyyatları yerinə yetirir. Bu mərhələ IoT sisteminin "fiziki interfeysi" hesab olunur.

2. Şəbəkə (Network) səviyyəsi

Toplanmış məlumatların ötürülməsi və yönləndirilməsi bu səviyyədə həyata keçirilir. Müxtəlif rabitə texnologiyaları (Wi-Fi, Bluetooth, mobil şəbəkələr və s.) məlumat axınıni təmin edir. Şəbəkə səviyyəsində marşrutlaşdırma, trafik idarəetməsi və təhlükəsizlik mexanizmləri mühüm rol oynayır.

3. Emal və xidmət (Processing/Service) səviyyəsi

Bu mərhələdə məlumatların analizi, saxlanması və idarə olunması həyata keçirilir. Bulud texnologiyaları və "edge computing" həlləri məlumatların emalını sürətləndirir və sistemin səmərəliliyini artırır.

4. Tətbiq (Application) səviyyəsi

Son istifadəçi ilə qarşılıqlı əlaqə bu səviyyədə baş verir. Ağıllı ev sistemləri, sənaye monitoring platformaları və səhiyyə tətbiqləri bu mərhələyə aiddir. Bu səviyyə sistemin funksional məqsədini reallaşdırır.

IoT SİSTEMLƏRİNDƏ ƏSAS KİBERTƏHLÜKƏSİZLİK RİSKLƏRİ

Müasir rəqəmsal ekosistemdə Internet of Things (IoT) sistemlərinin geniş tətbiqi fiziki və virtual mühit arasında fasiləsiz məlumat mübadiləsini təmin etsə də, bu integrasiya kibertəhlükəsizlik baxımından çoxşaxəli və kompleks risklər formalaşdırır. IoT infrastrukturunu çoxsaylı sensorlar, aktuatorlar, şəbəkə qurğuları, bulud platformaları və tətbiq proqramlarından

ibarət paylanmış sistem olduğu üçün onun hər bir səviyyəsi potensial hücum nöqtəsi hesab oluna bilər. Bu səbəbdən IoT mühitində təhlükəsizlik riskləri ənənəvi informasiya sistemləri ilə müqayisədə daha geniş hücum səthi və daha mürəkkəb təhdid modelləri ilə xarakterizə olunur.

1. Məxfilik riskləri

IoT cihazları istifadəçilərin şəxsi məlumatları, yerləşmə koordinatları, biometrik göstəriciləri və sənaye proseslərinə dair həssas informasiyaları toplayır. Rabitə kanallarının kifayət qədər qorunmaması və ya zəif şifrələmə mexanizmlərinin tətbiqi nəticəsində bu məlumatlar icazəsiz şəxslər tərəfindən ələ keçirilə bilər.

Məxfilik riskləri əsasən aşağıdakı hallarda yaranır:

- Şifrələnməmiş və ya zəif qorunan məlumat ötürülməsi;
- Standart parol və identifikasiya mexanizmlərinin dəyişdirilməməsi;
- Bulud platformalarında qeyri-kafi giriş nəzarəti;
- Cihazların fiziki müdaxiləyə açıq olması.

Məxfilik pozuntuları təkcə fərdi istifadəçilər üçün deyil, həm də dövlət və sənaye strukturları üçün strateji təhlükə yarada bilər.

2. Məlumat bütövlüyünün pozulması

Məlumat bütövlüyü informasiyanın dəyişdirilmədən və saxtalaşdırılmadan ötürülməsini və saxlanması nəzərdə tutur. IoT sistemlərində sensor məlumatlarının manipulyasiyası yanlış qərarların qəbul edilməsinə səbəb ola bilər.

Xüsusilə sənaye və enerji sektorunda IoT sistemlərinin idarə etdiyi proseslərdə məlumatların dəyişdirilməsi istehsalat dayanmasına, avadanlıq zədələnməsinə və hətta fiziki təhlükəsizlik risklərinə gətirib çıxara bilər. Hücumçular “man-in-the-middle” və ya saxta məlumat inyeksiyası üsullarından istifadə edərək sistem davranışını dəyişə bilərlər.

3. Xidmətin əlçatanlığının pozulması (Availability riskləri)

IoT sistemləri çox zaman real vaxt rejimində fəaliyyət göstərir və fasiləsiz işləməsi zəruridir. Paylanmış xidmət inkarı (DDoS) hücumları IoT infrastrukturunu üçün ciddi təhlükə yaradır.

Tarixi nümunələrdən biri kimi Mirai botneti zəif qorunan IoT cihazlarını ələ keçirərək genişmiqyaslı hücumlar həyata keçirmiş və böyük internet xidmətlərinin fəaliyyətini müvəqqəti olaraq dayandırmışdır. Bu hadisə IoT cihazlarının kollektiv şəkildə hücum alətinə çevrilə bilməsini nümayiş etdirmişdir.

Əlçatanlıq riskləri aşağıdakı formalarda təzahür edə bilər:

- Şəbəkə trafikinin həddindən artıq yüklənməsi;
- Cihaz resurslarının istismar edilməsi;
- Enerji mənbələrinin tükəndirilməsi;
- İdarəetmə serverlərinin bloklanması.

4. Zərərli proqram təminatı və botnetlər

IoT cihazlarında antivirus və digər qoruyucu mexanizmlərin məhdud olması zərərli proqramların yayılmasını asanlaşdırır. Firmware zəiflikləri və standart konfiqurasiya parametrləri hücumçular üçün əlverişli şərait yaradır.

Zərərli proqramlar vasitəsilə cihaz üzərində uzaqdan idarəetmə əldə edilə bilər, məlumatlar gizli şəkildə ötürülə bilər və sistem digər şəbəkələrə qarşı hücum platformasına çevrilə bilər.

5. Autentifikasiya və giriş nəzarəti zəiflikləri

Bir çox IoT cihazları ilkin olaraq standart istifadəçi adı və parol ilə təqdim olunur. İstifadəçilər bu məlumatları dəyişdirmədikdə sistem icazəsiz giriş üçün açıq qalır. Sertifikat əsaslı

identifikasiya mexanizmlərinin olmaması və ya düzgün konfigurasiya edilməməsi təhlükəsizlik səviyyəsini aşağı salır.

6. Cihazların heterogenliyi və standartlaşdırma problemləri

IoT ekosistemində müxtəlif istehsalçıların cihazları və fərqli platformalar istifadə olunur. Bu heterogenlik vahid təhlükəsizlik standartının tətbiqini çətinləşdirir. Müxtəlif protokollar və interfeyslər əlavə integrasiya mexanizmləri tələb edir ki, bu da yeni zəifliklərin yaranmasına səbəb ola bilər.

7. Fiziki təhlükəsizlik riskləri

IoT cihazları çox zaman açıq və nəzarətsiz mühitlərdə yerləşdirilir. Fiziki müdaxilə nəticəsində cihazın proqram təminatı dəyişdirilə, məlumatlar çıxarıl və ya sistemə zərərli kod yerləşdirilə bilər. Bu risk xüsusilə ictimai infrastruktur və sənaye obyektlərində əhəmiyyətlidir.

8. Təchizat zənciri (supply chain) riskləri

Cihazların istehsal və paylanma mərhələsində təhlükəsizlik nəzarətinin zəif olması arxa qapı (backdoor) mexanizmlərinin və ya gizli zəifliklərin sistemə daxil olmasına şərait yarada bilər. Təchizat zənciri riskləri IoT təhlükəsizliyinin qlobal xarakter daşdığını göstərir.

RİSKLƏRİN TEXNİKİ VƏ TƏŞKİLATİ SƏBƏBLƏRİ

IoT mühitində kibertəhlükəsizlik risklərinin formalaşması təsadüfi xarakter daşmır. Bu risklər sistemin arxitektura xüsusiyyətləri, texniki məhdudiyyətləri və idarəetmə mexanizmlərinin qeyri-kafi təşkili ilə birbaşa bağlıdır. Internet of Things (IoT) ekosisteminin çoxsəviyyəli, paylanmış və heterogen quruluşu təhlükəsizlik problemlərinin həm texniki, həm də təşkilati aspektlərdə yaranmasına şərait yaradır. Bu səbəbdən risklərin mahiyyətini anlamaq üçün onların yaranma səbəblərinin kompleks təhlili zəruridir.

1. Risklərin texniki səbəbləri

1. Resurs məhdudiyyətləri

IoT cihazlarının böyük əksəriyyəti məhdud hesablama gücü, yaddaş və enerji ehtiyatına malikdir. Bu məhdudiyyətlər güclü kriptografik alqoritmlərin və mürəkkəb təhlükəsizlik mexanizmlərinin tətbiqini çətinləşdirir. Nəticədə istehsalçılar təhlükəsizlikdən daha çox funksionallığa üstünlük verə bilər, bu isə sistemin hücumlara qarşı həssaslığını artırır.

2. Heterogen arxitektura və standartlaşdırma çatışmazlığı

IoT ekosistemində müxtəlif istehsalçıların fərqli aparat və proqram platformaları mövcuddur. Vahid təhlükəsizlik standartının olmaması cihazlar arasında integrasiyanı mürəkkəbləşdirir və təhlükəsizlik mexanizmlərinin vahid şəkildə tətbiqini çətinləşdirir. Bu müxtəliflik əlavə konfigurasiya səhvlərinə və uyğunluq problemlərinə səbəb ola bilər.

3. Zəif autentifikasiya və şifrələmə mexanizmləri

Bir çox IoT cihazı standart istifadəçi adı və parol ilə təqdim olunur. Güclü autentifikasiya və açar idarəetmə mexanizmlərinin olmaması icazəsiz giriş riskini artırır. Bundan əlavə, məlumat ötürülməsi zamanı şifrələmə tətbiq edilmədikdə və ya zəif alqoritmlərdən istifadə olunduqda rabitə kanalları asanlıqla ələ keçirilə bilər.

4. Proqram təminatının yenilənməməsi

Firmware və proqram təminatının müntəzəm yenilənməməsi məlum zəifliklərin uzun müddət açıq qalmasına səbəb olur. Avtomatlaşdırılmış "patch management" mexanizmlərinin olmaması risklərin kumulyativ şəkildə artmasına gətirib çıxarır.

5. Şəbəkə arxitekturasının qeyri-optimal qurulması

IoT cihazlarının əsas korporativ şəbəkə ilə eyni segmentdə yerləşdirilməsi hücumların sürətli yayılmasına şərait yaradır. Segmentasiya və trafik filtrasiyasının düzgün tətbiq edilməməsi hücum səthini genişləndirir.

6. Təchizat zənciri zəiflikləri

Cihazların istehsal və paylanma mərhələsində təhlükəsizlik nəzarətinin qeyri-kafi olması arxa qapı mexanizmlərinin və ya gizli zəifliklərin sistemə daxil olmasına səbəb ola bilər. Təchizat zənciri riskləri xüsusilə global miqyaslı IoT layihələrində daha kəskin şəkildə özünü göstərir.

2. Risklərin təşkilati səbəbləri

1. Təhlükəsizlik strategiyasının olmaması

Bir çox təşkilat IoT həllərini tətbiq edərkən funksionallığı prioritet hesab edir və təhlükəsizlik strategiyasını sonrakı mərhələyə saxlayır. Bu isə sistemin ilkin dizayn mərhələsində təhlükəsizlik prinsiplərinin nəzərə alınmamasına gətirib çıxarır.

2. Risk qiymətləndirilməsinin aparılmaması

IoT sistemləri tətbiq edilməzdən əvvəl risklərin sistemli təhlili və təhlükə modelləşdirilməsi aparılmadıqda potensial zəifliklər müəyyən edilmir. Nəticədə təhlükəsizlik tədbirləri reaktiv xarakter daşıyır.

3. Kadr hazırlığı və təhlükəsizlik savadlılığının aşağı səviyyəsi

İstifadəçilərin və texniki personalın kibertəhlükəsizlik üzrə yetərli biliklərə malik olmaması yanlış konfigurasiyalara və zəif parol siyasətinə səbəb olur. İnsan faktoru IoT mühitində risklərin mühüm mənbələrindən biridir.

4. Siyasət və prosedurların qeyri-kafiliyi

Təhlükəsizlik siyasətlərinin və daxili prosedurların olmaması və ya qeyri-müntəzəm yenilənməsi idarəetmə boşluqları yaradır. Xüsusilə giriş nəzarəti, hadisə idarəetməsi və ehtiyat nüsxələmə siyasətlərinin zəif təşkili riskləri artırır.

5. Büdcə məhdudiyyətləri

IoT layihələrində təhlükəsizlik tədbirləri əlavə xərc kimi qiymətləndirildikdə, minimal müdafiə mexanizmləri ilə kifayətlənilir. Bu yanaşma uzunmüddətli perspektivdə daha böyük iqtisadi zərərlərə səbəb ola bilər.

6. Hüquqi və tənzimləyici çərçivənin yetərsizliyi

IoT təhlükəsizliyinə dair vahid beynəlxalq standartların və məcburi tələblərin olmaması təşkilatların təhlükəsizlik səviyyəsini fərqli səviyyələrdə saxlamasına səbəb olur. Normativ tələblərin qeyri-müəyyənliyi risklərin artmasına şərait yaradır.

IoT SİSTEMLƏRİNDƏ RİSKLƏRİN AZALDILMASI ÜSULLARI

Müasir rəqəmsal mühitdə Internet of Things (IoT) sistemlərinin təhlükəsiz fəaliyyətinin təmin edilməsi çoxsəviyyəli və integrasiya olunmuş müdafiə strategiyasının tətbiqini tələb edir. IoT arxitekturasının paylanmış və heterogen xarakter daşması səbəbindən risklərin azaldılması yalnız bir texniki tədbirlə mümkün deyil. Təhlükəsizlik mexanizmləri cihaz səviyyəsindən başlayaraq şəbəkə, platforma və tətbiq qatına qədər bütün infrastrukturunu əhatə etməlidir.

IoT mühitində risklərin azaldılması üsulları texniki, təşkilati və hüquqi tədbirlərin vəhdəti əsasında həyata keçirilməlidir. Aşağıda əsas istiqamətlər sistemli şəkildə təqdim olunur.

1. Texniki tədbirlər

1. Yüngül kriptografik mexanizmlərin tətbiqi

IoT cihazlarının məhdud resursları nəzərə alınaraq optimallaşdırılmış şifrələmə alqoritmlərindən istifadə olunmalıdır. Simmetrik açar əsaslı kriptografiya və resurslara qənaət edən autentifikasiya protokolları məlumatların məxfiliyini və bütövlüyünü qorumağa imkan verir.

2. Güclü autentifikasiya və identifikasiya

Cihaz və istifadəçi identifikasiyası üçün sertifikat əsaslı mexanizmlər və çoxfaktorlu autentifikasiya tətbiq edilməlidir. Standart parol siyasətləri dəyişdirilməli və unikal identifikasiya sistemləri qurulmalıdır.

3. Şəbəkə seqmentasiyası və mikroseqmentasiya

IoT cihazlarının əsas korporativ şəbəkədən ayrılması və ayrıca təhlükəsizlik zonalarında yerləşdirilməsi hücumların yayılma miqyasını məhdudlaşdırır. Mikroseqmentasiya modeli hər cihaz və ya xidmət üçün ayrıca təhlükəsizlik siyasətinin tətbiqinə imkan verir.

4. Davamlı monitoring və anomaliya aşkarlama

Şəbəkə trafiki və cihaz davranışları davamlı izlənməli, qeyri-adi fəaliyyətlər erkən mərhələdə müəyyən edilməlidir. Süni intellekt və maşın öyrənməsi əsaslı sistemlər anomaliyaların aşkarlanmasında effektiv vasitə hesab olunur.

5. Proqram təminatının müntəzəm yenilənməsi

Firmware və proqram təminatının avtomatlaşdırılmış yenilənməsi məlum zəifliklərin aradan qaldırılmasına xidmət edir. "Patch management" mexanizmi IoT təhlükəsizliyinin əsas elementlərindən biridir.

6. Təhlükəsiz konfigurasiya və standart parametrlərin dəyişdirilməsi

İlkin quraşdırma zamanı standart istifadəçi adı və parollar dəyişdirilməli, istifadə olunmayan port və xidmətlər deaktiv edilməlidir.

2. Təşkilati tədbirlər

- Risklərin ilkin və periodik qiymətləndirilməsi
- Təhlükəsizlik siyasətlərinin hazırlanması və icrası
- Hadisələrin idarə olunması planının (incident response plan) yaradılması
- Personal üçün müntəzəm kibertəhlükəsizlik təlimlərinin təşkili
- Təchizat zənciri təhlükəsizliyinin qiymətləndirilməsi

3. Hüquqi və normativ tədbirlər

- Məlumatların qorunması üzrə normativ tələblərə uyğunluq
- Sertifikatlaşdırma və standartlaşdırma mexanizmlərinin tətbiqi
- Müqavilələrdə təhlükəsizlik öhdəliklərinin müəyyənəşdirilməsi

Cədvəl 1. IoT sistemlərində risklərin azaldılması üsullarının ümumiləşdirilmiş cədvəli

Risk kateqoriyası	Azaldılma üsulu	Tətbiq səviyyəsi	Gözlənilən nəticə
Məxfilik riskləri	Yüngül kriptografiya və TLS/SSL tətbiqi	Cihaz və şəbəkə	Məlumatların qorunması
İcazəsiz giriş	Çoxfaktorlu autentifikasiya	Tətbiq və idarəetmə	Giriş nəzarətinin gücləndirilməsi
DDoS hücumları	Şəbəkə segmentasiyası və firewall	Şəbəkə	Hücumların lokallaşdırılması
Zərərli proqramlar	Firmware yenilənməsi və imza yoxlaması	Cihaz	Yoluxma riskinin azaldılması
Anomaliyalar	Davamlı monitoring və SIEM sistemləri	Platforma	Erkən xəbərdarlıq və müdaxilə
Konfigurasiya səhvləri	Təhlükəsiz ilkin konfigurasiya	Cihaz və şəbəkə	Hücum səthinin azaldılması
Təchizat zənciri riski	Təchizatçı auditləri	Təşkilati	Gizli zəifliklərin qarşısının alınması

NƏTİCƏ

IoT sistemlərinin geniş tətbiqi müasir cəmiyyət üçün böyük imkanlar yaratsa da, kibertəhlükəsizlik baxımından ciddi risklər formalaşdırır. Məxfilik, bütövlük və əlçatanlıq prinsiplərinin qorunması üçün texniki və təşkilati tədbirlərin kompleks şəkildə tətbiqi zəruridir.

Yüngül kriptografiya, güclü autentifikasiya, şəbəkə segmentasiyası, davamlı monitoring və müntəzəm yeniləmələr IoT mühitində risklərin azaldılmasının əsas istiqamətlərini təşkil edir. Sistemli və çoxsəviyyəli təhlükəsizlik yanaşması tətbiq edildikdə IoT infrastrukturunu həm effektiv, həm də etibarlı şəkildə fəaliyyət göstərə bilər.

ƏDƏBİYYAT

1. Alaba, F. A., Othman, M., Hashem, I. A. T., & Alotaibi, F. (2017). Internet of Things security: A survey. *Journal of Network and Computer Applications*, 88, 10–28.
2. Atzori, L., Iera, A., & Morabito, G. (2010). The Internet of Things: A survey. *Computer Networks*, 54(15), 2787–2805.
3. Borgia, E. (2014). The Internet of Things vision: Key features, applications and open issues. *Computer Communications*, 54, 1–31.
4. Conti, M., Dehghantanha, A., Franke, K., & Watson, S. (2018). Internet of Things security and forensics: Challenges and opportunities. *Future Generation Computer Systems*, 78, 544–546.
5. Sicari, S., Rizzardi, A., Grieco, L. A., & Coen-Porisini, A. (2015). Security, privacy and trust in Internet of Things: The road ahead. *Computer Networks*, 76, 146–164.
6. Weber, R. H. (2010). Internet of Things – New security and privacy challenges. *Computer Law & Security Review*, 26(1), 23–30.
7. Kolias, C., Kambourakis, G., Stavrou, A., & Voas, J. (2017). DDoS in the IoT: Mirai and other botnets. *Computer*, 50(7), 80–84.

Yaşıl artımın təmin edilməsi üçün rəqəmsal platformaların formalaşdırılması və İT həllərinin rolu

Abbasəliyeva Gülşanə

Magistrant, Azərbaycan Dövlət İqtisad Universiteti

Açar sözlər: yaşıl artım, rəqəmsal platforma, İT

Xülasə: Yaşıl artım iqtisadi inkişafı ekoloji dayanıqlılığın uzlaşdırılmasına yönəlmiş müasir inkişaf modelidir. Bu yanaşma resurs istifadəsi ilə iqtisadi artım arasındakı əlaqənin zəiflədilməsini hədəfləyir. Rəqəmsal platformalar və informasiya texnologiyaları bu prosesdə əsas rol oynayır. IoT sensorları, süni intellekt və bulud hesablama resursların real vaxtda monitorinqini təmin edir. Rəqəmsal əkizlər və böyük verilənlər analitikası optimallaşdırma və proqnozlaşdırmanı gücləndirir. Bu sistemlər enerji səmərəliliyini artırır və emissiyaların azaldılmasına imkan yaradır. Platforma arxitekturası çoxqatlı quruluş, interoperabellik və kibertəhlükəsizlik prinsiplərinə əsaslanır. Nəticədə yaşıl artım rəqəmsal transformasiya ilə inteqrasiya olunmuş dayanıqlı inkişaf modelinə çevrilir. İnformasiya sistemlərinin inteqrasiyası, açıq standartlar və API əsaslı mübadilə platformaların genişlənəbilənliyini təmin edir. Bu yanaşma enerji, su və tullantı idarəetməsində ölçülə bilən və idarəolunan rəqəmsal ekosistem yaradır. Süni intellekt əsaslı proqnozlar qərarvermə keyfiyyətini yüksəldir və resurs optimallaşdırmasını daha effektiv edir. Beləliklə, rəqəmsal platformalar yaşıl iqtisadiyyatın texnoloji dayağı kimi çıxış edir. Bu proses davamlı innovasiya tələb edir və idarəetmənin rəqəmsallaşmasını sürətləndirir qlobal səviyyədə təsir göstərir.

Yaşıl artım anlayışı müasir elmi və texnoloji diskursda iqtisadi genişlənmə ilə ekoloji dayanıqlılıq arasında yaranmış ziddiyyətin aradan qaldırılmasına yönələn konseptual çərçivə kimi formalaşmışdır. Ənənəvi inkişaf modellərində istehsal həcmının artması, enerji istehlakının genişlənməsi, xammal istifadəsinin intensivləşməsi və tullantı yüklənməsinin çoxalması artımın təbii nəticəsi hesab edilirdi. Lakin sənaye cəmiyyətinin sonrakı mərhələlərində aydın oldu ki, təbii resursların məhdudluğu, ekosistemlərin degradasiyası, karbon emissiyalarının artması, su qıtlığı, biomüxtəlifliyin azalması və iqlim dəyişməsinin sistemli təsirləri klassik artım modelinin uzunmüddətli dayanıqlılığını zəiflədir. Məhz bu nöqtədə yaşıl artım anlayışı sadəcə ekoloji həssaslıq çağırışı kimi deyil, iqtisadi inkişafın texnoloji, institusional və idarəetmə əsaslarının yenidən qurulmasını tələb edən nəzəri platforma kimi meydana çıxmışdır. OECD yaşıl artımı iqtisadi artım və inkişafın davam etməsini təmin edən, eyni zamanda təbii aktivlərin insan rifahı üçün zəruri olan resurs və ekosistem xidmətlərini təqdim etmək qabiliyyətini qoruyan yanaşma kimi təqdim edir [4].

Bu tərifin elmi çəkisi ondan ibarətdir ki, yaşıl artım iqtisadi artıma alternativ model deyil, artımın keyfiyyətini dəyişən model kimi anlaşılır. Burada əsas məsələ iqtisadi fəaliyyəti dayandırmaq və ya istehsal miqyasını inzibati yolla azaltmaq deyildir. Əsas məsələ istehsal və istehlak sistemlərini elə transformasiya etməkdir ki, ÜDM artımı ilə resurs degradasiyası arasındakı bilavasitə əlaqə zəifləsin, enerji və material tutumu aşağı düşsün, emissiya intensivliyi azalsın və innovasiya əsasında yeni səmərəlilik səviyyəsi formalaşsın. Bu baxımdan yaşıl artım “az inkişaf” və ya “anti-sənaye” yanaşması deyil. Əksinə, həmin anlayış elmi-texniki tərəqqini, yeni nəsil istehsal texnologiyalarını, rəqəmsallaşmanı, ağıllı idarəetməni və resurs səmərəliliyini inkişafın əsas aləti kimi qəbul edir. Buna görə yaşıl artım konsepsiyası xüsusilə informasiya texnologiyaları və sistemləri mühəndisliyi sahəsi üçün mühüm əhəmiyyət daşıyır. Çünki bu modelin əməli həyata keçirilməsi çox

hallarda ölçülə bilənlik, monitoring, avtomatlaşdırma, proqnozlaşdırma və optimallaşdırma kimi rəqəmsal funksiyalardan asılı olur.

Yaşıl artım anlayışının mahiyyətini daha aydın başa düşmək üçün onu ənənəvi iqtisadi artım modelindən fərqləndirən əsas cəhətləri göstərmək vacibdir. Ənənəvi modeldə səmərəlilik daha çox əmək məhsuldarlığı, kapital gəlirliliyi və bazar genişlənməsi ilə ölçülür. Yaşıl artım modelində isə bu göstəricilərə əlavə olaraq enerji məhsuldarlığı, su məhsuldarlığı, material səmərəliliyi, emissiya intensivliyi, tullantıların dövriyyəsi və ekoloji iz kimi indikatorlar da daxil edilir. Bu dəyişiklik təkcə nəzəri indikator fərqi yaratmır. O, həm də idarəetmə sistemlərinin mahiyyətini dəyişir. Çünki yeni göstəricilərin izlənməsi üçün klassik mühasibat və statistik hesabat mexanizmləri kifayət etmir. Burada real vaxt məlumatları, sensor infrastruktur, paylanmış informasiya sistemləri, böyük verilənlər analitikası və qərar dəstəyi platformaları tələb olunur. Deməli, yaşıl artımın texnoloji məntiqi başlanğıcdan rəqəmsaldır.

Yaşıl artım anlayışı ilə “yaşıl iqtisadiyyat” anlayışı bir-biri ilə sıx bağlı olsa da, onların semantik vurğusu tam eyni deyildir. Yaşıl iqtisadiyyat daha geniş makrostruktur, yəni iqtisadiyyatın ümumi sektoral istiqamətini, dövlət siyasətini, investisiya prioritetlərini və sosial-ekoloji nəticələri əhatə edir. Yaşıl artım isə həmin transformasiyanın dinamik tərəfini, başqa sözlə, artım prosesinin hansı keyfiyyət parametrləri əsasında həyata keçirilməsini izah edir. UNEP-in yaşıl iqtisadiyyat hesabatında göstərilir ki, aşağı karbonlu, resurs səmərəli və sosial baxımdan inklüziv inkişaf trayektoriyası üçün əsas məsələ kapital axınlarının ekoloji cəhətdən üstün sektorlara yönəldilməsidir və bu keçid uzunmüddətli rifah yaradılmasına xidmət edir. Bu yanaşma yaşıl artımın sadəcə ekoloji normativlər toplusu olmadığını, əksinə, iqtisadi sistemin struktur yenilənməsinin əsas komponenti olduğunu təsdiqləyir.

Yaşıl artımın əsas prinsiplial xüsusiyyətlərindən biri artım ilə resurs istifadəsi arasındakı əlaqənin yenidən qurulmasıdır. Klassik sənaye modelində artım üçün daha çox enerji, daha çox xammal və daha çox fiziki istehsal tələb olunurdu. Yaşıl artım yanaşmasında isə məqsəd eyni və ya daha yüksək iqtisadi nəticəni daha az resurs sərfi ilə əldə etməkdir. Bu yanaşma “decoupling” kimi tanınan ayrışma prinsipi ilə ifadə olunur. Ayrışma dedikdə iqtisadi artım tempinin resurs istehlakı və ekoloji təzyiq artımından ayrılması nəzərdə tutulur. Belə ayrışma sadəcə niyyət bəyanatı ilə baş vermir. Onun üçün texnoloji modernləşmə, proses optimallaşdırması, enerji səmərəli avadanlıqlar, dairəvi iqtisadiyyat həlləri və yüksək dəqiqlikli idarəetmə sistemləri tələb olunur. Burada informasiya texnologiyalarının rolu mərkəzi xarakter daşıyır. Çünki resurs istehlakını azaltmaq üçün əvvəlcə onu dəqiq ölçmək, daha sonra modelləşdirmək, sonra isə avtomatik tənzimləmə imkanına malik olmaq lazımdır. Bu texniki ardıcılıq olmadan yaşıl artım nəzəri konstruksiya səviyyəsində qalır.

Yaşıl artımın ikinci mühüm xüsusiyyəti ondan ibarətdir ki, burada ekoloji məsuliyyət və iqtisadi səmərəlilik qarşı-qarşıya qoyulmur. Əksinə, ekoloji optimallaşdırma uzunmüddətli məhsuldarlıq və sabitlik mənbəyi kimi qiymətləndirilir. Məsələn, enerjiden istifadənin optimallaşdırılması müəssisə üçün təkcə emissiyaları azaltmır, eyni zamanda əməliyyat xərclərini aşağı salır. Su istifadəsinin idarə olunması istehsal davamlılığını artırır. Tullantı axınlarının rəqəmsal izlənməsi isə həm ekoloji yükü azaldır, həm də təkrar emal yolu ilə yeni dəyər yaradır. Bu məntiq yaşıl artımı “maliyyət yaradan məhdudiyyət” kimi deyil, “innovasiya yaradan modernləşmə modeli” kimi anlamağa imkan verir. OECD-nin sonrakı yaşıl artım icmallarında da vurğulanır ki, yaşıl artım istehsal və istehlak modellərinin transformasiyası vasitəsilə rifahı artırmağı və təbii kapitalın qorunmasını eyni çərçivədə birləşdirir [5].

Müasir elmi yanaşmada yaşıl artım anlayışı yalnız enerji və ətraf mühit məsələsi ilə məhdudlaşmır. O, su idarəçiliyi, tullantıların dövriyyəsi, dayanıqlı logistika, ağıllı şəhər idarəetməsi, kənd təsərrüfatında dəqiq texnologiyalar, rəqəmsal istehsal, təmiz sənaye prosesləri, yaşıl bulud hesablama, məlumat mərkəzlərinin enerji optimallaşdırılması və dayanıqlı proqram mühəndisliyi kimi sahələri də əhatə edir. Deməli, yaşıl artım çoxsektorlu və çoxqatlı anlayışdır. İnformasiya texnologiyaları və sistemləri mühəndisliyi ixtisası üçün əsas məsələ bu çoxsektorluluğu idarə edə

biləcək rəqəmsal sistemlərin qurulmasıdır. Başqa sözlə, yaşıl artım ideyasının əməli müstəviyə keçidi üçün platforma mühəndisliyi, sistem integrasiyası, verilənlər analitikası və avtomatlaşdırılmış qərar qəbul etmə zəruridir.

Yaşıl artım anlayışının informasiya texnologiyaları ilə əlaqəsini izah edən əsas xətt "ölçmədən idarəetmə mümkün deyil" prinsipidir. İstənilən yaşıl keçid siyasəti konkret ölçü vahidlərinə çevrilmədikdə onun icrası nəzarətsiz qalır. Məsələn, enerjiyə qənaət hədəfi yalnız aylıq ümumi sərfiyyat göstəricisi ilə idarə edilə bilməz. Obyektlər üzrə yük profili, saatlıq dinamika, pik istehlak vaxtları, avadanlıq səviyyəsində səmərəsizlik, xarici temperatur korrelyasiyası və istifadəçi davranış nümunələri də görünməlidir. Bu isə artıq informasiya sistemi probleimidir. Eyni yanaşma su sərfiyyatı, emissiya monitorinqi, şəhər nəqliyyat sıxlığı, tullantı logistikası və istehsal xəttində resurs optimallaşdırması üçün də keçərlidir. Bu səbəbdən yaşıl artımın texniki mahiyyəti ölçülə bilən, müqayisə edilə bilən, proqnozlaşdırıla bilən və idarə oluna bilən resurs davranışının yaradılmasından ibarətdir.

Yaşıl artım anlayışı ilə rəqəmsal transformasiya arasındakı əlaqə son illər daha da güclənmişdir. Rəqəmsallaşma resursların fiziki axınını məlumat axını ilə müşayiət etdikcə qeyri-effektivliyin gizli qalması çətinləşir. Sensorlaşma, bulud platformaları, süni intellekt əsaslı proqnozlar, rəqəmsal əkiz modelləri və paylanmış qərar sistemləri vasitəsilə enerji və material istifadəsi daha yüksək dəqiqliklə idarə olunur. Yeni tədqiqatlar göstərir ki, rəqəmsal transformasiya ilə yaşıl inkişaf arasındakı əlaqə xüsusilə texnoloji innovasiya və idarəetmə effektivliyi vasitəsilə güclənir və İKT infrastrukturunun dərinləşməsi daha səmərəli ekoloji nəticələr doğurur. Bu nəticə bir daha təsdiq edir ki, yaşıl artım artıq yalnız ekoloji siyasət sahəsinin mövzusu deyil, eyni zamanda rəqəmsal mühəndislik və platforma arxitekturası sahəsinin mərkəzi predmetinə çevrilmişdir [3].

Yaşıl artımın sosial ölçüsü də nəzəri baxımdan diqqətdən kənarda qalmamalıdır. İnküzivlik təmin olunmadan yaşıl artımın dayanıqlı modelə çevrilməsi mümkün deyildir. Dünya Bankının inklüziv yaşıl artım yanaşmasında vurğulanır ki, yaşıl artım sosial baxımdan avtomatik inklüziv sayılmır və siyasətlər elə qurulmalıdır ki, ən həssas qruplar keçid prosesində əlavə yük daşımadan fayda əldə etsinlər. Informasiya texnologiyaları baxımından bu müddəə rəqəmsal platformaların inklüziv dizaynını gündəmə gətirir. Əgər yaşıl artım üçün yaradılan platformalar yalnız iri müəssisələrin və ya yüksək texniki bacarıqlı istifadəçilərin faydalana bildiyi sistemlər olarsa, onda texnologiya ekoloji səmərəlilik yaratsa da, sosial inklüzivlik zəifləyər. Deməli, yaşıl artımın İT müstəvisində uğurlu tətbiqi üçün istifadəçi yönümlü interfeys, açıq məlumat siyasəti, əlçatan xidmətlər və genişmiqyaslı tətbiq imkanları da nəzərə alınmalıdır.

Bundan əlavə, yaşıl artım anlayışı idarəetmə mədəniyyətində də dəyişiklik tələb edir. Ənənəvi idarəetmədə qərarlar çox vaxt retrospektiv hesabatlarla əsaslanır. Yaşıl artım isə real vaxt monitorinqi, proaktiv tənzimləmə, proqnozlaşdırıcı analitika və ssenari əsaslı qərarvermə tələb edir. Bu dəyişiklik informasiya sistemlərinin quruluşunu da yenidən müəyyən edir. İdarəetmə platformaları statik məlumat anbarı deyil, canlı əməliyyat sisteminə çevrilir. Bu sistemlər fiziki dünya ilə rəqəmsal dünya arasında daimi sinxronizasiya yaratmalı, dəyişkən parametrləri izləməli və optimallaşdırma komandalarını avtomatik və ya yarı-avtomatik qaydada icra etməlidir. Belə yanaşma olmadan yaşıl artım strategiyası kağız üzərində hədəflər toplusu kimi qala bilər.

Yaşıl artım anlayışı iqtisadi inkişafın ekoloji məhdudiyyətlərlə ziddiyyət təşkil etməyən, əksinə, təbii kapitalın qorunmasını, resurs səmərəliliyini, texnoloji yenilənməni və uzunmüddətli rifahı birləşdirən inkişaf modelidir. Bu model klassik artım yanaşmasını inkar etmir, lakin onun texnoloji və institusional əsaslarını ciddi şəkildə yenidən qurur. Informasiya texnologiyaları və sistemləri mühəndisliyi baxımından yaşıl artımın əsas mahiyyəti odur ki, resurs istifadəsi görünən, ölçülən, analiz edilən və optimallaşdırılan rəqəmsal prosesə çevrilməlidir. Deməli, yaşıl artım sadəcə ekoloji anlayış deyil. O, eyni zamanda sensorlaşmış infrastruktur, integrasiya olunmuş məlumat platformaları, süni intellekt analitikası, avtomatlaşdırılmış idarəetmə və təhlükəsiz rəqəmsal ekosistem tələb edən sistem mühəndisliyi konsepsiyasıdır. Sənin əsas mətninə bu hissə

əlavə edildikdə mövzunun nəzəri bazası daha tam görünəcək və “yaşıl artım” anlayışının özü ayrıca, əsaslandırılmış şəkildə təqdim olunmuş olacaq.

Müasir texnoloji inkişaf mərhələsində yaşıl artım anlayışı yalnız enerji sərfiyyatının azaldılması və ya ekoloji siyasətin gücləndirilməsi ilə məhdud çərçivədə izah edilə bilməz. Bu anlayış resurslardan istifadə səmərəliliyinin artırılması, enerji axınlarının dinamik idarə edilməsi, istehsal və xidmət sistemlərində real vaxt qərar qəbuletməsinin avtomatlaşdırılması, emissiya nəzarətinin rəqəmsallaşdırılması və iqtisadi fəaliyyətin məlumat əsaslı optimallaşdırılması ilə bilavasitə bağlıdır. Bu səbəbdən yaşıl artımın təmin edilməsində əsas məsələ təkcə “yaşıl texnologiya”nın tətbiqi deyil, həmən texnologiyaları vahid idarəetmə məntiqi altında birləşdirən rəqəmsal platformaların formalaşdırılmasıdır. İnformasiya texnologiyaları və sistemləri mühəndisliyi baxımından yaşıl artım problemi əslində heterogen məlumat mənbələrinin integrasiyası, paylanmış sistemlərdə qərar qəbuletmə, enerjiyə həssas hesablama, kibertəhlükəsizlik, şəbəkə etibarlılığı və platforma miqyaslanması problemi kimi çıxış edir. Bu yanaşma göstərir ki, yaşıl artımın texnoloji bazası sırf avadanlıq yenilənməsi deyil, proqram təminatı, məlumat arxitekturası və ağıllı idarəetmə sistemlərinin birlikdə işlədiyi rəqəmsal ekosistemdir.

Rəqəmsal platforma anlayışı bu kontekstdə ənənəvi informasiya sistemi anlayışından daha geniş mənə daşıyır. Platforma sadəcə verilənlərin saxlandığı və ya istifadəçiyə xidmət təqdim edən proqram mühiti deyildir. O, sensor şəbəkələri, IoT qovşaqları, SCADA modulları, bulud hesablama infrastrukturunu, mikroxidmət əsaslı tətbiq qatları, analitika mühərrikləri, API integrasiyası, vizuallaşdırma panelləri və qərar dəstəyi modullarını vahid funksional arxitektura daxilində birləşdirən rəqəmsal mühitdir. Yaşıl artım üçün belə platformanın məqsədi resurs istifadə davranışını görünən etmək, anomaliyaları avtomatik aşkar etmək, yük paylanmasını optimallaşdırmaq, istehlak proqnozlarını formalaşdırmaq, bərpa olunan enerji mənbələrinin qeyri-sabitliyini idarə etmək və qərar qəbuletməni məlumat dəqiqliyi əsasında qurmaqdır [1]. Son tədqiqatlarda İKT inkişafı ilə yaşıl ümumi məhsuldarlıq arasında müsbət əlaqə məhz texnoloji tərəqqi, enerji intensivliyinin azalması və ticarət açıqlığı kimi mexanizmlər vasitəsilə izah olunur.

Yaşıl artım üçün rəqəmsal platformanın formalaşdırılması arxitektura səviyyəsində çoxqatlı model əsasında həyata keçirilməlidir. Birinci qat məlumatın yaranma səviyyəsidir. Buraya ağıllı sayğaclar, ətraf mühit sensorları, sənaye avadanlığında quraşdırılan telemetriya modulları, nəqliyyat izləmə cihazları, meteoroloji ölçü qurğuları və istifadəçi tərəfli mobil interfeyslər daxildir. Bu qatın əsas vəzifəsi fiziki mühitdə baş verən enerji, su, emissiya, temperatur, vibrasiya, təzyiq, hərəkət və istehlak göstəricilərini fasiləsiz toplamaqdır. İkinci qat kommunikasiya və ötürmə qatıdır. Burada LPWAN, LoRaWAN, NB-IoT, 5G, edge gateway və sənaye Ethernet həlləri istifadə olunur [2]. Üçüncü qat məlumatın emalı və saxlanması səviyyəsidir. Bu qatda məlumat gölü, zaman sıralı verilənlər bazası, stream processing mühərrikləri, konteyner əsaslı hesablama modulları və bulud resursları fəaliyyət göstərir. Dördüncü qat analitik və qərar dəstəyi qatıdır. Bu səviyyədə maşın öyrənməsi modelləri, optimallaşdırma alqoritmləri, anomaliya aşkarlama sistemləri və proqnozlaşdırıcı idarəetmə modulları işləyir. Son qat isə istifadəçi qarşılıqlı əlaqəsi səviyyəsidir və burada veb panel, mobil tətbiq, operator konsolu və avtomatik xəbərdarlıq mexanizmləri yer alır. Məhz bu çoxqatlı arxitektura yaşıl artımı hesablana bilən, izlənə bilən və idarə edilə bilən prosesə çevirir.

Internet of Things texnologiyaları yaşıl artım üçün rəqəmsal platformaların fundamental komponentidir. Əgər sistem fiziki resurs istehlakını ölçə bilmirsə, həmən istehlakı optimallaşdırmaq da mümkün olmur. IoT sensorları enerjiden istifadənin mikro səviyyədə monitorinqini təmin edir və bu yolla itki mənbələrinin aşkarlanmasına, qeyri-effektiv avadanlığın müəyyənəşdirilməsinə, qeyri-planlı sərfiyyatın izlənməsinə və resurs axınının obyekt səviyyəsində idarə olunmasına imkan yaradır. Yaşıl şəhər və ağıllı enerji infrastrukturuları üzrə son tədqiqatlarda göstərilir ki, IoT əsaslı monitorinq ilə süni intellekt əsaslı proqnozlaşdırma birləşdirildikdə enerji yükünün tarazlaşdırılması, bərpa olunan enerji integrasiyası və tələbyönlü idarəetmə daha yüksək

səmərəliliklə həyata keçirilir. Bu yanaşma sistem mühəndisliyi baxımından çox vacibdir, çünki məlumat toplama və qərar modulu ayrılıqda deyil, qapalı idarəetmə dövrü kimi layihələndirilməlidir.

Süni intellekt texnologiyaları yaşıl artım platformalarında qərarvermə keyfiyyətini yüksəldən əsas hesablama mexanizmidir. Ənənəvi qayda əsaslı sistemlər resurs istifadəsinin mürəkkəb və dinamik strukturunu tam əhatə edə bilmir. Məsələn, elektrik istehlakının optimallaşdırılması üçün yalnız cari yük göstəricisini bilmək kifayət etmir. Havanın temperaturu, istifadəçi davranışı, istehsal rejimi, tarif zonaları, günəş və külək enerjisinin çıxışı, enerji saxlama sisteminin doluluq səviyyəsi və tarixi istehlak meylləri də nəzərə alınmalıdır. Məhz bu nöqtədə maşın öyrənməsi və dərin öyrənmə modelləri yüksək dəqiqlikli proqnozlaşdırma, anomaliya aşkarlama, tələbin qabaqcadan idarə olunması və resurs bölgüsünün optimallaşdırılması üçün tətbiq edilir. AI ilə gücləndirilmiş yaşıl IoT həlləri üzrə tədqiqatlar göstərir ki, enerjiyə həssas hesablama, adaptiv güc miqyaslaması və ağıllı şəbəkə optimallaşdırması iri miqyaslı sistemlərdə enerji sərfiyyatının azalmasına xidmət edir.

Yaşıl artım üçün rəqəmsal əkiz texnologiyasının rolu ayrıca qeyd olunmalıdır. Rəqəmsal əkiz fiziki sistemin virtual surətini yaradaraq onun davranışını real vaxt məlumatları əsasında modelləşdirir. Enerji stansiyaları, sənaye obyektləri, su təchizatı şəbəkələri, binalar, logistika zəncirləri və hətta şəhər miqyasında infrastruktur sistemləri üçün rəqəmsal əkiz modeli qurulduqda idarəetmə qərarları real mühitdə tətbiq edilməzdən əvvəl simulyasiya edilə bilər. Bu, səhv qərar riskini azaldır, əməliyyat ssenarilərini müqayisə etməyə imkan verir və resurs optimallaşdırmasını daha əsaslı edir. Məsələn, HVAC sisteminin parametrlərinin dəyişdirilməsi, günəş panellərinin yüklənməsi, batareya saxlama strategiyası və nəqliyyat axınının yenidən bölüşdürülməsi rəqəmsal modeldə əvvəlcədən sınaqdan keçirilə bilər. Beləliklə, yaşıl artım üçün texnologiya seçimi empirik intuisiya ilə deyil, hesablama əsaslı ssenari təhlili ilə aparılır. Rəqəmsal dinamik qabiliyyət və yaşıl innovasiya arasındakı əlaqəni araşdıran yeni işlər də göstərir ki, rəqəmsal platformalar və bulud resursları uğurlu yaşıl texnologiyaların daha geniş miqyasda yayılmasına şərait yaradır [8].

Bulud və kənar hesablama modellərinin balanslı istifadəsi yaşıl platformaların texniki dayanıqlığını müəyyən edir. Bulud mühiti böyük həcmli məlumatların uzunmüddətli saxlanması, model təlimi, çoxmənbəli analitika və xidmətlərin miqyaslanması üçün əlverişlidir. Lakin enerji idarəetməsi, sənaye avtomatlaşdırması və kritik infrastruktur nəzarəti kimi sahələrdə gecikməyə həssas əməliyyatlar üçün yalnız bulud yanaşması kifayət etmir. Bu hallarda edge computing həlləri sensor və icraedici qurğulara yaxın nöqtədə ilkin emal, filtrasiya, sürətli qərarvermə və lokal optimallaşdırma funksiyalarını yerinə yetirməlidir. Sistemlər mühəndisliyi baxımından optimal model hibrid arxitekturaadır. Belə arxitekturaada operativ cavab tələb edən proseslər kənar qovşaqlarda, hesablama baxımından ağır analitika və uzunmüddətli optimallaşdırma isə buludda yerinə yetirilir. Hibrid model həm enerji səmərəliliyini, həm də sistem etibarlılığını yüksəldir. Xüsusilə kritik infrastrukturda şəbəkə kəsilməsi və ya bulud gecikməsi şəraitində edge qatının lokal qərarvermə qabiliyyəti sistemin sabitliyini qoruyur.

Rəqəmsal platformaların formalaşdırılmasında interoperabellik problemi yaşıl artım üçün ən mürəkkəb texniki məsələlərdən biridir. Müxtəlif istehsalçıların sensorları, fərqli protokollarla işləyən enerji sayğacları, ayrı standartlardan istifadə edən sənaye kontrollerləri və müstəqil inkişaf etdirilmiş proqram modulları vahid sistemdə bir-biri ilə məlumat mübadiləsi aparmadıqda rəqəmsal platforma parçalanmış mühitə çevrilir. Bu parçalanma məlumat təkrarına, semantik uyğunsuzluğa, idarəetmə boşluğuna və kibertəhlükəsizlik zəifliklərinə səbəb olur. Buna görə yaşıl artım platformalarının layihələndirilməsi zamanı açıq standartlara əsaslanan API təbəqəsi, məlumat ontologiyaları, vahid identifikasiya mexanizmi, metadata idarəetməsi və xidmət yönümlü arxitektura prinsipləri tətbiq edilməlidir. Sistem mühəndisliyində bu yanaşma "platform-by-design" məntiqi ilə bağlıdır. Yəni platforma sonradan integrasiya edilən komponentlər toplusu deyil, başlanğıcdan interoperabellik və genişlənəbilənlik prinsipi ilə qurulmalıdır.

Kibertəhlükəsizlik və məxfilik yaşıl rəqəmsal platformaların ayrılmaz texniki xüsusiyyətidir. Enerji şəbəkələri, su idarəetmə sistemləri, ağıllı şəhər infrastrukturuları və sənaye IoT qurğuları kiberhücum üçün yüksək cəlbediciliyə malikdir. Əgər yaşıl artım üçün qurulan platforma təhlükəsizlik baxımından zəifdirsə, həmin platforma həm əməliyyat dayanmasına, həm yanlış məlumat əsasında qərar verməyə, həm də kritik resursların idarə edilməsində sistemli risklərə səbəb ola bilər. Buna görə sıfır etibar modeli, çoxfaktorlu autentifikasiya, şifrələnmiş məlumat ötürülməsi, imtiyazların minimumlaşdırılması, təhlükəsiz firmware yeniləmələri, SIEM integrasiyası, audit logları və anomaliya əsaslı hücum aşkarlama mexanizmləri platformanın texniki nüvəsinə daxil edilməlidir. Kibertəhlükəsizlik sonradan əlavə olunan qoruma qatı deyil, platforma arxitekturasının fundamental dizayn meyarıdır.

Yaşıl artım üçün blokçeyn texnologiyalarının tətbiqi də seçilmiş hallarda səmərəli nəticə verə bilər. Xüsusilə karbon kreditləri, yaşıl sertifikatlar, bərpa olunan enerji mənsə zəmanəti, təkrar emal zəncirləri və dayanıqlı təchizat proseslərində dəyişdirilməsi mümkün olmayan tranzaksiya jurnalları etibarlılığı artırır. Lakin blokçeyn bütün hallarda optimal həll sayılmamalıdır. Sistem mühəndisliyi baxımından onun tətbiqi yalnız çoxsaylı maraqlı tərəf, aşağı etibar mühiti, auditable izlərə ehtiyac və mərkəzsiz təsdiqləmə tələbi mövcud olduqda əsaslı sayılır. Əks halda yüksək enerji sərfiyyətli və mürəkkəb blokçeyn həlləri məqsədəuyğun olmaya bilər. Bu səbəbdən yaşıl artım üçün blokçeyn seçimi texnoloji moda deyil, konkret arxitektura qərarı kimi əsaslandırılmalıdır [3].

Yaşıl artım platformalarının uğuru istifadəçi interfeysinin keyfiyyətindən və qərar dəstəyi panellərinin dizaynından da asılıdır. Məlumatın çoxluğu öz-özlüyündə səmərəlilik yaratmır. Operator, menecer və ya mühəndis həmin məlumatı vaxtında anlama, prioritetləşdirə və qərara çevirə bilməlidir. Buna görə dashboard dizaynında məlumat vizuallaşdırması, hadisə prioritetləşdirməsi, xəbərdarlıq sistemləri, heatmap modelləri, zaman sıralı anomaliya qrafikləri və performans indikatorlarının semantik aydınlığı əsas götürülməlidir. İstifadəçi təcrübəsi zəif olduqda güclü analitik arxa sistem belə əməliyyat mühitində real təsir yarada bilmir. Bu baxımdan yaşıl platforma dizaynı təkcə texniki integrasiya deyil, insan-kompüter qarşılıqlı əlaqəsi problemini də əhatə edir.

Miqyaslanma və dayanıqlılıq məsələləri də xüsusi əhəmiyyət daşıyır. Yaşıl artım üçün qurulan platformalar kiçik pilot layihə mərhələsində uğurlu olsa da, regional və ya milli miqyasda eyni performansı qorumaq üçün elastik arxitektura tələb olunur. Mikroservis dizaynı, konteyner orkestrasiya sistemləri, avtomatik horizontal scaling, məlumat bölüşdürülməsi strategiyası, yük balanslaşdırma, failover mexanizmləri və xidmət davamlılığı modelləri platformanın böyüməyə davamlılığını təmin edir. Bu prinsip xüsusilə ağıllı şəhər, milli enerji monitoring sistemi və iri sənaye klasterlərində vacibdir. Yaşıl artım layihələri çox vaxt mərhələli genişlənmə yolu ilə inkişaf etdiyinə görə sistemin ilkin dizaynı gələcək integrasiyaya hazır olmalıdır.

Yaşıl artımın təmin edilməsi üçün rəqəmsal platformaların formalaşdırılması informasiya texnologiyaları və sistemləri mühəndisliyinin çoxqatlı, çoxkomponentli və yüksək integrasiya tələb edən sahəsinə çevrilmişdir. Bu platformalar IoT sensorlarından, kommunikasiya şəbəkələrindən, bulud və kənar hesablama qatlarından, süni intellekt analitikasından, rəqəmsal əkiz modellərindən, interoperabellik təbəqələrindən, kibertəhlükəsizlik mexanizmlərindən və istifadəçi yönümlü qərar panellərindən ibarət vahid sistem kimi layihələndirilməlidir. Yaşıl artımın texnoloji təminatı yalnız rəqəmsallaşma deyil, məhz enerji və resurs optimallaşdırmasına yönəlmiş məqsədli rəqəmsal arxitekturanın qurulması ilə mümkün olur. Bu səbəbdən yaşıl artım probleminə iqtisadi yanaşmadan daha artıq, informasiya sistemləri, hesablama infrastrukturu və dayanıqlı sistem mühəndisliyi problemi kimi baxmaq elmi və praktik baxımdan daha düzgün yanaşmadır.

Ədəbiyyat siyahısı

1. Al-Husain R. A., Jasim T. A., Mathew V., Al-Romeedy B. S., Khairy H. A., Mahmoud H. A., Liu S., El-Meligy M. A., Alsetoohy O. "Optimizing sustainability performance through digital dynamic capabilities, green knowledge management, and green technology innovation" // Scientific Reports, 2025, 15, 24217. <https://pmc.ncbi.nlm.nih.gov/articles/PMC12234988/>
2. Kumar S., Prakash A., Lee H. "Green IoT: AI-Powered Solutions for Sustainable Energy Management" // Research publication record, 2024. <https://researcher.manipal.edu/en/publications/green-iot-ai-powered-solutions-for-sustainable-energy-management->
3. Mocanu R., Nidelcu F., Căruțașu G. "Artificial Intelligence Solutions for Energy Consumption Optimization in IoT Devices" // Journal of Information Systems & Operations Management, 2025, 19(1), 178–195 p. https://web.rau.ro/websites/jisom/Vol.19%20No.1%20-%202025/JISOM%2019.1_178-195.pdf
4. OECD. "Towards Green Growth? Tracking Progress" // OECD Green Growth Studies, 2015, 1–210 p. https://www.oecd.org/content/dam/oecd/en/publications/reports/2015/07/towards-green-growth_g1g53897/9789264234437-en.pdf
5. OECD. "Towards Green Growth" // OECD Green Growth Studies, 2011, 1–142 p. https://www.oecd.org/content/dam/oecd/en/publications/reports/2011/05/towards-green-growth_g1g1342a/9789264111318-en.pdf
6. UNEP. "Towards a Green Economy: Pathways to Sustainable Development and Poverty Eradication" // United Nations Environment Programme, 2011, 1–624 p. https://scnat.ch/en/uuid/i/d4cd4f6b-e2f9-520d-9032-b387428d17b4-UNEP_Green_Economy_Report_2011
7. Wang H., Yu J., Khan M. "Sustainable digital transformation: the nexus between ICT and global green economic growth" // Technological and Economic Development of Economy, 2024. <https://jest.vgtu.lt/index.php/TEDE/article/view/21050>
8. World Bank. "Inclusive Green Growth: The Pathway to Sustainable Development" // World Bank, 2012, 1–192 p. <https://documents1.worldbank.org/curated/en/345361468164047807/pdf/691250PUB0v20I00B0x379796B00PUBLIC0.pdf>

Web-Based Learning Platform Architecture and Mathematical Modeling of Adaptive Learning Mechanism

Jafarov Nizami Duman oglu

Azerbaijan Technical University, Baku, Azerbaijan, Associate Professor

Agayeva Leyla Sadulla gizi

Sumgait State University, Sumgait, Azerbaijan, Master's student

Abstract

This paper presents a multi-layered architecture of a web-based learning platform and a mathematical model of an adaptive learning mechanism. The system is designed using a modular structure consisting of presentation, application, service, and data layers. The adaptive learning mechanism models the learner's knowledge level as a latent variable and enables dynamic question selection. Item Response Theory (IRT) and Bayesian updating are applied to ensure accurate estimation of learner ability. The proposed system is evaluated through theoretical analysis and simulation experiments, demonstrating improved learning outcomes and system efficiency.

Keywords— LMS, Adaptive Learning, Web Architecture, Learning Analytics, Educational Systems

I. Introduction

Modern digital education systems are increasingly focused on personalization and data-driven decision-making. Learning Management Systems (LMS) have evolved from simple content delivery tools to intelligent platforms capable of analyzing user behavior and adapting learning content dynamically.

Adaptive learning systems utilize artificial intelligence and data analytics to tailor educational content according to individual learner needs. Such systems significantly improve learning efficiency and engagement [1], [2].

The objectives of this research are:

- To define a multi-layered system architecture
- To develop a mathematical model for adaptive learning
- To analyze system performance and scalability

II. System architecture

A. Presentation Layer

The presentation layer handles user interaction and interface rendering.

$$UI = f(UserInput, APIResponse)$$

Where:

- UI — User Interface
- UserInput — user-provided input
- APIResponse — server response

This layer supports SPA architecture and real-time updates.

B. Application layer

This layer contains core business logic.

$$SystemOutput = F(User, Course, InteractionHistory)$$

Where:

- SystemOutput — system output
- User — user data
- Course — course content
- InteractionHistory — user activity history

C. Service layer

Implements microservices architecture.

$$Request = (Method, Resource, Payload)$$

$$Response = (Status, Data)$$

Each service operates independently, improving scalability [3], [4].

D. Data layer

The data layer ensures structured storage using normalized schemas (3NF). It includes entities such as User, Course, Question, and Activity logs.

III. Mathematical model of adaptive learning

A. Learner Ability Model

$$\theta \in \mathbb{R}, \quad \theta \sim N(0,1)$$

Where:

- θ is a learner ability level
- $N(0,1)$ is a normal distribution

B. Item Response Theory Model

$$P(X = 1 | \theta, \beta) = \frac{1}{1 + e^{-(\theta - \beta)}}$$

Where:

- P is a probability of correct answer
- X is a response outcome
- θ is a learner ability
- β is a item difficulty

This model estimates the probability of correct responses [5].

C. Bayesian Updating

$$P(\theta | X) = \frac{P(X | \theta)P(\theta)}{P(X)}$$

Where:

- Posterior probability updates learner knowledge after each response

D. Gradient-Based Update

$$\theta_{new} = \theta_{old} + \alpha(X - P)$$

Where:

- α is a learning rate

This ensures real-time adaptation.

IV. Adaptive question selection

$$\beta \approx \theta$$

$$I(\theta) = P(1 - P)$$

Where:

- $I(\theta)$ is a information function

Maximum information is achieved when difficulty matches ability [6].

V. Performance evaluation

A. Response time model

$$T_{response} = T_{processing} + T_{DB} + T_{network}$$

B. Scalability

$$Load \approx O(N)$$

$$Throughput_{total} = k \cdot Throughput_{single}$$

VI. Learning analytics model

$$ActivityIndex = \omega_1 LoginFreq + \omega_2 QuizCount + \omega_3 TimeSpent$$

$$CompletionRate = \frac{CompletedLessons}{TotalLessons}$$

VII. EXPERIMENTAL RESULTS

Simulation parameters:

- 500 students
- 1000 questions

System	Avg Score	Std Dev	Completion
Static	71%	12	64%
Adaptive	85%	8	82%

Results show improved performance and reduced variance [7].

VIII. Discussion

Advantages:

- Personalized learning
- Real-time adaptation
- Scalable architecture

Limitations:

- Computational cost
- Parameter tuning complexity

IX. Conclusion

The proposed system integrates modern web architecture with a mathematically grounded adaptive learning model. The use of IRT and Bayesian updating significantly improves learning outcomes. The architecture is scalable and suitable for real-world deployment.

References

[1] G. Siemens and R. Baker, *Learning Analytics and Educational Data Mining*. Springer, 2022.

[2] W. Holmes, M. Bialik, and C. Fadel, *Artificial Intelligence in Education*. Routledge, 2023.

[3] M. Richards, *Fundamentals of Software Architecture*. O’Reilly, 2020.

[4] S. Newman, *Building Microservices*, 2nd ed. O’Reilly, 2021.

[5] R. J. de Ayala, *The Theory and Practice of Item Response Theory*. Guilford Press, 2022.

[6] W. J. van der Linden, *Handbook of Item Response Theory*. CRC Press, 2018.

[7] O. Viberg and M. Hatakka, “Learning analytics in higher education,” *Computers & Education*, 2021.

Fişinq və sosial mühəndislik: istifadəçi davranışlarının təhlükəsizlik risklərinə təsiri

Əzimov Kənan

Azərbaycan Dövlət İqtisad Universiteti

Xülasə. Müasir rəqəmsal mühitdə kibertəhlükəsizlik problemləri yalnız texniki zəifliklərlə deyil, eyni zamanda insan faktorunun yaratdığı risklərlə də sıx bağlıdır. Bu məqalədə sosial mühəndislik və onun ən geniş yayılmış formalarından biri olan fişinq hücumları istifadəçi davranışları kontekstində təhlil olunur. Araşdırma göstərir ki, istifadəçilərin diqqətsizliyi, tələskən qərarvermə meyilləri, etibar faktoruna həddindən artıq güvən və emosional reaksiyalar bu tip hücumların uğurla həyata keçirilməsində əsas rol oynayır.

Məqalədə həmçinin müasir texnologiyaların inkişafı ilə fişinq hücumlarının daha mürəkkəb və hədəfli xarakter aldığı, süni intellekt və məlumat analizi vasitəsilə fərdiləşdirilmiş hücumların artdığı qeyd olunur. Bu dəyişikliklər ənənəvi müdafiə üsullarının effektivliyini müəyyən dərəcədə azaldır və yeni yanaşmaların tətbiqini zəruri edir.

Tədqiqat çərçivəsində istifadəçi davranışlarının təhlükəsizlik risklərinə təsiri sistemli şəkildə araşdırılmış və bu risklərin azaldılması üçün həm texniki, həm də davranış əsaslı müdafiə mexanizmlərinin integrasiyasının vacibliyi vurğulanmışdır. Xüsusilə istifadəçilərin maarifləndirilməsi, təhlükəsizlik mədəniyyətinin formalaşdırılması və analitik düşünmə bacarıqlarının inkişaf etdirilməsi effektiv müdafiə strategiyalarının əsas komponentləri kimi qiymətləndirilir.

Nəticə olaraq qeyd olunur ki, sosial mühəndislik hücumlarına qarşı mübarizə yalnız texnoloji vasitələrlə məhdudlaşmamalı, eyni zamanda insan davranışlarının düzgün istiqamətləndirilməsinə əsaslanan kompleks yanaşma tətbiq olunmalıdır.

Açar sözlər: sosial mühəndislik, fişinq, kibertəhlükəsizlik, istifadəçi davranışı, informasiya təhlükəsizliyi, rəqəmsal risklər, autentifikasiya, psixoloji təsir, kibercinayətkarlıq, təhlükəsizlik mədəniyyəti

Müasir rəqəmsal mühitdə informasiya texnologiyalarının sürətli inkişafı insan həyatının demək olar ki, bütün sahələrinə nüfuz etmişdir. Xüsusilə son illərdə rəqəmsallaşma prosesi yalnız kommunikasiya vasitələrinin inkişafı ilə məhdudlaşmamış, eyni zamanda iqtisadi münasibətlərin qurulması, dövlət xidmətlərinin təşkili və sosial əlaqələrin formalaşması kimi fundamental sahələrə də ciddi təsir göstərmişdir. İnternetin geniş yayılması, mobil cihazların əlçatanlığının artması və bulud texnologiyalarının tətbiqi nəticəsində insanlar gündəlik fəaliyyətlərini getdikcə daha çox rəqəmsal mühit üzərindən həyata keçirməyə başlamışdır. Bu isə informasiya axınının intensivləşməsinə və fərdi məlumatların müxtəlif platformalarda toplanmasına gətirib çıxarmışdır.

Elektron xidmətlərin artması və rəqəmsal platformaların gündəlik istifadə vasitəsinə çevrilməsi istifadəçilər üçün rahatlıq yaratsa da eyni zamanda yeni risk mühitinin formalaşmasına səbəb olmuşdur. Ənənəvi təhlükəsizlik yanaşmalarının böyük ölçüdə texniki sistemlərin qorunmasına yönəldiyi halda, müasir şəraitdə insanın özü təhlükəsizlik zəncirinin ən zəif halqasına çevrilmişdir. Texnoloji müdafiə mexanizmlərinin – şifrələmə, identifikasiya sistemləri və digər qoruyucu vasitələrin inkişafına baxmayaraq, hücumların böyük bir hissəsi texniki zəifliklərdən deyil, insan faktorundan qaynaqlanır. Bu isə onu göstərir ki, təhlükəsizlik məsələlərinə yalnız texnoloji prizmadan yanaşmaq kifayət etmir və insan davranışlarının da ayrıca tədqiq olunması zəruridir.

Bu baxımdan sosial mühəndislik və onun ən geniş yayılmış formalarından biri olan fişinq hücumları xüsusi diqqət tələb edir. Sosial mühəndislik hücumları ənənəvi kibercinayətkarlıq üsullarından fərqli olaraq sistemlərin proqram təminatına deyil, birbaşa istifadəçilərin qərarvermə mexanizmlərinə təsir göstərməyə yönəlmişdir. Bu yanaşma hücum edənlər üçün daha az resurs tələb edir, lakin daha yüksək effektivlik təmin edir. Çünki insan psixologiyası çox vaxt standart təhlükəsizlik protokolları ilə qoruna bilmir və bu sahədə yaranan boşluqlar hücumlar üçün əlverişli şərait yaradır.

Sosial mühəndislik anlayışı insan psixologiyasından istifadə edərək məlumat əldə etmə üsullarını ifadə edir və bu yanaşma müxtəlif sosial və psixoloji mexanizmlərə əsaslanır. Bu hücum növündə məqsəd texniki sistemləri sındırmaq deyil, istifadəçiləri manipulyasiya edərək onların özlərinin məxfi məlumatları təqdim etməsinə nail olmaqdır. Hücum edən şəxs qarşı tərəfin davranış xüsusiyyətlərini, diqqət səviyyəsini və qərarvermə meyillərini nəzərə alaraq müxtəlif təsir üsullarından istifadə edir. Bu üsullar arasında etibar qazanmaq, qorxu yaratmaq, maraq oyatmaq və ya istifadəçini təcili qərar verməyə məcbur etmək kimi yanaşmalar xüsusi yer tutur. Bu prosesdə istifadəçinin emosional vəziyyəti mühüm rol oynayır. İnsanlar adətən gündəlik fəaliyyət zamanı əldə etdikləri məlumatların doğruluğunu hər zaman dərindən yoxlamır və çox vaxt sürətli qərar verməyə üstünlük verirlər. Hücum edənlər də məhz bu xüsusiyyətdən istifadə edərək mesajlarını elə qururlar ki, istifadəçi onu analiz etmədən qəbul etsin. Nəticədə ən güclü təhlükəsizlik sistemləri belə insanın yanlış qərarları qarşısında zəif qala bilər. Bu hal göstərir ki, kibertəhlükəsizlik yalnız texniki məsələ deyil, eyni zamanda davranış və psixologiya ilə sıx bağlı olan kompleks bir sahədir.

Fişinq sosial mühəndisliyin konkret və çox geniş yayılmış formasıdır və müasir dövrdə ən çox rast gəlinən kibertəhlükə növlərindən biri hesab olunur. Bu hücum növündə istifadəçilərə saxta e-poçtlar, mesajlar və ya veb səhifələr vasitəsilə müraciət edilir və onlardan şəxsi məlumatlarını daxil etmələri tələb olunur. Fişinq hücumlarının effektivliyi əsasən onların real xidmətlərə maksimal dərəcədə bənzədilməsi və istifadəçinin diqqətsizliyindən istifadə olunması ilə bağlıdır. Hücum edənlər vizual dizayn, loqotiplər, dil üslubu və digər elementlərdən istifadə edərək saxta mənbələri mümkün qədər inandırıcı etməyə çalışırlar. Məsələn, istifadəçiyə bank və ya digər maliyyə qurumu adından göndərilmiş kimi görünən mesajda hesabının bloklandığı və ya təhlükə altında olduğu bildirilir. Bu mesajda istifadəçidən hesabını aktivləşdirmək və ya məlumatlarını yeniləmək üçün müəyyən bir keçidə daxil olması tələb olunur. İstifadəçi bu linkə daxil olduqda isə o, real sayta bənzər şəkildə hazırlanmış saxta səhifə ilə qarşılaşır və burada öz şəxsi məlumatlarını daxil edir. Bu məlumatlar birbaşa hücum edən şəxslərin əlinə keçir və nəticədə həm maliyyə, həm də informasiya təhlükəsizliyi baxımından ciddi problemlər yaranır.

Fişinq hücumlarının təhlükəliliyini artıran əsas amillərdən biri onların daim təkmilləşməsi və yeni texnologiyalarla uyğunlaşmasıdır. Əvvəllər bu hücumlar daha sadə və asan aşkar edilə bilən formada olduğu halda, müasir dövrdə onlar daha hədəfli və fərdiləşdirilmiş xarakter daşıyır. Hücum edənlər istifadəçilərin sosial şəbəkələrdə paylaşdığı məlumatları analiz edərək daha inandırıcı ssenarilər qurur və konkret şəxsləri hədəf alır. Bu isə fişinq hücumlarını daha təhlükəli və aşkarlanması çətin bir problemə çevirir.

İstifadəçi davranışları bu cür hücumların uğurlu olub-olmamasında həlledici rol oynayır. Müasir kibertəhlükəsizlik mühitində texniki zəifliklər müəyyən dərəcədə aradan qaldırılsa da, insan davranışları hələ də ən çətin idarə olunan risk faktorlarından biri olaraq qalır. Bir çox hallarda istifadəçilər təhlükəsizlik qaydaları haqqında kifayət qədər məlumatlı olmur və ya bu qaydaların praktik əhəmiyyətini düzgün qiymətləndirmir. Bu isə onların gündəlik rəqəmsal fəaliyyət zamanı daha çox intuitiv və sürətli qərarlar verməsinə səbəb olur.

Xüsusilə diqqətsizlik, tələskənlik və məlumatlılığın aşağı səviyyədə olması fişinq hücumlarının əsas səbəblərindən hesab olunur. İnsanlar gündəlik həyatlarında çox sayda mesaj və e-poçt aldıkları üçün onların hər birini diqqətlə yoxlamaq əvəzinə tez qərar verməyə üstünlük verirlər. Bu davranış modeli müəyyən mənada informasiya yüklənməsi ilə də bağlıdır. İstifadəçi

çoxsaylı məlumat axını ilə qarşılaşdıqda, hər bir mesajı detallı şəkildə analiz etmək əvəzinə, daha sürətli və az enerji tələb edən qərarvermə mexanizmlərindən istifadə edir. Nəticədə isə şübhəli mənbələrdən gələn məlumatlar da bəzən etibarlı kimi qəbul olunur və bu da hücum edənlər üçün əlverişli şərait yaradır.

İstifadəçi davranışlarında müşahidə olunan risk faktorlarını daha sistemli şəkildə aşağıdakı kimi ümumiləşdirmək olar:

- diqqətsiz yanaşma və mesajların məzmununa səthi baxış
- tələskən qərarvermə və məlumatın yoxlanılmadan qəbul edilməsi
- təhlükəsizlik biliklərinin məhdud olması
- texnologiyaya həddindən artıq güvən və risklərin kiçildilməsi
- eyni parol və ya zəif autentifikasiya üsullarından istifadə vərdişi

Bu faktorlar ayrı-ayrılıqda müəyyən risk yaratsa da, birlikdə olduqda fişinq hücumlarının uğur ehtimalını əhəmiyyətli dərəcədə artırır. Xüsusilə texnologiyaya həddindən artıq güvən istifadəçilərin təhlükəsizlik tədbirlərini ikinci plana keçirməsinə səbəb olur. İstifadəçilər çox vaxt düşünür ki, istifadə etdikləri platforma və ya sistem artıq kifayət qədər qorunur və əlavə ehtiyat tədbirlərinə ehtiyac yoxdur. Bu isə onların daha az diqqətli davranmasına gətirib çıxarır.

Digər mühüm faktor istifadəçilərin etibar meyilləridir. İnsanlar adətən tanınmış qurumlara və ya rəsmi görünən mesajlara daha çox inanırlar və bu, sosial münasibətlərdə formalaşmış psixoloji stereotiplərlə bağlıdır. Hücum edənlər də məhz bu xüsusiyyətdən istifadə edərək özlərini bank, dövlət qurumu və ya tanınmış şirkət kimi təqdim edirlər. Bu zaman istifadəçi məlumatın doğruluğunu yoxlamadan hərəkət edir və mənbənin legitimliyini təsdiqləmədən verilən təlimatları yerinə yetirir. Bu isə nəticədə təhlükəsizlik riski ilə üzləşməyə səbəb olur. Etibarın bu şəkildə manipulyasiyası sosial mühəndisliyin əsas mexanizmlərindən biri kimi çıxış edir və bu sahədə ən effektiv üsullardan hesab olunur. Bundan əlavə, qorxu və təzyiq faktorları da istifadəçi davranışına ciddi təsir göstərir. Hücum mesajlarında tez-tez “hesabınız bağlanacaq”, “təcili təsdiq edin” kimi ifadələr istifadə olunur və bu cür yanaşmalar istifadəçidə psixoloji gərginlik yaradır. İnsan beyni belə hallarda daha çox sürətli qərar verməyə meyilli olur və analitik düşünmə arxa plana keçir. Bu vəziyyətdə istifadəçi hadisənin məntiqi tərəfini analiz etmək əvəzinə, yaranmış riskdən dərhal xilas olmaq istəyir. Nəticədə isə o, vəziyyəti tam dərk etmədən hərəkət edir və bu da hücumun uğurla nəticələnməsinə səbəb olur.

Bu hal göstərir ki, emosional vəziyyət təhlükəsizlik qərarlarına birbaşa təsir edir və istifadəçinin psixoloji durumu onun davranış modelini formalaşdıran əsas amillərdən biridir. Bu səbəbdən müasir kibertəhlükəsizlik yanaşmalarında yalnız texniki müdafiə mexanizmləri deyil, eyni zamanda istifadəçi davranışlarının və psixoloji reaksiyaların da nəzərə alınması vacib hesab olunur.

Texnoloji inkişaf fişinq hücumlarının daha da mürəkkəbləşməsinə səbəb olmuşdur. Əvvəllər bu hücumlar daha sadə və asan aşkar edilə bilən formada idisə, müasir dövrdə informasiya texnologiyalarının inkişafı onların strukturunu və tətbiq mexanizmlərini ciddi şəkildə dəyişdirmişdir. Xüsusilə süni intellekt, böyük verilənlərin analizi və avtomatlaşdırma texnologiyalarının geniş tətbiqi nəticəsində fişinq hücumları daha məqsədyönlü və fərdiləşdirilmiş xarakter almağa başlamışdır. Bu isə hücumların aşkarlanmasını çətinləşdirir və ənənəvi təhlükəsizlik yanaşmalarının effektivliyini müəyyən qədər azaldır.

Müasir fişinq hücumlarında istifadə olunan mesajlar artıq ümumi və standart mətnlərdən ibarət deyil. Hücum edənlər istifadəçilərin davranışlarını, maraq dairələrini və sosial əlaqələrini analiz edərək daha inandırıcı və kontekstə uyğun mesajlar hazırlayırlar. Sosial şəbəkələrdə paylaşılan məlumatlar, açıq mənbələrdə yerləşdirilən şəxsi məlumatlar və digər rəqəmsal izlər bu prosesdə mühüm rol oynayır. Nəticədə istifadəçi ona göndərilən mesajı adi bir xəbər və ya rəsmi bildiriş kimi qəbul edir və onun saxta olduğunu müəyyən etməkdə çətinlik çəkir. Bu cür yanaşma hədəfli fişinq hücumlarının – yəni konkret şəxslərə və ya təşkilatlara yönəlmiş hücumların geniş yayılmasına səbəb olmuşdur. Bununla yanaşı, avtomatlaşdırılmış sistemlər vasitəsilə qısa müddət

ərzində çoxsaylı istifadəçilərə eyni anda hücum etmək mümkün olmuşdur. Bu isə fişinq hücumlarının miqyasını genişləndirmiş və onların təsir dairəsini artırmışdır. Hücum edənlər artıq yalnız fərdi istifadəçiləri deyil, eyni zamanda böyük təşkilatları və onların əməkdaşlarını da hədəf olaraq daha ciddi nəticələrə səbəb ola bilirlər. Bu baxımdan texnoloji inkişaf yalnız hücumların keyfiyyətini deyil, həm də kəmiyyətini artıran əsas amillərdən biri kimi çıxış edir.

İstifadəçi davranışlarının təhlükəsizlik risklərinə təsirini azaltmaq üçün maarifləndirmə mühüm rol oynayır. Müasir kibertəhlükəsizlik yanaşmalarında istifadəçilərin yalnız texniki biliklərlə deyil, həm də riskləri tanımaq və düzgün qərar vermək bacarıqları ilə təchiz olunması əsas prioritetlərdən biri hesab olunur. İstifadəçilər fişinq hücumlarının əsas əlamətlərini, şübhəli mesajların strukturunu və təhlükəli davranış modellərini tanımalı, bu kimi hallarda daha ehtiyatlı və analitik yanaşma nümayiş etdirməlidirlər. Məsələn, naməlum linklərə daxil olmamaq, şəxsi məlumatları təsdiqlənməmiş mənbələrdə paylaşmamaq və iki faktorlu autentifikasiyadan istifadə etmək kimi tədbirlər riskləri əhəmiyyətli dərəcədə azalda bilər. Lakin bu tədbirlərin effektivliyi yalnız onların texniki tətbiqi ilə deyil, istifadəçinin bu tədbirlərin əhəmiyyətini dərk etməsi ilə birbaşa bağlıdır. Əgər istifadəçi təhlükəsizlik qaydalarını yalnız formal şəkildə qəbul edirsə, o zaman bu qaydaların praktik effektivliyi də azalır. Buna görə də maarifləndirmə prosesi yalnız məlumat verməklə məhdudlaşmamalı, eyni zamanda davranış dəyişikliklərinə yönəlməlidir.

Bununla yanaşı, təşkilatlar da öz əməkdaşlarını mütəmadi olaraq təlimləndirməli və təhlükəsizlik mədəniyyətini formalaşdırmalıdır. Təlimlər real ssenarilər əsasında qurulduqda və praktiki yanaşma tətbiq edildikdə onların effektivliyi daha yüksək olur. Bu cür yanaşma əməkdaşların potensial təhlükələri əvvəlcədən tanımasına və düzgün reaksiya verməsinə imkan yaradır. Eyni zamanda təşkilat daxilində təhlükəsizlik qaydalarına əməl olunmasının təşviq edilməsi ümumi risk səviyyəsinin azalmasına səbəb olur.

Digər tərəfdən, texniki müdafiə vasitələri də istifadəçi davranışlarının təsirini azaltmaq üçün vacibdir. Anti-fişinq sistemləri, e-poçt filtrləri və təhlükəsizlik xəbərdarlıqları istifadəçilərin səhv qərarlarının qarşısını müəyyən qədər ala bilər və potensial təhlükələri ilkin mərhələdə bloklaya bilər. Bu sistemlər xüsusilə genişmiqyaslı hücumların qarşısının alınmasında mühüm rol oynayır. Lakin bu texnoloji vasitələr tam qoruma təmin etmir və insan faktorunun rolu yenə də əsas olaraq qalır.

Bu səbəbdən texniki və davranış əsaslı yanaşmaların birgə tətbiqi daha effektiv nəticə verir. Yalnız texnologiyaya güvənmək və ya yalnız istifadəçi maarifləndirilməsinə fokuslanmaq kifayət etmir. Bu iki istiqamətin inteqrasiyası kompleks və davamlı təhlükəsizlik sisteminin formalaşdırılmasına imkan verir. Bu yanaşma həm fərdi istifadəçilər, həm də təşkilatlar üçün daha dayanıqlı müdafiə mexanizmlərinin yaradılmasını təmin edir.

Müasir dövrdə sosial mühəndislik hücumlarının qarşısının alınması yalnız texnoloji məsələ deyil, eyni zamanda sosial və psixoloji məsələ kimi də qiymətləndirilməlidir. İnsan davranışlarının təhlili və bu davranışların risklərə necə təsir etdiyinə araşdırılması kibertəhlükəsizlik strategiyalarının formalaşdırılmasında mühüm əhəmiyyət kəsb edir. Bu istiqamətdə aparılan tədqiqatlar göstərir ki, istifadəçilərin məlumatlılıq səviyyəsinin artırılması və onların davranış modellərinin təkmilləşdirilməsi hücumların uğur faizini əhəmiyyətli dərəcədə azalda bilər.

Nəticə olaraq qeyd etmək olar ki, fişinq və sosial mühəndislik hücumları müasir kibertəhlükəsizlik mühitinin ən ciddi problemlərindən biridir və onların təsiri getdikcə daha da genişlənir. Bu hücumların əsas hədəfi texniki sistemlər deyil, insan faktorudur və bu xüsusiyyət onları digər kibertəhlükələrdən fərqləndirir. İstifadəçi davranışları isə bu hücumların uğurlu olub-olmamasında həlledici rol oynayır və təhlükəsizlik səviyyəsini birbaşa müəyyən edir. Diqqətsizlik, etibar meyli və emosional qərarlar təhlükəsizlik risklərini artıran əsas amillər kimi çıxış edir. Buna görə də effektiv müdafiə yalnız texniki vasitələrlə deyil, eyni zamanda istifadəçilərin maarifləndirilməsi, onların analitik düşünmə bacarıqlarının inkişaf etdirilməsi və düzgün davranış vərdişlərinin formalaşdırılması ilə mümkündür. Bu yanaşma rəqəmsal mühitdə təhlükəsizliyin

təmin olunmasında əsas istiqamətlərdən biri kimi çıxış edir və gələcəkdə bu sahədə daha kompleks və integrasiya olunmuş həllərin tətbiqini zəruri edir.

Ədəbiyyat

1. Kevin D. Mitnick. *The Art of Deception: Controlling the Human Element of Security*. Wiley Publishing, 2002.
2. Christopher Hadnagy. *Social Engineering: The Science of Human Hacking*. Wiley, 2011.
3. APWG. *Phishing Activity Trends Report*, 2023.
4. Ross Anderson. *Security Engineering: A Guide to Building Dependable Distributed Systems*. Cambridge University Press, 2020.

ELEKTRON TİCARƏT PLATFORMALARININ API ARXİTEKTURASINDA BOLA ZƏİFLİYİNİN ANALİZİ VƏ QARŞISININ ALINMASI

Aysu Kərimli İlqar

Magistrant, Azərbaycan Dövlət İqtisad Universiteti

Xülasə. Müasir elektron ticarət platformaları daha çevik olmaq üçün API əsaslı mikroservis arxitekturalarına üstünlük verirlər. Lakin bu keçid özü ilə bərabər yeni təhlükəsizlik riskləri də gətirir. Ən kritik boşluqlardan biri istifadəçi məlumatlarının və ödəniş detallarının sızmasına səbəb olan BOLA (Obyekt Səviyyəsində Qüsurlu Avtorizasiya) zəifliyidir. Təəssüf ki, WAF kimi ənənəvi şəbəkə qoruyucu divarları kənardan tamamilə qanuni görünən bu növ dəyişdirilmiş API sorğularını aşkarlamaqda çox vaxt yetərsiz qalır. Təqdim olunan məqalədə BOLA zəifliyinin elektron ticarət mühitində necə işlədiyi və hücumçuların hansı yollardan istifadə etdiyi ətraflı təhlil olunur. Problemin həlli kimi isə sistem arxitekturasında təsadüfi identifikatorlara (UUID) keçid, obyekt səviyyəsində ciddi mülkiyyət yoxlamalarının (ownership checks) qurulması və API Şlüzü (API Gateway) əsaslı mərkəzləşdirilmiş avtorizasiya modeli təklif edilir. İrəli sürülən bu yanaşmalar onlayn mağazaların ümumi təhlükəsizlik sistemlərinin qurulması və daha da gücləndirilməsi baxımından mühüm əhəmiyyət daşıyır.

Açar sözlər: *elektron ticarət, API təhlükəsizliyi, BOLA, avtorizasiya, kiberhücum, veb tətbiq arxitekturası, informasiya təhlükəsizliyi.*

Aysu Karimli Ilgar

Master's Student

Azerbaijan State University of Economics

ANALYSIS AND PREVENTION OF BOLA VULNERABILITY IN THE API ARCHITECTURE OF E-COMMERCE PLATFORMS

Abstract. Modern e-commerce platforms increasingly adopt API-based microservice architectures to enhance agility. However, this transition introduces new security risks. One of the most critical vulnerabilities is BOLA (Broken Object Level Authorization), which leads to the leakage of user data and payment details. Unfortunately, traditional network defenses, such as Web Application Firewalls (WAF), often prove insufficient in detecting these modified API requests, as they appear entirely legitimate from the outside. This article provides a detailed analysis of the operational mechanism of the BOLA vulnerability and the attack vectors utilized in e-commerce environments. To address this problem, the study proposes implementing random identifiers (UUID) within the system architecture, establishing strict object-level ownership checks, and adopting a centralized authorization model based on an API Gateway. These proposed approaches are of fundamental importance for the development and further optimization of the overall security systems in online stores.

Keywords: *e-commerce, API security, BOLA, authorization, cyberattack, web application architecture, information security.*

Giriş

Son illərdə elektron kommersiyanın sürətli inkişafı onlayn satış sistemlərinin memarlığında köklü dəyişikliklərə, xüsusən də REST və GraphQL əsaslı API-lara keçidə səbəb olmuşdur. "Headless commerce" kimi yeni arxitekturalar əməliyyat çevikliyini artırsa da, çoxsaylı API uc nöqtələrinin xarici şəbəkəyə açıq olması hücum səthini kəskin genişləndirmişdir. Ənənəvi sistemlərdən fərqli olaraq, bugünkü e-ticarət API-larına yönələn hücumların strukturu fərqlidir. Bu səbəbdən, ənənəvi Şəbəkə və Veb Tətbiq Qoruyucu Divarları (WAF) kənardan qanuni görünən, lakin arxasında məntiqi boşluqlar gizlədən API hücumlarının qarşısını almaqda çox vaxt yetərsiz qalır [3].

OWASP (Open Worldwide Application Security Project) təşkilatının hesabatlarına əsasən, API təhlükəsizlik riskləri arasında birinci yeri məhz belə məntiqi boşluqlardan qaynaqlanan BOLA (Obyekt Səviyyəsində Qüsurlu Avtorizasiya) zəifliyi tutur [4]. Elektron ticarət sistemlərində müştərinin sifariş tarixçəsi, ödəniş detalları və fərdi məlumatları verilənlər bazasında unikal identifikatorlarla saxlanılır. Əgər API sorğuları zamanı server müraciət edilən obyektin həqiqətən sorğunu göndərən istifadəçiyə aid olub-olmadığını sərt şəkildə yoxlamırsa, hücumçular sadəcə URL daxilindəki ID göstəricilərini dəyişdirərək başqalarının məlumatlarına çıxış əldə edə bilirlər [6]. Bu cür avtorizasiya boşluqları sistemin bütövlüyünü pozmaqla yanaşı, kütləvi məlumat sızmalarına səbəb olur. Nəticə etibarlı ilə, elektron ticarət platformaları GDPR və PCI-DSS kimi beynəlxalq standartların tələblərini pozduqları üçün həm böyük məbləğdə maliyyə cərimələri, həm də ciddi reputasiya itkisi ilə üz-üzə qalırlar.

2. BOLA Zəifliyinin İşləmə Mexanizmi və Təsirləri

BOLA zəifliyinin yaranma mexanizmini tam başa düşmək üçün ilk növbədə informasiya təhlükəsizliyinin iki təməl anlayışı – autentifikasiya (kimlik doğrulama) və avtorizasiya (səlahiyyətləndirmə) arasındakı fərq aydınlaşdırılmalıdır. Autentifikasiya istifadəçinin kimliyini təsdiqləyərək ona sistemə giriş hüququ verir (məsələn, istifadəçi adı və şifrə vasitəsilə). Avtorizasiya isə artıq sistemə daxil olmuş istifadəçinin hansı spesifik resurslara və ya obyektlərə çıxış hüququnun olduğunu müəyyən edir [5]. Elektron ticarət API-larında BOLA problemi məhz bu iki proses arasındakı boşluqdan qaynaqlanır. Server istifadəçinin kimliyini uğurla təsdiqləyib sessiyasını qanuni şəkildə qəbul etsə də, həmin istifadəçi API sorğusundakı ID göstəricilərini dəyişərək başqa bir müştərinin sifarişinə müraciət etdikdə, server onun bu spesifik obyekt üzərindəki səlahiyyətini (avtorizasiyasını) yoxlamır. Nəticədə, sistem heç bir şübhə duymadan başqasına aid məxfi məlumatları icazəsiz şəxsə qaytarır.

2.1. Hücum Vektorunun Texniki Təhlili

Elektron ticarət platformasında BOLA hücumunun necə baş verdiyini tipik bir ssenari üzərindən izah etmək mümkündür. Fərz edək ki, hücumçu onlayn mağazada qeydiyyatdan keçib və öz keçmiş sifarişlərinin detallarına baxmaq istəyir. Bu zaman brauzer arxa planda serverə aşağıdakı kimi standart bir REST API sorğusu göndərir:

```
GET /api/v1/orders/71025 HTTP/1.1
```

```
Host: api.e-ticaret-platformasi.com
```

```
Authorization: Bearer eyJhbGciOiJIUzI1NiIsInR5cCI6Ikpz...
```

Bu sorğuda 71025 rəqəmi verilənlər bazasındakı xüsusi bir sifariş obyektinin identifikatorudur. Authorization başlığında Bearer tokeni isə istifadəçinin sistemə tam qanuni yolla daxil olduğunu, yəni autentifikasiyadan keçdiyini təsdiqləyir. Server bu sorğunu qəbul edir və 71025 nömrəli sifarişin detallarını qaytarır. Zəiflik məhz bu mərhələdə başlayır. Hücumçu xüsusi HTTP proksi alətlərindən istifadə edərək göndərilən sorğunu tutur və sadəcə identifikatoru dəyişdirərək (məsələn, 71026 edərək) yenidən serverə göndərir.

Əgər platformanın API arxitekturasında obyektin kimə məxsus olduğunu yoxlayan xüsusi bir mexanizm qurulmayıbsa, server sadəcə təqdim olunan tokenin vaxtının keçib-keçmədiyinə baxacaq. Token etibarlı olduğu üçün server 71026 nömrəli sifarişin əslində tamamilə başqa bir

müştəriyə aid olduğunu yoxlamadan, həmin sifarişə aid məxfi detalları birbaşa hücumçuya qaytaracaq.

2.2. E-ticarət Sistemlərinə Təsirləri

BOLA zəifliyinin istismarı elektron ticarət şirkətləri üçün aşağıdakı nəticələrə səbəb olur:

- **Məxfiliyin Pozulması:** Adətən, sistemdəki sifariş tarixçələrində müştərinin tam adı, ev ünvanı və bank kartının son 4 rəqəmi kimi həssas fərdi məlumatlar (PII) yer alır. Bu cür detalların kütləvi şəkildə sızması istifadəçiləri birbaşa və xüsusi hədəflənmiş fişinq hücumlarının asan qurbanına çevirir.
- **Maliyyə İtkiləri:** Əgər zəiflik məlumatları dəyişdirən (PUT, POST, DELETE) API-larda mövcuddursa, hücumçu başqa bir müştərinin çatdırılma ünvanını öz ünvanı ilə əvəzləyə və ya başqasının qeydiyyatdan keçmiş kartı ilə alış-veriş edə bilər.
- **Hüquqi Təzyiqlər:** Məlumat sızmaları şirkətlərin milyonlarla dollar dəyərində cərimələnməsi ilə nəticələnməyə bilər.

3. Zəifliyin Qarşısının Alınması üçün Arxitektura Həllər

Elektron ticarət sistemlərinin API infrastrukturunda BOLA zəifliyinin qarşısını almaq üçün sadəcə perimetr qoruması kifayət etmir. Həm verilənlər bazası, həm proqram kodu, həm də şəbəkə arxitekturası səviyyəsində çoxqatlı təhlükəsizlik tədbirləri tətbiq edilməlidir.

3.1. Təxmin Edilə Bilməyən İdentifikatorların (UUID) Tətbiqi

İnternet mağazaların əksəriyyətində istifadəçi, səbət və sifariş cədvəllərinin əsas identifikatorları (primary keys) avtomatik artan sadə rəqəmlərdən şəkildə qurulur. BOLA hücumlarını bu qədər təhlükəli və uğurlu edən əsas amil də elə budur: hücumçu növbəti ID-nin nə olacağını çox rahatlıqla təxmin edə bilər. Təhlükəsizlik arxitekturasında atılacaq ilk mühüm addım məhz bu ardıcıl rəqəmlərdən imtina etmək və obyektlərə riyazi baxımdan tapılması qeyri-mümkün olan 128-bitlik UUIDv4 formatı tətbiq etməkdir [1]. Bu halda URL strukturu `.../orders/550e8400-e29b-41d4-a716-446655440000` formasını alır. Lakin qeyd edilməlidir ki, UUID istifadəsi BOLA-nın köklü həlli deyil, sadəcə təxmin etmə ehtimalını trilyonda birə qədər azaldan ləngidici mitiqasiya mexanizmidir.

3.2. Obyekt Səviyyəsində Məxsusluğun Yoxlanılması

Məsələnin fundamental həlli isə biznes məntiqi səviyyəsində mülkiyyət yoxlamasının aparılmasıdır. Hər bir API uc nöqtəsinə (endpoint) müraciət edilən zaman, sistem tələb olunan obyekti bazadan çağırılmazdan əvvəl sorğunu göndərən istifadəçinin sessiya tokeninin (məsələn, JWT) içindəki `user_id` dəyərini oxumalıdır.

Daha sonra, verilənlər bazasına göndərilən SQL (və ya NoSQL) sorğusu sadəcə `SELECT * FROM orders WHERE order_id = ?` olmamalıdır. Təhlükəsiz proqramlaşdırma prinsiplərinə əsasən, bu sorğu mütləq istifadəçinin öz identifikatoru ilə əlaqələndirilməlidir: `SELECT * FROM orders WHERE order_id = ? AND user_id = ?` [5].

Məhz bu məntiq sayəsində, hücumçu hər hansı bir sifarişin ID-sini düzgün təxmin etsə belə, həmin obyekt başqa bir müştəriyə aid olduğu üçün məlumat bazası heç bir nəticə qaytarmayacaq. Əvəzində sistem, icazəsiz müdaxiləni bloklayaraq "HTTP 403 Forbidden" (Giriş qadağandır) və ya "404 Not Found" (Tapılmadı) xətası verəcək.

3.3. API Gateway və "Zero Trust" Arxitekturası

İrihəcmli e-ticarət platformalarının arxa planında onlarla fərqli mikroservis (məsələn, ödəniş, logistika, müştəri xidmətləri) eyni anda fəaliyyət göstərir. Təsəvvür edin ki, hər bir mikroservis üçün eyni mülkiyyət yoxlamasını (ownership check) təkrar-təkrar sıfırdan yazmaq lazımdır. Bu yanaşma nəinki proqramçı xətalarına zəmin yaradır, həm də sistemin fərqli nöqtələrində eyni təhlükəsizlik boşluqlarının təkrarlanmasına yol açır [2].

Məhz bu problemin qarşısını almaq üçün daxili arxitektura Zero Trust prinsipinə əsaslanan API Şlüzü (API Gateway) tətbiq edilməlidir. Bu modeldə bütün xarici HTTP sorğuları

birbaşa mikroservislərə deyil, ilk növbədə bu mərkəzi şlüzə daxil olur. API Gateway OAuth 2.0 və ya OpenID Connect kimi protokollardan istifadə edərək mərkəzi qərarvermə nöqtəsi kimi çıxış edərək istifadəçinin obyektə çatmaq üçün kifayət qədər səlahiyyətinin olub-olmadığını dəqiqləşdirir. Yalnız və yalnız bu avtorizasiya mərhələsi uğurla keçildikdən sonra sorğu aidiyyəti mikroservisə ötürülür. Bu cür mərkəzləşdirilmiş arxitektura model BOLA zəifliklərinin sistemin dərinliklərinə sızmadan, elə girişdəcə bloklanmasını təmin edən ən effektiv yoldur [4].

Nəticə

Elektron ticarət platformalarının müasir təhlükəsizlik paradigması sadəcə şəbəkənin (SSL/TLS) şifrələnməsindən və ya zərərli kod inyeksiyalarının bloklanmasından ibarət deyil. Aparılan təhlillər göstərir ki, BOLA kimi məntiqi zəifliklər sistemin daxili arxitekturasındakı dizayn və avtorizasiya xətlərindən yaranır və e-ticarət ekosistemi üçün ən böyük təhdid mənbəyidir.

Bu məqalədə irəli sürülən arxitektura həllər — təsadüfi identifikatorların (UUID) tətbiqi, obyekt səviyyəsində mərkəzləşdirilmiş və sərt mülkiyyət yoxlamalarının (ownership checks) aparılması, eləcə də API Gateway üzərindən "Zero Trust" modelinin qurulması elektron ticarət sistemlərinin məxfiliyini qorumaq üçün zəruri addımlardır. Bu araşdırma çərçivəsində əldə olunan nəzəri və praktiki nəticələr, dissertasiya işi çərçivəsində bütöv bir internet mağazanın təhlükəsizlik sisteminin işlənilməsi, onun modelləşdirilməsi və sınaqdan keçirilməsi üçün fundamental baza rolunu oynayacaqdır.

İstifadə edilmiş ədəbiyyat siyahısı

1. De Ryck, P. (2022). *API Security in Action*. Manning Publications, 88-95.
2. Richards, M., & Ford, N. (2020). *Fundamentals of Software Architecture: An Engineering Approach*. O'Reilly Media, 45-50.
3. Stuttard, D., & Pinto, M. (2021). *The Web Application Hacker's Handbook: Finding and Exploiting Security Flaws* (2nd ed.). Wiley, 112-118.
4. OWASP Foundation. (2023). *OWASP API Security Top 10 - 2023*. Open Worldwide Application Security Project, 4-12.
5. Hoffman, J. (2020). *Web Security for Developers: Real Threats, Practical Defense*. No Starch Press, 78-85.
6. Çelik, A. (2023). *İnformasiya Təhlükəsizliyi və E-ticarət Sistemləri*. Bakı: Akademik Nəşriyyat, 55-60.
7. Newman, S. (2021). *Building microservices: Designing fine-grained systems* (2nd ed.). O'Reilly Media.
8. Siriwardena, P. (2020). *Advanced API security: Securing APIs with OAuth 2.0, OpenID Connect, JWS, and JWE* (2nd ed.).

MALİYYƏDƏ SİMMETRİK ŞİFRƏLƏMƏNİN TƏTBİQLƏRİ

İbadova Səbinə Nadir


Azərbaycan Respublikasının Prezidenti yanında, Dövlət İdarəçilik Akademiyasının, 2ci kurs magistrantı

Açar sözlər: Simmetrik şifrələmə, maliyyə, onlayn bankçılıq, ödəniş sistemləri, maliyyə məlumat bazaları, maliyyə kommunikasiyası, kibertəhlükəsizlik, açar idarəetmə.

Giriş


Simmetrik şifrələmə elektron məlumatları həm şifrələmək, həm də deşifrə etmək üçün yalnız bir açarın (gizli açar) istifadə edildiyi şifrələmə növüdür. Simmetrik şifrələmə vasitəsilə əlaqə quran qurumlar açarı mübadilə etməlidirlər ki, həmin açar, şifrənin açılması prosesində istifadə olunsun. Bu şifrələmə üsulu mesajları şifrələmək və deşifrə etmək üçün bir cüt açarın- biri ictimai, digəri gizli istifadə edildiyi asimmetrik şifrələmədən fərqlənir.[1]

Simmetrik şifrələmə



Şəkil 1. Simmetrik şifrələmənin işləmə prinsipi

ASİMMETRİK ŞİFRƏLƏMƏ



Şəkil 2. Asimmetrik şifrələmənin işləmə prinsipi


Simmetrik şifrələmə alqoritmlərindən istifadə edərək məlumatın "şifrənməsində" məqsəd bundan ibarətdir ki, şifrələnmiş mətni açmaq üçün istifadə olunan gizli açarı olmayan heç kəs tərəfindən məlumat başa düşülməsin. Açara sahib olan nəzərdə tutulan alıcı mesajla sahib olduqdan sonra alqoritm öz hərəkətini tərsinə çevirir ki, mesaj orijinal oxuna bilən formasına qaytarılsın. Göndərən və alıcının hər ikisinin istifadə etdiyi məxfi açar xüsusi parol/kod ola bilər və ya təhlükəsiz təsadüfi nömrə generatoru (RNG) tərəfindən yaradılan təsadüfi hərf və ya rəqəmlər silsiləsi ola bilər. Bank səviyyəli şifrələmə üçün simmetrik açarlar FIPS 140-2 kimi sənaye standartlarına uyğun sertifikatlaşdırılmış RNG istifadə edərək yaradılmalıdır. [2]

Simmetrik şifrələmə alqoritmlərinin iki növü var:

1. Blok alqoritmləri. Blok şifrələmədə şifrələmə vahidi kimi bloktan (qeyd olunmuş bitlər ardıcılığı) istifadə edilir ki, o da eyni uzunluqda olan şifrələnmiş mətn blokuna çevrilir.


2. Axın alqoritmləri. Məlumat sistem yaddaşında saxlanılmaq əvəzinə axın zamanı şifrələnir. [3, səh 71-72]

BLOK ŞİFRƏLƏMƏ



Şəkil 3. Blok alqoritmi

AXIN ŞİFRƏLƏMƏ



Şəkil 4. Axın alqoritmi

Bugünkü kiber-dünyada məlumatların bütün formalarına icazəsiz giriş riski həmişə mövcuddur. Ən çox risk altında olan maliyyə və ödəniş sistemi məlumatlarıdır ki, bu da müştərilərin şəxsiyyətini müəyyənləşdirən məlumatları (PII) və ya ödəniş kartı detallarını ifşa edə bilər. Şifrələmə PII-ni qorumaq və ödəniş əməliyyatlarını emal edən müəssisələrin hər gün ,hər dəqiqə qarşılaşdığı riskləri azaltmaq üçün vacibdir. [1]

Simmetrik şifrələmənin onlayn bank əməliyyatlarında tətbiqi

Simmetrik şifrələmə onlayn bank əməliyyatlarının təhlükəsizliyinin təmin edilməsində mühüm rol oynayır. Onlayn bankçılıq təhlükəsiz kommunikasiya kanallarına və istifadəçi etimadnamələri, maliyyə əməliyyatları və şəxsi məlumatlar kimi həssas məlumatların qorunmasına əsaslanır. Bu təhlükəsizlik problemlərini müxtəlif yollarla həll etmək üçün simmetrik şifrələmə istifadə olunur: [4]

Məlumat məxfiliyi. Simmetrik şifrələmə istifadəçinin cihazı (məsələn, kompüter və ya mobil cihaz) və bankın serverləri arasında ötürülən məlumatların şifrələnməsi üçün istifadə olunur. Bu, icazəsiz şəxslər məlumatları ələ keçirərsələr belə, şifrələnmə zamanı istifadə olunan açar olmadan onu başa düşə və ya manipulyasiya edə bilməmələrini təmin edir. [4]

Təhlükəsiz giriş və doğrulama. Simmetrik şifrələmə istifadəçinin onlayn bank hesabına daxil olmaq üçün istifadə etdiyi məlumatlarını (istifadəçi adı və şifrə) qorumaq üçün tətbiq olunur. Məlumat ötürmə zamanı şifrələnir, bu da icazəsiz şəxslərin rabitəni kəsə bilsələr belə,lazımlı məlumat əldə etmələrini olduqca çətinləşdirir. [5]

Tranzaksiya təhlükəsizliyi. Maliyyə əməliyyatları, o cümlədən fond köçürmələri və hesab ödənişləri, həssas məlumatların mübadiləsini nəzərdə tutur. Simmetrik şifrələmə bu əməliyyatların məxfiliyini və bütövlüyünü təmin edir. Məbləğ və alıcı kimi əməliyyatın təfərrüatları ötürülməzdən əvvəl şifrələnir. [6]


Sessiyanın şifrələnməsi. Onlayn bank seansları simmetrik şifrələmə ilə təmin edilir. İstifadəçi daxil olduqdan sonra təhlükəsiz seans qurulur və həmin sessiya zamanı mübadilə edilən məlumatları şifrələmək üçün simmetrik açarlar yaradılır. Bu, icazəsiz şəxslərin istifadəçi ilə bank serveri arasındakı əlaqəni dinləməsinin qarşısını alır. [7]

Secure Sockets Layer (SSL) və Transport Layer Security (TLS). SSL və onun varisi TLS onlayn ünsiyyəti təmin etmək üçün geniş istifadə olunan protokollardır. Onlar simmetrik şifrələmə alqoritmlərindən istifadə edərək istifadəçinin brauzeri ilə bankın serveri arasında mübadilə edilən məlumatları şifrələyir.Bu şifrələmə ötürülən məlumatın məxfiliyini və bütövlüyünü təmin edir. [4]

Açar idarəetmə. Simmetrik şifrələmə şifrələmə açarlarının təhlükəsiz idarə edilməsini tələb edir. Onlayn bank sistemləri şifrələmə açarlarını icazəsiz girişdən qorumaq üçün etibarlı açar idarəetmə təcrübələrini həyata keçirir. Buraya açarların təhlükəsiz yaradılması, paylanması və saxlanması daxildir. [7]

Təhlükəsizlik standartlarına uyğunluq. Onlayn bankçılıqda simmetrik şifrələmə Ödəniş Kartı Sənayesi Məlumat Təhlükəsizliyi Standartı (PCI DSS) və digər regional və ya milli məlumatların mühafizəsi qanunları kimi təhlükəsizlik standartlarına və qaydalarına uyğun olmalıdır. Uyğunluq onlayn bank sisteminin müəyyən edilmiş təhlükəsizlik tələblərinə cavab verməsini təmin edir.[5]

Davamlı monitoring və yeniləmələr. Onlayn bankçılıq sistemləri potensial təhlükəsizlik təhdidlərini aşkar etmək və onlara cavab vermək üçün davamlı monitoringdən keçir. Ortaya çıxan zəiflikləri aradan qaldırmaq və sistemin ümumi təhlükəsizliyini artırmaq üçün şifrələmə protokolları və alqoritmlərinin müntəzəm yenilənməsi həyata keçirilir. [4]



Şəkil 5 Simmetrik şifrələmənin onlayn bank əməliyyatlarında tətbiqi sxemi

Simmetrik şifrələmənin maliyyə kommunikasiyasında tətbiqi

Simmetrik şifrələmə maliyyə rəhbərliyinin təmin edilməsində, maliyyə institutları, müəssisələr və fiziki şəxslər arasında mübadilə edilən həssas məlumatların məxfiliyinin və bütövlüyünün təmin edilməsində mühüm rol oynayır. Simmetrik şifrələmənin maliyyə rəhbərliyində necə tətbiq olunduğunun əsas aspektləri bunlardır:

Məlumatların məxfiliyi. Simmetrik şifrələmə əməliyyat təfərrüatları, hesab məlumatları və digər həssas məlumatlar daxil olmaqla, maliyyə mesajlarının məzmununu şifrələmək üçün istifadə olunur. Bu şifrələmə rəhbərliyi ələ keçirilsə belə, şifrə açma açarı olmadan məlumatın oxunmaz qalmasını təmin edir. [1]

Rəhbərliyi üçün təhlükəsiz protokollar. Maliyyə institutları tez-tez veb-əsaslı ünsiyyət üçün HTTPS (Hypertext Transfer Protocol Secure) kimi təhlükəsiz rəhbərliyi protokollarından və digər məlumat mübadiləsi növləri üçün təhlükəsiz fayl ötürmə protokollarından istifadə edirlər. Bu protokollar tranzit zamanı məlumatları qorumaq üçün simmetrik şifrələmədən istifadə edir. [5]

Mesaj şifrələmə. Elektron məlumat mübadiləsi (EDI), SWIFT (Society for Worldwide Interbank Financial Telecommunication) və ya digər rəhbərliyi kanalları vasitəsilə ötürülən maliyyə mesajları adətən simmetrik şifrələmə alqoritmlərindən istifadə etməklə şifrələnir. Bu, əməliyyat təfərrüatlarının məxfiliyini qoruyur və icazəsiz girişin qarşısını alır. [8]

Doğrulama və bütönlük. Simmetrik şifrələmə məlumatların autentifikasiyası mexanizmlərini təmin etməklə maliyyə kommunikasiyasının bütövlüyünü təmin etməyə kömək edir. Rəqəmsal imzalar və mesajın identifikasiyası kodları (MAC) simmetrik şifrələmə ilə yanaşı göndəricinin həqiqiliyini yoxlamaq və ötürülən məlumatların hər hansı saxtakarlığını və ya dəyişdirilməsini aşkar etmək üçün istifadə olunur. [3]

Əsas idarəetmə təcrübələri. Simmetrik şifrələmədə effektiv açar idarəçiliyi çox vacibdir. Maliyyə institutları şifrələmə açarlarının yalnız səlahiyyətli tərəflər arasında paylaşılmasını təmin

etmək üçün təhlükəsiz açar paylanması və idarəetmə təcrübələrindən istifadə edir. Açarların müntəzəm olaraq yenilənməsi və güclü, təsadüfi yaradılan açarların istifadəsi rabitənin təhlükəsizliyini artırır. [7]

Virtual şəxsi şəbəkələr (VPN). Maliyyə ünsiyyətində, xüsusən də uzaqdan bağlantılar və təşkilatlararası əlaqə üçün VPN-lərdən tez-tez istifadə olunur. Simmetrik şifrələmə VPN tunelləri daxilində məlumatların təhlükəsizliyini təmin edir, ictimai internet üzərində təhlükəsiz və özəl rabitə kanalı yaradır. [9]

Qaydalara uyğunluq. Maliyyə institutları məlumat təhlükəsizliyi və məxfiliyi ilə bağlı müxtəlif qaydalara və standartlara əməl etməlidir. Simmetrik şifrələmə həssas maliyyə məlumatlarının qorunması üçün möhkəm və standartlaşdırılmış metod təqdim etməklə bu uyğunluq tələblərinə cavab verdiyini göstərir. [4]

Təhlükəsiz məlumat saxlama. Maliyyə institutları çoxlu sayda əməliyyat və müştəri məlumatlarını saxlayır. Bu saxlanılan məlumatların təhlükəsizliyini təmin etmək üçün simmetrik şifrələmə tətbiq edilir və nəticədə fiziki təhlükəsizlik pozulsa belə, məlumatın icazəsiz girişdən qorunmasını təmin edir. [5]

Davamlı monitoring və insidentlərə cavab. Maliyyə təşkilatları potensial təhlükəsizlik təhdidlərini aşkar etmək və onlara cavab vermək üçün davamlı monitoring və insidentlərə cavab mexanizmləri tətbiq edir. Bura şübhəli fəaliyyətlərin monitoringi, nümunələrin təhlili və hər hansı təhlükəsizlik insidentlərinin operativ şəkildə həlli daxildir. [4]

Nəticə

Məqalə maliyyə əməliyyatlarının təmin edilməsində və həssas məlumatların qorunmasında simmetrik şifrələmənin əsas rolunu, simmetrik şifrələmənin onlayn bankçılıqda infrastrukturun əsas elementi olduğunu ümumiləşdirməklə yekunlaşır. O, maliyyə sektorunda inkişaf edən kibertəhlükəsizlik təhdidlərini həll etmək üçün davamlı innovasiya və əməkdaşlığa ehtiyac olduğunu vurğulayır.

ƏDƏBİYYAT

1. [1] <https://www.cryptomathic.com/news-events/blog/symmetric-key-encryption-why-where-and-how-its-used-in-banking>
2. [2] Selected articles on Key Management (2012-today) by Ashiq JA, Dawn M. Turner, Guillaume Forget, James H. Reinholm, Peter Landrock, Peter Smirnoff, Rob Stubbs, Stefan Hansen and more.
3. [3] Əliquliyev R.M., İmamverdiyev Y.N.. Kriptoqrafiyanın əsasları, Bakı 2006, səh 71-72.
4. [4] Uma Dixit. Cryptography — Security in E-Banking. IOSR Journal of Business and Management (IOSR-JBM).
5. [5] Kewin Chikomo, Ming Ki Chong, Alpan Arnab, Andrew Hutchison, “Security of Mobile Banking”.
6. [6] <https://www.linkedin.com/advice/3/how-can-you-secure-financial-transactions#how-does-cryptography-secure-financial-transactions>
7. [6] Simmetrik Açar Şifrələmə- bankçılıqda niyə, harada və necə istifadə olunur (2019), Peter Smirnoff & Dawn M. Turner.
8. [8] <https://www.devglan.com/online-tools/text-encryption-decryption>
9. [9] <https://openvpn.net/solutions/industries/finance/>

Müəssisələrdə Süni İntellektin Tətbiqi Və Mövcud Problemlər

Məmmədli İlkin magistrant

Azərbaycan Dövlət İqtisad Universiteti

Xülasə

Bu tədqiqat müəssisələrdə süni intellekt texnologiyalarının tətbiqinin cari vəziyyətini, əldə edilən üstünlükləri və mövcud problemləri araşdırır. Tədqiqatın məqsədi Azərbaycan və dünya iqtisadiyyatı kontekstində süni intellektin biznes proseslərinə integrasiyasının effektivliyini qiymətləndirmək, əsas maneələri müəyyənləşdirmək və praktiki tövsiyələr vermək olur. İş keyfiyyətli ədəbiyyat icmalı, müqayisəli təhlil və case-study metodlarına əsaslanır. Nəticələr göstərir ki, süni intellektin tətbiqi istehsal xərclərini azaldır, qərar qəbulunu sürətləndirir və müştəri məmuniyyətini artırır; lakin etik problemlər, məlumat məxfiliyi, ixtisaslı işçi qüvvəsinin çatışmazlığı və yüksək infrastruktur xərcləri bu texnologiyanın geniş yayılmasına mane olur. Tədqiqat müəssisə rəhbərləri, siyasətçilər və tədqiqatçılar üçün aktual tövsiyələr irəli sürür.

Açar sözlər: *süni intellekt, müəssisə, rəqəmsal transformasiya, maşın öyrənməsi, idarəetmə*

Abstract

This study examines the current state of artificial intelligence (AI) adoption in enterprises, the benefits achieved, and the existing challenges. The aim of the research is to assess the effectiveness of AI integration into business processes in the context of Azerbaijan and the global economy, identify key barriers, and provide practical recommendations. The work relies on a systematic literature review, comparative analysis, and case-study methodology. The findings indicate that AI adoption reduces production costs, accelerates decision-making, and improves customer satisfaction; however, ethical concerns, data privacy issues, a shortage of qualified personnel, and high infrastructure costs hinder its widespread diffusion. The study puts forward relevant recommendations for enterprise managers, policymakers, and researchers.

Keywords: *artificial intelligence, enterprise, digital transformation, machine learning, management*

JEL kodları: O33, M15, L25, D83

Giriş

Süni intellekt (Sİ) texnologiyaları son onillikdə global iqtisadiyyatın strateji prioritetinə çevrilmişdir. McKinsey Global Institute-un (2023) hesablamalarına görə, süni intellektin iqtisadiyyata potensial illik töhfəsi 13-22 trilyon ABŞ dolları aralığındadır. Bu rəqəmlər texnologiyanın transformativ gücünü əyani şəkildə ortaya qoyur. İstehsal, maliyyə, səhiyyə, logistika və pərakəndə satış kimi sahələrdə Sİ-nin tətbiqi nəinki xərcləri azaldır, həm də keyfiyyəti artırır və yeni iş modellərinin yaranmasına zəmin hazırlayır.

Azərbaycanda rəqəmsal transformasiya prosesləri dövlət siyasətinin ayrılmaz hissəsinə çevrilmişdir. "Azərbaycan 2030: Sosial-iqtisadi İnkişaf Konsepsiyası" çərçivəsində rəqəmsal iqtisadiyyatın inkişafı prioritet vəzifələrdən biri kimi müəyyən edilmişdir (Azərbaycan Respublikasının Prezidenti, 2021). Buna baxmayaraq, yerli müəssisələrin böyük əksəriyyəti süni intellektin tətbiqinin ilkin mərhələsindədir.

Tədqiqatın əsas məqsədi müəssisə səviyyəsində süni intellektin tətbiq sahələrini sisteməlik şəkildə araşdırmaq, üstünlüklərini müəyyən etmək və mövcud texniki, iqtisadi, hüquqi və etik problemləri təhlil etməkdən ibarətdir. Tədqiqat həm nəzəri, həm də tətbiqi baxımdan əhəmiyyət daşıyır: nəzəri baxımdan Sİ-nin müəssisə iqtisadiyyatına integrasiyasının konseptual çərçivəsini

zənginləşdirir, tətbiqi baxımdan isə idarəetmə qərarlarının optimallaşdırılmasına töhfə verir. Tədqiqatın informasiya bazasını beynəlxalq elmi jurnallar, hesabatlar və statistik məlumatlar təşkil edir. Tədqiqat 2019-2024-cü illər dövrünü əhatə edir.

Ədəbiyyat icmal

Süni intellektin müəssisələrə təsiri mövzusunda aparılmış tədqiqatlar üç əsas istiqamətdə cəmləşir:

1. Sİ-nin məhsuldarlığa təsiri
2. insan resurslarına və əmək bazarına yansımaları,
3. idarəetmə proseslərinin transformasiyası.

Brynjolfsson və McAfee (2014) öz əsərlərində rəqəmsal texnologiyaların ikinci maşın dövrü yaratdığını arqumentləşdirmişlər. Müəlliflər göstərmişlər ki, avtomatlaşdırma yalnız rutin tapşırıqları deyil, idrak tələb edən vəzifələri də əhatə etməyə başlayır. Bu konsepsiya Acemoğlu və Restrepo-nun (2022) tədqiqatlarında daha da inkişaf etdirilmiş, Sİ-nin əmək bazarında işçiləri əvəz etmə (displacement) və komplementarlıq effektləri müqayisəli şəkildə təhlil edilmişdir.

Müəssisə səviyyəsindəki empirik tədqiqatlar da mühüm nəticələr ortaya qoyur. Seamans və Raj (2018) ABŞ-ın istehsal sektorunda robotlaşmanın məhsuldarlığa müsbət, lakin ümumi məşğulluğa mürəkkəb təsir etdiyini müəyyən etmişlər. Bughin et al. (2018) Sİ-nin maliyyə sektorunda dəyər yaratma potensialının ən yüksək olduğunu, bununla belə insan nəzarətinin hələ də vacib rol oynadığını sübut etmişlər. Son dövr tədqiqatçıları — Davenport və Mittal (2023) — "augmented intelligence" konsepsiyasını irəli sürərək göstərmişlər ki, insan-maşın əməkdaşlığı tam avtomatlaşdırmadan daha yüksək nəticə verir.

Problemlər baxımından Russell (2019) Sİ-nin etik çərçivəsizliyi məsələsini araşdırmış, Zuboff (2019) isə "gözetleme kapitalizmi" konsepsiyası ilə məlumat iqtisadiyyatının gətirdiyi məxfilik risklərini gündəmə gətirmişdir. Azərbaycan kontekstindəki tədqiqatlar isə məhdud sayda olmaqla, əsasən dövlət sənədləri və beynəlxalq hesabatlara istinad edir (OECD, 2023; Dünya Bankı, 2023).

Ədəbiyyat icmal göstərir ki, mövcud tədqiqatlarda Azərbaycan müəssisələri üçün xüsusi ampirik araşdırmalar yoxdur. Bu tədqiqat həmin boşluğu doldurmaq məqsədi daşıyır.

Metod Və Dəyişənlər

Tədqiqatda üç əsas metoddan istifadə edilmişdir: sistematik ədəbiyyat icmal (SLI), müqayisəli təhlil və çox halı case-study metodu. Sistematik ədəbiyyat icmal üçün Web of Science, Scopus və Google Scholar bazalarından 2019-2024-cü illər arasında nəşr edilmiş 120-dən çox məqalə seçilmiş, onlardan meyarlara cavab verən 47-si ətraflı təhlil edilmişdir. Seçim meyarları:

1. müəssisə səviyyəsində Sİ tətbiqini əhatə etmək,
2. empirik və ya nəzəri baza olması,
3. ingilis, rus və ya Azərbaycan dilində olması.

Tədqiqatın əsas dəyişənləri aşağıdakılardır: asılı dəyişən- Sİ tətbiqinin müəssisə performansına təsiri (məhsuldarlıq artımı, xərc azalması, müştəri məmnuniyyəti); müstəqil dəyişənlər - Sİ investisiya həcmi, texnoloji hazırlıq səviyyəsi, idarəetmə yetkinliyi, işçilərin Sİ savadlılığı; nəzarət dəyişənləri- müəssisənin ölçüsü, sektoru və coğrafi mövqeyi.

Case-study hissəsində Amazon, Siemens və yerli bir logistika şirkətinin Sİ tətbiq təcrübələri müqayisəli şəkildə araşdırılmışdır. Müqayisə meyarları Yin (2018)-in çox-halı case-study protokoluna uyğun olaraq müəyyən edilmişdir.

İlkin Nəticələr Və Müzakirə Sİ Tətbiqinin Üstünlükləri

Ədəbiyyat icmalı və case-study nəticələri göstərir ki, Sİ-nin tətbiqi müəssisələrə dörd əsas istiqamətdə üstünlük verir:

Əməliyyat səmərəliliyi. Amazon-un anbar robotları (Kiva sistemləri) əməliyyat xərclərini 20% azaltmış, sifarişin yerinə yetirilmə sürətini 4 dəfə artırmışdır (Bughin et al., 2018). Şirkət özünün Sİ əsaslı tövsiyə alqoritmi sayəsində hər il müştəri itkisinin qarşısını alaraq təxminən 1 milyard dollar qənaət edir (ACM Transactions on Management Information Systems, 2015, vol. 6, no. 4, Article 13, s.7).

Qərar qəbuletmənin sürətlənməsi. Maşın öyrənməsi modellərinin tətbiqi maliyyə qərarlarının orta 60% daha sürətli qəbul edilməsinə imkan verir (Davenport & Mittal, 2023). Proqnozlaşdırıcı analitika vasitəsilə tələb planlaması daha dəqiq həyata keçirilir.

Müştəri təcrübəsinin yaxşılaşması. Chatbot və tövsiyə sistemlərinin tətbiqi müştəri məmnuniyyəti indeksini orta 15-25 bənd artırır (Huang & Rust, 2021). Fərdiləşdirilmiş marketing kampaniyaları satışları 10-30% artırır.

Yeni gəlir axınları. Sİ əsaslı məhsul və xidmətlər yeni biznes modelləri yaradır. Platformalaşma tendensiyası müəssisələrin ekosistem iqtisadiyyatına integrasiyasını sürətləndirir (Parker et al., 2016).

Mövcud problemlər

Texniki problemlər. Sİ modelləri böyük həcmdə keyfiyyətli məlumata ehtiyac duyur. Azərbaycanda, eləcə də bir çox inkişaf etməkdə olan ölkələrdə strukturlaşdırılmış verilənlər bazalarının çatışmazlığı ciddi maneə yaradır. Bundan əlavə, mövcud infrastrukturun (bulud hesablama, GPU klasterləri) yüksək qiyməti kiçik və orta müəssisələr üçün əlçatanlığı məhdudlaşdırır (OECD, 2023).

İnsan resursları problemi. Dünyada Sİ ixtisasçılarına olan tələb təklifi xeyli üstələyir. WEF-in (2023) hesabatına görə, 2030-cu ilə kimi global Sİ mütəxəssis çatışmazlığı 4 milyona çatacaq. Azərbaycanda bu problem xüsusən kəskin şəkildə hiss olunur: ali təhsil müəssisələrinin Sİ-yə hazırlıq proqramlarının sayı hələ məhduddur.

Etik və hüquqi problemlər. Sİ sistemlərinin qərəzli (bias ed) nəticələr verməsi, qara qutu (black box) effekti, alqoritmlərə hesabatlılığın çatışmazlığı ciddi etik narahatlıqlar doğurur. Avropa Birliyi-nin 2024-cü ildə qüvvəyə minən Sİ Aktı bu boşluğu doldurmağa cəhd etsə də, Azərbaycanda hüquqi çərçivə hələ formalaşma mərhələsindədir (Russell, 2019; Floridi et al., 2018).

Məlumat məxfiliyi. Müəssisə məlumatlarının Sİ modelləri tərəfindən emal edilməsi məlumat sızması riskini artırır. GDPR kimi tənzimləmələrin tətbiqi ilə bağlı uyğunluq xərcləri müəssisə büdcəsini əhəmiyyətli dərəcədə yükləyir (Zuboff, 2019).

Təşkilati dəyişimə müqavimət. İşçilərin iş yerinin itirilməsi qorxusu və dəyişikliyə psixoloji müqavimət Sİ tətbiqinin sürətini yavaşlatır. Seamans və Raj (2018) müəyyən etmişlər ki, daxili kommunikasiya strategiyaları bu müqaviməti azaltmaqda mühüm rol oynayır.

Nəticə Və Təvsiyələr

Bu tədqiqat müəssisələrdə süni intellektin tətbiqinin həm böyük potensial, həm də ciddi çağırışlar daşdığını ortaya qoydu. Sİ-nin müəssisə performansına müsbət təsirinin faktiki olaraq sübuta yetirilmiş olmasına baxmayaraq, bu texnologiyadan istifadənin qarşısında duran maneələr- texniki, maliyyə, insan resursları, hüquqi və etik- kompleks yanaşma tələb edir.

Tədqiqat nəticələri əsasında aşağıdakı tövsiyələr irəli sürülür:

Müəssisə rəhbərləri üçün: Sİ tətbiqini tam şirkət miqyasında deyil, pilot layihələrdən başlayaraq mərhələli şəkildə həyata keçirmək; işçilərin yenidən ixtisaslaşdırılmasına (reskilling) investisiya qoymaq; insan-maşın əməkdaşlığı modelini prioritetləşdirmək.

Siyasətçilər üçün: Sİ-yə dair milli strategiya çərçivəsinin işlənilib hazırlanması; hüquqi tənzimləmə mexanizmlərinin Avropa standartlarına uyğunlaşdırılması; KOM-lərin (kiçik və orta müəssisələr) Sİ-yə keçidini dəstəkləyən subsidiya mexanizmlərinin tətbiqi.

Tədqiqatçılar üçün: Azərbaycan müəssisə ekosistemi üçün xüsusi ampirik araşdırmalar aparmaq; Sİ-nin uzun müddətli əmək bazarı effektlərini longitudinal metodla izləmək; sektoral fərqliliklərə diqqət yetirmək.

Gələcək tədqiqatlar Sİ-nin Azərbaycan müəssisə sektoruna təsirini kəmiyyətə ölçən ampirik modellərin qurulmasına yönəlməlidir. Süni intellektin idarəetmə elminə inteqrasiyası qaçılmazdır; önəmli olan bu inteqrasiyanı məqsədyönlü, etik və insan mərkəzli şəkildə idarə etməkdir.

Ədəbiyyat Siyahısı

1. Acemoğlu, D., & Restrepo, P. (2022). Tasks, automation, and the rise in U.S. wage inequality. *Econometrica*, 90(5), 1973-2016. <https://doi.org/10.3982/ECTA19815>
2. Azərbaycan Respublikasının Prezidenti. (2021). Azərbaycan 2030: Sosial-iqtisadi inkişaf konsepsiyası. <https://president.az/az/articles/view/51513>
3. Brynjolfsson, E., & McAfee, A. (2014). *The second machine age: Work, progress, and prosperity in a time of brilliant technologies*. W. W. Norton & Company.
4. Bughin, J., Seong, J., Manyika, J., Chui, M., & Joshi, R. (2018). *Notes from the AI frontier: Modeling the impact of AI on the world economy*. McKinsey Global Institute.
5. Davenport, T. H., & Mittal, N. (2023). *All-in on AI: How smart companies win big with artificial intelligence*. Harvard Business Review Press.
6. Dünya Bankı. (2023). *World development report 2023: Migrants, refugees, and societies*. The World Bank. <https://doi.org/10.1596/978-1-4648-1941-4>
7. Floridi, L., Cows, J., Beltrametti, M., Chatila, R., Chazerand, P., Dignum, V., ... & Vayena, E. (2018). An ethical framework for a good AI society. *Minds and Machines*, 28(4), 689-707. <https://doi.org/10.1007/s11023-018-9482-5>
8. Huang, M. H., & Rust, R. T. (2021). A strategic framework for artificial intelligence in marketing. *Journal of the Academy of Marketing Science*, 49(1), 30-50. <https://doi.org/10.1007/s11747-020-00749-9>
9. McKinsey Global Institute. (2023). *The economic potential of generative AI: The next productivity frontier*. McKinsey & Company.
10. OECD. (2023). *OECD digital economy outlook 2023: Shaping the future of the digital economy*. OECD Publishing. <https://doi.org/10.1787/781185c4-en>
11. Parker, G. G., Van Alstyne, M. W., & Choudary, S. P. (2016). *Platform revolution: How networked markets are transforming the economy and how to make them work for you*. W. W. Norton & Company.
12. Russell, S. (2019). *Human compatible: Artificial intelligence and the problem of control*. Viking.
13. *ACM Transactions on Management Information Systems*, 2015, vol. 6, no. 4, Article 13
14. Seamans, R., & Raj, M. (2018). AI, labor, productivity, and the need for firm-level data. In A. Agrawal, J. Gans, & A. Goldfarb (Eds.), *The economics of artificial intelligence: An agenda* (pp. 553-565). University of Chicago Press.
15. World Economic Forum. (2023). *Future of jobs report 2023*. WEF. <https://www.weforum.org/reports/the-future-of-jobs-report-2023>
16. Yin, R. K. (2018). *Case study research and applications: Design and methods* (6th ed.). SAGE Publications.
17. Zuboff, S. (2019). *The age of surveillance capitalism: The fight for a human future at the new frontier of power*. PublicAffairs.

CREATION OF AN INTELLIGENT ROBOT FOR BANKING CONTACT CENTER TASKS, WITH COMMUNICATION IN KAZAKH AND RUSSIAN LANGUAGES

Turdalin Nurassyl Meirambekuly

Master's Student, School of Information Technology and Engineering, Kazakh-British Technical University, Kazakhstan, Almaty

Abstract

The design and deployment of an intelligent conversational robot for use in banking contact center operations are presented in this study. In order to meet the linguistic needs of Kazakhstan's banking clientele, the system can carry out natural language conversations in both Kazakh and Russian. The suggested architecture combines text-to-speech (TTS) modules, automated speech recognition (ASR), and domain-specific knowledge bases with large language model (LLM) capabilities. The robot minimizes operator load, responds to typical banking questions, and runs constantly without human interaction.

Keywords: intelligent robot, chatbot, contact center, natural language processing, Kazakh language, Russian language, banking automation, speech recognition, LLM.

1. Introduction

Contact centers handle hundreds of calls and messages every day, making the banking industry one of the most customer-intensive sectors. Conventional methods mainly rely on human operators, which results in high operating costs, uneven service quality, and lengthy customer wait times. The requirement to accommodate two state-relevant languages inside a single automated system adds to the difficulty in Kazakhstan, where financial institutions serve a multilingual population that speaks both Kazakh and Russian.

One of Kazakhstan's top financial technology firms, Kaspi.kz, handles millions of user interactions per month within its super-app ecosystem. Routine banking queries like account balance checks, card status updates, transaction histories, and loan information can be automated to greatly increase client satisfaction and free up human operators to address more complicated instances.

It is now possible to create conversational bots that comprehend and produce contextually appropriate responses in low-resource languages like Kazakh because to recent developments in large language models (LLMs) and multilingual natural language processing (NLP). The architecture, technological elements, and practical concerns for developing such a system that is suited to the needs of banking contact centers are described in this paper.

2. Related Work

In recent years, a lot of research has been done on conversational AI systems for customer support. Early systems used keyword matching and rule-based dialogue management [1]. Dialogflow and related systems have shown that deeper learning has made it possible for more reliable intent classification and entity recognition [2].

Since then, transformer-based architectures—specifically, BERT and GPT-family models—have raised the bar for natural language comprehension [3]. These capabilities were expanded to dozens of languages at once by multilingual variations like mBERT and XLM-RoBERTa [4]. Targeted

approaches are necessary because Kazakh is still underrepresented in the majority of publicly available NLP benchmarks and pretrained models.

In recent years, there has been an increase in Kazakh-specific research. KazBERT and related models show competitive performance on classification and question-answering tasks after being trained on Kazakh corpora [5]. Thanks to the efforts of local research teams and Nazarbayev University, speech recognition for Kazakh has also advanced. However, there is still a dearth of published research on the incorporation of these elements into a financial chatbot of production quality.

3. System Architecture

The input processing layer, the language understanding module, the conversation management system, the domain knowledge backend, and the response production and delivery layer are the five essential components of the suggested intelligent robot that work together in a coordinated pipeline.

Customer communications via phone (voice channel), the bank's mobile application chat, and the online interface are all accepted by the input processing layer. An automated speech recognition (ASR) engine translates audio signals into text for voice input. With automatic language detection based on phonological and lexical cues, the ASR component is set up to handle both Russian and Kazakh. Transcription is not required for text input; the raw message is sent straight to the language comprehension module.

The language understanding module performs named entity recognition (NER) and intent categorization using a refined multilingual transformer model. Account inquiries, card management, payment processing, loan inquiries, and complaint registration are among the recognized objectives. Account numbers, card numbers, dates, money amounts, and product names are among the entities that were extracted. A proprietary dataset of anonymised customer interactions gathered from Kaspi.kz's contact center logs is used to refine the model.

A state machine enhanced with a retrieval-augmented generation (RAG) component manages dialogue. While the RAG component gets pertinent passages from a curated banking knowledge library to accommodate open-domain questions about goods and regulations, the state machine enforces business logic limitations, such as needing user authentication before displaying account information.

The robot can retrieve real-time account balances, transaction details, and loan statuses thanks to the domain knowledge backend's real-time integration with core banking APIs. At the session beginning stage, multi-factor authentication ensures security, and all API requests are encrypted and recorded.

For structured data (such as "Your balance is 150,000 KZT"), the response generating layer uses template-based generation; for conversational and explanatory responses, it uses an LLM-based generator. A text-to-speech (TTS) module transforms the generated text into synthetic speech in the relevant language for voice channels.

4. Kazakh and Russian Language Support

There are particular technological difficulties in supporting Kazakh. The Kazakh language has an agglutinative morphology, which results in a large variety of possible word formations by expressing grammatical relationships through suffixes added to root words. Because of this, ASR and NLP are more difficult than analytical languages like English [6].

The NLP pipeline includes a morphological analyzer tailored to Kazakh that normalizes inflected forms to their base representations prior to intent classification in order to handle morphological complexity. To increase the robustness of the model, back-translated instances and artificially created morphological variations were included to the training dataset.

Based on a refined version of Whisper model, the ASR engine for Kazakh was created utilizing Kazakh voice corpora gathered from crowdsourced recordings and public broadcasting

sources. With further refinement on banking-domain vocabulary, the Russian ASR pipeline makes use of a more developed ecosystem of pretrained models.

Since switching in the middle of a conversation is uncommon in practice, language recognition is done at the session level rather than per utterance. The system allows users to specifically request a language change without losing the context of the chat. The system employs a fallback method that gives priority to the dominant language identified in the current message in cases of code-switching, where a user blends Kazakh and Russian in a single speech.

5. Evaluation and Results

Preliminary evaluation was conducted using a held-out test set of 2,000 customer interaction transcripts, equally split between Kazakh and Russian. Intent classification accuracy reached 91.3% for Russian and 87.6% for Kazakh, reflecting the greater availability of Russian training data. Entity recognition F1-scores were 88.4% and 83.1% respectively.

A pilot deployment was conducted in a controlled environment with 50 volunteer customers over a two-week period. Customer satisfaction scores averaged 4.1 out of 5 for the Russian channel and 3.8 out of 5 for the Kazakh channel, indicating room for improvement in Kazakh language quality. First-contact resolution rates — the proportion of queries fully resolved without escalation to a human operator — reached 74% for routine inquiries.

Response latency averaged 1.2 seconds for text channels and 2.8 seconds for voice channels, the latter including ASR and TTS processing time. These figures are within acceptable bounds for conversational systems, where user experience research suggests tolerance up to approximately 3 seconds [7].

6. Discussion

The results demonstrate that multilingual intelligent robots are feasible in the Kazakh banking context, though the performance gap between Kazakh and Russian remains a significant challenge. The primary bottleneck is data availability: Kazakh NLP resources are orders of magnitude smaller than those available for Russian or English, limiting the ceiling of model performance without significant investment in data collection and annotation.

From a practical standpoint, the banking domain provides a relatively constrained vocabulary and a predictable set of user intents, which partially compensates for the linguistic challenges. The majority of customer queries follow recognizable patterns, and template-based responses cover a large fraction of use cases.

Privacy and regulatory compliance are critical considerations in the banking sector. The system was designed to comply with Kazakhstan's Law on Personal Data and Cyber Security, with all sensitive data handled within the bank's private infrastructure and no customer information transmitted to external cloud providers.

Future work will focus on expanding the Kazakh training corpus through active learning — using the deployed system's logs to identify high-uncertainty cases for human annotation — and on improving the TTS voice quality for Kazakh to match the naturalness already achieved for Russian.

7. Conclusion

This paper presented the design and preliminary evaluation of an intelligent robot for banking contact center tasks, supporting both Kazakh and Russian languages. The system integrates multilingual ASR, transformer-based NLU, state machine dialogue management, real-time banking API access, and natural language generation into a coherent pipeline capable of resolving the majority of routine customer inquiries without human intervention.

The work contributes to the growing body of research on Kazakh-language NLP and demonstrates that production-quality multilingual chatbots are achievable for Central Asian banking institutions. The deployment experience at Kaspi.kz provides a real-world foundation for

future improvements and sets a precedent for similar implementations across the region's financial sector.

References

1. Weizenbaum, J. (1966). ELIZA — A computer program for the study of natural language communication between man and machine. *Communications of the ACM*, 9(1), 36–45.
2. Google LLC. (2023). Dialogflow: Build conversational AI applications. <https://cloud.google.com/dialogflow>
3. Vaswani, A., Shazeer, N., Parmar, N., et al. (2017). Attention is all you need. *Advances in Neural Information Processing Systems*, 30.
4. Conneau, A., Khandelwal, K., Goyal, N., et al. (2020). Unsupervised cross-lingual representation learning at scale. *Proceedings of ACL 2020*, 8440–8451.
5. Yeshpanov, R., Khassanov, Y., & Varol, H. A. (2022). KazNERD: Kazakh named entity recognition dataset. *arXiv:2111.13419*.
6. Makhambetov, O., Makazhanov, A., Yessenbayev, Z., et al. (2013). Assembling the Kazakh language corpus. *Proceedings of the 2013 Conference on Empirical Methods in Natural Language Processing*.
7. Nass, C., & Brave, S. (2005). *Wired for Speech: How Voice Activates and Advances the Human-Computer Relationship*. MIT Press.

İnformasiya sistemlərinin təhlükəsizliyinin arxitektura əsaslı qiymətləndirilməsi və integrativ metodoloji yanaşmalar

Gülzar Hidayətzadə Kamil

Magistr, Azərbaycan Dövlət İqtisad Universiteti

Xülasə

Bu tədqiqat informasiya sistemlərinin təhlükəsizliyinin qiymətləndirilməsi sahəsində mövcud metodoloji yanaşmaların müqayisəli təhlilinə həsr olunmuşdur. Məqalədə ənənəvi risk idarəetmə modelləri ilə müasir arxitektura əsaslı təhlükəsizlik qiymətləndirmə metodları arasında fərqlər sistemli şəkildə araşdırılmışdır. Xüsusilə CORAS, OCTAVE və Trike kimi metodların nəzəri əsasları, tətbiq sahələri və praktiki imkanları təhlil edilərək onların üstün və zəif tərəfləri müəyyənəşdirilmişdir. Tədqiqat göstərir ki, informasiya sistemlərinin təhlükəsizliyinin qiymətləndirilməsi yalnız kəmiyyət risk analizinə əsaslanmamalı, eyni zamanda sistem arxitekturası, komponentlərarası əlaqələr və təhlükələrin yaranma mexanizmləri nəzərə alınmalıdır. Müasir informasiya sistemlərinin çoxsəviyyəli və paylanmış xarakter daşması təhlükəsizlik qiymətləndirmə metodlarına əlavə tələblər formalaşdırır. Bu baxımdan auditoriya yönümlülük, abstraksiya səviyyələrinin dəstəklənməsi, əməkdaşlıq imkanları, modelləşdirmə texnikaları və nəticələrin validasiyası kimi meyarlar xüsusi əhəmiyyət kəsb edir. Aparılan təhlil nəticəsində müəyyən edilmişdir ki, mövcud metodların hər biri spesifik problemlərin həllinə yönəldiyindən universal yanaşma mövcud deyil. Buna görə də effektiv təhlükəsizlik qiymətləndirməsi üçün müxtəlif metodların integrasiyasına əsaslanan kompleks yanaşmanın tətbiqi məqsədəuyğun hesab olunur. Tədqiqatın nəticələri informasiya sistemlərinin təhlükəsizliyinin artırılması və idarəetmə qərarlarının daha əsaslandırılmış şəkildə qəbul edilməsi baxımından praktik əhəmiyyət daşıyır.

Açar sözlər: İnformasiya təhlükəsizliyi, Risk qiymətləndirilməsi, CORAS, OCTAVE, Trike, Sistem arxitekturası, Kibertəhlükəsizlik metodları

Giriş

İnformasiya təhlükəsizliyi sahəsində hücumların identifikasiyasına yönəlmiş təhlil metodları əsas etibarilə təhlükəli hadisələrin erkən mərhələdə aşkarlanmasını hədəfləyir. Bununla müqayisədə informasiya sistemlərinin təhlükəsizlik səviyyəsinin qiymətləndirilməsi metodları daha geniş və kompleks məqsədlərə xidmət edir. Bu yanaşmalar sistemin mövcud qorunma vəziyyətinin müəyyənəşdirilməsinə, potensial zəifliklərin aşkarlanmasına, risk yarada biləcək arxitektura elementlərinin təhlilinə və tətbiq olunan təhlükəsizlik tədbirlərinin adekvatlığının qiymətləndirilməsinə imkan yaradır. Xüsusilə böyük həcmli korporativ, paylanmış və kritik idarəetmə mühitlərində baş verən nasazlıqlar yalnız texniki xarakter daşmır. Bu kimi hallarda istehsal proseslərinin dayanması, təhlükəsizlik insidentlərinin baş verməsi, maliyyə itkiləri, biznes fəaliyyətinin fasiləsizliyinin pozulması və bəzi hallarda fiziki təhlükələrin yaranması kimi ciddi nəticələr ortaya çıxa bilər. (Ahmed, Kayis & Amornsawadwatana, 2007, s. 22–36)

Bu səbəbdən informasiya sistemlərinin təhlükəsizliyinin qiymətləndirilməsi yalnız risklərin qeydiyyatı ilə məhdudlaşmır, eyni zamanda idarəetmə qərarlarının əsaslandırılması üçün mühüm analitik alət kimi çıxış edir. Ənənəvi risk idarəetmə modelləri, bir qayda olaraq, potensial təhlükələrin başvermə ehtimalı və onların doğura biləcəyi nəticələrin dəyəri əsasında ümumi risk səviyyəsinin hesablanmasına yönəlmişdir. Bu tip yanaşmalar təşkilat daxilində müxtəlif risk

kateqoriyalarının müqayisəli təhlili üçün müəyyən dərəcədə faydalı hesab olunsada, təhlükəsizlik pozuntularının yaranma mexanizmini və onların aradan qaldırılması üçün optimal üsulların seçilməsini tam şəkildə izah etmir. İnformasiya sistemlərində müşahidə olunan təhlükəsizlik hadisələri isə çoxkomponentli, qarşılıqlı asılı və mürəkkəb xarakter daşıyan proseslərlə bağlıdır. Bu baxımdan yalnız kəmiyyət göstəricilərinə əsaslanan qiymətləndirmə metodları sistem arxitekturları və təhlükəsizlik üzrə mütəxəssislər üçün hər zaman kifayət qədər informativ olmur. Effektiv təhlil üçün sistem arxitekturasının quruluşu, komponentlərarası əlaqələr, məlumat axınlarının istiqaməti və funksional asılılıqların mahiyyəti dərinlən öyrənilməlidir. (Elzamly & Hussin, 2011, s. 250–263)

Əsas Hissə

Bu kontekstdə müasir yanaşmalar təhlükəsizlik qiymətləndirilməsini daha çox arxitektura yönümlü təhlil kimi şərh edir. Belə metodologiyada informasiya sistemi ayrı-ayrı funksional komponentlərə parçalanır, komponentlər arasındakı qarşılıqlı əlaqələr sistemli şəkildə araşdırılır və bu əsasda potensial təhlükələr, zəifliklər və onların aradan qaldırılmasına yönəlmiş tədbirlər müəyyən edilir. Bu yanaşmanın klassik risk idarəetmə modellərindən əsas fərqi ondan ibarətdir ki, diqqət risklərin nəticələrindən daha çox onların yaranma səbəblərinə yönəldilir. Məhz bu xüsusiyyət informasiya sistemlərinin təhlükəsizliyinin qiymətləndirilməsi metodlarının müasir təsnifatının əsasını təşkil edir. (Liu et al., 2011, s. 547–556)

Cədvəl 1 : İnformasiya sisteminin təhlükəsizliyini qiymətləndirməyə əsas yanaşmalar

Yanaşma	Mahiyyəti	Əsas üstünlükləri	Əsas məhdudiyyətləri
Kəmiyyət risk qiymətləndirilməsi (QRA)	Riskin ehtimal və təsirin hasilinə əsasən hesablanması	Müxtəlif risklərin vahid ölçü ilə müqayisəsinə imkan verir, müəssisə səviyyəsində qərarvermə üçün uyğundur	Riskin yaranma səbəblərini və texniki zəiflikləri kifayət qədər açmır, layihələndirmə mərhələsində praktik yönləndirmə zəifdir
İT təhlükəsizlik qiymətləndirilməsi	İnformasiya sistemində aid konkret təhlükə və zəifliklərin sənədləşdirilməsi və təhlili	İnformasiya təhlükəsizliyinə spesifikdir, təhdid və zəiflikləri daha məqsədli göstərir	Metoddan asılı olaraq abstraksiya, əməkdaşlıq və validasiya imkanları fərqli olur
Arxitekturala əsaslanan təhlükəsizlik qiymətləndirilməsi	Sistemin funksional komponentlərə bölünməsi və onların təhlükəsizlik baxımından sistemli analizi	Riskin səbəblərini, məlumat axınlarını və qarşılıqlı asılılıqları müəyyən etməyə imkan verir, layihələndirmə mərhələsi üçün əlverişlidir	Yaxşı model, sahə biliyi və vasitə dəstəyi tələb edir, mürəkkəb sistemlərdə icrası çətinləşə bilər

Mənbə:

https://www.researchgate.net/publication/200144485_Information_Security_Assessments_for_Embedded_Systems_Development_An_Evaluation_of_methods - əsasında müəllif tərəfindən hazırlanmışdır.

Cədvəldə təqdim olunan məlumatlar göstərir ki, kəmiyyət əsaslı risk qiymətləndirmə yanaşmaları əsasən müəssisə səviyyəsində risk portfelinin idarə olunması üçün daha uyğun hesab olunur. Bununla belə, bu yanaşmalar informasiya sisteminin daxili funksional məntiqinin və təhlükəsizlik boşluqlarının yaranma səbəblərinin müəyyənəşdirilməsi baxımından məhdud

imkanlara malikdir. (Deloitte, 2016) İnformasiya təhlükəsizliyinin qiymətləndirilməsinə yönəlmiş metodlar isə sistemi daha detallı və strukturlaşdırılmış şəkildə analiz etməyə şərait yaradır. Lakin bu metodların effektivliyi bir sıra amillərdən asılıdır. Buraya metodun hansı istifadəçi auditoriyası üçün nəzərdə tutulması, neçə abstraksiya səviyyəsini əhatə etməsi, müxtəlif iştirakçılar arasında əməkdaşlıq imkanlarını təmin etməsi, tətbiq olunan modellər və texniki yanaşmalar, eləcə də əldə olunan nəticələrin nə dərəcədə yoxlanıla bilməsi kimi meyarlar daxildir. Müasir informasiya sistemləri, xüsusilə kritik və paylanmış struktura malik olan sistemlər, ənənəvi informasiya texnologiyaları mühitlərindən bir sıra xüsusiyyətlərinə görə fərqlənir. İlk növbədə, bu tip sistemlər çoxsəviyyəli abstraksiya quruluşuna malikdir. Buraya fiziki cihazların yerləşməsi, cihaz daxilində məlumat axınları, cihazlararası kommunikasiya, təşkilatın daxili şəbəkə infrastrukturunu ilə integrasiya, istifadəçi müdaxiləsi və digər əlaqəli səviyyələr daxildir. Bu komponentlərin hər biri təhlükəsizlik baxımından paralel şəkildə nəzərə alınmalıdır. (Miler & Górski, 2004, s. 1–7)

İkinci mühüm xüsusiyyət ondan ibarətdir ki, belə sistemlərin layihələndirilməsi prosesində yalnız informasiya texnologiyaları üzrə mütəxəssislər deyil, eyni zamanda elektrik mühəndisləri, texnoloji proses mütəxəssisləri, istehsalat sahəsində çalışan ekspertlər və digər ixtisas sahibləri də iştirak edir. Bu iştirakçıların hamısının kibertəhlükəsizlik sahəsində eyni səviyyədə bilik və hazırlığa malik olmaması təhlükəsizlik qiymətləndirilməsi prosesini daha da mürəkkəbləşdirir. Üçüncü olaraq, bu tip sistemlərə dair hazırlanmış hesabatlar yalnız texniki personal üçün deyil, həm də idarəetmə səviyyəsində qərarvericilər, eləcə də bəzi hallarda tənzimləyici qurumlar və təhlükəsizlik strukturları üçün nəzərdə tutulur. Bu isə təqdim olunan nəticələrin həm texniki, həm də strateji baxımdan anlaşıqlı və əsaslandırılmış olmasını tələb edir. (İslam, 2009, s. 5–8)

Cədvəl 2 : İnformasiya sisteminin təhlükəsizliyini qiymətləndirmə metodlarına qoyulan əsas tələblər

Meyar qrupu	Əsas tələb	Təhlükəsizlik qiymətləndirilməsi üçün əhəmiyyəti
Auditoriya	Metod əsasən memarlar və hazırlayıcılar üçün işlək olmalı, digər tərəflər isə ekspert və rəyçi kimi qoşulmalıdır	Təhlükəsizliyin layihələndirmə mərhələsindən integrasiyasını təmin edir
Abstraksiya səviyyəsi	Sistem müxtəlif səviyyələrdə modelləşdirilə və detallı təhlilə imkan verməlidir	Təhlükənin kök səbəblərinin və konkret zəif nöqtələrin müəyyən olunmasına şərait yaradır
Əməkdaşlıq dəstəyi	Rollar, məsuliyyətlər, asinxron əməkdaşlıq və biliklərin paylaşılması mexanizmi olmalıdır	Çoxsahəli və paylanmış komandalar üçün praktik tətbiqi asanlaşdırır
Qiymətləndirmə obyektı	Təhlükəsizlik tədbirləri təsir və ehtimalın dəqiq hesablanması olmadan da müəyyən edilə bilməlidir	Layihələndirmə mərhələsində qərarverməni mümkün edir
Modellər və texnikalar	Məlumat strukturu, notasiya, cari və tələb olunan təhlükəsizlik səviyyəsi arasında fərq aydın olmalıdır	Təhlilin təkrarlana bilən və izah oluna bilən olmasını təmin edir
Validasiya və əsaslandırma	Yoxlama, izlenebilirlik, metrikalar, vasitə dəstəyi və fərziyyələrin açıq ifadəsi təmin edilməlidir	Nəticələrin etibarlılığını və audit oluna bilməsini artırır

Mənbə: https://www.researchgate.net/publication/200144485_Information_Security_Assessments_for_Embedded_Systems_Development_An_Evaluation_of_methods- əsasında müəllif tərəfindən hazırlanmışdır.

Bu meyarların hər biri ayrıca əhəmiyyət daşısa da, onların qarşılıqlı əlaqədə nəzərdən Bu meyarların hər biri ayrıca əhəmiyyət kəsb etsə də, onların qarşılıqlı şəkildə qiymətləndirilməsi daha mühüm hesab olunur. Auditoriya meyarı göstərir ki, təhlükəsizliyin qiymətləndirilməsi yalnız dar çərçivədə təhlükəsizlik analitiklərinin fəaliyyəti kimi məhdudlaşdırılmamalıdır. Tətbiq olunan metodologiya elə qurulmalıdır ki, sistemin arxitekturasını dərinlən bilən memarlar və proqram təminatı hazırlayıcıları onu praktik müstəvidə istifadə edə bilsinlər. Təhlükəsizlik mütəxəssisləri isə bu prosesdə əsasən metodoloji dəstək verən, istiqamətləndirici və rəy bildirən rolunda çıxış etməlidirlər. Əks halda qiymətləndirmə prosesi məhdud mütəxəssis dairəsində qalır və sistemin real struktur xüsusiyyətlərinin nəzərdən qaçırılması riski artır.

Abstraksiya səviyyəsi meyarı da təhlükəsizliyin qiymətləndirilməsində mühüm rol oynayır. Əgər təhlil yalnız təşkilati və ya konseptual səviyyədə aparılırsa, risklərin texniki səbəblərinin izahı çətinləşir. Digər tərəfdən, həddindən artıq aşağı texniki səviyyədə aparılan analiz ümumi sistem mənzərəsinin itirilməsinə səbəb ola bilər. Bu səbəbdən optimal metod həm yüksək səviyyəli sistem baxışını təmin etməli, həm də zəruri hallarda funksional komponentlər, proseslər və implementasiya səviyyəsinə qədər dərinləşmə imkanı yaratmalıdır. Bu xüsusiyyət xüsusilə mürəkkəb və paylanmış informasiya sistemləri üçün xüsusi əhəmiyyət daşıyır.

Əməkdaşlıq imkanlarının təmin edilməsi müasir informasiya mühitində daha da aktuallaşmışdır. Ənənəvi yanaşmalarda təhlükəsizlik təhlili əsasən məhdud sayda seminar və ya işçi görüşləri çərçivəsində həyata keçirilirdi. Lakin global və paylanmış inkişaf mühitində bütün maraqlı tərəflərin eyni vaxtda bir araya gətirilməsi həm təşkilati baxımdan çətin, həm də iqtisadi cəhətdən səmərəsizdir. Bu baxımdan təhlükəsizlik qiymətləndirmə metodları asinxron əməkdaşlığı dəstəkləməli, yəni iştirakçıların müxtəlif vaxtlarda və müxtəlif məkanlardan eyni model üzərində işləməsinə imkan yaratmalıdır. Bununla yanaşı, biliklərin saxlanması və təkrar istifadəsini təmin edən mərkəzləşdirilmiş repositoriya, aydın rol bölgüsü və məsuliyyət mexanizmlərinin mövcudluğu da vacibdir. (Dash & Dash, 2010, s. 629–636)

Qiymətləndirmə obyektinə yanaşma göstərir ki, təhlükəsizlik tədbirlərinin müəyyənləşdirilməsi üçün hər zaman hadisələrin dəqiq başvermə ehtimalını və maliyyə təsirinə hesablamaq mümkün olmur. Xüsusilə inkişaf mərhələsində olan və ya müxtəlif ssenarilərdə istifadə oluna biləcək sistemlər üçün belə proqnozlar yüksək qeyri-müəyyənlik daşıyır. Buna görə müasir yanaşmalarda diqqət daha çox “nə baş verə bilər?” sualından çox, “riskin yaranma səbəbi nədir və hansı arxitektura elementi bunu şərtləndirir?” sualına yönəldilir. Bu yanaşma təhlükəsizliyin ilkin mərhələdən sistemə inteqrasiya olunmasını nəzərdə tutan “security by design” prinsipinə uyğun gəlir. Modellər və texniki vasitələr təhlükəsizliyin qiymətləndirilməsi prosesinin metodoloji əsasını təşkil edir. Əgər nəticələrin sənədləşdirilməsi qaydaları, istifadə olunan obyektlərin strukturu, mövcud və tələb olunan təhlükəsizlik səviyyələrinin fərqləndirilməsi əvvəlcədən müəyyən edilməzsə, aparılan təhlil qeyri-sabit və təkrarlana bilməyən xarakter ala bilər. Formal notasiya və strukturlaşdırılmış modellərin tətbiqi isə nəticələrin həm avtomatlaşdırılmış şəkildə yoxlanılmasına, həm də sonradan müqayisə və yenidən təhlil olunmasına imkan yaradır. (Alberts et al., 1999)

Validasiya və əsaslandırma meyarı təhlükəsizlik qiymətləndirilməsinin etibarlılığını müəyyən edən əsas amillərdəndir. Təhlükəsizlik sahəsində bütün risklərin tam şəkildə aşkar edildiyini sübut etmək praktiki olaraq mümkün olmasa da, əldə olunan nəticələrin əsaslandırılma və izlənilə bilmə səviyyəsini artırmaq mümkündür. Bunun üçün istifadə olunan fərziyyələrin, məlumat mənbələrinin, qəbul edilmiş qərarların və edilən dəyişikliklərin açıq şəkildə sənədləşdirilməsi vacibdir. Bu prosesdə proqram vasitələrinin rolu da böyükdür. Effektiv alətlər modelin qurulması, yoxlanılması, dəyişiklik tarixçəsinin izlənməsi, ziddiyyətlərin aşkar edilməsi və bilik mübadiləsinin təşkili kimi prosesləri əhəmiyyətli dərəcədə asanlaşdırır. (Marsh & Microsoft, 2019)

Cədvəl 3 : Geniş yayılmış təhlükəsizlik qiymətləndirmə metodlarının müqayisəli xarakteristikası

Metod	Əsas fokus	Güclü tərəfləri	Məhdudiyyətləri
CORAS	Model əsaslı risk və təhlükəsizlik qiymətləndirilməsi	Müxtəlif abstraksiya səviyyələrini dəstəkləyir, model və təcrübə paketlərindən istifadə edir, vasitə dəstəyi mövcuddur	Workshop əsaslı əməkdaşlıq üstünlük təşkil edir, riskin kəmiyyətə endirilməsi yanaşması güclüdür
OCTAVE	Təşkilati səviyyədə aktiv, təhdid və zəifliklərin qiymətləndirilməsi	Əməkdaşlıq və strateji baxış güclüdür, ehtimalın kəmiyyət qiymətləndirilməsindən qaçır	Təşkilati səviyyədə qalır, texniki səbəblərin dərin təhlili məhduddur, proqram dəstəyi zəifdir
Trike	Təhlükə modelinin formalaşdırılması və təhlükəsizlik auditinə risk əsaslı yanaşma	Tələb olunan və faktiki təhlükəsizlik arasında fərqi aydın göstərir, formal modelləşdirmə güclüdür	Eksperimental xarakter daşıyır, əməkdaşlıq mexanizmləri kifayət qədər işlənməyib
EBIOS	İnformasiya sistemləri təhlükəsizlik risklərinin qiymətləndirilməsi və kommunikasiya edilməsi	Terminologiya və məlumat strukturu çox detallıdır, cari və tələb olunan təhlükəsizlik arasında fərqi nəzərə alır	Daha çox sabit vəziyyətdə olan sistemlər və idarəetmə səviyyəsi üçün uyğundur, davamlı inkişaf mühitinə zəif inteqrasiya olunur
Microsoft Threat Modeling	Təhdidlərin başa düşülməsi, riskin müəyyən edilməsi və zəiflətmə tədbirlərinin seçilməsi	Praktik yönümlüdür, vasitə dəstəyi var, inkişaf mühitində istifadə üçün əlverişlidir	Rollar aydın müəyyən olunmur, riskin qiymətləndirilməsi qismən subyektivdir, izlenebilirlik və cari təhlükəsizlik vəziyyətinin sənədləşdirilməsi məhduddur

Mənbə:

https://www.researchgate.net/publication/200144485_Information_Security_Assessments_for_Embedded_Systems_Development_An_Evaluation_of_methods- əsasında müəllif tərəfindən hazırlanmışdır.

Cədvəl 3-də ümumiləşdirilmiş metodların geniş təhlili göstərir ki, informasiya sistemlərinin təhlükəsizliyinin qiymətləndirilməsi sahəsində hələlik vahid və universal yanaşma tam şəkildə formalaşmamışdır. Mövcud metodların hər biri eyni problemin həllinə fərqli nəzəri prizmalardan yanaşır. Bəzi yanaşmalar təhlükəsizliyi təşkilati risklərin idarə olunması kontekstində qiymətləndirir, digərləri sistemi funksional komponentlərə bölərək təhdidlərin arxitektura səviyyəsində müəyyən edilməsinə üstünlük verir, digər qrup metodlar isə mövcud proqram təminatı və ya infrastruktur üzərində praktiki təhdid modelləşdirilməsinə əsaslanır. Bu səbəbdən həmin metodların yalnız “effektiv” və ya “zəif” kimi kateqoriyalara ayrılması düzgün yanaşma hesab olunmur. Onların real dəyəri daha çox hansı problem mühitinə yönəlməsində, prosesə hansı iştirakçı qruplarını cəlb etməsində və təhlükəsizliyi hansı abstraksiya səviyyəsində modelləşdirməsində özünü göstərir. (Cebula & Young, 2010)

CORAS metodu model əsaslı təhlükəsizlik qiymətləndirməsinin daha strukturlaşdırılmış və sistemli nümunələrindən biri kimi qəbul edilir. Bu yanaşmanın əsas prinsipi ondan ibarətdir ki,

risklərin yalnız siyahı şəklində təqdim edilməsi kifayət etmir; risklər sistemin strukturu, iştirakçı aktorlar, qorunan resurslar, mövcud zəifliklər və hadisələr arasındakı səbəb-nəticə əlaqələri ilə birlikdə kompleks şəkildə təsvir olunmalıdır. CORAS bu məqsədə grafik modellər, risk diaqramları və strukturlaşdırılmış məlumat təsvirləri vasitəsilə nail olur. Metod adətən sistemin kontekstinin müəyyənləşdirilməsi ilə başlanır, daha sonra qiymətləndirilən aktivlər, potensial təhlükə mənbələri, zəifliklər və arzuolunmaz hadisələr identifikasiya olunur. Növbəti mərhələdə bu elementlər arasındakı əlaqələr diaqramlaşdırılır və riskin formalaşma mexanizmi izah edilir. Beləliklə, CORAS yalnız riskin nəticələrini deyil, onun sistem daxilində yaranma prosesini açmağa yönəlir. (Trofymenko, 2019, s. 642–646)

Bu metodun mühüm üstünlüklərindən biri onun müxtəlif abstraksiya səviyyələrində tətbiq oluna bilməsidir. Yəni eyni informasiya sistemi həm yüksək idarəetmə baxımından, həm də texniki səviyyədə modelləşdirilə bilər. Bu xüsusiyyət xüsusilə korporativ və paylanmış sistemlər üçün əhəmiyyətlidir, çünki bu tip mühitlərdə təhlükəsizlik problemləri eyni zamanda idarəetmə, şəbəkə və tətbiq qatlarında meydana çıxır. CORAS metodunun digər üstün cəhəti əvvəlki qiymətləndirmə nəticələrinin və təcrübə paketlərinin saxlanılması imkanının olmasıdır ki, bu da institusional bilik bazasının formalaşmasına və növbəti analizlərdə mövcud biliklərdən istifadə edilməsinə şərait yaradır. Bununla yanaşı, metodun müəyyən məhdudiyyətləri də mövcuddur. Praktik tətbiq çox vaxt seminar və workshop formatına əsaslandığından coğrafi baxımdan paylanmış geniş komandalar üçün bu yanaşma müəyyən çətinliklər yarada bilər. Eyni zamanda, CORAS-ın ümumi risk idarəetmə yanaşmasına yaxın olması bəzi hallarda layihələndirmə mərhələsində arxitektura qərarların operativ qəbuluna kifayət qədər çevik dəstək vermir. (Trofymenko et al., 2019, s. 150–157)

OCTAVE metodu isə fərqli yanaşma prinsiplərinə əsaslanır. Bu metod təhlükəsizlik problemini ilk növbədə təşkilatın kritik informasiya aktivlərinin qorunması və təhlükəsizlik idarəetmə praktikasının formalaşdırılması kontekstində qiymətləndirir. OCTAVE əsasən özünüqiymətləndirmə (self-assessment) metodologiyası kimi xarakterizə olunur. Bu yanaşmada əsas fəaliyyət xüsusi yaradılmış “analysis team” tərəfindən həyata keçirilir və təşkilat daxilində müxtəlif işçi qrupları ilə keçirilən görüşlər, müzakirələr və strukturlaşdırılmış iş sənədləri vasitəsilə təhlükəsizlik problemləri sistemli şəkildə müəyyən edilir. Metodun tətbiqi üç əsas mərhələdən ibarətdir: ilkin olaraq informasiya aktivləri və onlar üçün kritik hesab olunan təhdidlər müəyyənləşdirilir, daha sonra mövcud infrastrukturun zəiflikləri təhlil olunur və sonda qoruma strategiyası ilə prioritet təhlükəsizlik tədbirləri formalaşdırılır.

OCTAVE metodunun əsas üstünlüklərindən biri ondan ibarətdir ki, o, təhlükəsizlik məsələsini yalnız texniki problem kimi deyil, eyni zamanda təşkilati idarəetmə kontekstində qiymətləndirir. Bu xüsusiyyət metodun rəhbərlik səviyyəsində qərarvermə prosesində istifadəsini mümkün edir və təhlükəsizlik mədəniyyəti, institusional proseslər, daxili qaydalar və praktik davranışlarla bağlı problemlərin aşkar edilməsində onun effektivliyini artırır. Bundan əlavə, OCTAVE yanaşması risklərin qiymətləndirilməsində ehtimal hesablamalarına həddindən artıq bağlı qalmır və təsirlərin keyfiyyət əsaslı təhlilinə imkan verir. Lakin metodun əsas məhdudiyyətlərindən biri onun texniki dərinliyinin nisbətən zəif olmasıdır. OCTAVE sistem arxitekturası daxilində konkret komponentlər, məlumat axınları və ya texniki zəifliklər səviyyəsində risklərin necə formalaşdığını eyni detallılıqla təqdim etmir. Bu səbəbdən metod təşkilati və idarəetmə səviyyəsində təhlükəsizlik məsələlərinin təhlili üçün uyğun olsa da, mürəkkəb korporativ informasiya sistemlərinin layihələndirilməsi mərhələsində komponent səviyyəsində qərarların qəbul edilməsi üçün yetərli hesab olunmur. (Yashchuk, 2024)

Trike metodu isə digər yanaşmalarla müqayisədə daha formal və strukturlaşdırılmış modelləşdirmə prinsiplərinə əsaslanır. Bu metodun əsas fərqləndirici xüsusiyyəti tələb olunan təhlükəsizlik vəziyyəti ilə faktiki sistem implementasiyası arasında aydın sərhəd qoyulmasıdır. Trike yanaşmasının mərkəzində hüquqlar, rollar, aktorlar, məlumatlar və proseslər arasındakı qarşılıqlı münasibətlər dayanır. İlkin mərhələdə müəyyən edilir ki, hansı subyekt hansı aktiv üzərində hansı

əməliyyatları hansı şərtlər daxilində icra edə bilər. Daha sonra bu normativ model sistemin faktiki quruluşu ilə müqayisə edilir və uyğunsuzluqlar müəyyən olunur. Təhlükələr məhz bu iki səviyyə arasında fərqlərin yarandığı nöqtələrdə üzə çıxarılır. Bu baxımdan Trike metodu yalnız riskləri təsvir etməklə kifayətlənmir, eyni zamanda təhlükəsizliyin hansı mərhələdə və hansı səbəbdən pozulduğunu da aşkar etməyə imkan verir.

Trike metodunun əsas üstünlüklərindən biri onun formal izlənilənlik (traceability) imkanlarının yüksək olmasıdır. Metod təhlükəsizlik tələbləri, sistem implementasiyası və təhdid modelləri arasında əlaqələri sistemli şəkildə qurur ki, bu da nəticələrin yoxlanılması və əsaslandırılması prosesini asanlaşdırır. Xüsusilə kritik sistemlərdə hər bir müdafiə tədbirinin hansı təhlükəsizlik tələbini qarşıladığını və hansı zəifliyi kompensasiya etdiyini göstərmək böyük əhəmiyyət kəsb edir. Trike bu baxımdan effektiv alət kimi çıxış edir. Bununla belə, metodun tətbiqi ilə bağlı müəyyən çətinliklər də mövcuddur. O, geniş praktik istifadədə tam yetkin metod kimi qəbul olunmur və daha çox eksperimental xarakter daşıyır. Bundan əlavə, əməkdaşlığın təşkili, biliklərin paylaşılması və müxtəlif maraqlı tərəflərin prosesə inteqrasiyası kimi məsələlər Trike metodologiyasında kifayət qədər inkişaf etdirilməmişdir. Bu səbəbdən metod formal baxımdan güclü olsa da, iri və çoxşaxəli təşkilatlarda onun əməli tətbiqi müəyyən çətinliklərlə müşayiət oluna bilər. (Cabinet of Ministers of Ukraine, 2023)

Nəticə

Aparılan tədqiqat informasiya sistemlərinin təhlükəsizliyinin qiymətləndirilməsi sahəsində mövcud metodoloji yanaşmaların çoxşaxəli və heterogen xarakter daşdığını göstərir. Müqayisəli təhlil nəticəsində müəyyən edilmişdir ki, ənənəvi kəmiyyət əsaslı risk idarəetmə modelləri müəssisə səviyyəsində ümumi risklərin qiymətləndirilməsi üçün faydalı olsa da, sistemin daxili strukturu və təhlükəsizlik boşluqlarının yaranma mexanizmlərinin aşkar edilməsi baxımından məhdud imkanlara malikdir. Bunun əksinə olaraq, müasir təhlükəsizlik qiymətləndirmə metodları – xüsusilə CORAS, OCTAVE və Trike – risklərin yalnız nəticələrini deyil, həm də onların yaranma səbəblərini və sistem daxilində formalaşma yollarını daha ətraflı şəkildə təhlil etməyə imkan verir.

Tədqiqat göstərir ki, informasiya sistemlərinin mürəkkəb və çoxsəviyyəli strukturu təhlükəsizlik qiymətləndirmə metodlarının seçiminə birbaşa təsir edir. Bu baxımdan auditoriya yönümlülük, abstraksiya səviyyələrinin çevik dəstəklənməsi, əməkdaşlıq imkanlarının təmin edilməsi, modelləşdirmə texnikalarının adekvatlığı və nəticələrin əsaslandırılması kimi meyarlar mühüm əhəmiyyət kəsb edir. Analiz edilmiş metodların hər biri bu meyarların yalnız müəyyən hissəsini tam şəkildə təmin etdiyindən, vahid və universal yanaşmanın mövcud olmadığı qənaətinə gəlmək mümkündür.

CORAS metodunun strukturlaşdırılmış model yanaşması və səbəb-nəticə əlaqələrinin vizuallaşdırılması imkanları, OCTAVE metodunun təşkilati təhlükəsizlik və idarəetmə səviyyəsində qərarverməyə yönəlməsi, Trike metodunun isə formal modelləşdirmə və izlənilənlik baxımından üstünlükləri onların fərqli tətbiq sahələrində effektivliyini təmin edir. Bununla yanaşı, hər bir metodun müəyyən məhdudiyyətlərinin mövcud olması onların ayrıca tətbiqinin bəzi hallarda yetərli olmadığını göstərir.

Bu baxımdan tədqiqatın əsas nəticəsi ondan ibarətdir ki, informasiya sistemlərinin təhlükəsizliyinin effektiv qiymətləndirilməsi üçün müxtəlif metodların inteqrasiyasına əsaslanan kompleks və adaptiv yanaşmanın tətbiqi daha məqsədəuyğundur. Belə yanaşma həm texniki, həm təşkilati, həm də arxitektura səviyyəsində risklərin daha dolğun və əsaslandırılmış şəkildə təhlilinə imkan yaradır. Gələcək tədqiqatlar üçün tövsiyə olunur ki, təhlükəsizlik qiymətləndirmə metodlarının inteqrasiyası, avtomatlaşdırılmış modelləşdirmə vasitələrinin tətbiqi və süni intellekt əsaslı risk analizi yanaşmaları daha dərinlən araşdırılsın. Bu istiqamətdə aparılacaq elmi araşdırmalar informasiya sistemlərinin təhlükəsizliyinin artırılması və müasir kibertəhlükəsizlik çağırışlarına uyğunlaşma baxımından mühüm əhəmiyyət kəsb edə bilər.

Ədəbiyyat Siyahısı

1. Ahmed, A., Kayis, B., & Amornsawadwatana, S. (2007). A review of techniques for risk management in projects. *Benchmarking: An International Journal*, 14(1), 22–36.
2. Elzamly, A., & Hussin, B. (2011). Managing software project risks with proposed regression model techniques and effect size technique. *International Review of Computers and Software*, 6(2), 250–263.
3. Elzamly, A., Hussin, B., & Salleh, N. (2015). Methodologies and techniques in software risk management approach for mitigating risks: A review. *Asian Journal of Mathematics and Computer Research*, 2(3), 184–198.
4. Liu, J. Y.-C., Chen, H.-G., Chen, C. C., & Sheu, T. S. (2011). Relationships among interpersonal conflict, requirements uncertainty, and software project performance. *International Journal of Project Management*, 29(5), 547–556.
5. Deloitte. (2016). Cyber risk reporting in the UK: Governance in focus. <https://www2.deloitte.com/content/dam/Deloitte/uk/Documents/audit/deloitte-uk-governance-in-focus-cyber-riskreporting.pdf>
6. Elzamly, A., & Hussin, B. (2016). Quantitative and intelligent risk models in risk management for constructing software development projects: A review. *International Journal of Software Engineering and Its Applications*, 10(1), 9–20.
7. Miler, J., & Górski, J. (2004). Risk-driven software process improvement—A case study. In *Proceedings of the European Software Process Improvement Conference (EuroSPI)* (pp. 1–7).
8. Islam, S. (2009). Software development risk management model—A goal driven approach. In *Proceedings of the Doctoral Symposium for ESEC/FSE* (pp. 5–8).
9. Dash, R., & Dash, R. (2010). Risk assessment techniques for software development. *European Journal of Scientific Research*, 42(4), 629–636.
10. Alberts, C. J., Behrens, S. G., Pethia, R. D., & Wilson, W. R. (1999). Operationally critical threat, asset, and vulnerability evaluation. Software Engineering Institute.
11. Marsh & Microsoft. (2019). 2019 global cyber risk perception survey. <https://www.microsoft.com/security/blog/wp-content/uploads/2019/09/Marsh-Microsoft-2019-Global-Cyber-Risk-Perception-Survey.pdf>
12. Marsh & Microsoft. (2022). Global cyber risk survey. <https://www.marsh.com/zm/services/cyber-risk/insights/global-cyber-risk-survey.html>
13. Cebula, J. J., & Young, L. R. (2010). A taxonomy of operational cyber security risks. Carnegie Mellon University.
14. Trofymenko, O. (2019). Monitoring the state of cyber security in Ukraine. In *Legal life of modern Ukraine: Materials of the international scientific and practical conference* (Vol. 1, pp. 642–646).
15. Trofymenko, O., et al. (2019). Cybersecurity of Ukraine: Analysis of the current state. *Ukrainian Information Security Research Journal*, 21(3), 150–157.
16. Yashchuk, V. I. (2024). The role and place of the cyber security strategy of Ukraine in ensuring the information security of the state.
17. Cabinet of Ministers of Ukraine. (2023). *Some issues of response by cyber security entities to various types of events in cyberspace* (Resolution No. 299, April 4, 2023).

COSO modeli əsasında daxili nəzarət sisteminin struktur komponentlərinin elmi əsaslandırılması

Salmanzadə Adışirin Məhəmməd oğlu

Magistr, Azərbaycan Dövlət İqtisad Universiteti

Xülasə

Məqalədə müasir idarəetmə sistemlərində daxili nəzarətin rolu və əhəmiyyəti elmi baxımdan təhlil olunur. Tədqiqat COSO modeli əsasında daxili nəzarət sisteminin struktur komponentlərinin mahiyyətinin açıqlanmasına həsr edilmişdir. Nəzarət mühiti, risklərin qiymətləndirilməsi, nəzarət fəaliyyətləri, informasiya və kommunikasiya, həmçinin monitoring komponentləri sistemli yanaşma əsasında araşdırılmışdır. Beynəlxalq təcrübə ilə Azərbaycan müəssisələrinin mövcud vəziyyəti arasında müqayisəli təhlil aparılmışdır. Məqalədə daxili nəzarət sisteminin səmərəliliyinin artırılmasına yönəlmiş elmi əsaslandırılmış tövsiyələr irəli sürülmüşdür.

Açar sözlər : *Daxili nəzarət, COSO modeli, risklərin idarə edilməsi, nəzarət mühiti, daxili audit, monitoring.*

Giriş

Müasir iqtisadi mühitdə idarəetmə sistemlərinin mürəkkəbləşməsi daxili nəzarətin əhəmiyyətini daha da artırır. Müəssisələrin davamlı fəaliyyəti effektiv nəzarət mexanizmlərinin mövcudluğundan birbaşa asılıdır. Daxili nəzarət sistemi idarəetmə qərarlarının əsaslandırılmasında mühüm institusional alət kimi çıxış edir. Bu sistem resurslardan səmərəli istifadəni və maliyyə intizamının qorunmasını təmin edir. Eyni zamanda daxili və xarici risklərin vaxtında müəyyənləşdirilməsinə şərait yaradır.

Beynəlxalq təcrübədə daxili nəzarət sisteminin elmi əsaslarının formalaşdırılmasında COSO modeli xüsusi əhəmiyyət kəsb edir. COSO modeli daxili nəzarətə sistemli və konseptual yanaşmanı təmin edən universal çərçivədir. Model idarəetmə proseslərinin bütün səviyyələrində nəzarətin təşkilini nəzərdə tutur. COSO yanaşması daxili nəzarətin məqsədləri ilə struktur komponentləri arasında məntiqi əlaqə yaradır. Bu yanaşma nəzarətin səmərəliliyinin artırılmasına yönəlmişdir.

COSO modelinə əsasən daxili nəzarət sistemi beş qarşılıqlı əlaqəli struktur komponentindən ibarətdir. Nəzarət mühiti təşkilati mədəniyyətin və etik dəyərlərin formalaşmasında əsas rol oynayır. Risklərin qiymətləndirilməsi potensial təhlükələrin müəyyən edilməsinə və prioritetləşdirilməsinə imkan verir. Nəzarət fəaliyyətləri, informasiya və kommunikasiya komponentləri idarəetmə proseslərinin operativliyini təmin edir. Monitoring isə daxili nəzarət sisteminin davamlılığını və effektivliyini qiymətləndirməyə xidmət edir.

Təhlil :

COSO modeli daxili nəzarət sisteminin struktur komponentlərini sistemli və məntiqi ardıcılıqla izah edir. Modelə əsasən nəzarət mühiti daxili nəzarət sisteminin fundamental bazasını formalaşdıran əsas komponentdir. Nəzarət mühiti rəhbərliyin idarəetmə fəlsəfəsini və təşkilati etik dəyərləri əks etdirir. Bu komponent daxili nəzarət mexanizmlərinin effektivliyinə birbaşa təsir göstərən institusional amildir. Təşkilati strukturun şəffaflığı nəzarət mühitinin keyfiyyətini müəyyən edən əsas göstəricidir (Abbasov, 2018, s. 45)..

Risklərin qiymətləndirilməsi komponenti daxili və xarici risklərin sistemli müəyyənləşdirilməsinə yönəldilmişdir. COSO modelində risk anlayışı strateji məqsədlərlə birbaşa əlaqələndirilir. Risklərin düzgün identifikasiyası idarəetmə qərarlarının əsaslandırılmasını təmin

edir. Bu komponent potensial təhlükələrin vaxtında qiymətləndirilməsinə imkan yaradır. Risk yönümlü yanaşma daxili nəzarətin proaktiv xarakterini gücləndirir.

Nəzarət fəaliyyətləri komponenti idarəetmə qərarlarının icrasına nəzarət mexanizmlərini əhatə edir. Bu fəaliyyətlər prosedur və qaydalar vasitəsilə nəzarətin praktik tətbiqini təmin edir. COSO modelində nəzarət fəaliyyətləri risklərin azaldılmasına yönəlmiş əməliyyat alətləri kimi çıxış edir. Onların effektivliyi institusional intizamın səviyyəsindən asılıdır. Düzgün qurulmuş nəzarət fəaliyyətləri idarəetmədə səhvlərin qarşısını alır.

İnformasiya və kommunikasiya komponenti daxili nəzarət sistemində məlumat axınlarının düzgün təşkilini təmin edir. Operativ və etibarlı informasiya idarəetmə qərarlarının keyfiyyətini yüksəldir. COSO modeli informasiya sistemlərini nəzarət mexanizminin ayrılmaz hissəsi kimi qəbul edir. Effektiv kommunikasiya təşkilat daxilində məsuliyyət bölgüsünü aydınlaşdırır. Bu komponent nəzarət proseslərinin koordinasiyasını gücləndirir (Aliyev, 2021, s. 62)..

Monitoring komponenti daxili nəzarət sisteminin davamlı qiymətləndirilməsini təmin edən əsas mexanizmdir. COSO modelində monitoring fasiləsiz və dövri qiymətləndirmə prinsiplərinə əsaslanır. Monitoring nəticələri nəzarət sistemində mövcud boşluqların müəyyənləşdirilməsinə imkan yaradır. Bu komponent daxili nəzarətin adaptivliyini və çevikliyini təmin edir.

Cədvəl 1 : COSO modeli üzrə daxili nəzarət sisteminin struktur komponentlərinin elmi xarakteristikası

Struktur komponenti	Elmi-nəzəri məzmunu	İdarəetmə sistemində rolu
Nəzarət mühiti	Təşkilati mədəniyyətin, etik dəyərlərin və idarəetmə fəlsəfəsinin formalaşmasını təmin edir	Daxili nəzarətin institusional əsasını yaradır və məsuliyyət bölgüsünü müəyyənləşdirir
Risqlərin qiymətləndirilməsi	Strateji və əməliyyat risklərinin müəyyənləşdirilməsi və prioritetləşdirilməsi prosesidir	İdarəetmə qərarlarının risk yönümlü əsaslandırılmasını təmin edir
Nəzarət fəaliyyətləri	Qaydalar, prosedurlar və mexanizmlər vasitəsilə risklərin azaldılmasına yönəlmiş tədbirlərdir	Qərarların icrasına nəzarət edir və əməliyyat səhvlərinin qarşısını alır
İnformasiya və kommunikasiya	Daxili və xarici informasiya axınlarının düzgün və vaxtında ötürülməsini təmin edir	Qərarvermə prosesinin operativliyini və şəffaflığını artırır
Monitoring	Daxili nəzarət sisteminin fasiləsiz və dövri qiymətləndirilməsini həyata keçirir	Sistem boşluqlarını müəyyən edir və nəzarətin davamlı səmərəliliyini təmin edir

Mənbə : COSO – Internal Control–Integrated Framework əsasında müəllif tərəfindən tərtib edilmişdir.

Nəzarət mühiti COSO modelində daxili nəzarət sisteminin əsasını təşkil edən fundamental komponent kimi xarakterizə olunur. Bu komponent təşkilati mədəniyyətin, etik dəyərlərin və rəhbərliyin idarəetmə fəlsəfəsinin formalaşmasını əhatə edir. Nəzarət mühitinin keyfiyyəti daxili nəzarət sisteminin ümumi səmərəliliyinə birbaşa təsir göstərir. Güclü nəzarət mühiti digər komponentlərin effektiv işləməsi üçün institusional zəmin yaradır. Beynəlxalq təcrübədə inkişaf etmiş müəssisələrdə nəzarət mühiti korporativ idarəetmə prinsipləri ilə sıx inteqrasiya olunur. Azərbaycan müəssisələrində isə nəzarət mühiti əsasən formal xarakter daşıyır. Etik kodekslərin və davranış standartlarının tətbiqi çox zaman deklarativ səviyyədə qalır. Bu isə daxili nəzarətin real təsir gücünü zəiflədir. Azərbaycan müəssisələrində nəzarət mühitinin gücləndirilməsi üçün etik kodekslərin tətbiqi, rəhbərliyin məsuliyyət mexanizmlərinin sərtləşdirilməsi və korporativ

idarəetmə prinsiplərinin institusional səviyyədə möhkəmləndirilməsi zəruridir (Məmmədov, 2020, s. 78).

Risqlərin qiymətləndirilməsi daxili nəzarət sisteminin dinamik və analitik komponentidir. COSO modelində risk anlayışı strateji məqsədlərlə birbaşa əlaqələndirilir. Risklərin düzgün identifikasiyası idarəetmə qərarlarının keyfiyyətinə əhəmiyyətli təsir göstərir. Bu komponent daxili nəzarətin proaktiv xarakter daşmasını təmin edir.

Beynəlxalq praktikada risklərin qiymətləndirilməsi ISO 31000 və RCSA modelləri ilə integrasiya olunur. Bu yanaşma risklərin ölçülməsində sistemlilik yaradır. Azərbaycan müəssisələrində isə risklərin qiymətləndirilməsi əsasən reaktiv yanaşma ilə aparılır. Risklərin qabaqlayıcı təhlili zəif inkişaf etmişdir. Risklərin qiymətləndirilməsi prosesinə risk xəritələrinin hazırlanması, risk reyestrlərinin tətbiqi və daxili auditlə koordinasiyanın gücləndirilməsi tövsiyə olunur.

Nəzarət fəaliyyətləri daxili nəzarətin praktik icra mexanizmini formalaşdırır. COSO modelində bu komponent prosedur və qaydalar sistemi kimi təqdim olunur. Nəzarət fəaliyyətləri risklərin azaldılmasına yönəlmiş konkret əməliyyat tədbirlərini əhatə edir. Bu komponent idarəetmə qərarlarının icrasına birbaşa nəzarəti təmin edir. İnkişaf etmiş idarəetmə sistemlərində nəzarət fəaliyyətləri avtomatlaşdırılmış informasiya sistemləri vasitəsilə həyata keçirilir. Azərbaycan müəssisələrində isə nəzarət fəaliyyətləri əsasən manuel və sənəd yönümlü xarakter daşıyır. Bu vəziyyət insan səhvlərinin yaranma ehtimalını artırır. Nəzarət fəaliyyətlərinin effektivliyini artırmaq üçün rəqəmsal nəzarət alətlərinin tətbiqi və daxili prosedurların standartlaşdırılması məqsədəuyğundur (Şeremet & Suyts, 2017, s. 101).

İnformasiya və kommunikasiya komponenti daxili nəzarət sistemində əlaqələndirici funksiyaları yerinə yetirir. COSO modelində etibarlı və vaxtında informasiya idarəetmənin əsas şərti kimi qəbul edilir. Effektiv kommunikasiya daxili nəzarət mexanizmlərinin koordinasiyasını gücləndirir. Beynəlxalq təcrübədə informasiya sistemləri integrasiya olunmuş idarəetmə platformaları üzərində qurulur. Azərbaycan müəssisələrində isə informasiya axınları fragmentar və qeyri-sistemli xarakter daşıyır. Bu isə qərarvermə prosesinin operativliyini zəiflədir. İnformasiya və kommunikasiya sistemlərinin integrasiyası, daxili hesabatlılığın rəqəmsallaşdırılması və məlumatların şəffaflığının artırılması tövsiyə edilir (Sawyer et al., 2003, s. 134).

Monitoring daxili nəzarət sisteminin davamlılığını təmin edən yekun komponentdir. COSO modelində monitoring fasiləsiz və dövrü qiymətləndirmə mexanizmlərinə əsaslanır. Monitoring nəticələri nəzarət sistemindəki boşluqları vaxtında aşkar etməyə imkan verir. Beynəlxalq praktikada monitoring funksiyası əsasən daxili audit vasitəsilə həyata keçirilir. Azərbaycan müəssisələrində isə monitoring mexanizmləri institusional baxımdan zəif inkişaf etmişdir. Daxili auditin müstəqillik səviyyəsi kifayət qədər təmin edilmir. Monitoring mexanizmlərinin gücləndirilməsi üçün daxili audit funksiyasının müstəqilliyinin artırılması və performans indikatorlarının tətbiqi vacibdir.

Aparılan təhlil göstərir ki, COSO modeli daxili nəzarət sisteminin elmi əsaslandırılması üçün universal və çevik çərçivə təqdim edir. Azərbaycan müəssisələrində bu modelin tətbiqi institusional və metodoloji təkmilləşdirmələr tələb edir. COSO komponentlərinin integrasiya olunmuş şəkildə tətbiqi idarəetmə səmərəliliyinin artırılmasına mühüm töhfə verə bilər. Təklif edilən tövsiyələr daxili nəzarət sisteminin milli şəraitdə adaptasiyasına elmi əsas yaradır.

Nəticə :

Daxili nəzarət sistemi müasir idarəetmə mexanizmlərinin əsas institusional elementlərindən biridir. COSO modeli daxili nəzarətin struktur komponentlərini sistemli və qarşılıqlı əlaqəli şəkildə izah edən universal konseptual çərçivə təqdim edir. Bu model daxili nəzarətin yalnız nəzarət funksiyası ilə məhdudlaşmadığını, eyni zamanda strateji idarəetmənin mühüm aləti olduğunu sübut edir. Nəzarət mühiti daxili nəzarət sisteminin effektivliyini müəyyən edən əsas amildir. Etik dəyərlərin, təşkilati mədəniyyətin və rəhbərliyin məsuliyyətli yanaşmasının

zəif olması digər komponentlərin fəaliyyətini məhdudlaşdırır. Risklərin qiymətləndirilməsi komponenti idarəetmədə proaktiv yanaşmanın formalaşmasına xidmət edir və qərarvermə prosesinin əsaslandırılmasını təmin edir. Nəzarət fəaliyyətləri isə risklərin azaldılmasında praktik mexanizm rolunu oynayır.

Araşdırma nəticəsində müəyyən edilmişdir ki, informasiya və kommunikasiya komponenti daxili nəzarət sisteminin koordinasiyaedici funksiyasını yerinə yetirir. Etibarlı və vaxtında informasiya axınlarının mövcudluğu idarəetmə qərarlarının keyfiyyətini əhəmiyyətli dərəcədə artırır. Monitoring komponenti daxili nəzarət sisteminin davamlılığını təmin edən əsas mexanizm kimi çıxış edir və sistemdə mövcud boşluqların vaxtında aşkar edilməsinə imkan yaradır. Beynəlxalq təcrübədə COSO modelinin tətbiqi institusional yanaşma və risk yönümlü idarəetmə prinsipləri əsasında həyata keçirilir. Azərbaycan müəssisələrində isə daxili nəzarət sisteminin tətbiqi əsasən formal xarakter daşıyır və praktik səmərəlilik baxımından məhdud qalır. Bu vəziyyət daxili nəzarət sistemlərinin milli şəraitə uyğunlaşdırılmasının zəruriliyini ortaya qoyur (Institute of Internal Auditors, 2017, s. 22)..

COSO modeli əsasında daxili nəzarət sisteminin struktur komponentlərinin tətbiqi idarəetmə səmərəliliyinin artırılmasına mühüm töhfə verə bilər. Təklif olunan konseptual yanaşmalar və tövsiyələr daxili nəzarət sisteminin təkmilləşdirilməsi üçün elmi və praktiki əsas yaradır. Bu istiqamətdə aparılacaq gələcək tədqiqatlar daxili nəzarət və daxili audit sistemlərinin integrasiyasının dərinləşdirilməsinə xidmət edə bilər (COSO, 2013, s. 17).

Ədəbiyyat siyahısı :

1. Abbasov, A. M. (2018). Maliyyə nəzarəti və auditin əsasları. Bakı: İqtisad Universiteti nəşriyyatı.
2. Aliyev, N. B. (2021). Risklərin idarə edilməsi və daxili nəzarət sistemləri. Bakı: ADİU nəşriyyatı.
3. COSO. (2013). Internal control – integrated framework. Committee of Sponsoring Organizations of the Treadway Commission.
4. Həsənov, E. Ə. (2019). Daxili nəzarət sisteminin təşkili və təkmilləşdirilməsi problemləri. Bakı: Elm və Təhsil.
5. Institute of Internal Auditors. (2017). International professional practices framework (IPPF). IIA.
6. ISO. (2018). ISO 31000: Risk management – Guidelines. International Organization for Standardization.
7. Məmmədov, R. T. (2020). Korporativ idarəetmədə daxili audit və nəzarət mexanizmləri. Bakı: Azərbaycan nəşriyyatı.
8. Pickett, K. H. S. (2010). The internal auditing handbook (3rd ed.). John Wiley & Sons.
9. Sawyer, L. B., Dittenhofer, M. A., & Scheiner, J. H. (2003). Sawyer's internal auditing (5th ed.). The Institute of Internal Auditors.
10. Spencer Pickett, K. H. (2011). The essential handbook of internal auditing (2nd ed.). John Wiley & Sons.
11. Ткаченко, И. А. (2016). Внутренний контроль и аудит в системе корпоративного управления. Москва: Юрайт.
12. Шерemet, А. Д., & Суйц, В. П. (2017). Аудит (6-е изд.). Москва: Инфра-М.

Scientific Justification of the Structural Components of the Internal Control System Based on the COSO Model

Abstract

The article examines the role and significance of internal control in modern management systems from a scientific perspective. The study focuses on the analysis of the structural components of the internal control system based on the COSO model. Control environment, risk assessment, control activities, information and communication, and monitoring components are analyzed using a systematic approach. A comparative analysis of international practices and the current state of Azerbaijani enterprises is conducted. The article proposes scientifically grounded recommendations aimed at improving the effectiveness of internal control systems.

Keywords : *Internal control, COSO model, risk management, control environment, internal audit, monitoring*

Научное обоснование структурных компонентов системы внутреннего контроля на основе модели COSO

Аннотация

В статье с научной точки зрения рассматривается роль и значение внутреннего контроля в современных системах управления. Исследование посвящено анализу структурных компонентов системы внутреннего контроля на основе модели COSO. В рамках системного подхода изучены контрольная среда, оценка рисков, контрольные процедуры, информационно-коммуникационные процессы и мониторинг. Проведен сравнительный анализ международного опыта и текущего состояния предприятий Азербайджана. В статье предложены научно обоснованные рекомендации по повышению эффективности систем внутреннего контроля.

Ключевые слова : *Внутренний контроль, модель COSO, управление рисками, контрольная среда, внутренний аудит, мониторинг*

Rəqəmsal Dövrə Bacarıqların Təkmilləşdirilməsi: E-Təlim və Rəqəmsal Bacarıqların İnkişafı Təşkilatın Rəqabət Qabiliyyətini Necə Gücləndirir?

Rəsulova Sevinc

Magistrant, Azərbaycan Dövlət İqtisad Universiteti

Xülasə

Rəqəmsal dövrün sürətlə dəyişən tələbləri ilə təşkilatlar üçün bacarıqların artırılması və rəqəmsal təlim proqramlarının inkişafı müəssisənin rəqabət qabiliyyətinin gücləndirilməsində mühüm rol oynayır. İnsan kapitalının inkişafı təşkilatların məhsuldarlığını artırmaqla yanaşı, işçilərin çevikliyini, innovativ düşünmə qabiliyyətlərini və yeni texnologiyalara uyğunlaşmalarını təmin edir. Bu isə onların rəqabət qabiliyyətini birbaşa təsir edir və təşkilatın bazaradakı mövqeyini gücləndirir. E-təlim platformaları və rəqəmsal bacarıqların inkişafı proqramları işçi bacarıqlarını artırmağa kömək edir, həmçinin onların performansını gücləndirərək təşkilatın ümumi fəaliyyətini yaxşılaşdırır. Rəqəmsal bacarıqların inkişafı ilə təşkilatlar öz işçi qüvvəsini daha çevik və uyğunlaşa bilən edir, bu da təşkilatların bazarda rəqabət üstünlüyü qazanmasına səbəb olur. Məqalə rəqəmsal təlim həllərinin məhsuldarlığı, innovasiyanı və təşkilatların çevikliyini artırmağa necə kömək etdiyini göstərir. E-təlim proqramları, işçi bacarıqlarının inkişafı ilə yanaşı, təşkilatın məqsədləri ilə uyğunlaşdırıldıqda işçi performansında əhəmiyyətli irəliləyişlərə səbəb olur. Nəticədə, təşkilatlar rəqabət qabiliyyətlərini artırır və daha effektiv fəaliyyət göstərirlər. Məqalə təşkilatların rəqəmsal təlim texnologiyalarından daha yaxşı istifadə etmələri üçün praktiki tövsiyələr təqdim edir və bu sahədə daha çox tətbiq imkanlarını araşdırır. Nəhayət, təşkilatların təlim metodlarının müasir texnologiyalarla uyğunlaşdırılması onların işçi qüvvəsinin inkişafını daha da sürətləndirir və təşkilatın uzunmüddətli müvəffəqiyyətini təmin edə bilər.

Açar sözlər: *Təkmilləşdirmə, e-təlim, rəqəmsal bacarıqlar, təşkilatın rəqabət qabiliyyəti.*

JEL kodları: J24, M12, M15, O33.

Upskilling in the Digital Era: How E-Learning and Digital Skills Development Strengthen Organizational Competitiveness?

*Rasulova Sevinj, Master's student
Azerbaijan State University of Economics*

Abstract

In today's rapidly changing digital environment, upskilling and the development of digital training programs play a crucial role in enhancing organizational competitiveness. Human capital development not only increases organizational productivity but also strengthens employees' adaptability, innovative thinking, and their ability to embrace new technologies. This, in turn, directly impacts their competitiveness and strengthens the organization's position in the market. E-learning platforms and digital skills development programs contribute to improving employee competencies, enhancing their performance, and optimizing the overall performance of organizations. Developing digital skills makes the workforce more agile and adaptable, allowing organizations to gain a competitive edge in the market. This paper explores how digital training

solutions help increase productivity, innovation, and organizational agility. E-learning programs, when aligned with organizational goals, lead to significant improvements in employee performance. As a result, organizations enhance their competitiveness and operate more effectively. The paper provides practical recommendations for organizations to make better use of digital training technologies and explores further implementation opportunities. Furthermore, aligning training methods with modern technologies can accelerate the development of the workforce and ensure the long-term success of the organization.

Keywords: *Upskilling, e-learning, digital skills, organizational competitiveness, digital transformation.*

JEL codes: *J24, M12, M15, O33.*

Giriş

Müasir dövrdə rəqəmsal texnologiyaların inkişafı istehsal və xidmət proseslərinə təsir etməklə yanaşı, işçi qüvvəsindən ehtiyac duyulan bacarıqlarda da köklü dəyişikliyə səbəb oldu. Müxtəlif xidmət və məqsədlər üçün qurulan proqram təminatları, bilik əsaslı qərarvermə sistemləri, həmçinin rəqəmsal platformaların sürətlə geniş kütlələrə yayılması nəticəsində müəssisələr daha çevik, innovativ və rəqəmsal bacarıqlara sahib olan kadrlara ehtiyac duyulur. Belə bir dövrdə insan kapitalının inkişafı və müasir tələblərə adaptasiyası təşkilatın davamlı və səmərəli fəaliyyətinin və öz sahəsində rəqabət üstünlüyünün əsas amillərindən biri kimi çıxış edir.

Rəqəmsal bacarıqların artırılması və inkişafı, müəssisənin mövcud işçi bazasını dövrün dəyişən tələblərinə uyğunlaşdırmaq üçün ən çox istifadə olunan yanaşmalardan biridir. Məhz elektron-təlim platformaları ixtisaslaşma biliklərinin daha geniş istifadəçilərə qısa vaxt ərzində, nisbətən aşağı xərcə çatdırılmasına şərait yaradır. Bununla belə, e-təlim proqramlarının və digər rəqəmsal inkişaf təşəbbüslərinin hər zaman eyni səviyyədə müsbət nəticə vermədiyi müşahidə edilir. Prosesin effektivliyi təşkilat və istifadəçi tərəfdən müxtəlif maneələr səbəbilə məhdudlaşa bilər. Bəzi nümunələrdə təşkilat tərəfindən təlim istiqamətləri strateji məqsədlərlə uyğunlaşmır, yaxud nəticələr düzgün qiymətləndirilmir.

Digər hallarda kadrların motivasiyası, təqdim olunan materialların keyfiyyəti və texniki çatışmamazlıq müqavimət amilləri kimi göstərilə bilər.

Bacarıq tələblərinin dəyişdirilməsinə əlavə olaraq, müəssisələr sadəcə tək bir işçi üzərindən deyil, ümumi orqanizasiya olaraq sisteməlik şəkildə baş verən dəyişiklik və inkişafə hansı sürətlə adaptasiya ola bilmələrinə görə mühakimə olunurlar. Bu o deməkdir ki, rəqabətliklə həmin müəssisənin "öyrənmə qabiliyyəti" ilə mütənasibdir: kadrların bilik və bacarıqlarında yaranan boşluqların zamanında müəyyən edilməsi, məlumat bazasının dövrü olaraq yenilənməsi, öyrənilmiş biliklərin tətbiq edilərək fəaliyyətin optimallaşdırılması. Elektron təlim platformaları bu məqsədlərin reallaşdırılması üçün böyük ölçüdə kömək göstərir, lakin belə bir sual da yaranır: Müəssisələr necə edə bilər ki, öyrənmə prosesi kursun başa çatması ilə məhdudlaşmasın, əksinə, real iş nəticələrini yaxşılaşdıraraq praktik qabiliyyətə çevrilsin.

Bir digər problem isə, öyrənmə təşəbbüslərinin sayca çox olmasına baxmayaraq, təşkilatın onları lazımi qaydada idarə edə bilməməsidir. Rəhbərlər kadrlarını elektron təlim platformalarına yönləndirdikdə əlçatanlıq və məzmun kitabxanasına əhəmiyyət verir, lakin bir çox hallarda öyrənmə şəraitinin keyfiyyəti, məşğulluq, iş saatları ərzində vaxtın səmərəli bölüşdürülməsi, təlimdən əlavə nəticələrin ölçülməsi kimi bəzi vacib nüanslar nəzərdən yayına bilər. Müəyyən situasiyalarda təlimlər individual uyğunluq təşkil etmir, yəni standart məzmununda keçirilir. Digərlərində isə öyrənmə performansın idarə edilməsi və prosesin inkişafından ayrı şəkildə irəliləyir. Bu kimi problemlər təlim proqramlarının etibarlılığını zəiflədə, həmçinin işçilərin motivasiyasını azalda bilər.

Son zamanlarda rəqəmsal öyrənmə və rəqəmsal bacarıqların inkişaf etdirilməsi informasiya təhlükəsizliyi, ədalətlik və inklüzivlik kimi daha geniş təşkilati məsələlərlə kəşisir. Şirkətlə öz məlumat bazalarını genişləndirdikcə və rəqəmsal qiymətləndirmələr tətbiq etdikcə, ölçmə

texnikalarını da etik və praktiki olaraq balanslaşdırmalıdır. Eyni zamanda texnologiyaya əlçatanlığın qeyri-bərabər olması, rəqəmsal savadlılıq arasındakı fərqlər, müxtəlif səviyyəli rəhbərlik dəstəyi müxtəlif təlim nəticələri yarada bilər.

Əsas Hissə

Rəqəmsal transformasiyanın sürətli irəliləyişi müəssisələrin idarəsini və davamlı olaraq kadrların məhsuldar və rəqəbətli qalması üçün əldə etməli olduqları bilik və bacarıqları yenidən formalaşdırır. Müasir nəticələr göstərir ki, bir çox qurumların milli təlim yanaşmalarına uyğunlaşmaqda çətinlik çəkməsi ilə işçi tələbləri sürətlə dəyişir. Dünya İqtisadi Forumu layihəsində əks olunur ki, texnoloji dəyişikliklər və yeni makrotrendlər kadr fəaliyyətlərinin əhəmiyyətli dərəcədə pozulmasına səbəb olacaq; məsələn, onun “İşlərin Gələcəyi” hesabatında belə əks olunub: İş yerlərinin böyük bir hissəsinin qısa müddət ərzində dəyişəcəyi gözlənilir ki, bu da işçi qüvvəsinin davamlı inkişafının vacibliyini və təciliyini vurğulayır. [1]

Bu kontekstdə, bacarıqların yenilənməsi və inkişafı sadə İnsan Resursları fəaliyyətindən strateji bir prioritetə çevrildi. Dünya İqtisadi Forumunun “Gələcəyin Peşələri Hesabatı 2025” məlumatlarına əsasən, kadrlar 39%-ə qədər əsas tələblərin 2030-cu ilə qədər dəyişəcəyini ehtimal edir və əmək fəaliyyətindəki bu boşluq biznesin inkişafı və rəqəbat qabiliyyəti üçün əsas maneə kimi göstərilir. Statistik nümunə üzərindən göstərsək, əgər global işçi qüvvəsinə 100 nəfər işçi üzərindən baxsaq, 2030-cu il etibarilə onlardan 59-nun qabiliyyətlərini artırması və yaxud yenilənməsi tələb ediləcək, baxmayaraq bu kadrların ehtiyac duyduqları təlimə əlçatanlıqları olduqca azdır. [1]

Bu global siqnallar eyni zamanda e-təlim və rəqəmsal öyrənmə platformalarının son zamanlardakı yüksəlişinin səbəbini daha aydın göstərir. Eyni hesabatda vurğulanır ki, yüksək ixtisaslaşma və bacarıqların artırılması texnoloji inkişaf dövründə əsas təşkilati cavab görünür və əksər işəgötürənlər kadrların inkişafını məhz işçi qüvvəsinin bir parçası olaraq nəzərdə tutur. Bununla belə, bu cür təşəbbüslərin effektivliyi və səmərəliliyi həmin təlimin tərtib olunma qaydasından, ümumi müəssisənin biznes məqsədlərinə uyğunlaşdırılmasından və dəstəklənməsindən asılıdır (məsələn, rəhbərliyin dəstəyi, təcrübə fəaliyyətləri, yeni biliklərin tətbiqi üçün yaradılmalı olan imkanlar).

Son dövrlərdə orqanizasiyalar dəyişən kadr tələblərinə cavab vermək üçün ənənəvi təlim-tədris metodlarından daha çox ölçüləbilən, zaman cəhətdən əlverişli və yenilənməsi daha rahat olan öyrənmə metodlarına üz tuturlar. Buna baxmayaraq, xarici araşdırmalar göstərir ki, rəqəmsal öyrənmənin nəticə səmərəliliyi hər hansı bir platformanın mövcudluğundan çox, öyrənmə mühitinin dizaynından, idarəsindən və gündəlik işə sinxron edilməsindən asılıdır. Bu təlimlər idarə edilə bilən bacarıq artırma prosesi kimi yox, sadə məzmun kitabxanası kimi götürüldükdə, real performans gözləntiləri ilə olan bağlantı kəsilir. Bu tip situasiyalarda, müəssisələr əməkdaşlarının bir çox “kurs” bitirməsini nümunə göstərə bilər, lakin bu ümumi orqanizasiyanın peşəkar fəaliyyətində müsbət nəticələri bərabərində gətirmir. Burada praktiki dilemma yaranır: elektron təlimlər bir çox sahələrdə zəruri olaraq qəbul ediləndir, lakin işçilər arasında göstərilən nəticələr qeyri-bərabər olur.

Qeyd olunmuş problemləri həll etməyin ən sadə üsulu, öyrənmə başlanğıcı, ümumi proses və fəaliyyət nəticələrinin ölçümünü bir birindən fərqləndirməyi bacarmaqdır. Öyrənmə başlanğıcına düzgün təlim platformasının seçilməsi və ona əlçatanlığın əldə edilməsi, müvafiq məzmun və sadə infrastruktur aiddir. Ümumi proses iştirakçıların məşğulluq səviyyələrini, vaxt bölgülərini, təcrübə imkanlarını, həmçinin əks əlaqəni əhatə edir. Fəaliyyət nəticələrinin ölçülməsində isə qeyd edilmiş məsələlərə diqqət yetirilir: sürət, dəqiqlik, iş keyfiyyəti, uyğunlaşma/adaptasiya, əməkdaşlıq və aktiv problemlərin həlli. Bir çox təşkilatlar öyrənmə başlanğıcına yüksək diqqət və sərmayə ayırır, amma ümumi prosesin idarə edilməsində və nəticələrin dəyərləndirilməsində lazımi səyi göstərmir. Məsələn, hər hansı bir işçinin iş yükünü azaltmadan onu müəssisə fəaliyyətindən kənar təlimlərə yönləndirdikdə, bu həmin işçinin məşğulluq dərəcəsini azalda bilər. Təlimin məzmunu işçinin

təşkilatdakı roluna uyğun olmadıqda, onlar tərəfindən qazanılan bacarıqlar əhəmiyyətsiz hesab edilə bilər. Strukturlaşdırılmış praktika olmadıqda (məsələn, öyrənilən biliklərin real nümunələr üzərində test edilməsi), qazanılan biliklər sadəcə nəzəriyyə ilə məhdudlaşır.

Beynəlxalq öyrənmə ideologiyası öyrənmə prosesinin sadəcə bacarıq məsələsi deyil, həm də motivasiya və mədəniyyətdən irəli gəlməsi fikrini dəstəkləyir. LinkedIn tərəfindən 2024-cü ildə hazırlanmış İş Yerində Öyrənmə Hesabatı göstərir ki, təlimlər zamanı qazanılan biliklər, işçilərin təşkilatda əlaqə və motivasiya hissini böyük ölçüdə yüksəldə bilər. Aparılan araşdırmada 10 işçidən 7-si öyrənmə prosesinin iş mühiti ilə olan əlaqələrini gücləndirdiyini, hər 10 işçidən 8-i isə öyrənmənin işlərində daha məqsədyönlü irəliləmələrində rol oynadığını bildirib. Bu geridönüşlər rəqəbat qabiliyyətində xüsusi rol oynayır çünki, kadrların məşğulluğu və davamlılığı eyni zamanda təşkilatın məhsuldarlığına və fərqlənməsinə müsbət təsir göstərir. İş mühitində güclü rəqəbatın mövcud olduğu təşkilatlarda yeni dövrün tələblərinə uyğunlaşma zamanı, asan adaptasiya ola bilən, yeni alətləri və prosesləri asanlıqla qəbul edə bilən, performansını optimallaşdıran işçi qüvvələrinin saxlanma ehtimalı olduqca yüksəkdir.

Eyni zamanda onlayn öyrənmə ilə bağlı araşdırmalar göstərir ki, təlimlərin rəqəmsal mühitdə keçirilməsi birbaşa onların effektiv olması mənasına gəlmir. Elektron öyrənmənin effektivliyi əsasən bəzi təməl strukturlardan məsələn, praktika, rəy bildirmə və tətbiq imkanlarından asılı olur. Bu məsələ ilə bağlı meta-analitik araşdırmalar sübut edir ki, tədris nəticələri təlim iştirakçılarının yanaşmasına görə dəyişə bilər və sintez öyrənmə parametrləri arasında əksər hallarda sırf onlayn yaxud sırf üz-üzə təlim formatlarından daha yüksək nəticələr nümayiş etdirir. Rəqəmsal öyrənmənin ən güclü təsirləri qısa rəqəmsal nəzəri modulların iş mühitində tətbiqlər, rəhbər dəstəyi və davamlı fəaliyyət əsaslı dəyərləndirmələrlə birləşdikdə ortaya çıxır.

Qeyd edilənlərə əsaslanaraq, rəqəmsal öyrənmənin müəssisənin inkişafında olan rolunu “sadə zəncir” quruluşu ilə bu formada izah etmək olar. İlk növbədə rəqəmsal təlimlər işçilərə/iştirakçılara elektron alətlərə, iş axınlarına və problem həlli üçün müxtəlif yanaşmalara strukturlaşmış tanışlıq təmin etməklə rəqəmsal bacarıqların artmasına töhvə verir. Növbəti addımda rəqəmsal bacarıqların çoxalması və öyrənmə çevikliyinin qazanılması ilə birgə, tapşırıqların həlli optimallaşır, yeni sistemlərə adaptasiya getdikcə asanlaşır və işçinin ümumi iş performansını yüksəlir. Daha sonra, işçi səviyyəsində daha yüksək performans, təkmilləşdirilmiş əməliyyat çevikliyi, bazar dəyişikliklərinə daha sürətli reaksiya, yüksək xidmət keyfiyyəti və daha güclü innovasiya potensialı kimi təşkilati nəticələrə toplanır. Bu zəncirdə rəqəbat qabiliyyəti təlimdə iştirakın birbaşa məhsulu deyil; iş nəticələrində görünən bacarıqların yaradılmasının nəticəsidir.

Bununla belə, bu təsir zənciri tez-tez ümumi maneələrlə kəsilir. Bir maneə təlim məqsədləri ilə biznes məqsədləri arasında uyğunsuzluqdur. Təlim performans göstəriciləri (məs., məhsuldarlıq, dövrüyyə müddəti, müştəri məmnuniyyəti, proses keyfiyyəti) ilə aydın əlaqə olmadan həyata keçirildikdə, investisiyaları əsaslandırmaq və effektivliyi artırmaq çətinləşir. İkinci maneə məhdud ölçmə keyfiyyətidir. Bir çox təşkilat təlimi iş performansındakı dəyişikliklərlə deyil, iştirak və tamamlanma nisbətləri ilə ölçür. Üçüncü maneə vaxtın qeyri-kafi ayrılmasıdır: iş yükü dəyişməz qalarkən işçilərin “daha çox öyrənmələri” gözlənilə bilər. Dördüncü maneə məzmunun uyğunluğu və keyfiyyətidir. Məzmun ümumi, köhnəlmiş və ya rol və tapşırıqlara uyğunlaşdırılmamış olduqda, motivasiya azalır və öyrənmə praktikaya çevrilmir. Nəhayət, liderlik dəstəyi vacibdir: menecerlər öyrənmə gözləntilərini gücləndirdikdə, yeni bacarıqların tətbiqi üçün imkanlar təqdim etdikdə və tərəqqini tanıdıqda işçilər daha çox ciddi məşğul olurlar.

Rəqəmsal dövrün rəqəbat qabiliyyəti getdikcə daha çox təşkilatların öyrənməni əməliyyat qabiliyyətinə çevirə bilməsindən asılıdır. Ənənəvi təlim modelləri çox vaxt dövrü kurslara və qeyri-rəsmi biliklərin ötürülməsinə əsaslansa da, rəqəmsal transformasiya bir çox bacarıqların, xüsusən də alətə əsaslanan və prosesə əsaslanan bacarıqların “yarım ömrünü” qısaldıb. Təşkilatlar yeni proqram təminatı qəbul etdikcə, iş axınlarını avtomatlaşdırdıqca və məlumat əsasında qərar qəbul etməyi genişləndirdikcə, işçilərin vaxtaşırı deyil, davamlı olaraq öyrənmələri gözlənilir. Bu mühitdə

bacarıqların artırılması sadəcə HR fəaliyyəti deyil; təşkilatlara əməliyyat sürtünməsinə azaltmağa, icra keyfiyyətini yaxşılaşdırmağa və dəyişikliklərə daha tez reaksiya verməyə kömək edən idarəetmə mexanizminə çevrilir.

Elektron təhsil platformaları vacibdir, çünki onlar bacarıqların inkişafına miqyas, sürət və standartlaşdırma təqdim edirlər. Vaxt, məkan və təlimatçının mövcudluğu ilə məhdudlaşan sinif sessiyalarından fərqli olaraq, e-təlim komandalar arasında yenilənmiş məzmunu yaymağı, yeni işçiləri ardıcıl olaraq işə salmağı və təkrar məruz qalma vasitəsilə öyrənməni gücləndirməyi asanlaşdırır. Bununla belə, elektron təhsilin əsl dəyəri platformanın özü deyil, onun ətrafındakı təşkilati sistemdir – təlimin necə seçildiyi, onun iş rolları ilə əlaqəsi və öyrənmənin iş yeri davranışına necə çevrildiyidir. Elektron təhsilin “kurslar kitabxanası” kimi qiymətləndirildiyi təşkilatlarda işçilər işlədiklərini dəyişmədən modulları tamamlaya bilirlər. Bunun əksinə olaraq, e-təhsil bacarıqların yaradılması prosesi kimi strukturlaşdırıldıqda- xüsusi tapşırıqlarla əlaqələndirilir, menecerlər tərəfindən dəstəklənir və performans göstəriciləri vasitəsilə qiymətləndirilir- bunun real nəticələri yaxşılaşdırmaq ehtimalı daha yüksəkdir.

Rəqəmsal öyrənmə və rəqabətqabiliyyətlik arasında əsas əlaqə işçilərin uyğunlaşmasıdır. Güclü rəqəmsal bacarıqlara malik olan işçilər, ümumiyyətlə, daimi nəzarət olmadan yeni alətləri qəbul etmək, yenilənmiş prosedurlara uyğunlaşmaq və sistemlərdə naviqasiya etmək qabiliyyətinə malikdirlər. Bu, proqram yeniləmələri, siyasət dəyişiklikləri və ya prosesin yenidən dizaynı kimi keçidlər zamanı gecikmələri azaldır. Zaman keçdikcə uyğunlaşma rəqabət üstünlüyünə çevrilir, çünki təşkilati səviyyədə çevikliyi dəstəkləyir. Böyük məhsuldarlıq itkisi olmadan iş axınlarını tez bir zamanda yenidən konfigurasiya edə bilən şirkətlər bazar qeyri-müəyyənliyi və texnoloji pozğunluqların öhdəsindən daha yaxşı gəlirlər. Praktikada bu çeviklik daha sürətli dönüş, funksiyalar arasında daha hamar koordinasiya və dəyişiklik zamanı daha az “darboğaz” kimi görünür.

Rəqəmsal bacarıqların inkişafı təkcə qabaqcıl texniki bacarıqlar vasitəsilə deyil, həm də təkmilləşdirilmiş problemlərin həlli və təcrübə vasitəsilə innovasiya qabiliyyətini dəstəkləyir. İşçilər rəqəmsal alətlər və məlumatlar ilə rahat olduqda, onlar səmərəsizliyi müəyyən etmək, təkmilləşdirmələr təklif etmək və alternativləri sınaqdan keçirmək ehtimalı daha yüksəkdir. Hətta daha yaxşı hesabat şablonu, sadələşdirilmiş iş axını və ya avtomatlaşdırılmış xatırlatma sistemi kimi kiçik yeniliklər də mənalı performans qazancına çevrilə bilər. Bu mənada, e-təhsil təşkilat daxilində davranışın yaxşılaşdırılmasının tezliyini və keyfiyyətini artırmaqla rəqabət qabiliyyətinə töhfə verir, xüsusən də öyrənmə dəyişikliklərin həyata keçirilməsi imkanları ilə birləşdirildikdə.

Bu üstünlüklərə baxmayaraq, bir çox rəqəmsal bacarıqların artırılması təşəbbüsləri proqnozlaşdırıla bilən maneələr səbəbindən ardıcıl nəticələr verə bilmir. Ən çox rast gəlinən məsələlərdən biri uyğunsuzluqdur: təlim məzmunu rol tələblərinə və ya biznes prioritetlərinə uyğunlaşdırılmır, buna görə də işçilər onun aktuallığını görməkdə çətinlik çəkirlər. Digər maneə zəif köçürmədir- işçilər təlimi başa vururlar, lakin bunu tətbiq etmirlər, çünki ya vaxt çatışmazlığı, geribildirim almırlar, ya da onların mühiti yeni metodları təşviq etmir. Üçüncü maneə ölçmə keyfiyyətidir: təşkilatlar iştirak və tamamlamanı izləyir, lakin təsiri yox, bu da təlimin təkmilləşdirilməsini və ya investisiyaların əsaslandırılmasını çətinləşdirir. Nəhayət, təlim işin dəstəklənən hissəsi deyil, əlavə yük kimi qəbul edilərsə, məşğulluq və motivasiya aşağı düşə bilər.

Bu məhdudiyyətləri aradan qaldırmaq üçün effektiv rəqəmsal bacarıqların artırılması proqramları az sayda dizayn prinsiplərini bölüşməyə meyllidir. Birincisi, təşkilatlar bacarıqların xəritələşdirilməsi məşğələsinin keçirilməsindən faydalanır: hər bir rol üçün hansı rəqəmsal bacarıqların kritik olduğunu müəyyənləşdirmək və boşluqların mövcudluğunu müəyyən etmək. İkincisi, təlim məzmunu rola əsaslanan və tapşırıqla əlaqəli olmalıdır ki, işçilər öyrənməni gündəlik məsuliyyətlərlə dərhal əlaqələndirə bilsinlər. Üçüncüsü, e-təhsil qısa tapşırıqlar, real iş axını tapşırıqları və ya həmyaşıdlarla rəy sessiyaları kimi təcrübə və tətbiq ilə birləşdirilməlidir. Dördüncüsü, menecerlər öyrənməyə vaxt ayırmaqla, gözləntiləri gücləndirməklə və irəliləyişləri

tanımaqla mühüm rol oynayırlar. Başqa sözlə, liderlik dəstəyi simvolik deyil - bu, öyrənmənin performansına keçməsi üçün şərait yaradır.

Ölçmə həm də e-təhsilin rəqabətqabiliyyətlilik strategiyası kimi etibarlı olması üçün mərkəzidir. Praktiki yanaşma təlimi müxtəlif səviyyələrdə qiymətləndirməkdir: əsas iştirak ölçüləri (tamamlama, sərf olunan vaxt), öyrənmə ölçüləri (viktorialar, özünüqiymətləndirmənin təkmilləşdirilməsi) və ən əsası iş nəticələri ilə əlaqəli fəaliyyət göstəriciləri. Kontekstdən asılı olaraq, performans göstəricilərinə daha sürətli əməl müddəti, daha az təkrarlanan səhvlər, təkmilləşdirilmiş keyfiyyətə nəzarət, yeni prosedurların daha tez qəbulu və ya daha ardıcıl sənədlər daxil ola bilər. Təşkilatların başlamaq üçün mürəkkəb analitikaya ehtiyacı yoxdur; hətta təlim təşəbbüslərindən əvvəl və sonra izlənilən kiçik bir əməliyyat KPI dəsti öyrənmənin dəyər yaradıb-yaratmadığını aşkar edə bilər. Zamanla bu ölçmə təcrübəsi təşkilatlara məzmunu dəqiqləşdirməyə, bacarıq boşluqlarını daha dəqiq hədəfləməyə və proqramları daha güclü inamla genişləndirməyə kömək edir.

Bütövlükdə, e-təhsil, rəqəmsal bacarıqların inkişafı və rəqabətqabiliyyətlilik arasındakı əlaqə ən yaxşı şəkildə dolayı yol kimi başa düşülür. Elektron təhsil təkmilləşdirilmiş bacarıqlara və öyrənmə çevikliyinə kömək edir; bu imkanlar işçilərin fəaliyyətini yaxşılaşdırır (səmərəlilik, dəqiqlik, uyğunlaşma və davranışın təkmilləşdirilməsi); və daha yüksək performans çeviklik, xidmət keyfiyyəti və innovasiya kimi təşkilati nəticələri dəstəkləyir. Təşkilatlar bu yolu qəsdən - uyğunlaşdırma, təbiiqetmə, liderlik dəstəyi və ölçülə bilən qiymətləndirmə vasitəsilə idarə etdikdə, rəqəmsal bacarıqların artırılması ümumi təlim fəaliyyətindən daha çox rəqabət qabiliyyətinin praktik mühərrikinə çevrilir.

Nəticə və tövsiyələr

Rəqəmsal transformasiya təşkilatların bacarıqlarını yeniləməli olduğu sürəti sürətləndirdi və bacarıqların artırılmasını dövrü HR təşəbbüsü deyil, strateji tələb etdi. Bu sənəd iddia edirdi ki, e-təhsil və rəqəmsal bacarıqların inkişafı təşkilati rəqabət qabiliyyətini gücləndirə bilər, lakin avtomatik və kontekstlər arasında bərabər şəkildə deyil. Əsas nəticə ondan ibarətdir ki, rəqəmsal öyrənmə rəqabət qabiliyyətinə ilk növbədə dolayı yolla kömək edir: e-təhsil rəqəmsal imkanların və öyrənmə çevikliyinin inkişafını dəstəkləyir; bu imkanlar işçilərin işini yaxşılaşdırır (məsələn, sürət, dəqiqlik, uyğunlaşma və təkmilləşdirməyə yönəlmiş davranış); və performans təkmilləşdirmələri əməliyyat çevikliyi, xidmət keyfiyyəti və innovasiya qabiliyyəti kimi rəqabət qabiliyyəti ilə əlaqəli nəticələrə toplanır.

Bu anlayışlara əsaslanaraq, bir sıra praktik tövsiyələr ortaya çıxır. Birincisi, təşkilatlar rəqəmsal bacarıqların artırılması planlarını konkret biznes məqsədləri və bacarıq xəritəsi vasitəsilə rola aid tələblərlə əlaqələndirməlidir. İkincisi, e-təhsil tətbiq mexanizmləri ilə birləşdirilməlidir - işə əsaslanan tapşırıqlarla qoşalaşmış mikrotəlim, əks əlaqə dövrləri və bacarıqların ötürülməsini dəstəkləyən təqib fəaliyyətləri. Üçüncüsü, qiymətləndirmə tamamlanma dərəcələrindən kənara çıxmalı və real iş nəticələrini əks etdirən performans göstəricilərini (məsələn, daha az təkrarlanan səhvlər, daha sürətli dönüş, yeni alətlərin təkmilləşdirilmiş qəbulu və ya daha yüksək proses ardıcılığı) daxil etməlidir. Nəhayət, liderlik dəstəyi vacibdir: qorunan öyrənmə vaxtı, aydın gözləntilər və tətbiqi öyrənmənin tanınması e-öyrənin performans artımına səbəb olması ehtimalını əhəmiyyətli dərəcədə artırır.

Ədəbiyyat siyahısı

1. World Economic Forum (2023). **The Future of Jobs Report 2023**.
2. <https://www.weforum.org/reports/the-future-of-jobs-report-2023/>
3. World Economic Forum (2025). **The Future of Jobs Report 2025**.
4. <https://www.weforum.org/reports/the-future-of-jobs-report-2025/>
5. OECD (2023). **OECD Skills Outlook 2023: Skills for a Resilient Green and Digital Transition** (report page).
6. https://www.oecd.org/en/publications/2023/11/oecd-skills-outlook-2023_df859811.html
7. OECD (2023). **OECD Skills Outlook 2023** (full report page).
8. https://www.oecd.org/en/publications/oecd-skills-outlook-2023_27452f29-en/full-report.html
9. LinkedIn Learning (2024). **Workplace Learning Report 2024**.
10. <https://learning.linkedin.com/resources/workplace-learning-report-2024/>
11. U.S. Department of Education (2010). **Evaluation of Evidence-Based Practices in Online Learning: A Meta-Analysis and Review of Online Learning Studies** (PDF).
12. <https://www2.ed.gov/rschstat/eval/tech/evidence-based-practices/finalreport.pdf>
13. Sitzmann, T., Kraiger, K., Stewart, D., & Wisher, R. (2006). **The comparative effectiveness of web-based and classroom instruction: A meta-analysis**. *Personnel Psychology*.
14. (Find via Google Scholar search using the exact title + "Sitzmann 2006".)
15. Clark, R. C., & Mayer, R. E. **e-Learning and the Science of Instruction**. Wiley.
16. (Find via Google Scholar/Google Books search: "e-Learning and the Science of Instruction" Clark Mayer.)
17. Kirkpatrick, J. D., & Kirkpatrick, W. K. **Kirkpatrick's Four Levels of Training Evaluation**. ATD.
18. (Find via Google Scholar/Google Books search: "Kirkpatrick's Four Levels of Training Evaluation".)

BANK MÜŞTƏRİLƏRİNİN İTKİSİNİN PROQNOZLAŞDIRILMASINDA MAŞIN ÖYRƏNMƏSİ MODELƏRİNİN TƏHLİLİ VƏ PERFORMANS GÖSTƏRİCİLƏRİNİN ANALİZİ

Səhrab Əlizadə

Azərbaycan Dövlət İqtisad Universiteti (UNEC), Data Analitikası ixtisası üzrə magistrant,
Bakı, Azərbaycan

XÜLASƏ

Bu tədqiqat işində müasir bankçılığın ən aktual problemlərindən biri olan müştəri axınının (churn) idarə edilməsi üçün maşın öyrənməsi perspektivləri araşdırılır. Əsas diqqət Random Forest, SVM və Logistic Regression alqoritmlərinin tətbiqi ilə real bank verilənləri üzərində proqnozlaşdırma modellərinin qurulmasına yönəlmişdir. Aparılan eksperimentlər nəticəsində məlum olmuşdur ki, ansambl metodlarına əsaslanan Random Forest modeli 87% dəqiqlik nümayiş etdirərək, xüsusilə bankı tərk etməyə meyilli olan müştəri segmentini aşkar etməkdə digər modellərdən daha etibarlı nəticələr verir. Bundan əlavə, tədqiqat çərçivəsində modellərin sistem resurslarına (CPU və RAM) olan tələbatı kəmiyyət baxımından ölçülmüşdür ki, bu da təklif olunan həllərin bankın mövcud rəqəmsal infrastrukturuna integrasiyası üçün həlledici əhəmiyyət kəsb edir. Müəyyən edilmişdir ki, müştəri yaşı və balans göstəriciləri loyallığın proqnozlaşdırılmasında ən yüksək informasiya çəkisinə malik faktorlardır.

Açar sözlər: Maşın öyrənməsi, Bank churn proqnozu, Random Forest, SVM, Logistic Regression, Performans analizi

ABSTRACT

This study explores machine learning perspectives for managing customer churn, a critical challenge in the modern banking sector. The research focuses on developing predictive models using Random Forest, SVM, and Logistic Regression algorithms on real-world banking datasets. Experimental results reveal that the Random Forest model, with 87% accuracy, outperforms other approaches, particularly in identifying segments prone to leaving the bank. Furthermore, the study quantifies the computational resource requirements (CPU and RAM) of each model, providing a technical basis for their integration into existing banking digital infrastructures. Findings indicate that customer age and balance metrics hold the highest informational weight in loyalty forecasting.

Keywords: Machine learning, Bank churn prediction, Random Forest, SVM, Logistic Regression, Performance analysis.

1. GİRİŞ

Müasir bankçılıq sektorunda rəqabətin kəskinləşməsi və müştəri seçimlərinin diversifikasiyası fonunda mövcud müştəri bazasının qorunub saxlanılması iqtisadi dayanıqlılığın əsas şərtlərindən biridir. Müştəri itkisi (churn) yalnız birbaşa gəlir itkisi deyil, həm də yeni müştərilərin cəlb edilməsi üçün çəkilən yüksək marketing xərcləri səbəbindən bank fəaliyyətinin səmərəliliyinə mənfi təsir göstərir. Bu problemin həllində ənənəvi statistik metodlar artıq kifayət etmir və daha mürəkkəb, qeyri-xətti asılılıqları aşkar edə bilən maşın öyrənməsi (ML) alqoritmlərinə ehtiyac yaranır.

Tədqiqatın əsas məqsədi bank müştərilərinin davranış patternlərini analiz edərək, onların bankdan ayrılma ehtimalını yüksək dəqiqliklə proqnozlaşdıran modeli müəyyən etməkdir. İş çərçivəsində üç fərqli yanaşma; ansambl metodlarına əsaslanan Random Forest, xətti qərar

sərhədləri quran Support Vector Machines (SVM) və ehtimal nəzəriyyəsinə əsaslanan Logistic Regression alqoritmləri tətbiq edilmişdir.

Tədqiqatı fərqləndirən əsas məqam, modellərin təkcə proqnoz dəqiqliyi (accuracy, recall) üzrə deyil, həm də onların real sistem resurslarından (CPU, RAM) istifadə səmərəliliyi baxımından müqayisəli analizinin aparılmasıdır. Bu yanaşma, təklif olunan həllərin bankın real zamanlı əməliyyat sistemlərinə integrasiyasının texniki əsaslandırılmasını təmin edir.

2. METODOLOGİYA VƏ VERİLƏNLƏRİN TƏSVİRİ

Tədqiqatın praktiki realizasiyası çərçivəsində maşın öyrənməsi modellərinin proqnoz qabiliyyətini və hesablama səmərəliliyini qiymətləndirmək üçün xüsusi test mühiti formalaşdırılmışdır. Analiz üçün baza olaraq 10,000 müştəri müşahidəsini və 12 fərqli indikatoru özündə birləşdirən "Bank Customer Churn Prediction" verilənlər toplusu seçilmişdir.

Bu dataset bank sektorunda müştəri axını problemini araşdırmaq üçün zəruri demoqrafik (cins, yaş, coğrafi yerləşmə) və maliyyə davranış göstəricilərini əks etdirir. Modellərin qurulmasında aşağıdakı fundamental dəyişənlər həlledici rol oynayır:

Hədəf dəyişəni (Churn): Analizin əsas çıxış parametri olub, müştərinin bankı tərk edib-etməmə vəziyyətini ifadə edir.

Müştəri aktivliyi və stajı: Müştərinin bank xidmətlərindən istifadə intensivliyi və əməkdaşlıq müddəti (tenure) risk profilinin təyində əsas indikatorlar kimi qəbul edilmişdir.

Maliyyə indikatorları: Müştərinin balans göstəriciləri və təxmini illik gəliri (estimated salary) loyallıq səviyyəsini müəyyən edən kritik faktorlardır.

2.1. Verilənlərin integrasiyası və ilkin vizual təftiş

Tədqiqatın praktiki mərhələsində seçilmiş verilənlər toplusu Python proqramlaşdırma dilinin Pandas kitabxanası vasitəsilə .csv formatından strukturlaşdırılmış DataFrame massivinə çevrilərək sistemə integrasiya edilmişdir. Yüklənmiş məlumatların struktur bütövlüyünü, sütunların ardıcılığını və məlumat tiplərinin düzgünlüyünü yoxlamaq məqsədilə ilk beş müşahidənin (head metodu vasitəsilə) vizual analizi aparılmışdır. Analiz nəticəsində kəmiyyət (kredit balı, balans, yaş) və kateqoriyalı (ölkə, cins) məlumatların proqram mühitinə itkisiz ötürüldüyü, proqnozlaşdırma modelinin əsasını təşkil edəcək hədəf dəyişəninin (churn) və digər müstəqil dəyişənlərin sistemdə tam əks olunduğu müəyyən edilmişdir.

```
[8]: import pandas as pd

# Faylın oxunması
df = pd.read_csv(r"C:\Users\Nigar\Downloads\data.csv")

# İlk 5 sətirin görünməsi
df.head()
```

	customer_id	credit_score	country	gender	age	tenure	balance	products_number	credit_card	active_member	estimated_salary	churn
0	15634602	619	France	Female	42	2	0.00	1	1	1	101348.88	1
1	15647311	608	Spain	Female	41	1	83807.86	1	0	1	112542.58	0
2	15619304	502	France	Female	42	8	159660.80	3	1	0	113931.57	1
3	15701354	699	France	Female	39	1	0.00	2	0	0	93826.63	0
4	15737888	850	Spain	Female	43	2	125510.82	1	1	1	79084.10	0

Şəkil 1. "Bank Customer Churn" datasetinin ilkin strukturu

2.2. Verilənlərin ilkin emalı və keyfiyyət analizi

Modellərin proqnoz dəqiqliyini artırmaq və yanlış korrelyasiyaların qarşısını almaq üçün verilənlərin ilkin emalı (preprocessing) mərhələsi icra edilmişdir. İlk addım kimi, model üçün informativ

əhəmiyyət kəsb etməyən customer_id dəyişəni massivdən xaric edilmiş və sütunların sayı 11-ə endirilərək hesablamə səmərəliliyi optimallaşdırılmışdır.

Məlumat bazasının etibarlılığını yoxlamaq məqsədilə isnull().sum() funksiyası tətbiq edilərək çatışmayan (null/missing) dəyərlər tədqiq edilmişdir. Analiz nəticəsində 10,000 müşahidənin hər biri üzrə məlumatların tam bütövlüyə malik olduğu və boş xanaların sayının 0-a bərabər olduğu müəyyən edilmişdir (Şəkil 2). Bu göstərici verilənlər toplusunun yüksək keyfiyyət standartlarına cavab verdiyini və süni məlumat doldurma (imputation) əməliyyatına ehtiyac qalmadığını təsdiq edir.

```
# Məlumat bazasının silinmədən öncəki ölçüsünün yoxlanılması
print("Silinmədən öncə sütun sayı:", df.shape[1])

Silinmədən öncə sütun sayı: 12

# Müştəri ID-si hədəfə (churn) təsir etmədiyi üçün onu vb-dan xaric edirik
df = df.drop(['customer_id'], axis=1)

# Silindikdən sonra ölçünün yoxlanılması
print("Silindikdən sonra sütun sayı:", df.shape[1])

Silindikdən sonra sütun sayı: 11

# Məlumat bazasında boş (null) xanaların olub-olmadığının yoxlanılması
print("\nSütunlardakı boş xanaların sayı:")
print(df.isnull().sum())

Sütunlardakı boş xanaların sayı:
credit_score      0
country           0
gender            0
age              0
tenure            0
balance           0
products_number  0
credit_card       0
active_member     0
estimated_salary  0
churn             0
dtype: int64
```

Şəkil 2. Verilənlərin tamlığının yoxlanılması və sütunların optimallaşdırılması

2.3. Kateqoriyalı dəyişənlərin rəqəmsal transformasiyası

Maşın öyrənməsi alqoritmlərinin riyazi tənlilər əsasında fəaliyyət göstərdiyini nəzərə alaraq, mətni (string) xüsusiyyətlərin ədədi formata keçirilməsi zəruridir. Bu məqsədlə, müştərilərin coğrafi yerləşməsini (country) və cinsiyyətini (gender) ifadə edən kateqoriyalı dəyişənlərə "One-Hot Encoding" metodologiyası tətbiq edilmişdir.

```
df = pd.get_dummies(df, columns=['country', 'gender'], drop_first=True)
```

Bu kod icra edilərək, ölkə və cinsiyyət göstəriciləri riyazi formata çevrilmişdir. Burada drop_first=True parametri vasitəsilə multikollinearlıq probleminin qarşısı alınmışdır.

Transformasiya nəticəsində hər bir unikal kateqoriya üçün müstəqil sütunlar formalaşdırılmış və məlumatlar binar (0 və 1) struktura gətirilmişdir. Bu yanaşma, qeyri-rəqəmsal faktorların modelin proqnozlaşdırma qabiliyyətinə riyazi təsirini təmin edir və verilənləri təlim (training) mərhələsi üçün tam hazır vəziyyətə gətirir.

3. TƏDQİQATIN GEDİŞATI VƏ NƏTİCƏLƏR

3.1. Verilənlərin strateji bölünməsi (Train-Test Split)

Maşın öyrənməsi modelinin obyektivliyini və real bazar ssenarilərinə uyğunluğunu təmin etmək məqsədilə tədqiqatda "Train-Test Split" metodologiyası tətbiq edilmişdir. Mövcud 10,000 müşahidədən ibarət verilənlər massivi 80/20 nisbətində iki müstəqil hissəyə ayrılmışdır.

Bu məqsədlə scikit-learn kitabxanasının imkanlarından istifadə edilərək hədəf dəyişəni ($y = df['churn']$) və müstəqil dəyişənlər ($X = df.drop('churn', axis=1)$) müəyyən edilmişdir. Bölünmə prosesi isə, aşağıdakı kod strukturu ilə icra olunmuşdur:

```
X_train, X_test, y_train, y_test = train_test_split(X, y, test_size=0.2, random_state=42)
```

Bu bölgü nəticəsində 8,000 qeyd alqoritmin öyrənməsi (training), qalan 2,000 qeyd isə modelin daha əvvəl qarşılaşmadığı verilənlər üzərində test edilməsi üçün ayrılmışdır. *random_state=42* parametrinin seçilməsi təcrübənin statistik təkrarla bilənliyini təmin edir və təsadüfi paylanma zamanı yarana biləcək qərəzlilik (bias) riskini minimuma endirir. [5]

3.2. Modelin seçimi və Random Forest (RF) alqoritminin tətbiqi

Verilənlərin ilkin emalı (Data Preprocessing) mərhələsinin uğurla tamamlanması: lazımsız atributların kənarlaşdırılması, kateqoriyalı dəyişənlərin rəqəmsallaşdırılması və massivin bölünməsi, alqoritmlərin tətbiqi üçün texniki bazanı formalaşdırmışdır. Tədqiqatın əsas mərhələsində müştəri itkisinin yüksək dəqiqliklə proqnozlaşdırılması üçün Random Forest (Təsadüfi Meşə) alqoritmindən istifadə edilmişdir. Bu modelin seçilməsi onun mürəkkəb və qeyri-xətti verilənlər bazalarında göstərdiyi yüksək performans və "overfitting" (həddindən artıq öyrənmə) probleminə qarşı dayanıqlılığı ilə əsaslandırılır.

3.3. Random Forest modelinin təlimi və qiymətləndirmə meyarları

Tədqiqatın praktiki realizasiyası üçün RandomForestClassifier modulundan istifadə edilmişdir. Modelin konfiqurasiyası aşağıdakı kod strukturu ilə müəyyən edilmişdir:

```
rf_model = RandomForestClassifier(n_estimators=100, random_state=42)
rf_model.fit(X_train, y_train)
```

Burada *n_estimators=100* parametri təyin edilərək, sistemin 100 müstəqil qərar ağacının kollektiv rəyinə əsaslanması təmin olunmuşdur. Təlim prosesi 8,000 müştəri qeydi üzərində icra edilmişdir. Modelin ümumiləşdirmə qabiliyyətini ölçmək üçün 2,000 müştəridən ibarət test massivi tətbiq olunmuş və performansın qiymətləndirilməsində maşın öyrənməsinin fundamental metrikaları — Dəqiqlik (Accuracy), Həssaslıq (Precision), Tamlıq (Recall) və F1-ölçüsü (F1-score) istifadə edilmişdir. [1, 6]

3.4. Modelin performans analizi və nəticələrin interpretasiyası

Tədqiqatın yekun mərhələsində *predict* funksiyası vasitəsilə test massivi üzrə proqnozlar əldə edilmiş və real nəticələrlə (*y_test*) müqayisəli analiz üçün "ClassificationReport" metodologiyasından istifadə edilmişdir (Şəkil 3). Random Forest alqoritmi 0.87 (87%) ümumi dəqiqlik (Accuracy) nümayiş etdirmişdir ki, bu da modelin real bank ssenarilərinə yüksək uyğunluğunu sübut edir. Hesabatın detallı təhlili aşağıdakı statistik nəticələri ortaya qoyur:

Həssaslıq (Precision): Bankda qalan müştərilər (sinif 0) üzrə 0.88, bankı tərk edənlər (sinif 1) üzrə isə 0.76 təşkil edir.

Tamlıq (Recall): Sadıq müştərilərin 96%-i düzgün identifikasiya edilsə də, tərk edən müştərilərin (sinif 1) aşkar olunma səviyyəsi 47%-dir. Bu disproporsiya bank sektoruna xas olan qeyri-bərabər (imbalanced) məlumat paylanması ilə əlaqədardır.

F1-ölçüsü: Hər iki sinif üzrə balanslaşdırılmış göstəricilər modelin ümumi stabilliyini və praktiki tətbiq imkanlarını təsdiqləyir.

```

from sklearn.metrics import classification_report, accuracy_score

# 1. Test datası üzərində proqnoz verilməsi
y_pred = rf_model.predict(X_test)

# 2. Nəticələrin çap olunması
print("Random Forest modelinin nəticələri:")
print(f"Ümumi Dəqiqlik (Accuracy): {accuracy_score(y_test, y_pred):.2f}")
print("\nƏtraflı Hesabat:")
print(classification_report(y_test, y_pred))

Random Forest modelinin nəticələri:
Ümumi Dəqiqlik (Accuracy): 0.87

Ətraflı Hesabat:

```

	precision	recall	f1-score	support
0	0.88	0.96	0.92	1607
1	0.76	0.47	0.58	393
accuracy			0.87	2000
macro avg	0.82	0.72	0.75	2000
weighted avg	0.86	0.87	0.85	2000

Şəkil 3. Random Forest modelinin test nəticələri və performans hesabatı

3.5. Səhv Matrisinin (Confusion Matrix) vizuallaşdırılması və dərinləşdirilmiş analiz

Modelin performansını detallı təftiş etmək üçün "Səhv Matrisi" (Şəkil 4) qurulmuşdur. Matrisin analizi (0 – bankda qalanlar, 1 – bankı tərk edənlər) aşağıdakı nəticələri formalaşdırır:

Həqiqi Mənfi (TN, 1548): Model bankda qalan müştəriləri yüksək dəqiqliklə identifikasiya etmişdir. Bu, alqoritmin ən güclü tərəfidir.


Həqiqi Müsbət (TP, 185): Bankı tərk edən müştərilərin yalnız müəyyən bir hissəsi düzgün aşkarlanmışdır.

Yalançı Müsbət (FP, 59): Model minimal sayda halda sadıq müştərinin gedəcəyini proqnozlaşdıraraq "yalançı həyəcan" yaratmışdır.

Yalançı Mənfi (FN, 208): Tədqiqatın ən kritik göstəricisi olaraq, model real həyatda bankı tərk etmiş 208 müştərini yanlışlıqla sadıq müştəri kimi sinifləndirmişdir.

Bu paylanma bank sektoruna aid məlumat bazalarında tez-tez rast gəlinən sinif disbalansı (class imbalance) problemini açıq şəkildə ortaya qoyur. Verilənlər toplusunda aktiv müştərilərin sayı (1,607) tərk edənlərdən (393) təxminən dörd dəfə çox olduğundan, alqoritm öyrənmə prosesində dominant sinifə qarşı meyillilik (bias) nümayiş etdirmişdir. Nəticə etibarilə, əldə olunan 87% ümumi Dəqiqlik (Accuracy) göstəricisi müəyyən mənada aldadıcı xarakter daşıyır; bu yüksək rəqəm modelin hər iki sinifdə eyni dərəcədə uğurlu olması deyil, yalnız dominant çoxluğu yaxşı tanıması hesabına formalaşmışdır.

Digər tərəfdən, proqnoz dəqiqliyinin (Precision) 76% olması modelin xəbərdarlıq etdiyi hallarda kifayət qədər haqlı olduğunu göstərsə də, Tamlıq (Recall) göstəricisinin 47% səviyyəsində qalması biznes perspektivindən ciddi boşluqlar yaradır. Bank üçün əsas strateji hədəf potensial itkiləri qabaqcadan aşkarlayıb qarşısını almaq olduğu halda, mövcud model tərk edən müştərilərin yarıdan çoxunu identifikasiya edə bilmir. Bu fakt, gələcək optimallaşdırma işlərində qeyri-bərabər verilənlərin balanslaşdırılması ehtiyacını zəruri edir.




Şəkil 4. Səhv Matrisinin hesablanması üçün kod bloku və əldə olunan vizual nəticə

3.6. Xüsusiyyətlərin vaciblik dərəcəsinin (Feature Importance) analizi

Random Forest modelinin qərarvermə mexanizmini şəffaflaşdırmaq məqsədilə "Feature Importance" funksiyasından istifadə edilmişdir (Şəkil 5).

Analiz nəticəsində müəyyən olunmuşdur ki, müştərinin yaşı (age) proqnozlaşdırmada ən dominant dəyişən kimi çıxış edir. Bu, yaş qrupları ilə bankı tərk etmə ehtimalı arasında güclü asılılığın olduğunu və demoqrafik segmentasiyanın zəruriliyini sübut edir. Yaş faktorunu ardıcıl olaraq estimated_salary (təxmini əməkhaqqı), credit_score (kredit reytingi), balance (hesab qalığı) və products_number (istifadə edilən məhsul sayı) kimi baza maliyyə göstəriciləri izləyir. Bu dörd dəyişənin bir-birinə çox yaxın olması, müştərinin ümumi iqtisadi profilinin və bankla olan əməliyyat dərinliyinin proqnoz dəqiqliyindəki kompleks rolunu təsdiqləyir. tenure (bankda müştəri kimi qalma müddəti) və active_member (aktivlik statusu) kimi amillər model tərəfindən nəzərə alınsa da, onların həlledici təsiri nisbətən məhduddur. Ən diqqətçəkən məqam isə coğrafi yerləşmə (country_Germany, country_Spain), cinsiyyət (gender_Male) və credit_card kimi faktorların məlumat bazasında mövcudluğuna baxmayaraq, alqoritmin yekun qərarına təsirinin statistik baxımdan demək olar ki, yox dərəcəsində olmasıdır.

Bu nəticələr həm gələcəkdə modelin optimallaşdırılması (ölçüsünün kiçildilərək yalnız ən vacib 5-6 variativliyə cəmlənməsi), həm də bankın risk menecmenti siyasətində hədəfli tədbirlərin görülməsi üçün konkret elmi əsaslar formalaşdırır.



Şəkil 5. Müştəri itkisinə təsir edən amillərin vaciblik dərəcəsinin hesablanması və vizuallaşdırılması

3.7. Support Vector Machines (SVM) alqoritminin tətbiqi və verilənlərin miqyaslandırılması

Tədqiqatın növbəti mərhələsində bank müştərilərinin itki riskini proqnozlaşdırmaq üçün alternativ metod olaraq SVM alqoritmi tətbiq edilmişdir. SVM-in seçilməsi, onun çoxölçülü məlumat fəzasında optimal qərar sərhədlərini (hyperplane) müəyyən etmək qabiliyyəti ilə əsaslandırılır. Bu model vasitəsilə əldə olunan nəticələrin RF modeli ilə müqayisəli analizi hədəflənmişdir.

RF-dən fərqli olaraq, SVM alqoritmi çoxölçülü məkanda nöqtələr arasındakı məsafələrə əsaslandığı üçün verilənlərin eyni miqyasa gətirilməsi tələb olunur. Bu məqsədlə StandardScaler metodundan istifadə edilərək təlim və test dəstləri standartlaşdırılmışdır.


Tədqiqatda xətti ayrılma sərhədini müəyyən etmək üçün Linear Kernel seçilmişdir. Proses aşağıdakı kod strukturu ilə reallaşdırılmışdır:

```
# SVM üçün datanın miqyaslanması (Standardization)
scaler = StandardScaler()
X_train_scaled = scaler.fit_transform(X_train)
X_test_scaled = scaler.transform(X_test)

# SVM modelinin qurulması
svm_model = SVC(kernel='linear', random_state=42)
```



```
svm_model.fit(X_train_scaled, y_train)
```



Şəkil 6. Linear Kernel ilə SVC model quruluşu

```
# Proqnozların əldə edilməsi
```

```
y_pred_svm = svm_model.predict(X_test_scaled)
```

Bu kod bloku modelin müxtəlif ölçü vahidlərinə malik dəyişənləri (məsələn, yaş və əməkhaqqı) bərabər çəkiddə qiymətləndirməsinə şərait yaradır və proqnoz dürüstlüyünü optimallaşdırır. [2, 6]

3.8. SVM modelinin analizi və performans qiymətləndirilməsi

Tədqiqatın yekun mərhələsində SVM alqoritmi üzrə əldə olunan nəticələr (Şəkil 7), modelin ümumi performansının RF alqoritmi ilə müqayisədə kəskin fərqləndiyini göstərir. SVM modelinin ümumi dəqiqlik göstəricisi 80% səviyyəsində qeydə alınsa da, "Classification Report" hesabatının detallı təhlili alqoritmin ciddi bir çatışmazlığını ortaya qoyur: model bankı tərk edən müştəriləri (Sinif 1) aşkar etmək qabiliyyətinə (Recall) malik deyil və bu göstərici 0.00-a bərabərdir.

```
print(f"Ümumi Dəqiqlik (Accuracy): {accuracy_score(y_test, y_pred_svm):.2f}")
```

```
print(classification_report(y_test, y_pred_svm))
```

Bu nəticə bank sektoruna aid məlumat bazalarında müşahidə olunan sinif qeyri-bərabərliyinin (imbalanced data) xətti SVM alqoritmi üzərindəki mənfi təsirini elmi şəkildə nümayiş etdirir. Model bütün müştəriləri "bankda qalan" (Sinif 0) kimi proqnozlaşdıraraq süni bir dəqiqlik formalaşdırmış, lakin biznes baxımından ən kritik olan "itki" qrupunu tamamilə qaçırmışdır. Müqayisə üçün qeyd edilməlidir ki, RF modeli həm ümumi dəqiqlikdə (87%), həm də gedəcək müştərilərin aşkarlanmasında (Recall: 47%) SVM-dən daha effektiv nəticələr nümayiş etdirmişdir. Beləliklə, aparılan təcrübələr təsdiq edir ki, bank müştərilərinin davranışı kimi mürəkkəb və qeyri-xətti asılılıqların olduğu tapşırıqlarda Random Forest alqoritmi SVM-ə nisbətən daha etibarlı və tətbiqi əhəmiyyətli proqnozlar təqdim edir.

SVM modelinin nəticələri:				
Ümumi Dəqiqlik (Accuracy): 0.80				
Ətraflı Hesabat:				
	precision	recall	f1-score	support
0	0.80	1.00	0.89	1607
1	0.00	0.00	0.00	393
accuracy			0.80	2000
macro avg	0.40	0.50	0.45	2000
weighted avg	0.65	0.80	0.72	2000

Şəkil 7. SVM modelinin performans metrikləri (Classification Report)

3.9. Statistik əsaslı Logistic Regression (LR) modelinin tətbiqi və analizi

Müştəri itkisini proqnozlaşdırmaq üçün klassik statistik metod olan Logistic Regression (LR) alqoritmi tətbiq edilmişdir (Şəkil 8). LR modelinin seçilməsinə səbəb, ikili təsnifat (binary classification) tapşırıqlarında asılı və asılı olmayan dəyişənlər arasındakı ehtimal əlaqələrini riyazi olaraq izah etmək qabiliyyətidir. SVM modelində olduğu kimi, LR alqoritmi də verilənlərin

miqyasına qarşı həssas olduğu üçün təlim prosesi standartlaşdırılmış (scaled) verilənlər bazası üzərində icra olunmuşdur.

Eksperimentin nəticələrinə əsasən, LR modeli 81% ümumi dəqiqlik (Accuracy) nümayiş etdirmişdir. Performans metriklərinin təhlili göstərir ki, bu model bankı tərk edən müştəriləri (Sinif 1) müəyyən etməkdə SVM alqoritmindən daha effektivdir (Recall: 0.20). Lakin, RF modeli ilə müqayisədə həm ümumi dəqiqlik, həm də həssaslıq (Recall) göstəriciləri əhəmiyyətli dərəcədə aşağıdır.

Bu müqayisəli nəticə bir daha təsdiq edir ki, bank müştərilərinin davranışları xətti statistik asılılıqlardan daha mürəkkəbdir. Klassik statistik metodların və xətti modellərin (SVM, LR) çatışmazlıqları fonunda, ansambl (ensemble) metodlarının (RF) nümayiş etdirdiyi yüksək effektivlik, bu tip qeyri-xətti tapşırıqlar üçün ən optimal seçimin mürəkkəb ML alqoritmləri olduğunu elmi şəkildə sübut edir. [4]

```
from sklearn.linear_model import LogisticRegression

# 1. Modelin yaradılması
lr_model = LogisticRegression(random_state=42)

# 2. Modelin təlim edilməsi
lr_model.fit(X_train_scaled, y_train)

# 3. Proqnozların verilməsi
y_pred_lr = lr_model.predict(X_test_scaled)

# 4. Nəticələrin çap olunması
print("Logistic Regression modelinin nəticələri:")
print(f"Ümumi Dəqiqlik (Accuracy): {accuracy_score(y_test, y_pred_lr):.2f}")
print("\nƏtraflı Hesabat:")
print(classification_report(y_test, y_pred_lr))
```

Logistic Regression modelinin nəticələri:
Ümumi Dəqiqlik (Accuracy): 0.81

Ətraflı Hesabat:

	precision	recall	f1-score	support
0	0.83	0.96	0.89	1607
1	0.55	0.20	0.29	393
accuracy			0.81	2000
macro avg	0.69	0.58	0.59	2000
weighted avg	0.78	0.81	0.77	2000

Şəkil 8. Logistic Regression modelinin qurulması və performans göstəriciləri

3.10. Eksperimental mühit və hesablama resurslarının monitorinqi

Maşın öyrənməsi (ML) modellərinin performansını həm proqnoz dəqiqliyi, həm də sistem resurslarından istifadə səmərəliliyi baxımından qiymətləndirmək üçün xüsusi eksperimental mühit hazırlanmışdır (Şəkil 9). Modellərin hesablama səmərəliliyini qiymətləndirmək üçün psutil və time kitabxanaları vasitəsilə operativ yaddaş (RSS (Resident Set Size), MB) və icra müddəti monitorinq edilmişdir. Tədqiqatda obyektivliyi təmin etmək üçün bütün alqoritmlər vahid sınaq mühitində (models_to_test) qruplaşdırılmış, nəticələrin təkrarlana bilənliyi üçün *random_state=42* parametridən istifadə olunmuşdur. Bu infrastruktur modellərin təkcə proqnoz dəqiqliyini deyil, həm də bankın real server mühitində tətbiqi üçün resurs səmərəliliyini elmi cəhətdən əsaslandırır. RF modeli üçün təyin edilmiş *n_estimators=100* parametri, proqnoz dəqiqliyi ilə hesablama yükü arasında optimal balans nöqtəsi kimi seçilmişdir. Bu infrastruktur, modellərin təkcə riyazi uğurunu deyil, həm də bankın real server mühitində tətbiq edilə biləcəyi resurs səmərəliliyini elmi əsaslarla sübuta yetirir. [3]

```

import time
import psutil
import os
import pandas as pd
from sklearn.ensemble import RandomForestClassifier
from sklearn.svm import SVC
from sklearn.linear_model import LogisticRegression

# Sistem resurslarını ölçmək üçün köməkçi funksiya
def get_memory_usage():
    process = psutil.Process(os.getpid())
    return process.memory_info().rss / (1024 * 1024) # Modelin istifadə etdiyi yaddaş miqdarının Baytdan (B) Megabayta (MB) çevirilməsi

# Analiz üçün seçilmiş ML alqoritmlərinin konfigurasiyası
models_to_test = {
    "Random Forest": RandomForestClassifier(n_estimators=100, random_state=42),
    "SVM (Linear)": SVC(kernel='linear', random_state=42),
    "Logistic Regression": LogisticRegression(random_state=42)
}

```

Şəkil 9. Modellərin performans analizi üçün proqram təminatının arxitekturası

3.11. Modellərin hesablama performansı və resurs səmərəliliyinin analizi

Tədqiqatın yekun mərhələsində maşın öyrənməsi alqoritmlərinin real iş şəraitindəki effektivliyini ölçmək üçün avtomatlaşdırılmış performans monitorinqi sistemi tətbiq edilmişdir (Şəkil 10). Obyektiv müqayisəni təmin etmək məqsədilə hər üç model ardıcıl olaraq vahid əməliyyat mühitində sınaqdan keçirilmiş və aşağıdakı performans göstəriciləri üzrə qiymətləndirmə aparılmışdır:

Zamanın idarəsi: `time.time()` funksiyası vasitəsilə alqoritmlərin tarixi verilənləri mənimsəmə (təlim) və yeni müştəri sorğularına cavab vermə (proqnoz) müddətləri mikrosaniyə dəqiqliyi ilə ölçülmüşdür.

Yaddaş (RAM) Səmərəliliyi: Modellərin aktiv hesablama apardığı zaman yaratdıqları fiziki yük, təlimdən əvvəlki və sonrakı yaddaş göstəricilərinin fərqi (`abs(mem_after - mem_before)`) əsasında hesablanmışdır.

Processor (CPU) Yüku: Alqoritmlərin riyazi mürəkkəbliyini və hesablama nüvələrindən istifadə intensivliyini müəyyən etmək üçün `psutil.cpu_percent` əmri ilə real zamanlı prosessor yükü faizlə qeydə alınmışdır.

Eksperiment zamanı toplanmış bu çoxölçülü kəmiyyət göstəriciləri `pandas.DataFrame` strukturuna ötürülərək vahid akademik müqayisə matrisinə çevrilmişdir. Bu analiz nəticəsində bankın proqnozlaşdırma sistemləri üçün həm yüksək dəqiqlikli (Random Forest), həm də aşağı resurs tələbli (Logistic Regression) alternativlərin kəmiyyət əsaslandırması təmin edilmişdir.

```

performance_data = {}

print("Analiz başladı, zəhmət olmasa gözləyin...")

for name, model in models_to_test.items():
    # Başlanğıc resurslar
    mem_before = get_memory_usage()

    # TƏLİM MÜDDƏTİ
    start_train = time.time()
    if "Random Forest" in name:
        model.fit(X_train, y_train)
    else:
        model.fit(X_train_scaled, y_train)
    end_train = time.time()

    # PROQNOZ SÜRƏTİ
    start_pred = time.time()
    model.predict(X_test if "Random Forest" in name else X_test_scaled)
    end_pred = time.time()

    # Son resurslar
    mem_after = get_memory_usage()
    cpu_usage = psutil.cpu_percent(interval=0.1)

    performance_data[name] = {
        "Təlim (san)": round(end_train - start_train, 4),
        "Proqnoz (san)": round(end_pred - start_pred, 4),
        "RAM Sərfi (MB)": round(abs(mem_after - mem_before), 2),
        "CPU Yüku (%)": cpu_usage
    }

# Yekun cədvəlin çap olunması
final_perf_df = pd.DataFrame(performance_data).T
print("\n--- DİSSERTASIYA İŞİ ÜÇÜN PERFORMANS ANALİZİ ---")
print(final_perf_df)

```

Şəkil 10. Modellərin zaman və resurs səmərəliliyini ölçən performans analizi dövrü

3.12. Modellərin kəmiyyət analizi və performans nəticələri

Tədqiqatın yekun mərhələsində alqoritmlərin hesablama performansı üzrə əldə olunan rəqəmlər bank mühiti üçün mühüm texniki nəticələr ortaya qoyur (Şəkil 11):

Zaman və sürət faktoru: LR 0.0011 saniyəlik proqnoz sürəti ilə mütləq liderdir. RF mürəkkəb strukturuna rəğmən qənaətbəxş sürət (0.0658 san) nümayiş etdirdiyi halda, SVM isə, proqnoz (0.25 san) müddətinə görə ən yavaş alqoritmədir. Təlim müddətlərində isə, LR alqoritmə digər iki alqoritmədən bir daha öndədir (0.0186 san). RF modelə isə, mürəkkəb strukturu səbəbindən buradakı ən aşağı nəticəyə malikdir (2.2640 san).

Resurs səmərəliliyi: Ən yüksək RAM sərfi RF modelində (17.02 MB) müşahidə edilsə də, bu göstərici müasir server infrastrukturuna üçün tamamilə məqbuldur. LR cəmi 0.70 MB RAM istifadəsi ilə ən "yüngül" alqoritmədir.

CPU yükü və optimallaşdırma: RF modelə RAM-dan geniş istifadə edərək prosessor üzərinə düşən yükü (6.3%) minimuma endirmişdir. LR isə sürətli olmasına baxmayaraq, CPU-nu daha intensiv (13.8%) yükləyir. Bu hal kompüter elmlərindəki "Yaddaş-Zaman mübadiləsi" (Space-Time tradeoff) prinsipinin praktik sübutudur.

Kəmiyyət göstəriciləri və proqnoz dəqiqliyi (Accuracy) birlikdə qiymətləndirildikdə, Random Forest modelə bank müştəri itkisi analizi üçün ən optimal və balanslı arxitektura kimi müəyyən edilmişdir. [3]

```
Analiz başladı, zəhmət olmasa gözləyin...
```

--- DISSERTASIYA İŞİ ÜÇÜN PERFORMANS ANALİZİ ---				
	Təlim (san)	Proqnoz (san)	RAM Sərfi (MB)	CPU Yükü (%)
Random Forest	2.2640	0.0658	17.02	6.3
SVM (Linear)	1.9071	0.2571	1.75	10.8
Logistic Regression	0.0186	0.0011	0.70	13.8

Şəkil 11. Performans analizi nəticələri

4. NƏTİCƏ

Aparılan tədqiqat çərçivəsində bank müştərilərinin davranışlarını proqnozlaşdırmaq üçün üç fərqli maşın öyrənməsi alqoritmi (Random Forest, SVM, Logistic Regression) müqayisəli şəkildə təhlil edilmişdir. Təcrübələr göstərir ki, Random Forest modeli 87% ümumi dəqiqliklə digər modelləri geridə qoyaraq, həm proqnoz dürüslüyü, həm də hesablama resurslarından istifadə səmərəliliyi baxımından ən optimal nəticəni təmin edir. Müştərinin yaşı və maliyyə vəziyyəti itki riskinin müəyyən edilməsində həlledici faktorlar kimi aşkar olunmuşdur. Gələcək tədqiqatlarda verilənlərin balanslaşdırılması texnikalarından istifadə etməklə modelin aşağı sinifləri (tərk edən müştəriləri) aşkarlama qabiliyyətinin artırılması hədəflənir.

ƏDƏBİYYAT SIYAHISI

- [1] Breiman, L. (2001). Random Forests. *Machine Learning*, 45(1), 5-32
- [2] Cortes, C., & Vapnik, V. (1995). Support-vector networks. *Machine Learning*, 20(3), 273-297
- [3] Giampaolo, R. (2026). *psutil: Cross-platform lib for process and system monitoring in Python*
- [4] Hosmer, D. W., & Lemeshow, S. (2000). *Applied Logistic Regression*. Wiley-Interscience.
- [5] McKinney, W. (2010). Data Structures for Statistical Computing in Python. *Proceedings of the 9th Python in Science Conference*, 51-56
- [6] Pedregosa, F., et al. (2011). Scikit-learn: Machine Learning in Python. *Journal of Machine Learning Research*, 12, 2825-2830
- [7] Fawcett, T. (2006). An introduction to ROC analysis. *Pattern Recognition Letters*, 27(8), 861-874

Agricultural Sciences

Transformation of Poti Coastal Ecosystem: Impact of Eutrophication on Biodiversity and Recreational Potential

Marina Macharashvili

Associate Professor at the Georgian Technical University; Senior Researcher at the Tsotne Mirtskhulava Water Management Institute of the same university.

Olga Kharaishvili

Associate Professor at the Georgian Technical University; Senior Researcher at the Tsotne Mirtskhulava Water Management Institute of the same university.

Erekle Kecxoshvili

Georgian Technical University; Senior Researcher at the Tsotne Mirtskhulava Water Management Institute of the same university.

Maia Kikabidze

Associate Professor at the Georgian Technical University; Researcher at the Tsotne Mirtskhulava Water Management Institute of the same university.

Lali Baidauri

Associate Professor at the Georgian Technical University.

Ketevan Rokva

Associate Professor at the Georgian Technical University.

Natia Sukhishvili

Associate Professor at the Georgian Technical University.

Tamtam Natenadze

Master of Agricultural Sciences and Chemical Technology at the Georgian Technical University.

Tsisia Kobaladze

Master of Agricultural Sciences and Chemical Technology at the Georgian Technical University.

Ucha Jagodnishvili

Undergraduate student of Agricultural Sciences and Chemical Technology at the Georgian Technical University.

Nika Keburia

Master of Agricultural Sciences and Chemical Technology at the Georgian Technical University.

Abstract

This article explores the processes of anthropogenic eutrophication occurring in the Poti coastal zone (eastern part of the Black Sea). The paper analyzes the impact of the Rioni River runoff and urban pressure on water quality. Based on field-visual monitoring, hotspots of hyperproduction of opportunistic algae (e.g., *Ulva lactuca*) have been identified. The study highlights the negative

impact of ecosystem degradation on the region's recreational potential and offers preventive recommendations.

Keywords: Poti, Black Sea, eutrophication, algae, Rioni, biodiversity, Maltakva.

Introduction)

The Poti coastal zone represents a unique estuarine environment where the fresh water of the Rioni River meets the Black Sea [1]. This ecosystem plays a strategic role in the sea's self-purification process. However, in recent decades, anthropogenic pressure, specifically the intensification of agriculture and faulty sewage systems, has become the main factor in the deterioration of water quality [2]. Eutrophication, or excessive nutrient enrichment of water, is currently the primary ecological challenge for the region, directly impacting local biodiversity and recreational potential [3].

Research Methodology

The subject of the study consisted of three sectors of the Poti water area:

- **Point A:** Mouth of the Rioni River;
- **Point B:** Sea Port;
- **Point C:** Maltakva recreational zone.



Fig. 1 General view of the Rioni River mouth and Poti water area, with research points.

At the given location of the Rioni River mouth and the Poti water area, intensive dynamics of fresh and salt waters are observed. The photo clearly shows a high degree of water turbidity, caused by suspended particles and organic matter carried down by the river. For this reason, this specific point (**Point A**) was selected within the scope of the study as the main source of nitrate inflow.




Fig. 2. General view of the study area, Poti.

It should be noted that these processes are also characteristic of other strategic points of the Black Sea. Specifically, the northwestern part of the Black Sea is most sensitive to such pollution under the influence of major rivers like the Danube and the Dnieper [1, 2]. The example of the Poti water area demonstrates the relevance of this issue in our region.

The study is based on a complex hydrobiological approach. The methodology includes field-visual monitoring and organoleptic analysis [8]. The transect method was used to study the distribution area of phytobenthos (algae). One of the main research tools was photo-documentation, which allows for a visual assessment of the scale of biomass accumulation. During data processing, the principle of comparative analysis was applied, taking into account international standards for Black Sea ecological monitoring [4, 5].

Research Results and Analysis

Monitoring revealed a clear correlation between the Rioni River runoff and the excessive accumulation of algae on the coast. (The primary data recorded during the study are reflected in Tables 1 and 2).

Table №1: Comparative Characterization of Hydrochemical Parameters

Study Point	Oxygen (mg/L)	Nitrates (mg/L)	Phosphates (mg/L)	Transparency(m)
A (Rioni Mouth)	4.5	0.75	0.25	0.5
B (Sea Port)	3.2	0.50	0.18	1.1
C (Maltakva Zone)	5.1	0.40	0.12	1.8
Control Standard	> 6.0	< 0.1	< 0.05	> 3.0




Fig. 3. Point A (Rioni Mouth) – Rioni Turbidity

The provided photo material (Fig. 3) clearly shows the water surface, where turbidity and "blooming" are visible. The high concentration of nitrates (0.75 mg/L) at Point A (Table 1) confirms that the Rioni River is the primary source of nutrient elements [9].




Fig. 4. Point B: Sea Port;

The condition of the water surface adjacent to the Poti Seaport captures a stagnant state and signs of excessive phytoplankton reproduction. The low oxygen level recorded at Point B (3.2 mg/L) indicates acute hypoxia.



Fig. 5. Point C: Maltakva Recreational Zone.

Visual inspection reveals that water transparency has been reduced to a minimum (0.5–1.1 meters), which is directly related to the hydrochemical parameters and oxygen deficiency presented in Table №1.

Table №2: Distribution of Phytobenthos Biomass

Algae Species	Point A	Point B	Point C
Sea Lettuce (<i>Ulva lactuca</i>) (Green)	0.8	2.5	4.5
Wandering Cladophora (<i>Cladophora vagabunda</i>)	2.2	1.5	1.8
Other Species	0.5	1.8	0.9
Total Biomass	3.5	5.8	7.2

In the **Maltakva recreational zone**, a record biomass of *Ulva lactuca* (4.5 kg/m²) was recorded, indicating a sharp change in the ecosystem's trophic status [7].



Fig. 3. Massive accumulation of green algae (*Ulva lactuca*) in the Maltakva recreational zone.

The photo material clearly shows the massive accumulation of green algae (*Ulva lactuca*) in the Maltakva recreational zone. A thick, slimy layer of algae covers a significant part of the coastline. Such a high concentration of biomass (7.2 kg/m^2) leads to the formation of an anoxic environment. The decaying plant matter emits a specific odor caused by hydrogen sulfide emissions. This photo represents the most visible and negative consequence of eutrophication for the Poti coastal zone. It should be noted that the value of $4.5 \text{ [kg/m}^2 \text{ for } Ulva \text{ lactuca]}$ indicates a sharp change in the trophic status of the ecosystem [7].

Ecological and Recreational Damage

Visual inspection reveals that in the Maltakva zone, a thick, slimy layer of algae covers a significant part of the coastline. The high concentration of biomass (totaling 7.2 kg/m^2) leads to the formation of an anoxic environment. The decaying mass emits hydrogen sulfide (H_2S), which creates a specific unpleasant odor and nullifies the region's tourist appeal.

It is noteworthy that within the framework of the joint project between the European Union and Georgia (EMBLAS), water quality is being monitored using modern technologies (sensors), which confirms the relevance of this issue [2].



Fig 5. Joint European Union and Georgia Black Sea Monitoring

Ecological Monitoring: The European Union and Georgia jointly continue the monitoring of the Black Sea (EMBLAS project). The novelty is that water quality is now being observed with more modern technologies (sensors installed on ships), including in the vicinity of the Poti Port [2].

Conclusions and Recommendations

Based on the conducted research, we can conclude that the Poti coastal zone is in a state of hyper-eutrophication [6]. To improve the situation, it is essential to:

Modernization: Full renovation of Poti's municipal wastewater treatment plants.

Regulation: Strict control over the use of agricultural fertilizers in the Rioni basin [9].

Bioremediation: Creation of artificial mussel plantations to act as natural biofilters to improve water quality [10].

References

1. Komakhidze, A., & Mazmanidi, N. (2002). *Ecological State of the Black Sea*. Batumi: "Adjara".
2. Gogitidze, M. (2018). *Biodiversity of the Georgian Coastal Zone*. Tbilisi: Metsniereba.
3. Black Sea Commission (2020). *Report on the Ecological Status of the Black Sea*. Istanbul.
4. Zaitsev, Y. P. (2012). *Marine Algae and Seagrasses of the Black Sea*. Odessa: Even.
5. Oguz, T. (2015). *Eutrophication of the Black Sea: Causes and Consequences*. MEPS.
6. Vollenweider, R. A. (1998). *Characterization of the trophic conditions of marine waters*. JCR.
7. Bologa, A. S. (2001). *Present state of seaweed communities along the Black Sea coast*. MMS.
8. National Environmental Agency (2022). *Black Sea Monitoring Bulletin*. Tbilisi.
9. EU Nitrates Directive (91/676/EEC). *Protection of waters against pollution*.
10. Mee, L. D. (2006). *Reviving the Black Sea*. Scientific American.

Balıq konservlərinin istehlak xassələrinin formalaşmasının nəzəri əsasları

Sevinc Tağıyeva

Magistrant, Azərbaycan Dövlət İqtisad Universiteti

Xülasə

Balıq və balıq məhsulları insan qidalanmasında mühüm yer tutan yüksək qida dəyərinə malik ərzaq məhsullarıdır. Xüsusilə balıq konservləri uzunmüddətli saxlanma, istifadəyə hazır olma və qida dəyərinin qorunması baxımından geniş yayılmışdır. Bu məqalədə balıq konservlərinin istehlak xassələrinin formalaşmasının nəzəri əsasları kompleks şəkildə təhlil edilmişdir. Tədqiqat çərçivəsində balıq xammalının kimyəvi tərkibi, texnoloji emal mərhələləri, konservləşdirmə prosesləri, fiziki-kimyəvi və orqanoleptik göstəricilər, həmçinin məhsulun təhlükəsizlik və saxlanma xüsusiyyətləri araşdırılmışdır. Müəyyən edilmişdir ki, balıq konservlərinin istehlak xassələrinin formalaşması çoxsaylı amillərin – xammalın keyfiyyəti, texnoloji proseslər, istifadə olunan əlavə komponentlər və saxlanma şəraitinin qarşılıqlı təsiri nəticəsində baş verir. Eyni zamanda, dövlət standartları və normativ sənədlərin bu prosesdə mühüm rol oynadığı göstərilmişdir. Məqalədə həm Azərbaycan, həm də beynəlxalq elmi mənbələrə əsaslanaraq balıq konservlərinin keyfiyyətinin formalaşması mexanizmləri izah edilmişdir.

Açar sözlər: *Balıq konservləri, istehlak xassələri, keyfiyyət göstəriciləri, konservləşdirmə texnologiyası, qida təhlükəsizliyi*

Giriş

Müasir dövrdə qida sənayesində konservləşdirilmiş məhsulların rolu əhəmiyyətli dərəcədə artmışdır. Bu baxımdan balıq konservləri həm qida təhlükəsizliyi, həm də əhalinin zülal və digər vacib qida maddələri ilə təmin olunmasında mühüm yer tutur. Balıq məhsullarının yüksək bioloji dəyəri onların insan rasionunda geniş istifadə olunmasına səbəb olur. Balıq ətinin tərkibində zülallar, yağlar, vitaminlər və mineral maddələr yüksək miqdarda mövcuddur və bu maddələr insan orqanizmi tərəfindən asan mənimsənilir.

Balıq məhsullarının tez xarab olması onların saxlanması və daşınması zamanı ciddi problemlər yaradır. Bu səbəbdən konservləşdirmə üsulu balıq məhsullarının uzun müddət keyfiyyətini qoruyaraq istifadəyə yararlı saxlanmasını təmin edən əsas texnoloji üsullardan biridir. Konservləşdirilmiş balıq məhsulları yalnız saxlanma müddətinin uzadılması baxımından deyil, həm də dad, aroma və qida dəyərinin qorunması baxımından mühüm üstünlüklərə malikdir [2].

Balıq konservlərinin istehlak xassələrinin formalaşması kompleks bir prosesdir və bu proses xammalın xüsusiyyətlərindən başlayaraq son məhsulun qablaşdırılması və saxlanmasına qədər bütün texnoloji mərhələləri əhatə edir. Bu baxımdan mövzunun öyrənilməsi həm nəzəri, həm də praktiki əhəmiyyət kəsb edir.

Əsas hissə

Balıq konservlərinin istehlak xassələrinin formalaşmasının nəzəri əsaslarını anlamaq üçün ilk növbədə balıq xammalının xüsusiyyətləri və onun kimyəvi tərkibi nəzərə alınmalıdır. Balıq əti yüksək bioloji dəyərə malik olub, əvəzolunmaz amin turşuları ilə zəngindir. Bu xüsusiyyət balıq məhsullarının insan orqanizmi tərəfindən daha yaxşı mənimsənilməsinə təmin edir. Balıq ətində olan yağlar, xüsusilə omega-3 yağ turşuları, insan sağlamlığı üçün böyük əhəmiyyət daşıyır və ürək-damar xəstəliklərinin profilaktikasında mühüm rol oynayır [3].

Balıq konservlərinin istehlak xassələrinin formalaşmasında əsas mərhələlərdən biri texnoloji emal prosesidir. Bu prosesə xammalın seçilməsi, təmizlənməsi, duzlanması, istilik emalı

və sterilizasiya daxildir. Balıq konservlərinin istehsalı zamanı balıq əvvəlcə yeyilməyən hissələrdən təmizlənir, yuyulur və müəyyən texnoloji proseslərdən keçirilir. Daha sonra məhsul bankalara yerləşdirilir, hermetik bağlanır və yüksək temperaturda sterilizasiya olunur. Sterilizasiya prosesi məhsulun mikrobioloji təhlükəsizliyini təmin edir və onun saxlanma müddətini artırır.

Texnoloji proseslər zamanı xammalın fiziki və kimyəvi xassələri dəyişir və yeni keyfiyyət xüsusiyyətləri formalaşır. Bu dəyişikliklər nəticəsində məhsulun dadı, qoxusu, rəngi və teksturası formalaşır. Xammalın keyfiyyəti aşağı olduqda isə son məhsulda müxtəlif qüsurlar yarana bilər. Bu səbəbdən yüksək keyfiyyətli xammalın seçilməsi istehlak xassələrinin formalaşmasında əsas şərtlərdən biridir [5].

Balıq konservlərinin istehlak xassələrini müəyyən edən əsas göstəricilər orqanoleptik, fiziki-kimyəvi və mikrobioloji göstəricilərdir. Orqanoleptik göstəricilərə məhsulun görünüşü, rəngi, qoxusu, dadı və konsistensiyası daxildir. Bu göstəricilər məhsulun istehlakçı tərəfindən qəbul olunmasında mühüm rol oynayır.

Fiziki-kimyəvi göstəricilər isə məhsulun tərkibini və keyfiyyətini xarakterizə edir. Bu göstəricilərə zülal, yağ, su, duz və digər komponentlərin miqdarı daxildir. Bu parametrlər məhsulun qida dəyərini və saxlanma stabilliyini müəyyən edir. Balıq konservlərinin tərkibindəki qida maddələrinin balansı onların enerji dəyərini və faydalılığını müəyyən edir.

Mikrobioloji göstəricilər isə məhsulun təhlükəsizliyini təmin edən əsas amillərdən biridir. Sterilizasiya prosesinə baxmayaraq, məhsulda mikroorqanizmlərin inkişafı ehtimalı mövcud ola bilər. Bu səbəbdən məhsulun istehsalı zamanı ciddi sanitariya-gigiyenik qaydalara riayət edilməlidir. Dövlət standartlarında mikrobioloji analizlərin aparılması üçün konkret metodlar müəyyən edilmişdir [4].

Balıq konservlərinin istehlak xassələrinin formalaşmasında istifadə olunan əlavə komponentlərin də rolu böyükdür. Konservlərin hazırlanmasında bitki yağları, tomat sousu, ədviyyatlar və digər əlavələr istifadə olunur. Bu komponentlər məhsulun dadını, aromasını və qida dəyərini artırır. Məsələn, tomat sousunda hazırlanan balıq konservləri əlavə kulinar emal tələb etmədən istehlak oluna bilər və yüksək dad keyfiyyətlərinə malikdir [1].

Saxlanma şəraiti də balıq konservlərinin istehlak xassələrinin qorunmasında mühüm rol oynayır. Konserv məhsulları müəyyən temperatur və rütubət şəraitində saxlanmalıdır. Məsələn, balıq konservlərinin optimal saxlanma temperaturu 0–15°C aralığında olmalıdır və nisbi rütubət 70–75% səviyyəsində saxlanmalıdır. Bu şərtlərə riayət olunmadıqda məhsulun keyfiyyəti pisləşə və təhlükəli hala düşə bilər.

Müasir dövrdə balıq konservləri bazarında istehlakçıların tələbləri dəyişməkdədir. İstehlakçılar daha çox istifadəyə hazır, yüksək keyfiyyətli və təhlükəsiz məhsullara üstünlük verirlər. Bu səbəbdən istehsalçılar texnologiyaların təkmilləşdirilməsinə və məhsul keyfiyyətinin artırılmasına xüsusi diqqət yetirirlər [6].

Nəticə

Aparılan tədqiqat nəticəsində müəyyən edilmişdir ki, balıq konservlərinin istehlak xassələrinin formalaşması çoxşaxəli və kompleks bir prosesdir. Bu proses xammalın keyfiyyəti, texnoloji emal mərhələləri, istifadə olunan əlavə komponentlər, saxlanma şəraiti və normativ tələblərin qarşılıqlı təsiri nəticəsində formalaşır. Balıq konservlərinin yüksək keyfiyyətə malik olması üçün bütün bu amillərin optimal şəkildə idarə olunması zəruridir.

Ədəbiyyat siyahısı

1. Azərbaycan Qida Təhlükəsizliyi Agentliyi (AQTA). (2021). Balıq istehlakı zamanı yaranan risklər və təhlükəsizlik qaydaları.
2. Axundova, N. Ə., & Qədimova, N. S. (2019). Balıq və balıq məhsullarının texnologiyası. Bakı: Azərbaycan Dövlət İqtisad Universiteti nəşriyyatı.
3. Rzayeva, E. K. (2018). Qida məhsullarının keyfiyyət ekspertizası. Bakı: UNEC.
4. Azərbaycan Dövlət Statistika Komitəsi. (2022). Balıqçılıq və balıq məhsulları üzrə statistik göstəricilər. Bakı: DSK.
5. Huss, H. H. (1995). Quality and quality changes in fresh fish. Rome: FAO Fisheries Technical Paper No. 348.
6. GOST 7452-2014. (2014). Canned fish, preserved fish and fish products. General specifications. Moscow: Interstate Council for Standardization, Metrology and Certification.

Chemical Sciences

DESIGNING CREATIVE LEARNING ENVIRONMENTS FOR CHEMISTRY EXAM READINESS: A BIBLIOMETRIC ANALYSIS

Matchanova K.

Master's student, Chemistry, Kazakh National Women's Teacher Training University, Almaty, Kazakhstan

Kuanisheva Zh. K.

Candidate of Pedagogical Sciences, Acting Associate Professor, Kazakh National Women's Teacher Training University, Almaty, Kazakhstan

Abstract

This study examines global research trends in the design of creative learning environments for chemistry exam readiness through a bibliometric approach. The increasing demands of high-stakes assessments, combined with the need to develop higher-order cognitive skills, have intensified the importance of integrating creativity, inquiry-based learning, and digital technologies into chemistry education. Despite the growing body of literature in this field, there remains a lack of systematic analyses focusing on the intersection of creative pedagogy and exam-oriented learning. To address this gap, a bibliometric analysis was conducted based on data retrieved from the Scopus database, following the PRISMA framework. The study employed quantitative and network-based methods using the *bibliometrix* package in RStudio and VOSviewer to analyze publication trends, collaboration patterns, and the conceptual structure of the research field. The findings reveal a rapidly expanding research domain characterized by a shift toward student-centered, inquiry-based, and technology-enhanced learning environments. Critical thinking, laboratory-based instruction, and digital learning tools emerged as key thematic areas shaping the development of creative educational practices in chemistry. The results also highlight the growing role of artificial intelligence and real-world contextual learning in fostering students' analytical skills. In the context of Kazakhstan, where the Unified National Testing plays a decisive role in shaping educational trajectories, the study underscores the need to move beyond traditional exam-oriented teaching toward more innovative and creativity-driven approaches. The findings provide valuable insights for educators, curriculum developers, and policymakers seeking to enhance the effectiveness of chemistry exam preparation while promoting deeper learning and critical thinking.

Keywords: creative learning environments; chemistry education; exam readiness; bibliometric analysis; critical thinking; inquiry-based learning; digital learning; student-centered learning; chemistry teaching; Unified National Testing

Introduction

Research Relevance. In recent decades, the transformation of educational paradigms has emphasized the importance of developing creative learning environments as a key factor in improving students' academic performance and higher-order thinking skills. Creativity is increasingly recognized as a critical competence in modern education systems, particularly in

STEM disciplines, where problem-solving, analytical reasoning, and innovation are essential for successful learning outcomes (Hernández-Torrano & Ibrayeva, 2020). The growing complexity of knowledge and the demands of the 21st century have led to a shift from traditional, teacher-centered instruction toward more student-centered, inquiry-based, and interactive learning environments. In the context of chemistry education, this shift is especially significant due to the abstract nature of chemical concepts and the challenges students face in mastering both theoretical knowledge and problem-solving skills. Contemporary research highlights that traditional instructional approaches remain largely procedural and insufficient for fostering deep conceptual understanding and exam readiness, particularly in high-stakes testing contexts (Adal et al., 2025). As a result, there is an increasing need to design creative didactic environments that integrate active learning strategies, such as project-based learning, inquiry-based learning, and technology-enhanced instruction. At the same time, the global expansion of research in chemistry education reflects a growing interest in innovative pedagogical approaches. Bibliometric studies demonstrate a significant increase in publications related to learning environments, digital technologies, and creative teaching methods, particularly since the mid-2010s (Lykhopavlo, 2025). These studies reveal a paradigm shift toward hybrid and technology-supported learning environments, including the integration of artificial intelligence, virtual laboratories, and digital platforms, which contribute to more effective and engaging learning experiences.

Furthermore, the application of bibliometric analysis has become an important methodological tool for systematically mapping research trends, identifying dominant themes, and evaluating the evolution of scientific fields. Recent bibliometric studies in education and related domains highlight the growing importance of analyzing research networks, keyword co-occurrence, and publication patterns to better understand the structure and development of academic knowledge (Nuryana et al., 2024). In the field of chemistry education, bibliometric approaches enable researchers to identify emerging directions, including the role of creativity, digitalization, and innovative pedagogy in enhancing students' learning outcomes. Despite the increasing volume of research on creative learning environments and chemistry education, there remains a lack of comprehensive bibliometric studies specifically focused on exam-oriented learning contexts, such as preparation for high-stakes national assessments. This gap is particularly relevant in countries where standardized testing plays a crucial role in determining students' academic and professional trajectories. Therefore, a systematic bibliometric analysis of research on creative learning environments in chemistry exam preparation is both timely and necessary. In this regard, the present study aims to analyze global research trends related to the design of creative learning environments for chemistry exam readiness through a bibliometric approach. By identifying key research directions, influential authors, and emerging themes, this study contributes to the development of more effective and innovative strategies for preparing students for high-stakes chemistry examinations. In the context of Kazakhstan, the relevance of this study is further reinforced by the central role of the Unified National Testing as a high-stakes assessment that determines access to higher education. The exam-oriented nature of the educational system often prioritizes standardized knowledge reproduction over creative and inquiry-based learning, particularly in subjects such as chemistry. Therefore, the development of creative learning environments tailored to exam preparation is critically important for improving both academic performance and the quality of education in Kazakhstan.

Problem Statement. Despite the growing emphasis on innovative and student-centered pedagogies in chemistry education, a significant discrepancy persists between contemporary educational approaches and the realities of exam-oriented instruction. In many educational systems, preparation for high-stakes examinations remains predominantly focused on rote memorization, algorithmic problem-solving, and standardized practice tasks, which limit the development of higher-order cognitive skills and creative thinking. This contradiction is particularly

evident in chemistry, where students are required not only to recall factual knowledge but also to apply conceptual understanding in complex problem-solving situations. Furthermore, while the concept of creative learning environments has gained increasing attention in educational research, its practical integration into exam preparation contexts remains insufficiently explored. Teachers often face institutional constraints, including rigid curricula, limited instructional time, and assessment systems that prioritize measurable outcomes over creative competencies. As a result, the potential of creative didactic environments to enhance students' exam readiness is not fully realized. Studies on creativity in education, chemistry teaching methodologies, and exam preparation are often conducted in parallel but rarely intersect in a systematic manner. This lack of integration leads to an incomplete understanding of how creative learning environments can be effectively designed and implemented specifically for chemistry exam readiness. Consequently, educators and policymakers lack a coherent evidence-based framework to guide instructional practices in this area.

Research Gap. Although a substantial body of literature addresses creative pedagogies, digital learning environments, and chemistry education, there is a notable absence of comprehensive bibliometric analyses that synthesize these domains within the context of exam-oriented learning. Existing bibliometric studies tend to focus either on general trends in creativity research or on broader aspects of science education, without specifically examining the intersection of creativity, chemistry instruction, and high-stakes exam preparation. Moreover, previous research has largely overlooked the structural and thematic evolution of this field, including key research clusters, influential authors, collaborative networks, and emerging keywords related to creative learning environments in chemistry. The lack of such systematic mapping limits the ability to identify dominant research directions and underexplored areas, thereby hindering the development of targeted pedagogical innovations. In addition, there is insufficient attention to the contextual dimension of exam preparation, particularly in countries where standardized testing plays a decisive role in educational trajectories. The specific challenges associated with designing creative didactic environments under exam pressure remain underrepresented in the global research landscape. Therefore, this study addresses these gaps by conducting a comprehensive bibliometric analysis of research on creative learning environments in chemistry education with a focus on exam readiness. By integrating insights from multiple research domains, this study aims to provide a structured overview of the field, identify key trends and gaps, and contribute to the development of more effective and creative approaches to chemistry exam preparation.

The aim of this study is to systematically analyze global research trends on the design of creative learning environments for chemistry exam readiness through a bibliometric approach, in order to identify key thematic directions, influential contributors, and emerging research gaps in the field.

RQ: *What are the global research trends, thematic structures, and emerging directions in the design of creative learning environments for chemistry exam readiness as revealed through bibliometric analysis?*

Significance of the study. This study holds significant theoretical, methodological, and practical value within the field of chemistry education. From a theoretical perspective, it contributes to the development of educational research by integrating three interconnected domains: creative learning environments, chemistry pedagogy, and exam-oriented instruction into a unified analytical framework. By applying a bibliometric approach, the study provides a systematic mapping of the intellectual and conceptual structure of this research field, thereby advancing understanding of how creativity is incorporated into chemistry education in the context of exam readiness. From a methodological perspective, the study demonstrates the potential of bibliometric analysis as a robust research tool for synthesizing large-scale scientific data,

identifying influential research trends, and uncovering patterns in the evolution of academic knowledge. The findings may serve as a foundation for future interdisciplinary studies that aim to explore the intersection of creativity, assessment, and STEM education. From a practical perspective, the study is particularly relevant for educators, curriculum developers, and policymakers seeking to enhance the effectiveness of chemistry exam preparation. By identifying dominant pedagogical approaches and emerging innovations, the research supports the development of more engaging, student-centered, and creativity-oriented instructional strategies that can improve students' academic outcomes in high-stakes testing contexts.

Importantly, in the context of Kazakhstan, the significance of this study is amplified by the central role of the Unified National Testing in determining students' access to higher education. The prevailing emphasis on exam performance often leads to the dominance of traditional teaching methods focused on memorization and test drilling. In this regard, the findings of this study can inform the modernization of teaching practices by promoting the integration of creative learning environments into chemistry instruction, thereby contributing to the improvement of both exam readiness and the overall quality of secondary education in Kazakhstan. The study contributes to bridging the gap between theoretical research and educational practice, offering evidence-based insights that can support the development of innovative and effective approaches to chemistry exam preparation in both global and national contexts.

Methodology

This study employed a bibliometric analysis combined with a systematic literature review approach following the PRISMA guidelines to ensure transparency, reproducibility, and methodological rigor (see Figure 1).




Figure 1. - PRISMA flow diagram of study selection for the bibliometric analysis of creative didactic environments in chemistry exam preparation

Data Source and Search Strategy. The Scopus database was selected as the primary source of scientific literature due to its broad coverage of high-quality peer-reviewed publications in the fields of education and chemistry. The search was conducted using a structured query applied to titles, abstracts, and keywords, focusing on the intersection of creative learning environments, chemistry education, and exam readiness. The search query included combinations of relevant keywords such as:

TITLE-ABS-KEY ("critical thinking" AND "chemistry") AND PUBYEAR > 2004 AND PUBYEAR < 2026 AND (LIMIT-TO (SUBJAREA , "CHEM")) AND (LIMIT-TO (LANGUAGE , "English")) AND (LIMIT-TO (SRCTYPE , "j")) AND (LIMIT-TO (PUBSTAGE , "final")) AND (LIMIT-TO (DOCTYPE , "ar")) AND (LIMIT-TO (OA , "all"))

The search was limited to publications written in English, published between 2015 and 2025, and restricted to peer-reviewed journal articles at the final publication stage. Additional filters were applied to ensure data quality and relevance, including document type (articles), subject area (chemistry and education), and open-access availability where applicable. The initial search yielded 801 records. Prior to manual screening, automated filtering tools available in Scopus were applied to refine the dataset. No duplicate records were identified, while 554 records were excluded based on predefined filtering criteria, including document type restrictions, incomplete bibliographic data, language limitations, and lack of relevance determined through keyword matching. Following this stage, 247 records remained for further screening. Titles and

abstracts of all selected records were carefully reviewed to assess their relevance to the research objective namely, the design of creative learning environments in chemistry education aimed at enhancing exam readiness. All records met the initial inclusion criteria and were advanced to the full-text assessment stage.

Full-text retrieval was attempted for all 247 studies; however, 113 records were not accessible due to limited availability, restricted access, or incomplete publication data. Consequently, 134 full-text articles were assessed for eligibility based on clearly defined inclusion and exclusion criteria. Studies were included if they:

- (1) focused on chemistry education;
- (2) addressed creative or innovative teaching methods;
- (3) demonstrated a connection to academic performance or exam preparation.

Studies were excluded if they did not explicitly relate to chemistry education, lacked a focus on creativity or innovation in pedagogy, or were not connected to exam-oriented learning outcomes. At this stage, 65 studies were excluded 27 due to the absence of a chemistry education focus and 38 due to a lack of direct relevance to creative pedagogies or assessment contexts. As a result, a total of 69 studies met all inclusion criteria and were included in the final bibliometric analysis.

The final dataset was exported from Scopus in CSV format, including full bibliographic information such as authors, affiliations, abstracts, keywords, cited references, and citation counts. The dataset was then imported into RStudio using the *bibliometrix* package. To complement the statistical analysis, the dataset was also analyzed using VOSviewer software for advanced network visualization. Co-authorship, co-citation, and keyword co-occurrence networks were constructed using fractional counting and normalized association strength. Clustering was performed using the VOSviewer modularity-based algorithm to identify thematic communities within the research field. Network maps were interpreted based on node size (indicating frequency or impact), link strength (indicating relationships), and cluster density, providing a visual representation of the intellectual, social, and conceptual structure of the domain.

Results and Discussion

The bibliometric dataset covers the period from 2011 to 2025 and includes a total of 69 documents published across 22 sources, involving 227 authors. The annual growth rate of publications is 23.86%, indicating a rapidly expanding research interest in the field of creative learning environments and chemistry education. The average number of co-authors per document is 3.33, reflecting a moderate level of collaboration among researchers. At the same time, the proportion of international co-authorship is 13.04%, suggesting that although the field is developing, global collaboration remains relatively limited. The average number of citations per document is 6.362, and the average document age is 3.99 years, which indicates that the field is relatively recent and actively evolving.

Table 1. Top 10 Most Cited Articles on the Development of Critical Thinking in Chemistry Education

No.	Article Title	Authors	Journal	Year	Citations
1	Leveraging ChatGPT for Enhancing Critical Thinking Skills	Guo, Y.; Lee, D.	Journal of Chemical Education	2023	178
2	How Can Socio-scientific Issues Help Develop Critical Thinking in Chemistry Education? A Reflection on the Problem of Plastics	López-Fernández, M.D.M.; González-García, F.; Franco-Mariscal, A.J.	Journal of Chemical Education	2022	30
3	Examining the Effect of Lab Instructions on Students' Critical Thinking during a Chemical Inquiry Practical	Van Brederode, M.E.; Zoon, S.A.; Meeter, M.	Chemistry Education Research and Practice	2020	20
4	Teaching an Undergraduate Organic Chemistry Laboratory Course with a Tailored Problem-Based Learning Approach	Costantino, L.; Barlocco, D.	Journal of Chemical Education	2019	20
5	Interfacing DNA and Aptamers with Gold Nanoparticles: From Fundamental Colloid and Interface Sciences to Biosensors	Ding, Y.; Liu, J.	Chinese Journal of Chemistry	2024	18
6	Improvement of Student Critical Thinking Skills with the Natural Product Mini Project Laboratory Learning	Hakim, A.; Liliasari; Kadarohman, A.; Syah, Y.M.	Indonesian Journal of Chemistry	2016	18
7	Rational Design and Cellular Synthesis of Proteins with Unconventional Chemical Topology	Li, T.; Zhang, F.; Fang, J.; Liu, Y.; Zhang, W.-B.	Chinese Journal of Chemistry	2023	9
8	Fun with Flags and Chemistry	Coudret, C.; Dietrich, N.	Journal of Chemical Education	2020	9
9	The Science of Human Health – A Context-Based Chemistry Course for Non-Science Majors Incorporating Systems Thinking	Armstrong, D.; Poë, J.C.	Journal of Chemical Education	2020	9
10	Bioorthogonal Cleavage Chemistry: Harnessing the Bond-Break Reactions for Biomolecule Manipulations in Living Systems	Zhu, Y.; Lin, F.; Liu, Z.; Fan, X.; Chen, P.R.	Chinese Journal of Chemistry	2025	7

The analysis of the most cited publications provides insights into the intellectual structure and influential research directions within the field. The most highly cited article, “*Leveraging ChatGPT for Enhancing Critical Thinking Skills*” (Guo & Lee, 2023), with 178 citations, reflects the growing impact of artificial intelligence in education, particularly in fostering higher-order thinking skills. This indicates a shift toward integrating advanced digital tools into chemistry education. The second most cited study focuses on socio-scientific issues in chemistry education, particularly environmental problems such as plastics. This highlights the importance of contextual and real-world problem-based learning in developing students’ critical thinking. Several highly cited articles emphasize inquiry-based and problem-based learning approaches. For example, studies by Van Brederode et al. (2020) and Costantino and Barlocco (2019) demonstrate that laboratory-based instruction and tailored problem-based learning significantly contribute to the development of critical thinking skills in chemistry. In addition, some of the highly cited works originate from interdisciplinary fields, such as nanotechnology and biochemistry (e.g., Ding & Liu, 2024; Zhu et al., 2025). Although not exclusively focused on pedagogy, these studies contribute to the conceptual complexity of chemistry education and indirectly support the development of analytical thinking. Notably, the *Journal of Chemical Education* appears as the leading source among the top-cited articles, confirming its central role in disseminating influential research in chemistry education.

To further explore the conceptual structure of the research field, a Multiple Correspondence Analysis (MCA) was conducted based on the co-occurrence of authors’ keywords. This method allows for the identification of underlying thematic relationships and clustering patterns within the literature, revealing how key concepts are interconnected across the domain




Figure 2. - Conceptual structure map of research on creative learning environments in chemistry education based on multiple correspondence analysis of creative learning environments in chemistry education.

The conceptual structure map (Figure 2) presents the spatial distribution of keywords across two principal dimensions, reflecting the intellectual organization of the research field. The positioning of keywords indicates their semantic proximity, while clusters represent groups of related research themes. The analysis reveals the presence of two major thematic clusters.

The first cluster, located on the left side of the map, is centered around general educational concepts such as *education*, *teaching*, *students*, *e-learning*, *artificial intelligence*, and *critical thinking*. This cluster reflects the foundational pedagogical discourse in chemistry education, emphasizing the development of cognitive skills and the integration of digital technologies into teaching practices. The presence of terms such as *critical thinking skills* and *chemical education* highlights the strong focus on enhancing students' intellectual abilities within instructional settings.

The second cluster, positioned on the right side of the map, represents more specialized and applied domains of chemistry education. It includes keywords such as *student-centered learning*, *problem solving*, *analytical chemistry*, *laboratory instruction*, *hands-on learning*, and *curriculum*. This cluster indicates a shift toward practice-oriented and application-based approaches, where emphasis is placed on experiential learning, inquiry-based strategies, and discipline-specific content.

Notably, the proximity of terms such as *inquiry-based learning*, *collaborative learning*, and *misconceptions* suggests the importance of interactive and constructivist approaches in addressing conceptual difficulties in chemistry. Additionally, the presence of *computer-based learning* and *internet/web-based learning* highlights the growing role of digital environments in shaping modern chemistry education.

The central area of the map includes bridging concepts such as *chemistry education*, *bibliometric analysis*, and *higher education*, which connect the two clusters and indicate interdisciplinary integration between pedagogical theory and applied instructional practices.

The conceptual structure demonstrates a clear transition from traditional teaching paradigms toward more student-centered, technology-enhanced, and inquiry-driven learning environments. This shift is particularly relevant for the development of creative didactic environments aimed at improving students' exam readiness. In the context of Kazakhstan, these findings underscore the necessity of transforming traditional exam-oriented instruction into more flexible and creativity-based learning models. The identified clusters suggest that integrating student-centered and inquiry-based approaches, along with digital tools, may significantly enhance students' understanding of chemistry and their performance in high-stakes assessments such as the Unified National Testing.

To complement the conceptual structure analysis, a keyword co-occurrence network was constructed using VOSviewer in order to visualize the relationships between the most frequently




Figure 3. Keyword co-occurrence network in research on creative learning environments in chemistry education

used terms in the field. This approach allows for the identification of thematic clusters and the strength of connections between key research topics.

Figure 3 illustrates the network of keyword co-occurrences, revealing the structural relationships and dominant thematic clusters within the research field. The size of the nodes reflects the frequency of keyword occurrence, while the thickness of the links indicates the strength of connections between terms. Different colors represent distinct thematic clusters. The analysis identifies three major clusters.

The first cluster (green) is centered around *critical thinking*, which appears as one of the most influential and highly connected nodes in the network. It is closely associated with terms such as *education*, *artificial intelligence*, *chemistry*, and *critical thinking skills*. This cluster reflects the core pedagogical focus of the field, emphasizing the development of higher-order cognitive skills and the integration of modern technologies into chemistry education.

The second cluster (blue) is related to laboratory-based and practice-oriented learning. It includes keywords such as *laboratory instruction*, *organic chemistry*, *hands-on learning*, and *undergraduate education*. This cluster highlights the importance of experiential learning and practical engagement in developing students' understanding of chemical concepts.

The third cluster (red) represents inquiry-based and technology-enhanced learning approaches. It includes terms such as *inquiry-based learning*, *internet/web-based learning*, *analytical chemistry*, and *graduate education*. This cluster indicates the growing role of digital tools and inquiry-driven strategies in modern chemistry education.

A notable feature of the network is the central bridging role of *chemistry education*, which connects all clusters and reflects the integrative nature of the field. Additionally, the strong linkage between *critical thinking* and both technological and instructional approaches suggests that the development of cognitive skills is increasingly supported by digital and interactive learning environments. The network structure demonstrates a clear trend toward the integration of three key dimensions:

- (1) cognitive skill development (critical thinking),
- (2) practical laboratory experience, and
- (3) technology-enhanced and inquiry-based learning.

In the context of Kazakhstan, these findings emphasize the importance of incorporating student-centered, inquiry-based, and technology-supported approaches into chemistry education. Such integration can contribute to the creation of creative learning environments that not only improve conceptual understanding but also enhance students' readiness for high-stakes assessments such as the Unified National Testing

Discussion

The findings of this study provide important insights into the evolving landscape of research on creative learning environments in chemistry education, particularly in the context of exam readiness. The bibliometric results demonstrate a clear and consistent shift from traditional, teacher-centered instructional models toward more student-centered, inquiry-based, and technology-enhanced approaches. The dominance of *critical thinking* as a central node in the keyword network confirms its fundamental role in contemporary chemistry education. This aligns with previous research emphasizing the importance of higher-order cognitive skills in STEM learning (Hernández-Torrano & Ibrayeva, 2020). The strong connection between critical thinking and artificial intelligence, particularly reflected in highly cited works such as Guo and Lee (2023), indicates the increasing role of digital technologies in supporting cognitive skill development. Furthermore, the prominence of inquiry-based and problem-based learning approaches identified in this study is consistent with earlier findings (Van Brederode et al., 2020; Costantino & Barlocco, 2019), which demonstrate that active engagement in laboratory and real-world problem-solving

contexts significantly enhances students' analytical abilities. The inclusion of socio-scientific issues, such as environmental challenges (López-Fernández et al., 2022), further reinforces the importance of contextualized learning in developing critical thinking.

The conceptual and network analyses also highlight the growing integration of interdisciplinary and applied domains, including analytical chemistry, biochemistry, and digital learning environments. This reflects the increasing complexity of chemistry education, where students are expected not only to understand theoretical concepts but also to apply them in diverse and technologically mediated contexts. However, despite these global trends, a notable gap remains between research advancements and classroom practices, particularly in exam-oriented educational systems. In the context of Kazakhstan, this gap is especially pronounced due to the dominant role of the Unified National Testing, which often prioritizes memorization and algorithmic problem-solving over creative and inquiry-based learning. The results of this study suggest that integrating the identified pedagogical approaches such as inquiry-based learning, laboratory instruction, and digital technologies into exam preparation strategies can significantly enhance both conceptual understanding and exam performance. This implies the need for a systemic transformation of teaching practices, curriculum design, and assessment models in Kazakhstan.

Conclusion

This study conducted a comprehensive bibliometric analysis of research on creative learning environments in chemistry education with a focus on exam readiness. The findings reveal a rapidly growing and evolving research field characterized by increasing attention to critical thinking, student-centered learning, and technology-enhanced instructional approaches. The analysis identified three dominant dimensions shaping the field: cognitive skill development, experiential laboratory learning, and the integration of digital and inquiry-based methods. These elements collectively contribute to the design of creative learning environments that support both deep understanding and effective exam preparation. Importantly, the study highlights a significant gap between global research trends and traditional exam-oriented teaching practices. In the context of Kazakhstan, this gap underscores the urgent need to modernize chemistry education by incorporating more innovative and creativity-driven approaches. The findings of this study have important implications for educators, curriculum developers, and policymakers. By adopting evidence-based strategies identified through bibliometric analysis, it is possible to enhance students' readiness for high-stakes assessments such as the Unified National Testing while simultaneously promoting critical thinking and deeper learning. Future research should focus on empirical validation of these approaches in specific educational contexts, as well as on the development of practical models for integrating creative learning environments into exam-oriented systems.

References

- Adal, S., Çepni, S., Akylbekova, T., et al. (2025). Enhancing research skills in chemistry education via integrated project and inquiry-based learning. *Science Education International*.
- Armstrong, D., & Poë, J. C. (2020). The science of human health: A context-based chemistry course for non-science majors incorporating systems thinking. *Journal of Chemical Education*.
- Costantino, L., & Barlocco, D. (2019). Teaching an undergraduate organic chemistry laboratory course with a tailored problem-based learning approach. *Journal of Chemical Education*.
- Coudret, C., & Dietrich, N. (2020). Fun with flags and chemistry. *Journal of Chemical Education*.
- Ding, Y., & Liu, J. (2024). Interfacing DNA and aptamers with gold nanoparticles: From fundamental colloid and interface sciences to biosensors. *Chinese Journal of Chemistry*.

Guo, Y., & Lee, D. (2023). Leveraging ChatGPT for enhancing critical thinking skills. *Journal of Chemical Education*.

Hakim, A., Liliyasi, Kadarohman, A., & Syah, Y. M. (2016). Improvement of student critical thinking skills with the natural product mini project laboratory learning. *Indonesian Journal of Chemistry*.

Hernández-Torrano, D., & Ibrayeva, L. (2020). Creativity and education: A bibliometric mapping of the research literature. *Thinking Skills and Creativity*, 35, 100625.

Li, T., Zhang, F., Fang, J., Liu, Y., & Zhang, W.-B. (2023). Rational design and cellular synthesis of proteins with unconventional chemical topology. *Chinese Journal of Chemistry*.

López-Fernández, M. D. M., González-García, F., & Franco-Mariscal, A. J. (2022). How can socio-scientific issues help develop critical thinking in chemistry education? A reflection on the problem of plastics. *Journal of Chemical Education*.

Lykhovavlo, N. Y. (2025). A bibliometric analysis of learning environments in chemistry education. *Science Education Quarterly*.

Nuryana, I., Sugeng, B., Soesilowati, E., & Andayani, E. S. (2024). Critical thinking in higher education: A bibliometric analysis. *Journal of Applied Research in Higher Education*.

Van Brederode, M. E., Zoon, S. A., & Meeter, M. (2020). Examining the effect of lab instructions on students' critical thinking during a chemical inquiry practical. *Chemistry Education Research and Practice*.

Zhu, Y., Lin, F., Liu, Z., Fan, X., & Chen, P. R. (2025). Bioorthogonal cleavage chemistry: Harnessing bond-break reactions for biomolecule manipulations in living systems. *Chinese Journal of Chemistry*.

Physical and Mathematical Sciences

ӘОК 372.853

Оқушылардың физикаға қызығушылығын есептерді шығарумен арттыру

Рахымбеков А.Ж

ф-м.ғ.к., профессор, ғылыми жетекші

Алтайқызы Арай

студент, І.Жансүгіров атындағы Жетісу университеті, Талдықорған, Қазақстан

Абылғазина Нурила Ерланқызы

студент, І.Жансүгіров атындағы Жетісу университеті, Талдықорған, Қазақстан

Шаймерденова Перизат Ерсиновна

студент, І.Жансүгіров атындағы Жетісу университеті, Талдықорған, Қазақстан

Аннотация: Физика сабақтарында оқушылардың эксперимент жүргізу дағдыларын қалыптастыру мен олардың шығармашылық ойлауын дамыту жеке тұлғаның жан-жақты жетілуіне ықпал етеді. Әсіресе бұл бағытта эксперименттік сипаттағы тапсырмаларды қолдану өте тиімді. Сонымен қатар, эксперименттік тапсырмалар оқушылардың пәнге деген қызығушылығын арттырып, физиканы өмірмен байланыстыра түсінуіне жағдай жасайды. Нәтижесінде оқушылардың білім деңгейі тереңдеп, өз бетімен жұмыс істеу дағдылары қалыптасады.

Түйін сөздер: эксперимент, шығармашылық, есеп, шарты, анализ, өлшеулер, есептер, тәжірибе, тәсіл, іс-әрекет.

Физиканы оқыту барысында есептер шығару ерекше маңызды орын алады. Себебі есептерді жүйелі түрде орындау оқушылардың оқу материалын терең әрі саналы меңгеруіне мүмкіндік береді. Сонымен қатар, олар теориялық білімдерін практикада қолдануға дағдыланып, алған білімдерін нақты жағдайларда пайдалана білу қабілетін қалыптастырады және бекітеді.

Есеп шығару үдерісі тек білімді қайталау құралы ғана емес, сонымен бірге оқушының ойлау қабілетін дамытудың тиімді тәсілі болып табылады. Әсіресе, есептерді шешу барысында оқушылар өздігінен ізденуге, логикалық тұрғыдан ойлауға және кездескен қиындықтарды жеңуге үйренеді. Бұл олардың ерік-жігерін, табандылығын арттырып, оқу іс-әрекетіне деген қызығушылығын күшейтеді. Осы тұрғыдан алғанда, есеп шығару оқу процесінің ажырамас бөлігі болып саналады[1].

Физика есептерін орындау оқушылардың физикалық ұғымдарды дұрыс қалыптастыруына және табиғаттағы құбылыстарды терең түсінуіне ықпал етеді. Сонымен қатар, оларды практикада қолдана білу дағдыларын дамытады. Бұл өз кезегінде оқушылардың ғылыми дүниетанымының қалыптасуына негіз болады.

Білімді тиімді меңгеру адамның танымдық әрекетіне байланысты. Егер оқу барысында бірнеше сезім мүшелері қатар іске қосылса, білімнің меңгерілу деңгейі арта түседі. Осыған байланысты физиканы оқытуда тәжірибелік жұмыстар мен эксперименттердің маңызы ерекше. Физикалық эксперимент оқушыларға құбылыстарды тікелей бақылауға, оларды

сезінуге және нақты түсінуге мүмкіндік береді. Қабілеттілік – адамның даму барысында қалыптасатын қасиет. Ол туа біткен емес, керісінше, оқу және тәрбие үдерісінде дамиды. Сондықтан оқушының қабілеті оның білім алу әрекетінде, мұғалімнің бағыт-бағдары мен педагогикалық ықпалы арқылы жетіледі.

Қазіргі білім беру жүйесінің негізгі мақсаттарының бірі – жан-жақты дамыған, шығармашылық тұрғыдан ойлай алатын жеке тұлғаны қалыптастыру. Осы тұрғыдан алғанда, оқыту үдерісі тек білім берумен шектелмей, оқушының шығармашылық қабілеттерін дамытуға бағытталуы тиіс. Әрбір оқушының бойында шығармашылық мүмкіндіктер бар, ал оны дамыту – мұғалімнің басты міндеттерінің бірі.

Оқушылардың шығармашылық қабілетін дамыту үшін оларды дайын ақпаратты қабылдаушы емес, білімді өз бетімен ізденіп, меңгеретін тұлға ретінде қалыптастыру қажет. Бұл үшін дәстүрлі оқыту әдістерін қайта қарастыру маңызды. Өйткені дәстүрлі сабақтарда мұғалім негізгі ақпарат беруші рөлін атқарып, ал оқушы көбіне тыңдаушы қызметінде ғана қалады. Мұндай жағдайда оқушының белсенділігі шектеліп, шығармашылық ойлауы жеткілікті деңгейде дамымайды.

Шығармашылыққа негізделген оқытуда оқушы оқу үдерісінің белсенді қатысушысына айналады. Ол өз бетінше ойлап, мәселені шешудің түрлі жолдарын іздейді. Әсіресе физика пәнінде есептер шығару, зертханалық жұмыстар мен эксперименттік тапсырмалар оқушылардың логикалық және шығармашылық ойлауын дамытуда маңызды рөл атқарады. Есептің шартынан оның шешіміне дейінгі жолды табу барысында оқушы талдау, салыстыру, жалпылау сияқты ойлау операцияларын қолданады.

Шығармашылық қызметтің маңызды ерекшелігі – мәселені шешуге деген ішкі қызығушылық пен тұрақты ойлану процесі. Оқушыға берілген тапсырма оның назарын толықтай аударып, санасында ұзақ уақыт бойы сақталуы мүмкін. Тіпті ол басқа істермен айналысса да, мәселенің шешімі туралы ойлау жалғаса береді. Бұл – шығармашылық ойлаудың табиғи көрінісі. Мұндай жағдайда оқушының мәселені өз бетінше шешуі ерекше маңызға ие, себебі дербес ізденіс арқылы алынған білім анағұрлым терең әрі берік болады[2].

Бастапқы кезеңде оқушыларға есеп шығару қиын болуы мүмкін және көп уақытты талап етеді. Алайда тәжірибе жинақталған сайын олардың ойлау жылдамдығы артып, күрделі тапсырмаларды шешу қабілеті дамиды. Сондықтан оқушыларға уақыт беріп, олардың өз бетімен жұмыс істеуіне мүмкіндік жасау қажет.

Шығармашылық қабілеттерді дамытудың тиімді жолдарының бірі – эксперименттік тапсырмаларды пайдалану. Әсіресе оларды үй тапсырмасы ретінде беру оқушының өздігінен зерттеу жүргізуіне, бақылау жасауына және қорытынды шығаруына мүмкіндік береді. Бұл тәсіл оқушылардың танымдық қызығушылығын арттырып қана қоймай, олардың ғылыми-зерттеу дағдыларын қалыптастырады. Мысалы, келесі есепті қарастырайық:

Шарты: Егер, бөлме температурасы 10 К -ге көтерілсе, ауаның қандай массасы бөлмеден шығып кетеді.

Шешуі: Клапейрон – Менделеевтың заңы бойынша бөлменің көлемі мен қысымы біркелкі, бұдан шығатыны:

$$\Delta m \sim \frac{m \Delta T}{T} = \rho V \frac{\Delta T}{T},$$

Мұндағы, ρ - ауаның тығыздығы, V – бөлменің көлемі, Осыдан $V \approx 2 \cdot 10^3 \text{ м}^3, T \approx 300 \text{ К}, \rho \approx 1.3 \frac{\text{кг}}{\text{м}^3}$ шығатыны $\Delta m \approx 80 \text{ кг}$.

Жауабы: $\Delta m \approx 80 \text{ кг}$.

Қорытындылай келе, оқыту үдерісін шығармашылық бағытта ұйымдастыру оқушылардың жеке тұлға ретінде дамуына, олардың дербес ойлау қабілетінің қалыптасуына және білімді тиімді меңгеруіне ықпал етеді. Сондықтан қазіргі білім беру жүйесінде

оқушының белсенділігін арттырып, шығармашылық әлеуетін ашуға бағытталған әдістерді кеңінен қолдану қажет. Экспериментті жүргізудің дидактикалық құрылымы төмендегідей болуы мүмкін: демонстрациялық тәжірибелер, фронталды тапсырма[3].

Қысқасы, физика есептерін шығару оқушылардың білімін тереңдетіп қана қоймай, олардың танымдық белсенділігін арттырады, шығармашылық ойлауын дамытады және ғылыми көзқарасын қалыптастырады. Сондықтан есеп шығару әдістерін тиімді ұйымдастыру – сапалы білім берудің маңызды шарттарының бірі.

ӘДЕБИЕТ

- 1.Қазақстан Республикасының 2015 жылға дейінгі білім беруді дамыту тұжырымдамасы. //Егемен Қазақстан, — Астана, 12.26. 2011 ж.
- 2.Техникалық және кәсіптік білім беруді дамытудың 2008-2012 жылдарға арналған мемлекеттік бағдарламасы. 2008 ж. 01.07.№626. //Казахстанская правда. — Астана, 2008 ж. 19 шілде.
- 3.Қазақстан Республикасының білім беру жүйесін 2011-2020 жылға дейін дамытудың Мемлекеттік бағдарламасы. — Астана, 07.12.

Philological Sciences

Қазақ тілі және ұлттық құндылықтар (10-сынып) (Авторлық бағдарламаны тәжірибеде қолдану және зерттеу нәтижелері)

Манасова Жадра Амангельдиевна

Шымкент қаласы білім басқармасына қарасты, «№ 127 жалпы орта білім беретін мектебі» КММ, *Қазақ тілі мен әдебиеті пәні мұғалімі*

Аңдатпа. Бұл мақалада 10-сынып оқушыларына арналған «Қазақ тілі және ұлттық құндылықтар» атты авторлық бағдарламаның мазмұны, оны оқу үдерісіне енгізу жолдары және зерттеу нәтижелері баяндалады. Бағдарлама оқушылардың тілдік құзыреттілігін арттыра отырып, ұлттық құндылықтарды терең түсінуге, оларды құрметтеуге және қоғамдық өмірде орынды қолдануға бағытталған. Мақалада қолданылған әдістердің тиімділігі, сабақтардағы тәжірибелік жұмыс нәтижелері, бағдарламаның мұғалімдер мен оқушылар үшін артықшылықтары мен қиын тұстары жан-жақты талданады. Сонымен бірге авторлық бағдарламаның оқушылардың тұлғалық дамуына, мәдени-әлеуметтік көзқарасының кеңеюіне әсері талқыланады. Ұлттық мазмұнды тілдік мақсаттармен үйлестірудің қазіргі білім беру жүйесіндегі орны мен маңыздылығы ғылыми-тәжірибелік тұрғыдан негізделеді.

Түйінді сөздер: қазақ тілі, ұлттық құндылықтар, авторлық бағдарлама, тілдік құзыреттілік, мәдени код, құндылыққа бағытталған оқыту, функционалдық сауаттылық.

Кіріспе

Қазіргі жаһандану жағдайында ұлттық болмысты сақтау, рухани құндылықтарды жас ұрпаққа сіңіру – білім беру жүйесі алдында тұрған негізгі міндеттердің бірі. Қазақ тілі пәнін оқыту тек тілдік дағдыларды меңгертумен шектелмей, ұлттық дүниетаным мен мәдени мұраны ұғындырумен үйлескенде ғана терең нәтижелерге қол жеткізуге болады. Осы тұрғыда «Қазақ тілі және ұлттық құндылықтар» атты авторлық бағдарламаның өзектілігі арта түседі. Бағдарлама 10-сынып оқушыларының жас ерекшелігіне, когнитивтік даму деңгейіне және білім алуға мотивациясына сәйкестендіріліп жасалған.

Зерттеулерге сүйенсек, оқушылардың ұлттық тарих, мәдениет, дәстүр жөніндегі білімдері көбіне фрагменттік сипатта болады. Бұл олқылықты тілдік оқу материалдары арқылы толықтыру – тиімді әрі қолжетімді жолдардың бірі. Шетелдік ғалымдар (Б.Хюбнер, Э.Холл, Дж.Брунер) мәдени-тілдік сәйкестіктің тұлға дамуына әсерін атап өтсе, отандық зерттеушілер (Қ.Жұбанов, Р.Сыздық, Н.Уәли) ұлттық құндылықтарды тіл арқылы меңгертудің әдістемелік негіздерін қалыптастырған.

Мақаланың мақсаты:

- авторлық бағдарламаның құрылымын, мазмұнын және әдістемелік ерекшеліктерін таныстыру;
- бағдарламаны практикалық сабақтарда қолдану жолдарын сипаттау;
- бағдарламаның тиімділігін талдау және зерттеу нәтижелерін ұсыну.

Міндеттері:

1. Бағдарламада қолданылатын әдіс-тәсілдерге сипаттама беру.
2. Сабақ барысы мен оқушылардың нәтижелерін салыстырмалы түрде талдау.
3. Ұлттық құндылықтарды тіл сабақтарына енгізудің тиімді жолдарын көрсету.
4. Педагогтерге әдістемені қолдануға қатысты ұсыныстар әзірлеу [1].

Әдістеме

Авторлық бағдарлама құндылыққа бағытталған оқыту (Value-based education), коммуникативтік әдіс, функционалдық сауаттылықты дамыту, ұлттық мәдени кодты интеграциялау принциптері негізінде жасалған.

1. Бағдарламаның негізгі қағидалары:

- ❖ Ұлттық мазмұнды тілдік мақсатпен үйлестіру
- ❖ Оқушының тұлғалық дамуын басты назарда ұстау
- ❖ Интерактивті әдістерді қолдану
- ❖ Жобалық және зерттеушілік жұмысқа бағыттау
- ❖ Шынайы өмірмен байланыс орнату

2. Қолданылған педагогикалық технологиялар

- ❖ CLIL (Content and Language Integrated Learning) – тіл мен мазмұнды кіріктіре оқыту.
- ❖ Проблемалық оқыту технологиясы – ұлттық құндылықтар айналасындағы сұрақтарды талқылау.
- ❖ Жобалық әдіс – «Қазақтың салт-дәстүрлері», «Ұлттық тағамдар», «Отбасы құндылықтары» тақырыптарында шағын зерттеу жобалары.
- ❖ Сыни ойлауды дамыту технологиясы (СТО) – INSERT, RAFT, PMI стратегиялары.
- ❖ Диалогтік оқыту – пікірталас, топтық әңгіме, рөлдік ойындар [2].

3. Бағдарлама құрылымы

Бағдарлама 5 негізгі модульден тұрады:

№	Модуль атауы	Қысқаша мазмұны
1	Ұлттық тіл және мәдениет	Тіл – мәдени код. Тілдің ұлттық сана қалыптастырудағы рөлі.
2	Салт-дәстүр және әдет-ғұрып	Мәтіндер, эссе, пікірталас арқылы талдау.
3	Ұлттық өнер және тұлғалар	Жыр, күй, поэзия тілдік талдауы.
4	Отбасы құндылықтары	Коммуникативтік тапсырмалар, сұхбат алу.
5	Қазіргі қоғамдағы ұлттық идентичность	Жастар мәдениеті, құндылық трансформациясы.


Практикада қолдану

Авторлық бағдарлама 2024-2025 оқу жылында 10-сынып оқушыларымен апробациядан өтті. Сабақтар аптасына 2 сағат көлемінде жүргізілді. Әр модуль аяқталғаннан кейін оқушылардың тілдік, мәдени-коммуникативтік, зерттеу дағдылары бағаланып отырды.

1. Сабақтарда қолданылған жұмыс түрлері

1) «Ұлттық құндылық деген не?» концепт-картасы

Оқушылар топта жұмыс істеп, төмендегідей диаграмма құрастырды:



2) Мәтінмен жұмыс

«Тіл – ұлттық болмыстың айнасы» мәтіні негізінде тапсырмалар:

- ❖ Түйінді ойды табу
- ❖ Құндылық категорияларын бөлу
- ❖ Тілдік құрылымдарды талдау
- ❖ Пікір жазу

3) Дебат сабақтары

Тақырыптар:

- ❖ «Жаһандану ұлттық тілге қауіп төндіре ме?»
- ❖ «Дәстүрді сақтаудың заманауи жолдары»

4) Жобалық жұмыстар

Мысалы, «Қазақтың қонақжайлық дәстүрі» жобасы:


- ❖ дереккөздер жинау;
- ❖ ата-әжелермен сұхбат;
- ❖ нәтижені инфографикамен рәсімдеу.

2. Зерттеу нәтижелері

Бағдарламаның нәтижелілігі төмендегі критерийлер бойынша бағаланды:

Критерий	Бастапқы деңгей	Қорытынды деңгей
Мәтінді түсіну	62%	87%
Пікір білдіру	48%	82%
Ұлттық құндылықтар бойынша білім	55%	91%
Тілдік нормаларды қолдану	60%	85%

3. Диаграмма (нәтижелердің өсу динамикасы)



МТ – мәтін түсіну

ПБ – пікір білдіру

ҰҚ – ұлттық құндылықтар

ТН – тіл нормалары

4. Артықшылықтар мен кемшіліктер

Артықшылықтары:

- ✓ ұлттық мазмұн оқушылардың қызығушылығын арттырды;
- ✓ тілдік дағдылар едәуір күшейді;
- ✓ оқушылар жобалық жұмыстарға белсенді қатысты;
- ✓ отбасы мүшелерімен сұхбат алу оқушылардың әлеуметтік байланысын күшейтті.

Кемшіліктері:

- ✓ кейбір тақырыптарға қосымша уақыт қажет болды;
- ✓ оқушылардың бастапқы деңгейі әртүрлі болғандықтан, саралап оқытуға көп күш жұмсалды;
- ✓ ұлттық материалды цифрлық форматқа бейімдеу қиындық тудырды.

Ұсыныстар

Ұлттық құндылықтарды тіл сабақтарына интеграциялау – жүйелі дайындықты қажет ететін үдеріс. Сондықтан мұғалімдерге төмендегідей ұсыныстар беріледі:

1. **Сабақ жоспарлауда мазмұнды тілдік мақсатпен байланыстыру** – ұлттық тақырып тек талқылау объектісі емес, тілдік дағдыны дамыту құралы болуы тиіс.
2. **Интерактивті әдістерді көбірек қолдану** – пікірталас, рөлдік ойындар, сұхбат, жағдаяттық тапсырмалар оқушылардың белсенділігін арттырады.
3. **Жобалық жұмыстарды жүйелі енгізу** – отбасылық дәстүрлер, ұлттық құндылықтар жөніндегі шағын зерттеу жобалары оқушылардың ақпарат жинау, сұхбат алу, талдау дағдыларын дамытады.
4. **Цифрлық платформаларды пайдалану** – Padlet, Canva, Quizizz арқылы инфографика, деректер қозғалысын тиімді көрсетуге болады.
5. **Бағалау критерийлерін нақты белгілеу** – тілдік норма, мазмұн тереңдігі, дәлелді пікір, ұлттық түсініктерді қолдану.
6. **Әртүрлі деңгейдегі сыныптарға бейімдеу** – күрделі мәтіндерді жеңілдету, сөздік беру,

үлгі көрсетіп, шағын қадамдармен жұмыс жүргізу [3].

Қорытынды

«Қазақ тілі және ұлттық құндылықтар» авторлық бағдарламасын енгізу оқушылардың тілдік құзыреттілігі мен ұлттық дүниетанымын қалыптастыруда тиімді нәтиже берді. Бағдарлама ұлттық мазмұнды тіл үйрету мақсаттарымен байланыстырып, оқушыларға қазақ мәдениеті мен қоғамындағы құндылықтар жүйесін түсіндіруде маңызды рөл атқарды. Жүргізілген тәжірибелік сабақтар мен зерттеу нәтижелері көрсеткендей, оқушылардың мәтінді түсіну, пікір айту, ұлттық құндылықтарды талдау және тілдік нормаларды қолдану дағдылары айтарлықтай артты.

Бұдан бөлек, оқушылар ұлттық құндылықтарды зерттеу арқылы өз отбасы, ауыл-аймақ тарихына қайта үңіліп, рухани байланысын күшейтті. Авторлық бағдарлама тіл үйренуді тек теориялық үдеріс емес, тұлғалық-мәдени даму алаңы ретінде көрсетті.

Зерттеу нәтижелері бұл әдістеменің білім беру процесінде қолдануға жарамды, тиімді құрал екенін дәлелдейді. Келешекте бағдарламаны кеңейтіп, цифрлық ресурстармен толықтыру білім сапасын одан әрі арттыра түсері анық.

Қолданылған деректер тізімі:

1. Жұбанов Қ. Қазақ тілі жөніндегі зерттеулер. – Алматы: Ғылым, 2019. – 320 б.
2. Уәли Н. Тіл ұлттық танымның кілті. – Алматы: Ан Арыс, 2019. – 280 б.
3. Әбдіғалиева Б.Б. Қазақ тілін оқыту әдістемесі. – Астана: Фолиант, 2020. – 348 б.
4. Қалиев Б. Тіл және мәдениет: өзара ықпалдастық мәселелері. – Алматы: Қазақ университеті, 2019. – 214 б.
5. Mayer R. Multimedia Learning. – Cambridge: Cambridge University Press, 2020. – 380 p.

Казахский язык и национальные ценности (10-класс)

(Применение авторской программы на практике и результаты исследования)

Манасова Жадра Амангельдиевна

КГУ «Средняя общеобразовательная школа № 127»

Управления образования города Шымкент

Учитель казахского языка и литературы

Аннотация. В данной статье рассматриваются содержание и особенности внедрения авторской программы «Казахский язык и национальные ценности», предназначенной для учащихся 10-класса, а также результаты практического исследования. Программа направлена на развитие языковой компетентности школьников, глубокое понимание национальных ценностей, формирование уважительного отношения к ним и умение применять их в современной социальной среде. В статье проводится анализ эффективности использованных методик, результатов практических занятий, преимуществ и затруднений, возникших у учителей и учащихся в процессе реализации программы. Кроме того, рассматривается влияние авторской программы на личностное развитие обучающихся и расширение их культурно-социального мировоззрения. Научно-практически обоснована значимость интеграции национального содержания с языковыми целями в современной системе образования.

Ключевые слова: казахский язык, национальные ценности, авторская программа, языковая компетентность, культурный код, ценностно-ориентированное обучение, функциональная грамотность.

Kazakh language and national values (Grade 10)
(Application of the author's program in practice and research results)

Manassova Zhadra Amangeldiyevna

KSU «Secondary school № 127»,

Department of Education of Shymkent City

Kazakh language and literature teacher

Abstract. This article examines the content and implementation features of the author's educational program «Kazakh Language and National Values» designed for 10th-grade students, as well as the results of its practical application and research. The program aims to enhance students' linguistic competence, develop a deep understanding of national values, foster respect for these values, and promote their appropriate use in social life. The article provides an analysis of the effectiveness of the applied methods, outcomes of practical lessons, and the advantages and challenges experienced by teachers and learners during program implementation. Additionally, the study discusses the program's impact on students' personal development and the expansion of their cultural and social worldview. The importance of integrating national content with language learning objectives is theoretically and practically justified within the context of modern education.

Keywords: Kazakh language, national values, author's program, linguistic competence, cultural code, value-based education, functional literacy.

Histoire et évolution de la famille des langues romanes

Aziza Aliyeva

Université d'Etat de Nakhtchévan, Professeur en chef, <https://orcid.org/0009-0002-9812-5006>

Aysel Hassanova

étudiante en 4ème année de spécialité française, Université d'Etat de Nakhtchévan , Azerbaïdjan, Nakhchévan

Abstract

Dans cet article on met en lumière des travaux essentiels pour la compréhension de l'histoire, de l'évolution linguistique, ainsi que des différences et des ressemblances entre les langues de la famille romane. Cette comparaison présente des perspectives variées et approfondies sur le sujet, enrichissant ainsi la recherche académique dans ce domaine linguistique. Les langues qui se trouvent dans la famille de langues romanes regroupent un ensemble de langues venant du latin vulgaire et parlées principalement dans la grande partie de l'Europe et dans certaines régions du monde. L'histoire des langues commence avec la chute de l'Empire romain. C'est une période durant laquelle le latin s'est diffusée en diverses variantes régionales. Ensuite ces langues ont ensuite évolué d'une forme indépendante et influencées par des contextes historiques, géographiques et culturels distincts. L'étude de leur évolution soit historique, soit linguistique permet de comprendre les mécanismes de changement linguistique. En même temps la comparaison des différences et ressemblances de ces langues filles révèle les liaisons étroites qui unissent ces langues venant d'une protolangue. Ainsi, malgré ces langues sont différentes l'une de l'autre, elles partagent un point commun qui facilite et aide les apprendre mutuellement. Grâce à ce témoignage linguistique on peut souligner leur héritage latin partagé.

Mots-clés : Langues romanes ; latin vulgaire ; évolution linguistique ; histoire ; différences et ressemblances ; langues néolatines ; héritage latin ; proto langue ; langues filles ; *langues mères*

Introduction

La famille des langues romanes, est issue de la modification du latin vulgaire, crée un ensemble linguistique fascinante. Elle témoigne de l'histoire culturelle, politique et sociale de l'Europe. Dans cette famille il se trouve des langues majeures telles que l'italien, le portugais, l'espagnol, le français et le roumain. Dans cette famille de langues on peut trouver aussi de nombreux dialectes et variations régionales. On ne peut pas considérer la diversité des langues romanes tout simplement le résultat d'une séparation géographique, c'est aussi d'une multitude d'interactions historiques, d'influences culturelles et de changements linguistiques.

L'arrivée de ces langues jusqu'à nos jours est un aperçu précieux de l'histoire, et de modification linguistique et des processus d'innovation qui ont exécuté leur développement à travers le temps. Cet article nous permet d'examiner et d'étudier d'abord l'histoire des langues romanes, en feuilletant leurs origines latines et leur évolution au fil des siècles. En seconde place, nous analyserons les différences qui distinguent ces langues sœurs. Il s'agit des variations phonétiques, des structures grammaticales ou du lexique. Enfin, pour conclure nous mettrons en lumière les ressemblances qui unissent et mettent ensemble ces langues dans un groupe qui témoignent d'une racine commune et de convergences culturelles.

Ainsi, ce voyage dans des langues romanes nous permettra de comprendre leur diversité et leur richesse mais aussi de mieux analyser la parenté de la branche linguistique et culturelle. Malgré

le latin classique est une langue morte elle a donné naissance plusieurs langues vivantes. Cette langue représente une grande valeur pour les sociétés contemporaines.

L'histoire des langues romanes ; leurs origines latines et leurs évolutions

Comme c'est déjà marqué en haut les langues romanes prennent leurs racines dans le latin vulgaire. La langue parlée par les Romains et leurs sujets dans les provinces de l'Empire romain. Quand l'Empire romain a commencé à se décomposer, de faire sa chute les différentes régions ont débuté à développer leurs propres variantes du latin. Cette langue a été influencée par les langues locales, les dialectes et les contacts culturels des voisins. Ce processus de mutation linguistique fut particulièrement maintenu par les invasions germaniques. L'ère médiévale a été marquée par de grandes vagues de migrations humaines à travers le continent. Au fil des siècles, le latin vulgaire s'est modifié en langues distinctes. Elle a marqué le début de la diversification qui a donné naissance aux langues romanes modernes.

L'apparition des dialectes régionaux ont commencé à partir du Xe siècle. Les variations de dialectes du latin a commencé à se consolider en langues plus clairement définies. Les premiers textes écrits en langues romanes apparaissent, tels que les poèmes en occitan et les textes en ancien français. Ces dialectes régionaux comme l'italien, l'espagnol, le portugais, le roumain et le français, évoluent sous l'influence de facteurs sociaux, politiques et culturels locaux. Les cours royales, les administrations et les institutions religieuses jouent un rôle crucial dans la promotion de certaines langues au détriment d'autres, favorisant leur standardisation.

Le processus d'établissement des langues romanes modernes se poursuit jusqu'au début du XIXe siècle. Ce phénomène est souvent associé à la montée du nationalisme et à la nécessité de créer une identité linguistique nationale. Les grammairiens et les écrivains de chaque langue s'efforcent de codifier les règles grammaticales et d'enrichir le vocabulaire. Les révolutions politiques et les mouvements culturels, comme le romantisme, encouragent également l'utilisation de ces langues dans la littérature et les arts, contribuant à leur prestige. Ainsi, les langues romanes modernes se configurent comme des entités linguistiques autonomes, capables de se défendre et de se promouvoir sur la scène internationale.

L'histoire des langues romanes est marquée par un processus complexe d'évolution et de diversification, influencé par des facteurs internes et externes. Leurs origines latines partagées sont constamment réinterprétées à travers les prismes des dialectes régionaux et des contextes culturels uniques, tout en maintenant un lien indéniable avec leur ancêtre commun.

Bien qu'issues d'une même racine latine, les langues romanes présentent une diversité remarquable qui se manifeste à travers plusieurs dimensions. Dans cette section, nous examinerons les principales différences qui caractérisent ces langues, notamment les variations phonétiques, les structures grammaticales distinctes et les particularités lexicales (3, 78).

Les variations phonétiques dans les langues romanes

L'une des différences les plus évidentes entre les langues romanes réside dans leurs variations phonétiques. Chaque langue a développé des caractéristiques sonores uniques au fil des siècles. Par exemple, en espagnol, les voyelles sont souvent plus claires et plus courtes qu'en français, où l'on trouve des voyelles nasales et des diphtongues. De plus, la prononciation des consonnes varie également ; le "c" en espagnol peut se prononcer comme un "s" ou un "k" selon le contexte, tandis qu'en italien, le "c" est généralement prononcé comme "tch" devant "i" ou "e". Ces différences phonétiques peuvent parfois rendre la compréhension mutuelle difficile entre locuteurs de différentes langues romanes.

Les distinctes grammaires et syntaxe dans les langues romanes

Les langues romanes diffèrent également par leurs structures grammaticales et syntaxiques. Par exemple, l'accord des adjectifs avec le nom est plus rigide en espagnol et en italien qu'en français, où certaines exceptions existent. En outre, l'utilisation des temps verbaux peut varier ; alors que le français utilise abondamment le passé composé, l'espagnol et l'italien préfèrent souvent le

passé simple dans la langue écrite. Ces distinctions grammaticales influent sur la manière dont les idées sont exprimées et structurées dans chaque langue.

Le lexique et les emprunts lexicaux dans les langues romanes

Le lexique des langues romanes est également une source de diversité. Bien que ces langues partagent un grand nombre de mots d'origine latine, elles ont également intégré des emprunts lexicaux provenant d'autres langues et cultures, ce qui a enrichi leur vocabulaire de manière unique. Par exemple, le français a intégré de nombreux mots d'origine anglo-saxonne en raison de son histoire coloniale et commerciale, tandis que le roumain a incorporé des termes slaves, grecs et turcs, reflétant son évolution géographique et historique (5, 26). Ces emprunts lexicaux, ainsi que les évolutions sémantiques, montrent comment chaque langue a su s'adapter à son contexte socioculturel spécifique.

En résumé, les différences entre les langues romanes sont marquées par des variations phonétiques, des structures grammaticales distinctes et un vocabulaire riche et diversifié. Ces éléments font de chaque langue romane une entité unique tout en préservant un lien indéniable avec ses sœurs. Dans la section suivante, nous explorerons les ressemblances qui unissent ces langues, malgré leurs différences apparentes.

Les ressemblances entre les langues romanes

Les langues romanes, bien qu'elles présentent une diversité impressionnante, partagent également de nombreuses ressemblances qui témoignent de leur origine commune et de leur évolution parallèle (7, 53). Ces similitudes peuvent être observées dans plusieurs domaines, notamment le lexique, la grammaire, et les influences culturelles.

Les racines communes et lexique partagé dans les langues romanes

L'une des caractéristiques les plus notables des langues romanes est la présence de racines communes. En raison de leur dérivation du latin vulgaire, ces langues possèdent un grand nombre de mots qui ont des origines similaires. Par exemple, le mot latin *aqua* pour *eau* est devenu *eau* en français, *acqua* en italien, *agua* en espagnol, et *água* en portugais. Cette continuité lexicale crée des ponts entre les différentes langues et facilite la compréhension mutuelle à un certain niveau. De plus, de nombreux termes techniques et scientifiques sont partagés entre les langues romanes, souvent en raison des échanges culturels et académiques tout au long de l'histoire. Ces emprunts lexicaux renforcent encore l'impression d'un patrimoine linguistique commun.

Les structures grammaticales similaires, les similitudes dans les langues romanes

Les langues romanes présentent également des structures grammaticales qui, bien que variées, montrent des similitudes significatives. Par exemple, la conjugaison des verbes suit des modèles qui, bien qu'ils diffèrent d'une langue à l'autre, conservent des traits communs. La distinction entre les modes (indicatif, subjonctif, impératif) et les temps (présent, passé, futur) est une caractéristique partagée qui reflète l'héritage latin (9, 21).

De plus, la construction des phrases dans les langues romanes suit souvent un schéma similaire, avec un ordre sujet-verbe-objet (SVO) prédominant, bien que des variations puissent exister. Ces structures communes facilitent l'apprentissage de ces langues pour les locuteurs d'autres langues romanes.

Les influences culturelles et historiques sur les langues romanes

Les ressemblances entre les langues romanes ne se limitent pas seulement à des aspects linguistiques, mais s'étendent également aux influences culturelles et historiques. Les échanges commerciaux, les conquêtes et les migrations ont favorisé une interaction continue entre les locuteurs des différentes langues romanes. Cela a permis une diffusion des idées, des arts et des traditions, renforçant ainsi les liens entre ces cultures. La littérature, la musique et l'art des pays romains montrent souvent des thèmes et des motifs similaires, enracinés dans des expériences historiques communes. Par exemple, le Moyen Âge a vu l'émergence de la poésie courtoise dans

plusieurs des langues romanes, créant ainsi un héritage culturel partagé qui perdure encore aujourd'hui.

En résumé, malgré leurs différences, les langues romanes partagent un socle commun qui est le fruit d'une histoire linguistique riche et complexe. Ces ressemblances sont essentielles pour comprendre non seulement la structure de ces langues, mais aussi leur rôle dans la formation de l'identité culturelle des peuples qui les parlent.

Conclusion

La famille des langues romanes représente un fascinant témoignage de l'évolution linguistique et culturelle qui a suivi la chute de l'Empire romain. À travers les siècles, ces langues ont subi des transformations notables, influencées par divers facteurs historiques, sociaux et géographiques. L'étude de leurs origines latines révèle non seulement la richesse du patrimoine linguistique européen, mais aussi la complexité des interactions entre les différentes cultures qui ont façonné ces langues.

Les différences observées entre les langues romanes, qu'il s'agisse des variations phonétiques, des structures grammaticales distinctes ou du lexique emprunté, témoignent de la diversité qui existe au sein de cette famille linguistique. Toutefois, il est essentiel de ne pas perdre de vue les ressemblances qui unissent ces langues. Les racines communes, les structures grammaticales similaires et les influences culturelles partagées soulignent un héritage linguistique qui transcende les frontières nationales (12, 39).

L'étude des langues romanes est ainsi une exploration des spécificités linguistiques, mais aussi une invitation à réfléchir sur les dynamiques culturelles et historiques qui continuent de façonner notre compréhension du monde aujourd'hui. La richesse de cette famille de langues, tant dans ses diversités que dans ses similitudes, offre une perspective précieuse sur l'évolution des sociétés humaines et leur capacité à s'adapter tout en préservant des éléments d'identité partagés.

Bibliographie

1. **Ducrot, O. & Todorov, T.** (1979). *Dictionnaire encyclopédique des sciences du langage*. Paris: Seuil.
2. **Harris, A. C. & Campbell, L.** (1995). *Historical Syntax in Cross-Linguistic Perspective*. Cambridge: Cambridge University Press.
3. **Grand Larousse de la langue française** (1971). Les langues romanes. Paris : Librairie Larousse.
4. **Léglise, I.** (2011). *Les langues romanes: histoire et structure*. Paris: Presses Universitaires de France.
5. **Lloyd, J.** (1999). *The Romance Languages*. Cambridge: Cambridge University Press.
6. **Meyer, C. F.** (2005). *English Corpus Linguistics: An Introduction*. Edinburgh: Edinburgh University Press.
7. **Ortega, M.** (2010). *La néologie dans les langues romanes*. Lyon: Presses Universitaires de Lyon.
8. **Roberts, I. & Roussou, A.** (2003). *Syntactic Change: A Comparative Study*. Cambridge: Cambridge University Press.
9. **Thomason, S. G. & Kaufman, T.** (1988). *Language Contact, Creolization, and Genetic Linguistics*. Berkeley: University of California Press.
10. **The Functions of Modal Verbs in French** I. Gassimova, A Aliyeva Porta Universorum 1 (10), 195-203 DOI: <https://doi.org/10.69760/portuni.0110020>
11. Functional properties of Phraseological units in French A Aliyeva - Sciences of Europe, (1) (111-116) 2023
12. **Martinet, A.** (1960). *Éléments de linguistique générale*. Paris : Armand Colin.

Қазақтың жер-су атауларының тарихи-танымдық маңызы

Бисенбаева Меруерт Кенжеғұлқызы

«Өрлеу» БАҰО АҚ Алматы облысы бойынша, кәсіби даму институты

Қуантаева Ақмарал Тұрсынбекқызы

Алматы облысы Талғар ауданы МЖДШО бар, №17 ОМ КММ

Иманалиева Алтынгүл Нурсалимовна

Алматы облысы Талғар ауданы МЖДШО бар, №17 ОМ КММ

Султанбаева Асел Зейнегабыловна

Алматы облысы Талғар ауданы МЖДШО бар, №17 ОМ КММ

Түйіндеме: Жер-су атаулары географиялық белгі ретінде адрестік қызмет атқарумен қатар, сол жерді мекендеген халықтың салт-дәстүрі, ой-санасы, рухани болмысының көріністерін бойына терең сақтаған танымдық және кумулятивтік маңызы зор мәдени құндылық болып та табылады.

Қай халықтың болмасын болмысы мен дүниетанымы, этникалық мәдениеті мен рухани өмірі қай кезде, қандай жағдайда болсын, белгілі бір географиялық кеңістікте көрініс табады, нақтылы тарихи дәуірлердің жемісі болып саналады. Ал халықтың барлық өмір-тіршілігі, ғасырлар бойы қалыптасқан мәдени, рухани байлығы болса, ең алдымен сол халықтың ана тілінен өз өрнегін табады да, асыл қазына болып қалыптасып, атадан балаға, ұрпақтан ұрпаққа ауысып отырады. Бұл - тіл атаулының бәріне тән объективті заңдылық, ортақ қасиет, сондықтан географиялық көне атаулар тарихи ескерткіштер іспетті, себебі өткен замандардың мұралары ретінде мемлекеттер мен халықтардың тарихының, жер жағдайларының, материалдық және рухани географиялық мәдениеттерінің белгілі бір тарихи кезеңдердегі келбетін, қалпын көрсетеді.

Тілдің өмірі тіл иесінің әлеуметтік өмірімен астарлас, өзектес, бірінсіз-бірі бола алмайтын құбылыс. Тілдің де сол халықпен бірге жасап келген тұрақ-мекені, өзен-көлі, тау-тасы, сай-саласы - адам өміріне қатысты оны қоршаған кеңістіктегі барлық нысан сол халықтың этникалық және азаматтық тарихымен бірге туып, біте қайнасқан дәуірлері болатыны шындық және осы табиғи тұтастық тарихи деректерден гөрі тіл байлығынан көбірек көрінеді деп есептеледі. Өйткені тарихи деректер әртүрлі себептермен сақталмауы да, сақталған күнде де анық жетпеуі мүмкін, ал тіл, оның деректері қанша дәуірді басынан өткізсе де, толассыз толығып, ғасырлар бойы жаңарып, жаңғырып отырса да, өткен өмірдің куәгері болуы сөзсіз деп есептеледі.

Кең-байтақ қазақ даласында әрбір тарихи кезеңде тілдері мен діни наным-сенімдері әртүрлі тайпалар мен рулар өмір сүріп, мекен етті, сонымен қатар көрші елдермен қарым-қатынас та ежелгі дәуірлерде-ақ болған. Қазақ тіліндегі жер-су атауларының тарихи-әлеуметтік қабаттары мен даму кезеңдерін: *көне түркілік (жалпы түркілік), қазақ тіліне тән төл және кірме* қабаты бойынша саралауға болады. Ал аймақтық топонимияда осы қатынас іздерімен қатар, сол аймақтың географиялық, шаруашылық ерекшеліктері болатыны айқын. Осыған орай, баяндамада қазақ жеріндегі топонимдердің кірме қабаты жайында айтылады.

Кілт сөздер: этномәдениет, топоним, ұлттық топонимдік кеңістік, топонимдік жүйе, этимология

Abstract: Geographical names, along with the fulfillment of the address function as a geographical mark, are a cultural value with cognitive and cumulative value, which deeply intake the traditions, consciousness and mind, as well as manifestations of the spiritual life of the people, who inhabited that locality.

Existence and world outlook, ethnic culture and spiritual life of any nation are always reflected in a certain geographical space and are the result of certain historical eras. All life activity, all the centuries-old cultural and spiritual wealth, first of all, are imprinted with a pattern in the native language of people of this locality, and turning into an invaluable treasure, passes from one generation to another. All this is an objective regularity, a common feature inherent to all languages in the world, therefore ancient geographical names are considered as a kind of historical monuments, since they, as heritage of past centuries, clearly show us the image of certain eras of history, conditions of the terrain, material and spiritual geographic culture of states and nations.

The existence of language is a process, which is closely related to the social life of the native speaker that can not exist without each other. Lands and settlements, rivers and lakes, mountains and rocks - just like language, are interconnected with man, all objects in the surrounding space are born with the ethnic and civil history of people of this locality, fuses with that period and this natural integrity is more often manifested not in the historical information, but in the richness of the language. This is related to the fact that historical information for various reasons may not be preserved, or be not completely reliable while preserving, while language, its information, no matter how many centuries and eras will pass, regardless of uninterrupted replenishment, countless updates and renewals, will remain undoubted proof of previous eras.

The immense Kazakh steppe was inhabited and settled by tribes and clans with different languages and religious beliefs and traditions in different historical periods, and relations with neighboring countries have also been maintained since ancient times. The historical and social layers and stages of the development of geographical names in the Kazakh language can be differentiated in the following layers: ancient Turk (common Turkish) layer, a native Kazakh words and layer of borrowed words. Undoubtedly, in the regional toponymy, the geographic, economic features of that region are imprinted in the footsteps of this connection. In this regard, the report includes the theme of the borrowed layer of toponyms that can be found on the Kazakh land.

Key words: ethnoculture, toponym, national toponymic space, toponymic culture, etymology.

Атамекен, жер-су атауларының этнос санасында бекіп қалыптасу жолы тым әріден басталады. Ол белгілі адамдар қауымының жетілумен тікелей байланысты. Ә. Т. Қайдардың пайымдауынша, «**этнос** - ғылым жүзінде: «өткен дәуірлерде дүниеге келіп, белгілі географиялық ортада қалыптасқан, шұғылданған тіршілік-тірлігі бірыңғай, мінез-құлқы ұқсас, діні де, тілі де бір, салт-дәстүрі мен әдет-ғұрпы ортақ, өзінің ортақ тегін, туыстығын, тұтастығын сезіне білетін, сатылап даму барысында аналық, аталық, рулық, тайпалық, ұлыстық және халықтық дәуірлерді басынан кешіріп, бүгінде дербес ел болып отырған адамдар қауымы» болып танылады [1,10-б.].

Бұл тұжырым **ұлт-этнотың** бүгінгі күнге жету жолы ұзақ: сайраған сара жолы да, кедір-бұдыр бұралаңы да бар дегенді аңғартады. Оладың әр қалтарыс-қатпарында халықтың тынысы, тіршілігі, өмірінің өзегі-мәдениеті, тарихы сияқты рухани, материалдық байлығы жатыр, солардың маңызды бөлігі жер-су атаулары болса, оның көне қабаты тарихтың хатындай сыр сақтаған байлығы болып табылады. Осының бәрі тіл арқылы жетеді, тіл арқылы өрнектеледі, тіл арқылы көрінеді. Этнос тарихы тіл тарихына қарағанда, өзгеруге азды-көпті икемді келеді: ол экстралингвистикалық, экономикалық, қоғамдық-әлеуметтік саяси себептерге байланысты болып келеді де, тіл және этнос арақатынасына елеулі әсерін тигізеді.

Кең-байтақ қазақ даласында әрбір тарихи кезеңде тілдері мен діни наным-сенімдері әртүрлі тайпалар мен рулар өмір сүріп, мекен етті, сонымен қатар көрші елдермен қарым-қатынас та ежелгі дәуірлерде-ақ болған. Соның бәрі тілдің лексикасында көрініс табады. Зерттеушілердің пікірінше, қазақ тілінің сөздік құрамындағы кірме сөздер, негізінен, араб, парсы, монғол, орыс тілдерінен енген болса [2,133-156 бб.], қазақ тілі лексикасындағы жалқы есімдер де құрамы мен құрылымы шығу тегі жағынан алуан түрлі. Т. Жанұзақов: «Қазақ халық географиялық терминдерінің бір сарасы басқа тілден енген болып табылады. Сол терминдердің қосылуы арқылы жасалған топонимдер де әр облыста кездесіп отырады. Сондай-ақ, жергілікті тілдерде қолданылатын аясы тар терминдер мен апеллативтер де ұшырасады», -деп, олардың араб, иран, монғол, орыс тілдерінен енген деп топтайды, **иран** тілдерінде тән: *абат, сеңгір, дара, кент, шаһар, дарат, қала, дар, мар, шуй, дария* т.б.; **араб** тілінен: *сайр, рабат, хасар*; **монғол** тілінен: *аймақ, арасан, арал, бақан*; **орыс** тілінен: *балка, село, станица, заимка, усть* т.б. сөздердің апеллатив ретінде жер-су атауларын жасауға қатысатынын көрсетеді [3,54-55-бб.].

Қазақ тілі ғылымында қазақ тілінің монғол тілдерімен қарым-қатынасы екі түрлі жағдайда қарастырылады. Оның алғашқысы - қазақ тіліндегі монғол тілдерінен тікелей ауысып кірген сөздер жайында екені анық, бұл екі халықтың ғасырлар бойы көршілес тұрып қарым-қатынас жасауы себеп болған. Сонымен қатар, XII ғасырда монғолдардың Қазақстан және Орта Азия жерін жаулап алып, ол жерлерде Шыңғыс әулеті билеген ұлыстар мен ордалардың ХҮ ғасырға дейін үстемдік етуінің әсері тиген. Тіпті, қазақ хандықтары ХҮ-ХҮІІІ ғасырларда да монғолдармен тегі бір Жоңғар қалмақтары қазақ жеріне үнемі шапқыншылық жасап отырғаны белгілі [4,146-б.].

Қазақ тіліне монғол тілдерінен сөз ауысу үдерісін монғол шапқыншылығымен ғана байланыстырмай, түркі және монғол тілдеріндегі ортақтықтан іздеу ХҮІІІ ғасырдағы түркітанушы ғалымдардың пікірлерінен бастау алады. Ш.Сарыбаев швед ғалымы И.Страленбергтің, шығыстанушы, этнограф, әйгілі ғалым Шоқан Уәлихановтың еңбектерінде түркі және монғол тілдерінің туыстығы жайында сөз қозғап, «түркі-монғолға ортақ сөздер» тіркестік атауын қолданғанын келтіреді және де қазақ тілі мен монғол тілдерін салыстыра зерттеу арқылы екі тілге ортақ лексиканың: *адамның дене мүшелері, азық-түлік, туыстық атаулар, киім-кешек, үй жануарлары, жабайы аң-құс жануарлар, құрал-жабдық, өсімдік, табиғат* т.б. тақырыптық топтарын анықтайды, бұлардың ішінде жер-су атауларын жасауға негіз болатын апеллативтер мол [5:141-176;537-539-бб.]. «...ортақ тілдік материалдардың бәрін түркі тілдерінен монғол тілдеріне немесе керісінше, монғол тілдерінен түркі тілдеріне енген, демек бір тілден екінші тілге ауысқан элементтер деп кесіп айту қиын. Олай дейтін себебіміз, әдетте,сөздік қор өзгергіш келетіні рас, ал тілдің грамматикалық құрылысы әлдеқайда тұрақты. Өзара туыс емес тілдер бір-бірінен жұрнақ, жалғау, есімдік, етістік, сын есім, еліктеуіш сөздерді мол көлемде қабылдай алмайды. Бұлар бір тілден екінші тілге ауыса бермейтін сөздер. Ауыса қалғанның өзінде бірен-саран сөздердің төңірегінен аспайды. Оның үстіне, әдетте, өз бойында көне тілдің ерекшеліктерін молырақ сақтап қалған *жер-су атауларының* құрамында монғол тіліне ұқсас көптеген сөздердің сақталып қалуы, монғол мен түркі тілдерінің туыстығына тағы бір дәлел бола алады» [5,539-б.],- деп түйін жасайды.Тілдердің туыстығын тек лексикалық элементтерді ортақтығымен дәлелдеу мүмкін емес, осыған орай, Ш.Сарыбаев: «Тілдердің туыстығын дәлелдейтін ең үлкен факт - тілдердің грамматикалық құрылысындағы ортақтық», -деп, *-шы/ші,-лық/лік, -ла/ле* жұрнақтарымен қатар, көптік жалғауының монғол тілінде *-нар* (ахнар-ағалар т.б.) қолданылатынын айта келе, «Бірақ дәстүрлі, атам заманнан келе жатқан байырғы ортақ лексиканың көпшілігін ауысып келген сөздер дегеннен гөрі түркі-монғол тілдерінің ежелгі бірлігінен туған сөздер деп есептеген дұрысырақ болар деп ойлаймыз»[5,538-539-бб.],- деген пайым жасайды.

Қазақ тіліне монғол тілінен кірген сөздер, негізінен, әкімшілік, ел билеуге байланысты, сонымен қатар, жер-су аттары да мол кездеседі. Жер-су атауларының тақырыптары әр алуан, олардың арасында жердің бедеріне, байлығына т.б. ерекшелігіне және тарихи оқиғаларға қатысты атаулар бар. А. Әбдірахмановтың еңбегінен көпшілікке белгілі: *Тарбағатай* (суырлы), *Қандағатай* (бұғылы), *Толағай* (бас), *Катонқарағай* (катонқайың), *Баянауыл* (Баин ола-Бай тау), *Долаңқара* (жеті тау), *Зайсан* (жақсы), *Нұра* (жыра), *Мұқыр* (шолақ, қысқа), *Қорғалжын* (қорғасын), *Қордай* (қарлы), *Алтай* (алтын тау), *Нұра* (көл, өзен), *Нарынқол* (жіңішке өзен) т. б. [6].

Түркі және монғол тілдерінің байланысын салыстырмалы тұрғыда зерттеуші Г.Сағидолданың пайымдауынша: «Қазіргі қазақ тіліндегі сан ондаған сөздердің түп-төркіні түркі монғол ортақтығына барып саятындығы, қайсы біреулері қазақ халқымен аралас-құраласта, қарым-қатынаста (саяси, әлеуметтік, жаугершілік т.б.) болған әрқилы халықтар тілінен енген кірме сөздер болып келетіндігі белгілі. Бұл құбылыс қазақ тілінің лексикалық жүйесінде сөздердің нақты категориясы ретінде орын алатын географиялық атауларға да қатысты болып келеді. Топонимдер (географиялық атаулар) тілдегі бар сөздер негізінде жасалатынын ескерсек, жер-су аттарының қыр-сыры, мән-мағынасы, қойылу себептері сияқты мәселелер, яғни топонимдер тарихы тіл тарихымен астасып жатары сөзсіз» [7, 3-б.].

Белгілі халықтың топонимиясының қалыптасуында географиялық орта, территориядағы этникалық құрам, халықтың дүниетанымы, тарихи оқиғалар, нақты территорияда өмір сүруші этностың діні, салты, дәстүрі әдет-ғұрпы, шаруашылығы, тұрмыстық тіршілік-тынысы т.б. факторлар негізгі роль атқаратыны белгілі. Осыған орай, Г. Сағидолда «... өткен өмір жолында алуан қилы тарихи оқиғаларды басынан кешірген, әрқилы халықтардың араласуы тым жиі болған қазіргі Қазақстан және Монғолия территориялары үшін топожүйелердің біртекті мүмкін емес. Қазақстан топонимиясы үшін «субстраттық, жалпытүркілік, қазақ тіліндегі, сондай-ақ әртүрлі тілдерден енген кірме атаулар негізіндегі топонимдік қат-қабаттылық тән болса, Монғолия топонимиясы - таза монғол тіліндегі атаулардан, тұңғыс-маньчжур және түркі тілдерінен енген кірме атаулардан тұрады» [7, 74-75-бб.], - деп тұжырымдайды.

Бұдан географиялық атаулардың қалыптасуында кірме элементтердің өзінің аралас келетіні тек араб, парсы тілдерінен ауысқан элементтерге ғана қатысты емес, өзге тілдермен қарым-қатынас нәтижесінің көрінісі де осындай екені аңғарылады. Бұл мәселеге қатысты Г. Сағидолда: «Қазақ топонимиясындағы жалпытүркілік және таза қазақ тілінде жасалған атаулар қабатына, сондай-ақ монғол топонимиясындағы таза монғол тілінен жасалған атаулар қабатына зер салсақ, оларды салыстыра барласақ, бұл атаулық қабаттарды құраушы топонимдердің көбісінің түп негізінде түркі-монғол ортақтығына алып баратын апеллатив лексика жатқандығын аңғарамыз» [7, 75-б.], - дейді. Осыған орай, қазақ және монғол топонимиясында кездесетін, екі басқа нысанға берілген, екі түрлі тілдік ортада пайда болған, атаулық тұрғыдан алғанда, әрқайсысы жеке-дара топоним қызметін атқарып жүрген, ішкі мазмұны мен сыртқы тұрпаты бірдей, бірімен-бірі апеллатив лексика тұрғысынан да сәйкес келіп жататын атауларды *гомогенді*, *тектес* топонимдар деп атайды. «Мұндай топонимдерге тереңдей үңілсек, оны жасауға қатысушы апеллатив лексиканың пайда болу, даму тарихы түркі-монғол ортақтығына барып саятындығын, ал топонимді мен атаулық мән-мағынасының табиғаты түркі, монғол халықтарының мәдени тарихи байланысына алып баратындығын аңғарамыз. Гомогенді топонимдер арқылы біз бұл екі халықтың өмір салтындағы, дүниетанымындағы, тұрмыс-тіршілігіндегі, діни наным-сенім, салт-дәстүр, ырым-рәсімдеріндегі ұқсас жақтарды барлай аламыз» [7, 88-б.], - дей келе, Г. Сағидолда қазақ-монғол топонимиясындағы ортақ гомогенді географиялық атаулар қатарына: *Алтынбұлақ/Алтанбұлағ*; *Харгол/Қарақол*; *Зост/Жосаты/Жезді/Зэст*; *Айғыржон/Азрагын нуруу*; *Өлеңті/Өлеңті*; *Алтынтау/Алтан уул*; *Көкоба/Хөховоо*; *Босаға*

тау/Босго уул; Шідерті/Чөөдөрөт; Қабырға тау/Хавирға уул; Қатынсу/Хатангол; Хантауы/ Хаануул; Қарағанды/Харғанат; Қарауылтөбе/Харуулыновоо; Алтай/ Алтай; Тамырсу/Тамиргол; Хантәңірі/Хантәңгэр; Мойылты/Мойлт; Қияқты/Хиягт тәрізділерді жатқызуға болады деп есептейді

Қазақ және монғол топонимдерінде орын алатын гомогенді топонимдердің пайда болу тарихы қазақ, монғол халықтарының көне мәдениетімен, оның тарихымен сабақтасып жатады. Екі халық өмір сүретін ландшафтағы ұқсастық, жан-жануар мен өсімдік әлемі, әлеуметтік- экономикалық, мәдени өмірдің кей ортақ белгілері т.б. факторлар қазақ және монғол топонимияларына ортақ пайда болуына негіз болды. Бұл,әсіресе, күн көріс көзі көшпелі мал шаруашылығына негізделгендіктен, осы салаға қатысты гомогенді топонимдердің саны біршама

Хан тәңірі - Тянь-Шанның орталық бөлігіндегі оқтай шаншылған, биіктігі 6995 метр биік шың, Қазақстан Республикасы мен Қырғызстанның шекарасында. Атаудың шығуы туралы Е. Қойшыбаев: «Көне түркі тайпаларының бірі тува түркілері де қазіргі Саян тауын *Хантәңірі* - «аспан тау» деп атаған. Бұл жайғдайлардан Біз *Хантәңірін* көне түркілердің «аспантау» мағынасындағы атауы деп айта аламыз» [8,233-б.],-деп тұжырымдайды. Т. Жанұзақов атаудың көне түркі тілінде *тангар/тәңрі* тұлғасында «көк», «аспан», «құдай» мағыналарын білдіргенін, осы мағынада монғол тілінде де *тэнэр* аталған мағынада қолданылатынын айтады. Ерте замандарда Тенгір көне түркілердің «еңбасты құдайы» саналғаны белгілі. Олардың әулие, құдайларын *Тенгри* (тәңірі), *Умай* (Умай), *Иер-Суб* (жер-су) атағаны жайында VIII-VIII ғасырлардағы Орхон ескерткіштерінде де жазылған. Т. Жанұзақов атау жөніндегі Клоссонның *тенгір* сөзін Хун, Үйсін дәуіріне жатқызып, оның «аспан», «әулиеге балаған көк» деген тұжырымын келтіре отырып, Хан тәңірі атауы «аспанмен таласқан, көкке тірелген биік тау», «аспан тәңірісі, құдайы» деген мағынада қойылған сияқты деп есептейді [3,192-193-бб.]. Аталған тұжырымдарды қолдауға себеп болған -текст атаулардың өзге түркі халықтарының жерінде кездесетіні. Атап айтқанда, Хакас жерінде *хан-тигр*, Кузнецк Алатауының оңтүстігінде, Минусин мен Кузнец ойпатының аралығында *Тигр Тізі* атты таулар, Алтайда *Тенери* - «көкаспан», *Тенери-айры* - «аспан айрығы» атты көлдер бары келтіріледі. Тау, көл атауларының «аспан», «көк», «құдай» мағынасы сол кездегі адамдардың отқа, аспанға, табиғатқа табынудан пайда болған наным-сеніміне байланысты қалыптасқан.

Алатау - тау, басы Хантәңірінен баталып, аяғы Шымкентке дейін созылып жатқан асқар биік, заңғар тау. Түркілер ежелгі замандардың өзінде-ақ биік шыңды, басында мәңгілік мұз бен аппақ қар жатқан тауларды *Алатау* атаған. Оны: *Кузбас Алатауы, Жоңғар Алатауы, Іле Алатауы, Қырғыз Алатауы, Тянь-Шань Алатауы* атаулары көрсетеді. Е. Қойшыбаев осы атаулардағы *ала* сөзінің мағынасы қазақ тіліндегі «ақ пен көктің аралас түсіне» қатысты емес, *ұлу* немесе одан да көнелеу *оло* тұлғасынан шығады деп есептейді [8,42-б.]. Демек, *Алатау* - «ұлы, аса зор, биік тау» деген мағынаға ие екені байқалады [3,152-б.].

Нарынқол - Райымбек ауданындағы өзен және осы өзеннің жағасындағы елді мекен. Т. Жанұзақов зерттеушілердің атаудың бірінші сыңары *нарын* сөзін монғол тіліндегі *нарийан* «жіңішке», ал екінші сыңарындағы *қол* «өзен» деген уәжді ұстанып келгенін айтады. Я. Бичурин еңбектеріндегі Қытай ескерткіштерінен оқылған үйсіндерге тән саналатын: *Дагань, Тархан, Чаян, Бури (бөрі), Ақа, Жосы, Аран, Ши, Сойыс, Тау, Нор, Темір, Темірлік, Күңгел, Нарын, Долос, Талас, Қарқара, Ақсай*, т.б. атаулардың қазіргі сөйлеу тілінде бәрінің де қолданыс табатынын көрсетеді. [3,121-122-бб.]. Райымбек ауданындағы:*Темірлік, Нарынқол, Қарқара, Ақсай, Талас* атауларының сақталып бұл күнге жетуі ғаламат құбылыс екені сөзсіз. Осы деректерге қарай, Т. Жанұзақов *Нарын* тек үйсін сөзі емес, жалпы түркі тіліне ортақ сөз деп таниды. Якут тілінде *нарын* «жіңішке, нәзік» мағынасын білдірсе, *Нарын құмы* (Еділ-Орал өзендері аралығында), *Нарын өзені* (Сырдарияның жоғарғы ағысында, Тувада), *Нарын тауы* (Қырғызстанда)т.б.

Нарынқол атауының екінші сыңарындағы **қол** -«өзен, өзен тарамы, сай» мағынасындағы көне түркі сөзі, ол Мойын Чор ескерткішінде кездеседі. Сондықтан **Нарын** атауы тек монғол тіліне тән демей, монғол, түркі тіл бірлігі кезіне ортақ сөз, атау ретінде қарауды ұсынады. Демек, **Нарынқол** атауы - «жіңішке өзен» мағынасын білдіретін ерте заманнан келе жатқан атау деп тұжырымдайды [3,121-122-бб.].

Бұл деректерге қарағанда, өзен аты оның тұрпатына қарай қойылған деп түсіну керек, **Нарынқол** кең арналы өзен емес, ені шағын, жіңішке. Атаудың түркі тілдерінде ұшырасуы - оның көнелігінің көрінісі, ал ол таза түркі тіліне тән атау ма, монғол тіліне тән бе деген мәселе әлі де анықтауды қажет етеді. Және де түркі тілдері мен монғол тілдері арасындағы ортақтықты жоққа шығармайды. Жалпы, қазіргі күні белгілі бір атауды бір семьяға жататын тілдерің біреуіне ғана үзілді-кесілді таңып бекіту аса қиын екені көрінеді.

Шарын - Ұйғыр ауданындағы өзен, көне түркі тілінде - *чаран* -«арынды, тасқынды, екпінді, қарқынды өзен» Қырғыз тілінде *шар* - «жылдам, тез, арынды ағыс», монғол тілінде *царга* -«арынды, асау, тентек». Демек, өзен аты түркі, монғол тілдеріне ортақ келіп, «арынды, қарқынды, екпінді, тасқынды» деген мағынаны білдірген [3,134-б.]. Атау қойылған есте жоқ ескі заманда бұл өзеннің өткел бермес асау болғаны анық.

Сөйтіп, монғол тілдік қатарға: *Хантәңірі, Кербұлақ, Қастек, Егінді, Нарын, Нарынқол, Қарқара, Шарын, Қошқар* т. б. атаулар қазақ және монғол тілдеріне ортақ ұғымдарға қатысты жасалғаны байқалады, кей жағдайда көне түркілік элементтер де араласады, олардың нақты шекарасын ашу әзірге қиындау. Бұның себебін Г.Сағидолдақызы түркі, монғол халықтарының ұзақ уақытқа созылған трихи қарым-қатынасы, мал шаруашылығына негізделген көшпелі өмір салтындағы ортақтық, территориялық аралас-құраластық т.б. арқылы түсіндіреді [7,59-б.], өйткені бұл халықтардың тілдерінде де өз бейнесін, өз таңбасын қалдырғаны даусыз. Мұндай экстралингвистикалық факторлар монғол тілдерінен түркі тілдеріне, түркі тілдерінен монғол тілдеріне тілдік элементтердің енуін, өзара алмасуын, ауысуын қамтамасыз еткен.

Қазақ топонимиясының негізгі өзегін қазақ тілінде жасалған атаулар құрайды, осы қазақ атауларының жасалуына негіз болған апеллатив лексика мен халықтық географиялық терминдердің бірқатары түркі және монғол тілдеріне ортақ лексика болып келеді. Сонымен қатар, қазақ топонимиясында монғол текті кірме атаулар молынан кездеседі. Ал монғол топонимиясы құрамында да түркі тектес атаулар, монғолдың төл атаулары болып есептелетін түркі-монғол параллельдері негізінде жасалған топонимдер, атау жасау процесіне актив қатысатын түркі-монғолға ортақ географиялық терминдер орын алады.

Әдебиеттер

1. Қайдар Ә. Т. Қазақ тілінің өзекті мәселелері.-Алматы:Ана тілі,1998.-304 б.
2. Жанұзақ Т. Жер-су атаулары (этимологиялық анықтамалық).- Алматы: Арыс, 2005.-256 б.
3. Әбдірахманов А. Топонимика және этимология. - Алматы: Ғылым,1975.-206 б.
4. Қойшыбаев Е. Основные типы топонимов Семиречья. Автореф. дисс. канд. филол. наук. Алматы, 1967.-24 с.
5. Щербак А.М. Введение в сравнительное изучение тюркских языков.- Санкт-Петербург: Наука,1994.-191 с.
6. Болғанбайұлы Ә., Қалиұлы Ғ. Қазіргі қазақ тілінің лексикологиясы мен фразеологиясы.- Алматы:Санат,1997.- 256 б.
7. Сарыбаев Ш.Ш. Қазақ тіл білімінің мәселелері.-Алматы:Арыс,2000.- 624 б.
8. Сағидолда Г. Түркі (қазақ) және монғол халықтарының тарихи-мәдени байланыстарының топонимияда бейнеленуі. - Алматы: ЖШС Полиграфист, 2000.-254 б.

Biological Sciences

БИОЛОГИЧЕСКАЯ РЕМЕДИАЦИЯ НЕФТЕЗАГРЯЗНЁННЫХ ПОЧВ С ИСПОЛЬЗОВАНИЕМ МИКРОБНОГО КОНСОРЦИУМА

Алдибай Салтанат Нурланқызы

Магистрант, Евразийский национальный университет имени Л.Н. Гумилёва, Астана, Казахстан.

Мухтаров Абилхас Капизович

Кандидат химических наук, доцент, Евразийский национальный университет имени Л.Н. Гумилёва, Астана, Казахстан.

Аннотация

В работе исследована эффективность биологической ремедиации нефтезагрязнённых почв с использованием микробного консорциума. Объектом исследования служили почвенные образцы, отобранные на территории Мангистауской области Республики Казахстан. В состав разработанного биопрепарата вошли представители родов *Rhodococcus*, *Pseudomonas* и *Acinetobacter*, обладающие высокой способностью к деградации нефтяных углеводородов.

Эксперимент проводился в лабораторных условиях в течение 30 суток. Оценивались изменения содержания нефтяных углеводородов, концентрации тяжёлых металлов, а также физико-химические и биологические свойства почвы. Установлено, что применение биопрепарата способствует значительному снижению содержания нефтепродуктов - более чем в 2–3 раза по сравнению с исходным уровнем. Одновременно наблюдалось уменьшение концентрации тяжёлых металлов и улучшение агрохимических показателей почвы.

Отмечено смещение pH в сторону нейтральных значений, увеличение содержания гумуса и рост микробиологической активности в несколько раз. Полученные результаты свидетельствуют о том, что использование микробного консорциума обеспечивает не только деградацию загрязнителей, но и восстановление функционального состояния почвенной экосистемы. Разработанный биопрепарат может рассматриваться как перспективное средство для комплексной биологической ремедиации нефтезагрязнённых почв.

Ключевые слова: биоремедиация, нефтезагрязнённые почвы, микробный консорциум, нефтеокисляющие микроорганизмы, деградация углеводородов, почвенная микробиота, биопрепараты.

Введение

Загрязнение почв нефтью и нефтепродуктами на сегодняшний день остаётся одной из наиболее актуальных экологических проблем, особенно для регионов с развитой нефтедобывающей и нефтеперерабатывающей промышленностью. В процессе добычи, транспортировки и хранения нефти неизбежно происходят утечки, аварии и хронические

загрязнения, которые приводят к накоплению углеводов в почвенной среде. Со временем такие загрязнения приобретают устойчивый характер и оказывают длительное негативное воздействие на экосистемы [1].

Нефтяные углеводороды существенно изменяют свойства почвы. Они нарушают её структуру, ухудшают водно-воздушный режим, снижают доступность питательных веществ и подавляют развитие почвенной микрофлоры. В результате происходит деградация почвенного покрова, снижение биологической активности и ухудшение условий для роста растений. При длительном воздействии это может приводить к практически полной утрате функциональности почвы как экологической системы [2].

Нефтяное загрязнение часто сопровождается накоплением тяжёлых металлов, что ещё больше усложняет ситуацию. Такие элементы, как кадмий, свинец, хром и другие, обладают токсичными свойствами и способны накапливаться в почве, переходя по трофическим цепям в растения и далее в организмы животных и человека. Таким образом, проблема приобретает не только экологическое, но и санитарно-гигиеническое значение [3].

Традиционные методы очистки загрязнённых почв, включая механические и химические способы, несмотря на свою эффективность в отдельных случаях, имеют ряд существенных недостатков. Они могут быть дорогостоящими, энергоёмкими, а также приводить к дополнительному нарушению почвенной структуры. В ряде случаев такие методы не обеспечивают полного удаления загрязнителей или сопровождаются образованием вторичных отходов [4,5].

В связи с этим всё большее внимание уделяется биологическим методам ремедиации, основанным на использовании микроорганизмов, способных разлагать нефтяные углеводороды. Биоремедиация рассматривается как экологически безопасная и экономически целесообразная альтернатива традиционным технологиям. Микроорганизмы используют углеводороды в качестве источника углерода и энергии, превращая их в менее токсичные соединения, что способствует постепенному восстановлению почвы [6,7].

Особый интерес представляет использование микробных консорциумов, включающих несколько видов микроорганизмов с различными метаболическими возможностями. В отличие от отдельных штаммов, консорциумы способны обеспечивать более полную деградацию сложных смесей углеводов, так как разные микроорганизмы участвуют в разложении различных фракций нефти. Кроме того, такие системы обладают большей устойчивостью к изменяющимся условиям среды [8].

Несмотря на значительное количество исследований в данной области, остаются нерешённые вопросы, связанные с подбором эффективных штаммов, оптимизацией состава биопрепаратов и оценкой их воздействия на почвенную экосистему в целом [9]. В частности, важно учитывать не только степень удаления загрязнителей, но и восстановление биологической активности почвы, что является ключевым показателем её экологического состояния.

В условиях Мангистауской области Республики Казахстан проблема нефтяного загрязнения почв имеет особую актуальность. Интенсивное развитие нефтегазового комплекса в регионе сопровождается высоким уровнем антропогенной нагрузки на окружающую среду. Поэтому поиск эффективных и экологически безопасных методов ремедиации загрязнённых почв является важной научной и практической задачей.

Целью данной работы является исследование эффективности биологической ремедиации нефтезагрязнённых почв с использованием микробного консорциума. Для достижения поставленной цели были сформулированы следующие задачи: выделение и идентификация нефтеокисляющих микроорганизмов, разработка состава биологического

препарата, а также оценка его влияния на содержание нефтяных углеводородов, тяжёлых металлов и основные свойства почвы.

Материалы и методы

Исследования проводились на образцах почвы, отобранных на территории Мунайлинского района Мангистауской области Республики Казахстан. Выбор данного региона был обусловлен его высокой техногенной нагрузкой, связанной с добычей и транспортировкой нефти. Отбор проб осуществлялся с поверхностного горизонта почвы (0-20 см) с соблюдением общепринятых требований к почвенным исследованиям.

Перед началом эксперимента образцы почвы были гомогенизированы и очищены от посторонних включений. Далее проводилось их разделение на контрольные и опытные варианты.

Выделение и культивирование микроорганизмов

Для выделения нефтеокисляющих микроорганизмов использовались селективные питательные среды, позволяющие отбирать штаммы, способные использовать нефть в качестве единственного источника углерода и энергии. В процессе работы применялись следующие среды:

Таблица 1 - Используемые питательные среды

№	Наименование среды	Тип среды	Назначение
1	Минеральная среда Ворошилова–Диановой	Жидкая	Выделение нефтеокисляющих микроорганизмов
2	Агаризованная среда Чапека	Твердая	Получение чистых культур и отдельных колоний

Минеральная среда Ворошилова–Диановой не содержит органических источников углерода, поэтому в нее дополнительно вносилась нефть, выступающая единственным субстратом для роста микроорганизмов. Такой подход позволил отобрать наиболее активные нефтеокисляющие формы.

После первичного отбора культуры переносились на агаризованную среду Чапека, где проводилось выделение чистых штаммов и получение отдельных колоний для дальнейшего анализа.

Формирование микробного консорциума

На основе выделенных штаммов был сформирован микробный консорциум, включающий представителей родов:

- *Rhodococcus sp.*
- *Pseudomonas sp.*
- *Acinetobacter sp.*

Выбор данных микроорганизмов обусловлен их высокой способностью к деградации углеводородов нефти и широким распространением в природных экосистемах. Особенностью консорциума является его функциональная разнородность — разные штаммы участвуют в разложении различных фракций нефти, включая алифатические и ароматические соединения.

Идентификация выделенных микроорганизмов проводилась на основе анализа генов 16S рРНК и *gyrB*. Полученные последовательности сравнивались с базами данных, что позволило определить таксономическую принадлежность штаммов. Полученные результаты подтверждают, что консорциум состоит из высокоактивных нефтеокисляющих

микроорганизмов с высокой степенью генетического сходства. На основе выделенного микробного консорциума был разработан жидкий биологический препарат.

Таблица 2 - Состав биопрепарата

Компонент	Содержание, %	Функция
Микробный консорциум	10	Дегградация нефтяных углеводородов
Стерильная вода	70	Дисперсионная среда
Калий гумат	10	Стимуляция микробиологической активности
Глицерин	5	Стабилизация клеток
Меласса	5	Источник органического питания

Полученный препарат представляет собой жидкую форму, обеспечивающую равномерное распределение микроорганизмов в почве и создание благоприятных условий для их активности.

Эксперимент проводился в лабораторных условиях в течение 30 суток. Почвенные образцы были разделены на следующие варианты:

- контроль (без внесения препарата),
- опыт 1 - биопрепарат в концентрации 1%,
- опыт 2 - биопрепарат в концентрации 2%.

Поддерживались оптимальные условия влажности и температуры, способствующие развитию микроорганизмов. Для оценки эффективности ремедиации использовались следующие методы: содержание нефтяных углеводородов - методом газовой хроматографии; концентрация тяжёлых металлов - методом атомно-абсорбционной спектрометрии; pH почвы - потенциометрическим методом; содержание гумуса - по стандартным агрохимическим методикам; микробиологическая активность - методом подсчёта колониеобразующих единиц (КОЕ/г).

Результаты и обсуждение

В ходе проведённого исследования была выполнена комплексная оценка влияния разработанного микробного биопрепарата на состояние нефтезагрязнённой почвы. Особое внимание уделялось не только снижению содержания загрязняющих веществ, но и изменению основных физико-химических и биологических характеристик почвенной среды. В целом полученные результаты показали, что внесение биопрепарата приводит к заметным и достаточно устойчивым изменениям уже в течение 30 суток. Причём эффект носит комплексный характер и затрагивает сразу несколько взаимосвязанных параметров.

Изменение основных показателей почвы

Одним из первых оцениваемых параметров была реакция почвенной среды (pH), поскольку именно она во многом определяет активность почвенной микрофлоры и доступность питательных элементов.

Таблица 3 - Изменение основных показателей почвы

Показатель	Исходное состояние	Контроль	Биопрепарат (1%)	Биопрепарат (2%)
pH	8,0	7,7	7,2	7,1
Гумус, %	7,7	7,6	8,6	9,3
Микробиологическая активность, КОЕ/г	$1,1 \times 10^6$	$2,4 \times 10^6$	$3,7 \times 10^6$	$5,0 \times 10^6$

Как видно из представленных данных, исходная почва характеризовалась слабощелочной реакцией. В контрольном варианте за 30 суток наблюдается лишь незначительное снижение pH, что, скорее всего, связано с естественными процессами стабилизации. Однако в опытных вариантах изменение выражено значительно сильнее - реакция среды смещается в сторону значений, близких к нейтральным. На первый взгляд, разница в несколько десятых долей pH может показаться несущественной. Но в реальности именно такие изменения создают более благоприятные условия для развития микроорганизмов, особенно тех, которые участвуют в разложении органических загрязнителей.

Не менее показательной является динамика содержания гумуса. В опытных вариантах его количество возрастает, причём наиболее выраженный эффект наблюдается при внесении биопрепарата в концентрации 2%. Это может свидетельствовать об активизации процессов гумусообразования, а также о накоплении продуктов микробного метаболизма.

Отдельного внимания заслуживает показатель микробиологической активности. В исходной почве он был относительно низким, что типично для загрязнённых экосистем. После внесения биопрепарата наблюдается резкий рост численности микроорганизмов - в 2-4 раза по сравнению с исходным уровнем.

Динамика содержания нефтяных углеводов

Ключевым показателем эффективности ремедиации является изменение содержания нефтяных углеводов в почве.

Таблица 4 - Динамика содержания нефтепродуктов в почве

Вариант	Начальное содержание, г/кг	15 суток	30 суток
Контроль	5,9	5,4	5,1
Биопрепарат (1%)	5,9	3,6	2,4
Биопрепарат (2%)	5,9	3,1	1,9

В контрольном варианте снижение содержания нефтепродуктов происходит медленно и не превышает естественного уровня самоочищения. Даже спустя 30 суток сохраняется значительная часть исходного загрязнения.

Совершенно иная картина наблюдается при использовании биопрепарата. Уже на промежуточном этапе (15 суток) фиксируется заметное уменьшение концентрации углеводов. К концу эксперимента степень очистки становится ещё более выраженной.

При этом увеличение концентрации биопрепарата приводит к дополнительному усилению эффекта. Однако стоит отметить, что разница между 1% и 2% вариантами уже не столь значительна, как между контролем и обработкой. Возможно, это указывает на существование определённого «порогового» уровня эффективности, после которого дальнейшее увеличение дозы даёт ограниченный прирост результата.

С точки зрения микробиологии, такие результаты можно объяснить активным использованием углеводов в качестве источника углерода и энергии. При этом разные микроорганизмы консорциума, вероятно, участвуют в разложении различных фракций нефти, обеспечивая более полную деградацию загрязнителя. Помимо органических загрязнителей, важным аспектом исследования было изучение динамики тяжёлых металлов.

Таблица 5 - Изменение содержания тяжёлых металлов в почве

Металл	Исходное значение	Контроль	Биопрепарат (1%)	Биопрепарат (2%)
Cd	0,95	0,82	0,53	0,44
Pb	5,2	5,0	3,3	2,5
Cr	5,3	4,8	3,1	2,5
Zn	21,8	21,0	14,5	9,8
Cu	2,9	2,5	1,9	1,4

Результаты показывают, что даже при относительно коротком сроке эксперимента наблюдается снижение содержания тяжёлых металлов в почве. В контрольных образцах изменения минимальны, что свидетельствует о слабой способности почвы к самоочищению от данного типа загрязнителей.

В вариантах с биопрепаратом снижение выражено значительно сильнее. Особенно это заметно для таких элементов, как цинк и свинец. При повышении концентрации препарата эффект усиливается, что указывает на зависимость процесса от активности микробного сообщества. Микроорганизмы способны связывать и фиксировать тяжёлые металлы, переводя их в менее доступное и менее токсичное состояние. Такие процессы, как биосорбция, образование комплексов и осаждение, играют здесь ключевую роль.

Заключение

В результате проведённого исследования установлено, что разработанный микробный биопрепарат на основе консорциума нефтеокисляющих микроорганизмов (*Rhodococcus*, *Pseudomonas*, *Acinetobacter*) является эффективным средством биологической ремедиации нефтезагрязнённых почв.

Экспериментальные данные показали, что применение биопрепарата способствует существенному снижению содержания нефтяных углеводородов в почве. В отличие от естественных процессов самоочищения, протекающих медленно и ограниченно, использование микробного консорциума обеспечивает ускоренную деградацию загрязнителей. При этом повышение концентрации препарата сопровождается усилением эффекта, хотя зависимость не носит строго линейного характера.

Одновременно с этим отмечено снижение содержания тяжёлых металлов, что свидетельствует о дополнительном экологическом эффекте биопрепарата. Вероятно, данный процесс обусловлен способностью микроорганизмов к биосорбции и переводу металлов в менее подвижные формы, что снижает их токсичность и доступность для растений.

Важным результатом является положительное влияние биопрепарата на физико-химические и биологические свойства почвы. Зафиксировано смещение реакции среды в сторону нейтральных значений, увеличение содержания гумуса и значительный рост микробиологической активности. Последний показатель особенно показателен, поскольку отражает восстановление жизнеспособности почвенной экосистемы.

В целом полученные результаты позволяют рассматривать разработанный биопрепарат не только как средство удаления нефтяных загрязнений, но и как фактор комплексного восстановления почвенной среды. Перспективы дальнейших исследований могут быть связаны с изучением эффективности препарата в полевых условиях, оптимизацией его состава и оценкой длительного воздействия на почвенные экосистемы в различных климатических и техногенных условиях.

Список литературы

- 1 Yarzabal L. A., Chica E. J. Microbial-based technologies for improving smallholder agriculture in the Ecuadorian Andes: current situation, challenges, and prospects //Frontiers in Sustainable Food Systems. – 2021. – T. 5. – C. 617444.
- 2 El-Saadony M. T. et al. Plant growth-promoting microorganisms as biocontrol agents of plant diseases: Mechanisms, challenges and future perspectives //Frontiers in plant science. – 2022. – T. 13. – C. 923880.
- 3 Seenivasagan R., Babalola O. O. Utilization of microbial consortia as biofertilizers and biopesticides for the production of feasible agricultural product //Biology. – 2021. – T. 10. – №. 11. – C. 1111.
- 4 Sammauria R. et al. Microbial inoculants: potential tool for sustainability of agricultural production systems //Archives of microbiology. – 2020. – T. 202. – №. 4. – C. 677-693.
- 5 Aamir M. et al. Microbial bioformulation-based plant biostimulants: A plausible approach toward next generation of sustainable agriculture //Microbial endophytes. – Woodhead Publishing, 2020. – C. 195-225.
- 6 Elnahal A. S. M. et al. The use of microbial inoculants for biological control, plant growth promotion, and sustainable agriculture: A review //European Journal of Plant Pathology. – 2022. – T. 162. – №. 4. – C. 759-792.
- 7 Khoshru B. et al. Current scenario and future prospects of plant growth-promoting rhizobacteria: an economic valuable resource for the agriculture revival under stressful conditions //Journal of Plant Nutrition. – 2020. – T. 43. – №. 20. – C. 3062-3092.
- 8 Pan X. et al. Nanobiopesticides in sustainable agriculture: developments, challenges, and perspectives //Environmental Science: Nano. – 2023. – T. 10. – №. 1. – C. 41-61.
- 9 Khan N. et al. Current progress and future prospects of agriculture technology: Gateway to sustainable agriculture //Sustainability. – 2021. – T. 13. – №. 9. – C. 4883.

Microwave-Synthesized Multicomponent Nanoparticle-Drug Combinations as Selective Adjuvants for Proton Therapy in Non-Small Cell Lung Cancer

David Aphkhazava

PhD, Professor, University of Georgia, Tbilisi, Georgia. Orcid: <https://orcid.org/0000-0001-6216-64>

Babry Oren

Founder and CEO, Folium pX, USA

Archil Chirakadze

PhD, Georgian Technical University Institute "Techinform", Tbilisi, Georgia, Georgian Technical University Institute of Cybernetics, Tbilisi, Georgia, Ivane Javakhishvili Tbilisi State University Institute of Physics, Tbilisi, Georgia

Nodar Mitagvaria

Professor, Dr., Academician of Georgian National Academy of Sciences. Ivane Beritasvili Center of Experimental Biomedicine, Tbilisi, Georgia

Neli Makhviladze

PhD, Director of Institute "Techinformi", Georgian Technical University, Tbilisi, Georgia

Marina Devdariani

Department of Blood Circulation and Metabolism, Ivane Beritashvili Center of Experimental Biomedicine, Tbilisi, Georgia

Irina Bedinashvili

Georgian Technical University, Tbilisi, Georgia

Mzia Tsiklauri

PhD, Affiliated Professor of the Medical Programs of Gr. Robakidze University, Microbiology, Immunology, Virology, Infection Control. Invited Professor of the Medical Programs of Alte University, Tbilisi, Georgia. Invited Professor of the Medical Programs of Caucasus International University, Laboratory Medicine, Tbilisi, Georgia. Member of the Georgian Immunologists Association, Member of the Accreditation Council of the Quality Development, Center of the Ministry of Education of Georgia

Manana Makharadze

Prof. David Agmashenebeli University of Georgia, Tbilisi, Georgia.

Nodar Sulashvili

MD, PhD, Doctor of Pharmaceutical and Pharmacological Sciences In Medicine, Invited Lecturer (Professor) of Scientific Research-Skills Center at Tbilisi State Medical University; Professor of Medical and Clinical Pharmacology of International School of Medicine at Alte University; Professor of Pharmacology of Faculty of Medicine at Georgian National University SEU, Associate Affiliated Professor of Medical Pharmacology of Faculty of Medicine at Sul Khan-Saba Orbeliani University; Associate Professor of Medical Pharmacology at School of Medicine at David Aghmashenebeli University of Georgia; Associate Professor of Biochemistry and Pharmacology Direction of School of Health Sciences at the University of Georgia. Associate Professor of Pharmacology of Faculty of «Research Retrieval and Academic Letters» (April 2-3, 2026). Warsaw, Poland 427 Dentistry and Pharmacy at Tbilisi Humanitarian Teaching University; Tbilisi, Georgia; Orcid: <https://orcid.org/0000-0002-9005-8577>.

Priyanka Haibat Khadake

Alte University, Tbilisi, Georgia

Tanvi Naresh Patil

Alte University, Tbilisi, Georgia

Ganesh Ratnakar Narawane

Alte University, Tbilisi, Georgia

Corresponding author: Professor David Aphkhazava

Abstract

Non-small cell lung cancer remains the principal contributor to lung-cancer mortality worldwide, and durable local control continues to be constrained by the need to protect the surrounding thoracic organs while overcoming tumor-specific resistance mechanisms. Proton therapy offers a compelling physical solution because the Bragg peak permits steep dose fall-off and reduced exit dose, but the biological effectiveness of treatment in non-small cell lung cancer is still limited by heterogeneity in redox state, DNA-damage repair capacity, hypoxia, and stromal protection. The present manuscript describes a proton-therapy-oriented preclinical platform based on microwave-synthesized copper oxide and zinc oxide nanodispersions combined with clinically familiar drug backbones, especially gemcitabine plus cisplatin and carboplatin plus paclitaxel. Selectivity was examined by comparing A549 non-small cell lung cancer cells with normal human dermal fibroblasts, and biological effects were quantified by MTT viability testing together with Annexin V-FITC/propidium iodide analysis of apoptosis and necrosis. Acute translational safety was further explored in chick embryos and Wistar rats. Across the tested multicomponent formulations, cancer-cell selectivity increased by approximately 3- to 7-fold relative to conventional components used alone while preserving the existing safety profile, and the strongest gemcitabine-cisplatin-centered combinations exceeded gemcitabine control by 8.7- to 15.2-fold. These findings are mechanistically consistent with literature showing that oxide nanoparticles can intensify oxidative stress, ion imbalance, mitochondrial dysfunction, and DNA injury, thereby magnifying the effectiveness of established antitumor regimens in biologically vulnerable tumor cells. The broader thoracic-oncology literature supports the translational rationale for this approach because proton therapy can substantially improve dose shaping in lung cancer, yet still benefits from selective biological intensification, and contemporary nanomedicine studies continue to highlight radiosensitization, metal-based enhancement, iron-oxide multifunctionality, boron-oriented proton concepts, and receptor-guided delivery as promising

routes for improving therapeutic ratio. Taken together, the data support microwave-synthesized nanoparticle-drug combinations as a practical and scalable strategy for selective intensification of future proton-based treatment in non-small cell lung cancer, while also identifying the next developmental priorities as receptor-targeted uptake, mechanistic biomarker validation, rigorously specified proton-irradiation experiments, and advanced in vivo efficacy studies.

Keywords

non-small cell lung cancer; proton therapy; microwave synthesis; copper oxide nanoparticles; zinc oxide nanoparticles; radiosensitization; gemcitabine; cisplatin; carboplatin; paclitaxel; selective toxicity; folate receptor alpha

Introduction

Non-small cell lung cancer (NSCLC) accounts for the large majority of lung malignancies and remains difficult to cure because treatment success is determined not only by tumor control but also by preservation of surrounding thoracic structures, including uninvolved lung parenchyma, heart, esophagus, spinal cord, brachial plexus, and mediastinal tissues. This therapeutic challenge has made NSCLC a central disease site in the evolution of conformal radiation technologies. Reviews dedicated to proton therapy in thoracic oncology consistently conclude that NSCLC is unusually well suited to benefit from highly shaped dose deposition, particularly when tumors are centrally located, large, recurrent, or adjacent to dose-limiting organs, yet the same literature also emphasizes that durable gains in outcome depend on more than geometric precision alone (Mesko et al., 2018; Brooks et al., 2019; Harada et al., 2017; Nichols et al., 2012; Chang et al., 2005).

The appeal of proton therapy derives from the Bragg peak, which allows energy deposition to be concentrated within the target with rapid dose fall-off beyond the tumor. In thoracic practice, this property can reduce unnecessary irradiation of the heart and lungs, limit integral dose, facilitate treatment of complex target volumes, and improve the feasibility of dose escalation or re-irradiation in selected patients. Consensus statements and institutional experiences have identified potential benefits in early-stage disease, postoperative settings, locally advanced tumors treated with concurrent systemic therapy, and recurrent disease requiring highly individualized planning. However, improved dose distribution does not automatically guarantee a proportionate improvement in tumor eradication because the biological barriers to response remain substantial, including hypoxia, stem-like tumor cell populations, intrinsic repair proficiency, and the protective effects of the tumor microenvironment (Doyen et al., 2016; Liao et al., 2018; Chang et al., 2016; Schild et al., 2014; Patel et al., 2021; Lazarev et al., 2021).

This distinction between physical precision and biological adequacy is especially important in NSCLC. A treatment plan may achieve excellent conformity while still encountering residual resistance at the cellular level, particularly in heterogeneous tumors with variable metabolic states and uneven vascularity. Comparative studies of proton and photon therapy have shown encouraging reductions in dose to organs at risk, but they have also reinforced the conclusion that the therapeutic window can be widened further if the biological susceptibility of malignant tissue is selectively increased rather than if normal tissues are simply exposed to less collateral dose. In other words, the next major step in thoracic proton therapy is likely to come from biologically informed intensification strategies that complement dosimetric gains instead of merely depending on them (Chen et al., 2023; Volpe et al., 2022; He et al., 2024; Zou et al., 2020; Boyce-Fappiano et al., 2021; Shepherd et al., 2018; Schonewolf et al., 2021).

Nanoparticle-enabled radiosensitization has emerged as one of the most promising ways to accomplish this goal. Across multiple material classes, radiosensitizing nanoparticles have been shown to influence secondary-electron generation, reactive oxygen species accumulation, lipid peroxidation, mitochondrial injury, lysosomal dysfunction, and DNA-damage complexity. Their

value lies not only in their physicochemical properties but also in their ability to exploit malignant-cell vulnerabilities, such as elevated basal oxidative stress, altered metal handling, disordered antioxidant balance, and enhanced endocytic activity. Recent reviews focused on ionizing radiation and nanomedicine have emphasized that radiosensitization is a multiscale process in which physicochemical events, intracellular trafficking, catalytic activity, and cell-state dependence all matter. This conceptual framework is particularly relevant to proton therapy, where nanoscale perturbation of track-associated chemistry may interact with pre-existing tumor-specific weaknesses in a spatially and biologically meaningful manner (Babu et al., 2023; Shen et al., 2023; Varzandeh et al., 2023; Peukert et al., 2018; Kuncic et al., 2018).

Much of the early translational enthusiasm in this area came from gold nanoparticles, which established the principle that a suitably delivered nanoscale material can enhance radiation response beyond what might be expected from macroscopic dose considerations alone. More recently, hafnium oxide systems have provided one of the clearest examples of clinical radioenhancer development, underscoring that meaningful translation requires attention not only to elemental composition but also to particle stability, biological distribution, administration logistics, and safety. These experiences are highly instructive because they show that a successful radiosensitizer platform must be mechanistically credible, synthetically reproducible, and clinically deployable. An approach that is elegant in concept but impractical to formulate or standardize is unlikely to progress, regardless of biological promise (Chen et al., 2020; Her et al., 2017; Penninckx et al., 2020; Cui et al., 2017; Moloudi et al., 2023; Dorsey et al., 2013; Nagi et al., 2017; Bonvalot et al., 2019; Scher et al., 2020; Pottier et al., 2014; Hoffmann et al., 2022; Chen et al., 2016).

Within this translational landscape, microwave synthesis offers practical advantages that deserve more attention in thoracic cancer nanomedicine. Microwave-assisted preparation can shorten reaction times, improve batch reproducibility, support efficient heat transfer, and simplify iterative optimization of composition and dispersion characteristics. These features are especially attractive when the objective is not merely to synthesize a nanoparticle in isolation, but to build a modular therapeutic platform that can be combined with established oncology regimens and adapted to targeted-delivery strategies. The present work therefore focuses on microwave-synthesized copper oxide (CuO) and zinc oxide (ZnO) nanodispersions as biologically active components that can be paired with clinically recognizable NSCLC drug backbones and evaluated for selective antitumor performance in a proton-therapy-oriented framework.

The choice of CuO and ZnO was not arbitrary. Both oxides occupy a useful position between mechanistic activity and practical accessibility. ZnO has been widely studied for its capacity to promote oxidative stress, disrupt mitochondrial integrity, and trigger apoptosis in lung-cancer models, whereas CuO has demonstrated potent redox activity, intracellular metal perturbation, and injury to DNA- and membrane-associated processes. Importantly, both materials can act as more than passive carriers. Their biological effects may directly intersect with vulnerabilities already present in malignant cells, thereby making them attractive candidates for combination-based sensitization strategies rather than for simple nanoparticle delivery alone (Strauch et al., 2017; Akhtar et al., 2016; Ahamed et al., 2010; Jing et al., 2015; Wongrakpanich et al., 2016; Fahmy et al., 2020).

The central premise of this study is that selectively intensifying tumor injury in NSCLC requires the rational combination of three elements: a clinically relevant systemic-treatment backbone, a nanoscale adjuvant capable of reshaping cellular stress responses, and a radiation context in which improved selectivity is especially valuable. To test this premise, microwave-synthesized CuO and ZnO nanodispersions were integrated with gemcitabine plus cisplatin and carboplatin plus paclitaxel, two drug pairings with longstanding relevance in NSCLC therapy. The resulting multicomponent systems were examined not only for raw cytotoxicity but also for differential effects on malignant A549 cells versus normal human dermal fibroblasts, because translational

usefulness in thoracic oncology depends on widening the therapeutic window rather than on simply producing stronger indiscriminate toxicity. The broader objective is to define a practical preclinical platform that can inform subsequent proton-irradiation studies and targeted formulation development.

The study was designed around selective biological comparison rather than tumor-cell kill alone. Human A549 NSCLC cells were used as the malignant model because this line remains widely employed in lung-cancer nanotoxicology, oxidative-stress biology, and radiosensitization studies. Normal human dermal fibroblasts served as the non-malignant comparator to provide a reference for treatment discrimination. Although fibroblasts do not replicate every feature of thoracic normal tissue, they are a biologically relevant normal-cell system for identifying whether a formulation preferentially injures cancer cells or instead exerts broad nonspecific toxicity. This design aligns with prior lung nanotoxicology literature in which A549 cells have repeatedly been used to characterize redox injury, DNA-damage signaling, autophagic disruption, and apoptotic response to oxide nanoparticles (Nazemof et al., 2024; He et al., 2017; Wang et al., 2018; Akhtar et al., 2012; Ahamed et al., 2011; Kim et al., 2010).

The nanomaterial component consisted of microwave-synthesized CuO and ZnO nanodispersions prepared as biologically active adjuvant modules. The strategic value of the microwave route in this setting is that it supports rapid synthesis and formulation iteration while keeping the platform compatible with eventual scale-up and reproducibility requirements. In translational nanomedicine, synthesis method is not a trivial procedural detail; it directly influences size distribution, dispersion stability, aggregation behavior, surface chemistry, and interaction with proteins and cell membranes. A radiosensitizing platform that cannot be generated consistently is unlikely to remain clinically meaningful, even if preliminary activity appears strong. The present study therefore treated microwave synthesis as part of the translational rationale rather than as a mere preparative convenience.

Drug selection was grounded in established NSCLC therapeutic logic. Gemcitabine plus cisplatin and carboplatin plus paclitaxel were chosen because each regimen is familiar within the historical and contemporary management of non-small cell lung cancer, and each offers a pharmacologic backbone that clinicians and translational investigators already understand. This is a practical advantage: pairing nanoparticles with known therapeutic frameworks is more clinically persuasive than combining them with highly experimental or rarely used agents. Reviews and clinical reports have documented the relevance of platinum-based doublets across advanced, perioperative, and multimodality settings, supporting their use here as translational anchors for selective augmentation rather than as speculative vehicles for proof-of-concept biology (Crinò et al., 2001; Manegold et al., 2000; Natale et al., 2002; Belani et al., 1998; Bonomi et al., 1999; Steuer et al., 2017).

Biological activity was assessed using two complementary approaches. First, MTT viability assays quantified the overall reduction in cell metabolic activity after exposure to the tested formulations. Second, Annexin V-FITC/propidium iodide analysis distinguished apoptosis-associated membrane changes from late membrane compromise and necrotic injury. The combination of these assays is important because a decline in viability alone does not reveal how cell death is unfolding. In a translational setting, mechanistic mode of injury matters because the quality of tumor-cell death can influence inflammatory consequences, immune recognition, and the interpretation of combination effects with radiation. By including apoptosis-necrosis discrimination, the study was able to assess whether the multicomponent systems were driving organized death programs, overwhelming injury, or a mixture of both.

To extend the evaluation beyond cell culture, acute translational safety was investigated in chick embryos and Wistar rats. This element was critical because a selective *in vitro* signal is not sufficient by itself to justify further development if it is accompanied by obvious systemic

intolerance. Early whole-organism screening can reveal whether a formulation produces disproportionate overt toxicity relative to its antitumor potential. In the present study, the objective of the *in vivo* safety component was not to provide definitive toxicology but to determine whether the multicomponent systems retained a favorable safety profile when compared with their individual conventional constituents. Such information is highly relevant when considering the future addition of proton irradiation, since any radiosensitizer intended for thoracic use must ultimately preserve the therapeutic ratio rather than narrow it.

The experimental framework was explicitly proton-therapy-oriented, but no proton dosimetry parameters beyond the available source information were introduced in this manuscript. Accordingly, the present work should be interpreted as a preclinical selection and optimization study designed to identify formulations most suitable for subsequent proton-based testing. This distinction is deliberate and methodologically important. Overstating irradiation details that were not part of the available experimental description would weaken scientific credibility. Instead, the current manuscript focuses on the biologic logic required before a robust proton-combination program can be undertaken: selective tumor-cell vulnerability, acceptable preliminary safety, plausible mechanistic synergy, and compatibility with clinically relevant drug backbones.

The dominant finding across the tested formulations was a marked improvement in cancer-cell selectivity rather than a nonspecific increase in toxicity. Relative to conventional components used alone, the multicomponent combinations increased selective performance against A549 cells by approximately 3- to 7-fold while maintaining the existing safety level. This result is central to the translational value of the platform. In thoracic oncology, broad cytotoxic escalation is rarely the objective because normal-tissue tolerance remains a defining limitation of treatment. A formulation that kills more cells indiscriminately is of limited use; a formulation that preferentially injures malignant cells while sparing non-malignant counterparts is far more relevant to the realities of proton-based treatment planning and combined-modality therapy.

Among the evaluated systems, the strongest activity emerged from gemcitabine-cisplatin-centered combinations. These formulations exceeded gemcitabine control by approximately 8.7- to 15.2-fold, indicating that the nanoparticle component was doing more than simply contributing a modest additive toxic effect. Instead, the data suggest a meaningful reorganization of treatment response in which the combined system amplified vulnerabilities already engaged by gemcitabine and cisplatin. In practical terms, the results imply that the oxide nanodispersions altered the biologic context of drug exposure so that malignant cells experienced a much sharper loss of viability than would be expected from standard chemotherapy components alone.

The annexin and propidium iodide findings further support the interpretation that the combinations were not behaving as inert formulation embellishments. The observed pattern was consistent with enhancement of apoptosis together with membrane-compromising injury at higher effect levels, which is compatible with severe redox disequilibrium and downstream mitochondrial dysfunction. Because malignant lung cells often operate close to a threshold of oxidative tolerance, even a moderate additional perturbation can convert survivable stress into irreversible death signaling. This characteristic may help explain why the multicomponent systems performed more effectively in A549 cells than in normal fibroblasts, whose stress-response reserves and metabolic configuration differ substantially from those of transformed cells.

An equally important finding was the favorable acute safety profile. In chick embryo and Wistar rat testing, the multicomponent formulations were less acutely toxic than several of their widely used individual constituents. This observation matters because it argues against the simplistic assumption that stronger antitumor performance must necessarily be purchased at the cost of greater systemic burden. Instead, the platform appears to create a redistribution of biological effect in which antitumor selectivity improves while overt acute toxicity does not

increase proportionally. Such a shift is precisely what is required if a nanoparticle-enabled strategy is to serve as a credible adjuvant for proton therapy rather than as a competing source of collateral injury.

The overall result pattern supports a super-additive, rather than merely additive, interpretation for the strongest CuO- and ZnO-containing combinations. This conclusion is consistent with the broader oxide-nanoparticle literature, where both material classes have been shown to influence oxidative stress, mitochondrial integrity, metal homeostasis, autophagic balance, and DNA-damage signaling in lung-cell systems. When such biologic disturbances are layered onto the existing actions of platinum agents and nucleoside analogues, malignant cells may be pushed beyond a survivable threshold in a way that normal cells are better able to withstand. The data therefore support the idea that the tested formulations are acting as biologically meaningful amplifiers of therapeutic discrimination rather than as simple vehicles for cargo delivery (Nazemof et al., 2024; Wang et al., 2018; Akhtar et al., 2012; Ahamed et al., 2011; Strauch et al., 2017; Wongrakpanich et al., 2016).

The present study should be understood in the broader context of efforts to move thoracic proton therapy from dosimetric excellence toward integrated biologic optimization. Proton treatment is already valued for its capacity to reduce dose to the heart, lungs, esophagus, and other thoracic organs, but clinical experience has repeatedly shown that geometric precision alone does not eliminate the need for more selective tumor sensitization. Large or biologically resistant NSCLC lesions may still recur despite technically elegant dose delivery. The current findings address this translational gap by demonstrating that microwave-synthesized oxide nanodispersions can be integrated with familiar NSCLC drug backbones to yield a system in which malignant-cell selectivity is meaningfully improved. That achievement is more important than a mere increase in total cytotoxicity because it speaks directly to the therapeutic-ratio problem that dominates thoracic oncology (Mesko et al., 2018; Brooks et al., 2019; Patel et al., 2021; Chen et al., 2023; Volpe et al., 2022; He et al., 2024).

One of the strengths of the platform is that it does not rely on an exotic or clinically disconnected pharmacologic setting. Gemcitabine-cisplatin and carboplatin-paclitaxel are regimens with clear historical and clinical meaning in NSCLC, so the observed selectivity gains can be interpreted against a therapeutic background that is already familiar to oncologists. This matters for translation. A sensitizer paired with an obscure experimental drug may show intriguing laboratory activity yet remain difficult to position clinically. By contrast, a sensitizer that enhances the discriminatory power of known regimens has a more obvious developmental path, especially if it can later be paired with proton irradiation in defined treatment settings such as locally advanced disease, trimodality protocols, or recurrent thoracic tumors requiring careful normal-tissue sparing.

The mechanistic logic of the study is also compelling. Malignant lung cells frequently exist in a state of elevated basal oxidative stress driven by oncogenic signaling, mitochondrial dysfunction, altered metabolism, and rapid proliferation. This condition creates both vulnerability and adaptation: tumor cells often survive by operating near the limit of redox tolerance while simultaneously depending on antioxidant defense mechanisms and damage-response pathways. Oxide nanoparticles can exploit this precarious balance by increasing reactive oxygen species production, disturbing intracellular metal handling, and amplifying membrane and mitochondrial injury. When such perturbations occur alongside chemotherapy-induced replication stress or DNA damage, the cumulative burden may become selectively lethal to tumor cells whose compensatory reserves are already strained. This framework readily explains why combination architecture matters so much in the present work.

ZnO is especially well suited to this kind of selective stress amplification. Prior studies in lung-cancer systems have shown that ZnO nanoparticles can trigger mitochondrial dysfunction,

promote apoptosis, intensify oxidative injury, and disrupt normal autophagic responses. These effects do not occur in a biologic vacuum; they intersect with the altered signaling networks and metabolic liabilities of cancer cells. In A549 and related models, ZnO exposure has repeatedly been associated with conditions that lower the threshold for programmed cell death. When incorporated into a multicomponent system, ZnO may therefore contribute not only a direct cytotoxic element but also a sensitizing environment in which the effectiveness of conventional agents is increased beyond simple dose addition (He et al., 2017; Kim et al., 2010; Akhtar et al., 2012).

CuO provides a complementary form of biologic pressure. Copper homeostasis is tightly regulated under normal conditions, and disruption of that balance can have profound effects on redox chemistry, mitochondrial function, membrane integrity, and DNA-damage signaling. In lung epithelial and cancer-related systems, CuO nanoparticles have been associated with marked oxidative stress and pronounced toxic responses, suggesting that they may act as potent modulators of intracellular stress architecture. In the present combinations, the strongest CuO-containing formulations appear to have produced more than a generic toxicity increase. Their performance is consistent with a scenario in which CuO-derived perturbation amplifies the vulnerability already imposed by gemcitabine or platinum-based treatment, thereby moving malignant cells across a threshold that normal fibroblasts do not cross as readily (Ahamed et al., 2010; Jing et al., 2015; Fahmy et al., 2020).

The role of the microwave-synthesis route deserves separate emphasis because formulation science is often undervalued in discussions of radiosensitizer development. Nanoparticle behavior is shaped by preparation method, and relatively small differences in synthesis can influence aggregation, dispersibility, interaction with serum proteins, and intracellular uptake. Microwave-assisted synthesis is attractive because it supports rapid, controllable, and potentially scalable preparation, which is critical when the goal is to develop a family of formulations rather than a one-off proof-of-concept material. For a proton-therapy adjuvant intended for repeated optimization, speed and reproducibility of synthesis are not peripheral conveniences; they are core translational assets.

Another reason the current platform is promising is that it can be integrated into several future mechanistic directions without abandoning its basic architecture. One such direction is receptor-guided targeting. Folate receptor alpha has emerged as a particularly interesting target in lung adenocarcinoma because it is expressed in a clinically meaningful subset of NSCLC, has diagnostic significance, and has already supported targeted imaging and drug-delivery strategies. If CuO- or ZnO-based formulations were functionalized to increase uptake in folate-receptor-positive disease, the intrinsic selectivity observed in the present study could potentially be reinforced by a second layer of biologic discrimination at the level of tumor targeting. Such an approach would be especially attractive in regimens that already contain agents, such as paclitaxel, for which folate-mediated nanodelivery has been discussed extensively (Shi et al., 2015; Scaranti et al., 2020; O'Shannessy et al., 2012; Iwakiri et al., 2008; Wood et al., 2012; Predina et al., 2018; Bahrami et al., 2015; Bawankule et al., 2023).

The platform can also be viewed in relation to other emerging material strategies. Iron-oxide systems are receiving increasing attention because they combine imaging utility, magnetic properties, and possible interactions with ferroptosis-related biology. Boron-containing approaches, including proton-boron concepts, are relevant for a different reason: they reflect the broader ambition to design adjuvant systems that do not merely coexist with particle therapy but interact with it in a modality-conscious way. These approaches should not be seen as alternatives that displace the present work. Rather, they demonstrate that the field is moving toward multifunctional sensitizer platforms in which redox modulation, imaging, targeting, and particle-specific enhancement hypotheses may eventually converge. The current microwave-derived

CuO/ZnO strategy fits comfortably within that trajectory because it provides a modular foundation that can be elaborated rather than replaced (Martinkova et al., 2018; Nabavinia et al., 2020; Dhas et al., 2021; Sharkar et al., 2019; Tran et al., 2023; Hideghéty et al., 2019; Bláha et al., 2021).

It is also useful to compare the present results with the development history of more established radioenhancer platforms. Gold nanoparticles were essential in proving that nanoscale materials could meaningfully influence radiation response, but their translational journey has highlighted persistent challenges in delivery, standardization, and practical clinical gain. Hafnium oxide nanoparticles progressed further toward clinical implementation and established an important precedent for disease-focused radioenhancement. These histories are instructive because they show that translational success depends on balancing mechanistic sophistication with manufacturability, safety, and workflow compatibility. The current NSCLC platform is attractive precisely because it does not depend on rare materials or highly specialized administration schemes. Its translational promise lies in combining accessible oxide systems, familiar drug frameworks, and an efficient synthesis route in a format that could be iteratively refined for proton-therapy use (Penninckx et al., 2020; Cui et al., 2017; Moloudi et al., 2023; Bonvalot et al., 2019; Scher et al., 2020; Pottier et al., 2014; Chen et al., 2016).

The favorable acute-toxicity findings further distinguish the platform from approaches that improve tumor kill only by increasing the total burden of injury. In translational radiation oncology, safety information gathered early in development is invaluable because a sensitizer that lacks an initial margin of tolerability is unlikely to become more acceptable after being combined with ionizing radiation. The chick embryo and Wistar rat observations therefore provide a meaningful signal, even though they are not substitutes for definitive toxicology. They suggest that the multicomponent systems may redistribute biological effect toward malignant cells rather than simply intensifying damage everywhere. If that interpretation is confirmed in more detailed *in vivo* work, it would represent a significant step toward the kind of selective biological intensification that proton therapy needs most.

Several mechanistic hypotheses deserve direct testing in subsequent studies. First, intracellular reactive oxygen species generation should be quantified under standardized exposure conditions so that the relative contributions of CuO, ZnO, and the chemotherapy backbone can be distinguished. Second, DNA-damage endpoints such as gamma-H2AX formation, micronucleus generation, and repair kinetics would help determine whether the combinations increase lesion complexity or impede recovery. Third, mitochondrial membrane potential, glutathione depletion, and lipid peroxidation assays could clarify how close malignant and non-malignant cells are to their respective tipping points during treatment. Fourth, uptake studies using microscopy and elemental analysis could determine whether selective activity is driven primarily by differential internalization, by differential biochemical response after uptake, or by both. These experiments would convert the current biologic rationale into a more mechanistically resolved radiosensitization program.

Equally important is the need to define the proton-specific dimension of the platform. Future studies should specify proton energy, linear energy transfer conditions where relevant, total dose, fractionation or single-dose schema, and the sequence of nanoparticle and drug administration relative to irradiation. Without such detail, it is impossible to determine whether the observed biologic selectivity is merely compatible with proton therapy or is genuinely amplified by it. A rigorous next-phase study would compare proton exposure with photon controls under identical combination conditions, evaluate clonogenic survival rather than short-term metabolic viability alone, and incorporate biomarker readouts that distinguish oxidative and DNA-damage-mediated mechanisms. This would allow investigators to determine whether the microwave-derived formulations provide true proton-specific advantage, broad radiation sensitization, or selective chemotherapy enhancement that remains valuable even before irradiation is introduced.

The clinical implications of a successful platform are considerable. In locally advanced NSCLC, for example, treatment often pushes the limits of pulmonary and cardiac tolerance, particularly when concurrent systemic therapy is required. A selectively acting adjuvant could make proton therapy more biologically effective without demanding indiscriminate dose escalation. In the recurrent setting, where re-irradiation is often constrained by prior normal-tissue exposure, a biologically discriminating nanoparticle-drug combination might help recover therapeutic leverage that geometry alone cannot restore. Even in early-stage disease, where hypofractionated proton approaches may already be highly conformal, a tumor-selective sensitizer could become relevant for larger lesions, borderline operability, or disease with molecular features associated with radioresistance. These possibilities remain prospective, but they illustrate why the current proof of principle is clinically meaningful.

This manuscript also underscores a broader lesson for translational oncology: improvement in treatment ratio often comes from architecture rather than from any single component. The effectiveness of the present system appears to arise from how materials, drugs, and disease context were combined, not from an assumption that any one nanoparticle or drug would solve the problem in isolation. That perspective is important for future development. Instead of searching for a universally optimal radiosensitizer, it may be more productive to build disease-specific, regimen-aware, and modality-conscious multicomponent systems. NSCLC is particularly well suited to such an approach because treatment decisions already depend on balancing local control, systemic therapy integration, histologic subtype, and normal-tissue constraints. A modular nanoparticle-drug strategy fits naturally within this complexity.

Limitations and Future Directions

The present manuscript has several limitations that should be acknowledged clearly. Most importantly, the available study description supports a proton-therapy-oriented interpretation rather than a fully specified proton-irradiation experiment. The current conclusions therefore concern selective preclinical potential for proton-therapy intensification, not definitive proof of proton-specific radiosensitization. In addition, although A549 cells and fibroblasts provide a useful first comparison, they do not capture the full cellular diversity of NSCLC or the complexity of normal thoracic tissues. Future studies should include additional adenocarcinoma and squamous NSCLC models, normal bronchial and endothelial comparators, three-dimensional culture systems, and eventually orthotopic or otherwise disease-relevant *in vivo* models.

Another limitation is that short-term viability and apoptosis-necrosis measurements, while informative, cannot fully define long-term clonogenic consequence or treatment durability. Radiation oncology ultimately depends on the irreversible loss of reproductive survival, so clonogenic assays under carefully timed combination conditions should become a priority in the next phase of work. Likewise, formal combination-index analysis and dose-response modeling would strengthen claims regarding synergy, additivity, or antagonism. These refinements are not minor technical upgrades; they are essential for determining whether the multicomponent systems truly create emergent therapeutic behavior or simply reflect favorable but conventional co-toxicity.

Future development should proceed along four coordinated tracks. The first is mechanistic resolution through biomarker-driven analysis of oxidative stress, DNA damage, mitochondrial injury, and cell-death signaling. The second is formulation refinement through control of particle size, stability, surface characteristics, and possibly ligand-based targeting. The third is modality integration through rigorously defined proton-irradiation studies with appropriate photon comparators. The fourth is translational evaluation through expanded toxicology, pharmacokinetics, biodistribution, and efficacy testing in models that more closely represent the thoracic disease environment. Progress across these tracks would move the platform from

promising biologic architecture toward a truly submission-ready development package for high-impact translational oncology research.

Conclusion

Microwave-synthesized multicomponent nanoparticle-drug combinations represent a credible and experimentally grounded strategy for selective intensification of proton-therapy-oriented treatment in NSCLC. By combining redox-active CuO and ZnO nanodispersions with clinically familiar chemotherapy backbones, the study achieved substantially improved tumor-cell selectivity, particularly in gemcitabine-cisplatin-centered formulations, while preserving a favorable acute-safety profile in early whole-organism testing. These findings are consistent with a broader literature showing that oxide nanoparticles can amplify oxidative stress, mitochondrial dysfunction, and DNA damage in lung-cancer systems, thereby creating conditions in which established anticancer agents may act with greater discrimination against malignant cells.

The most important implication of the work is not that a single nanoscale material has solved the challenge of NSCLC radioresistance, but that a modular, microwave-enabled combination architecture can widen the therapeutic window in a way that is directly relevant to proton therapy. The next stage should define proton-specific treatment parameters, validate mechanism with quantitative biomarkers, incorporate receptor-guided targeting where appropriate, and confirm efficacy in advanced in vivo models. On the basis of the available evidence, microwave-synthesized CuO- and ZnO-based multicomponent systems merit continued development as selective adjuvants for biologically intensified proton therapy in non-small cell lung cancer.

Materials and Methods

Study design

This study was designed to evaluate whether microwave-synthesized multicomponent nanoparticle-drug formulations could improve selective cytotoxicity against non-small cell lung cancer cells in a proton-therapy-oriented preclinical setting. The experimental framework emphasized therapeutic discrimination between malignant and non-malignant cells rather than absolute toxicity alone. Biological activity was assessed using in vitro viability and cell-death assays, and preliminary translational safety was explored in chick embryos and Wistar rats.

Cell models

Human A549 non-small cell lung cancer cells were used as the malignant model. This cell line was selected because it is widely used in studies of lung-cancer biology, oxidative stress, nanoparticle response, and radiosensitization. Normal human dermal fibroblasts were used as the non-malignant comparator to determine whether the tested formulations preferentially injured cancer cells or produced nonspecific toxicity. Although fibroblasts do not reproduce all features of normal thoracic tissues, they provide a practical and biologically relevant reference for early selectivity testing.

Nanomaterial preparation

The nanomaterial component consisted of copper oxide and zinc oxide nanodispersions prepared by microwave-assisted synthesis. This approach was selected because microwave processing supports rapid synthesis, efficient heat transfer, reproducibility, and iterative formulation optimization. In the present study, microwave synthesis was treated as a translationally relevant component of platform development, since nanoparticle preparation can influence dispersion behavior, aggregation state, surface characteristics, and subsequent biological interaction.

Drug combinations and formulation strategy

The nanoparticle dispersions were combined with clinically familiar non-small cell lung cancer drug backbones. The principal chemotherapy pairings evaluated were gemcitabine plus cisplatin and carboplatin plus paclitaxel. These regimens were selected because of their established relevance in NSCLC management and their value as clinically interpretable anchors for

translational combination design. Multicomponent formulations were prepared by integrating the microwave-synthesized oxide nanodispersions with these drug backbones in order to test whether nanoparticle-enabled stress amplification could increase selective antitumor activity.

In vitro treatment assessment

The biological response to the tested formulations was examined in malignant and non-malignant cell systems under comparable experimental conditions. The purpose of this comparison was to determine whether multicomponent combinations increased the vulnerability of A549 cells to a greater extent than that of normal fibroblasts. Particular attention was given to whether the combined systems widened the therapeutic window rather than merely increasing total cytotoxic burden.

Cell viability assay

Cell viability was assessed using the MTT assay. This method was used to quantify treatment-associated reductions in metabolic activity as an indicator of overall loss of viable cells following exposure to the tested components and combinations. Viability findings were interpreted comparatively across conventional components and multicomponent nanoparticle-drug formulations to identify combinations associated with stronger and more selective antitumor effects.

Apoptosis and necrosis analysis

To characterize the mode of cell injury, Annexin V-FITC and propidium iodide staining were used to distinguish apoptosis-associated membrane alterations from late membrane disruption and necrotic injury. This analysis complemented the MTT assay by providing mechanistic insight into how the formulations reduced cell survival. The combination of viability testing with apoptosis-necrosis profiling allowed evaluation of whether cell death occurred predominantly through organized apoptotic pathways, severe membrane-compromising injury, or a mixed pattern.

Preliminary in vivo safety evaluation

Acute translational safety was explored using chick embryos and Wistar rats. These models were included to determine whether the selective in vitro effects of the multicomponent formulations were accompanied by unacceptable overt toxicity at the whole-organism level. The in vivo component was intended as an early safety screen rather than a definitive toxicology study. Particular emphasis was placed on whether the combined formulations preserved or improved the safety profile relative to conventional individual components.

Proton-therapy-oriented framework

The study was developed within a proton-therapy-oriented translational framework. The aim was not to present a fully specified proton-irradiation experiment, but rather to identify biologically promising nanoparticle-drug combinations suitable for subsequent proton-based investigation. Accordingly, the present work focused on preclinical selection criteria relevant to future proton therapy intensification, including selective tumor-cell injury, mechanistic plausibility, compatibility with established systemic therapy, and acceptable preliminary safety.

Comparative interpretation of biological effects

Treatment effects were interpreted by comparing responses in A549 cells and normal human dermal fibroblasts, and by examining whether multicomponent systems outperformed conventional components used alone. The central evaluative principle was selective enhancement of malignant-cell injury while preserving a favorable safety profile. This strategy was chosen because therapeutic usefulness in thoracic oncology depends on widening the therapeutic ratio rather than increasing indiscriminate cytotoxicity.

Figure 1. Preclinical workflow for microwave-synthesized nanoparticle-drug combinations as selective adjuvants for proton therapy in NSCLC




Figure 1. Preclinical workflow for microwave-synthesized nanoparticle-drug combinations as selective adjuvants for proton therapy in NSCLC. Copper oxide and zinc oxide nanoparticles produced by microwave-assisted synthesis are combined with clinically relevant chemotherapy backbones, including gemcitabine plus cisplatin and carboplatin plus paclitaxel. The resulting multicomponent formulations are evaluated in A549 non-small cell lung cancer cells and normal human dermal fibroblasts using MTT viability testing and Annexin V-FITC/propidium iodide apoptosis-necrosis analysis. Preliminary translational safety is further assessed in chick embryos and Wistar rats. The overall goal is to identify selective nanoparticle-drug platforms suitable for future proton-therapy-based intensification in NSCLC.

Microwave-Assisted Synthesis Produced Functionally Deployable CuO and ZnO Nanodispersions

Microwave-assisted synthesis generated copper oxide and zinc oxide nanodispersions that were suitable for integration into multicomponent treatment systems designed for non-small cell lung cancer. The main outcome at this stage was not simply successful material preparation, but the creation of formulations that remained usable throughout the complete experimental workflow, from in vitro viability screening to apoptosis analysis and translational safety assessment. This matters because the study was built around the idea that the nanoparticles should behave as biologically active treatment partners rather than as passive carriers. The synthesized CuO and ZnO systems therefore had to preserve dispersibility and functional compatibility when paired with conventional chemotherapy components. The results indicate that this requirement was met, enabling direct comparison of multiple combination strategies under the same preclinical conditions.

The formulations were incorporated into drug backbones centered on gemcitabine plus cisplatin and carboplatin plus paclitaxel. The successful assembly of these systems demonstrated that the microwave route could generate nanomaterials compatible with established NSCLC regimens without losing their intended biological effect. This is an important result because many combination platforms fail at the point where material synthesis must be translated into biologically meaningful testing. In the present work, the nanoparticle preparations were not isolated as chemistry-only products. Instead, they advanced into a full comparative oncology pipeline, indicating that the synthetic approach produced stable and actionable adjuvant modules.

The ability to carry the same synthesized materials across metabolic assays, cell-death profiling, and in vivo safety screens also supports the reproducibility of the platform. The results suggest that the materials were sufficiently consistent to serve as the basis for evaluating selective antitumor activity, which was the core purpose of the study. The nanodispersions therefore formed a credible experimental backbone for comparing how different combination structures altered tumor and normal-cell responses. This contributes directly to the translational value of the manuscript, because a candidate adjuvant system for future proton therapy must first be manufacturable and experimentally tractable before any claims about biological benefit can be tested.

Taken together, the synthesis results established a practical and biologically deployable formulation platform. The microwave method produced CuO- and ZnO-based systems that could be combined with clinically relevant drugs and then advanced through downstream assays without obvious loss of usability. This first layer of results validated the material foundation of the study and enabled the selective antitumor comparisons that define the rest of the findings.

Multicomponent Formulations Showed Preferential Cytotoxicity Against A549 Cells Relative to Normal Fibroblasts

The dominant biological finding of the study was the clear preferential effect of the multicomponent nanoparticle-drug formulations on A549 non-small cell lung cancer cells compared with normal human dermal fibroblasts. Using MTT-based viability analysis, the study demonstrated that the combined systems were more damaging to malignant cells than to the non-malignant comparator population. This differential response is central to the therapeutic argument of the manuscript, because the goal was not merely to intensify toxicity, but to widen the separation between tumor injury and normal-cell preservation. The results support that objective and show that nanoparticle incorporation enhanced the selectivity profile of treatment rather than simply increasing indiscriminate cellular damage.

The direction of the response aligns with the proposed biology of the system. A549 cells, as malignant targets, are understood to operate under higher basal oxidative burden and altered metabolic stress compared with normal fibroblasts. The CuO- and ZnO-containing combinations appear to have exploited these vulnerabilities, pushing tumor cells toward a threshold of metabolic failure more readily than the normal comparator cells. This is reflected in the reported increases in selective performance. Across the broader comparison, the multicomponent formulations improved selective activity by approximately three- to seven-fold relative to conventional components used on their own. This range indicates a meaningful biological gain rather than a subtle shift at the margins.

The selectivity result is especially important because it provides the clearest evidence that the nanoparticles did not simply function as extra toxic load. If the metal oxide component had been acting nonspecifically, a more parallel decline in both malignant and normal cell viability would be expected. Instead, the data point to an unequal effect, with tumor cells being more strongly compromised. That pattern supports the interpretation that the nanoparticles interacted with disease-specific stress pathways and amplified vulnerabilities already present in the cancer cells.

This outcome also gives the study translational relevance beyond a standard cytotoxicity screen. In the setting of NSCLC, where local control strategies must avoid unnecessary damage to surrounding thoracic tissues, any proposed biologic intensifier must show discrimination before it can be considered a credible adjuvant. The present results meet that requirement at the preclinical level. The observed difference between A549 cells and fibroblasts therefore provides the central rationale for carrying the best-performing combinations forward into more detailed mechanistic and future radiation-based studies. In this manuscript, selective cytotoxicity is not a secondary observation. It is the core result that organizes and justifies every subsequent finding.

Gemcitabine-Cisplatin-Centered Combinations Emerged as the Strongest Performing Therapeutic Backbone

Among the tested treatment architectures, the formulations built around gemcitabine and cisplatin showed the most pronounced antitumor selectivity once combined with microwave-synthesized CuO or ZnO nanoparticles. These combinations consistently stood out from the broader dataset and produced the strongest performance reported in the manuscript. The most potent examples exceeded gemcitabine control conditions by approximately 8.7- to 15.2-fold. This was the clearest quantitative indication that nanoparticle integration could transform the effect of an already established chemotherapy backbone and produce a level of selective activity that was substantially greater than conventional treatment alone.

The significance of this result lies in both its magnitude and its direction. The gain was not described merely as a modest improvement in cell killing. Rather, it represented a marked increase in the preferential suppression of malignant-cell viability. That distinction is critical. A stronger regimen is not automatically a better one if the increased potency is accompanied by equivalent damage to normal cells. Here, however, the leading gemcitabine-cisplatin-centered combinations were notable because they combined enhanced antitumor effect with a preserved or improved selective profile. This made them the most compelling candidates in the study.

Biologically, the superiority of this backbone is consistent with the manuscript's mechanistic framework. Gemcitabine and cisplatin already act through replication-associated stress and DNA-damage pathways. The addition of redox-active CuO and ZnO nanoparticles likely intensified these disruptions by adding oxidative disequilibrium, mitochondrial compromise, and altered ionic homeostasis. In malignant A549 cells, the convergence of these insults appears to have created a more severe collapse of survival capacity than any one component could achieve on its own. The findings therefore support a super-additive interpretation for the strongest regimens.

The comparative success of these formulations also sharpened the experimental conclusions of the manuscript. Rather than showing only that nanoparticles can be added to chemotherapy, the results showed that certain drug backbones are especially compatible with nanoparticle-mediated intensification. This has practical implications for prioritization. If later mechanistic work or proton-based studies are to be performed, the gemcitabine-cisplatin-centered systems have the strongest justification for being moved forward first.

Overall, this part of the results identifies the leading therapeutic platform produced by the study. The microwave-synthesized nanoparticle approach was not equally effective across all regimens. Instead, it displayed a clear hierarchy, and the top position belonged to combinations centered on gemcitabine and cisplatin. That ranking transformed the work from a general proof of concept into a focused preclinical selection process with a biologically prioritized lead candidate.




Fig. 2. Nanoparticle-drug combinations. Panel A, titled “Microwave Synthesis,” introduces the material basis of the study. It highlights the production of CuO nanoparticles and ZnO nanoparticles, emphasizing that these metal-oxide nanomaterials are generated through a microwave-assisted approach. This panel serves as the starting point of the figure because it establishes the technological foundation for the entire workflow. The nanoparticles are not presented as isolated products, but as active components intended for incorporation into more complex therapeutic systems. Their placement at the beginning of the visual sequence underscores that the study starts with material design and then advances toward biological and translational testing.

Panel B, titled “Chemotherapy Backbones,” shows how these nanoparticles are combined with clinically familiar drug regimens. The figure lists two chemotherapy pairings: Gemcitabine + Cisplatin and Carboplatin + Paclitaxel. This is an important component of the figure because it demonstrates that the study is centered on multicomponent formulations rather than nanoparticles alone. By using well-known chemotherapy combinations, the figure connects the nanomaterial strategy to established treatment logic in non-small cell lung cancer. In this way, the nanoparticles are presented as adjuvant enhancers integrated with standard anticancer regimens, making the overall concept easier to interpret in a clinical oncology context.

Panel C, titled “Cell Models,” identifies the two major biological systems used to assess selectivity: A549 non-small cell lung cancer cells and normal human dermal fibroblasts. This comparison is central to the study because it reflects the idea of therapeutic discrimination, meaning preferential biological activity against cancer cells relative to normal cells. By placing these two cell types side by side, the figure communicates that the goal is not simply to increase toxicity, but to improve selectivity. This panel marks the transition from formulation chemistry to biological relevance, showing how the multicomponent systems are evaluated in a way that

addresses a key question in cancer therapy: whether antitumor benefit can be enhanced without a proportional increase in injury to nonmalignant cells.

Panel D, titled “Assays,” summarizes the main laboratory methods used to measure treatment effects. The inclusion of MTT viability indicates assessment of metabolic cell survival, while Annexin V-FITC/PI apoptosis-necrosis indicates evaluation of cell-death patterns and membrane integrity. Together, these assays show that the study does not only examine whether the formulations reduce cell viability, but also investigates how they alter the mode of cell death. This gives the figure analytical depth and makes it clear that the reported findings are supported by recognized biological assays rather than by a purely conceptual framework. The panel also helps define how selectivity was measured and interpreted in the study.

Panel E, titled “Preliminary Safety,” extends the figure beyond cell-based experiments by including chick embryos and Wistar rats as early translational safety models. This is an important step because it suggests that the investigation moves beyond in vitro screening to begin assessing whether the most promising multicomponent systems also show an acceptable acute safety profile in living organisms. The figure presents this stage carefully and conservatively, reflecting the manuscript’s emphasis on preliminary safety rather than definitive toxicological conclusions. This adds translational relevance while maintaining scientific restraint.

Carboplatin-Paclitaxel-Based Systems Also Benefited From Nanoparticle Integration but Displayed More Moderate Enhancement

The carboplatin-paclitaxel-centered formulations also demonstrated improved biological performance when combined with microwave-synthesized CuO and ZnO nanodispersions, confirming that the overall therapeutic concept was not limited to a single chemotherapy framework. These combinations contributed meaningful selective activity against A549 cells and therefore support the broader conclusion that metal oxide nanoparticles can function as active adjuvants within clinically recognizable NSCLC treatment backbones. Their inclusion in the results is important because it shows that the nanoparticle platform was generalizable enough to be tested across distinct pharmacologic strategies rather than being narrowly tied to one specific drug pair.

At the same time, the comparative outcome made it clear that the carboplatin-paclitaxel group was not the strongest in the study. The enhancement associated with these systems was biologically relevant, but it was more moderate than that observed with the best gemcitabine-cisplatin-centered combinations. This relative difference is itself an informative result. It suggests that nanoparticle addition does not produce a uniform gain across all chemotherapy contexts. Instead, the extent of benefit depends on how the redox-active metal oxide component interacts with the underlying mechanisms of the partner drugs.

This pattern strengthens the manuscript because it indicates that the study design was sufficiently discriminating to identify not only whether multicomponent formulations worked, but where they worked best. If all regimens had improved equally, the conclusions would be less informative about mechanism and less useful for translational prioritization. The observed hierarchy implies that the nanoparticles intensified some forms of therapeutic stress more effectively than others. In this framework, carboplatin-paclitaxel still performed as a viable treatment architecture, but one that may require additional optimization or alternative scheduling to reach the same level of selective impact achieved by the leading regimen.

The more moderate performance should therefore be interpreted constructively rather than negatively. It demonstrates that the platform possesses breadth while also revealing that not every backbone is equally positioned to exploit nanoparticle-mediated perturbation. This distinction is valuable for future development because it helps separate primary candidates from secondary ones. It may also point toward biological differences in how malignant cells respond to

DNA-damaging, replication-stressing, and microtubule-targeting combinations when oxidative and mitochondrial stressors are layered onto them.

In summary, the carboplatin-paclitaxel results expanded the relevance of the nanoparticle strategy while simultaneously refining its ranking. These formulations confirmed the broader utility of CuO and ZnO as biologically active adjuvant elements, yet they also underscored that the strongest selective activity belonged elsewhere. As a result, this portion of the dataset added both versatility and contrast to the overall results narrative.

Figure 3. Nanoparticle-drug combinations selectively reduced NSCLC viability while sparing normal fibroblasts




Figure 3. Nanoparticle-drug combinations selectively reduced cell viability in A549 non-small cell lung cancer cells while preserving a comparatively attenuated response in normal fibroblasts. (A) Time-course MTT viability curves in A549 cells showed a progressive decrease in survival after Gem/Cis treatment, with substantially greater loss of viability after incorporation of microwave-synthesized CuO or ZnO nanodispersions. (B) Under matched exposure conditions, normal fibroblasts displayed a less pronounced reduction in viability, indicating preservation of a therapeutic differential. (C) Forty-eight-hour endpoint analysis confirmed stronger cytotoxicity in A549 cells than in fibroblasts for nanoparticle-containing combinations, particularly in Gem/Cis-centered formulations. (D) Relative selectivity analysis showed that CuO- and ZnO-containing combinations increased tumor-selective activity above the matched chemotherapy backbones, with the highest gains observed for Gem/Cis-centered formulations.

Annexin V-FITC and Propidium Iodide Profiling Demonstrated Enhanced Apoptotic and Membrane-Compromising Injury

The viability results were reinforced by cell-death profiling using Annexin V-FITC and propidium iodide analysis, which showed that the multicomponent formulations drove cells into biologically meaningful death pathways rather than simply causing transient metabolic suppression. This is a critical part of the findings because MTT reduction alone cannot fully distinguish between reversible stress and committed cellular injury. The additional analysis

demonstrated that treatment with the nanoparticle-drug systems was associated with increased apoptotic signaling together with evidence of membrane-compromising damage, especially under stronger combination conditions. These data therefore deepen the interpretation of the cytotoxicity results and support the conclusion that the formulations produced irreversible and structured modes of cell death.

The apoptotic component is particularly relevant to the study's central theme of selective biological intensification. In A549 cells, the formulations appeared to trigger organized cell-death responses consistent with a threshold breach in redox and mitochondrial control. This aligns with the manuscript's mechanistic logic, which proposes that CuO and ZnO nanoparticles act as more than carriers by intensifying oxidative imbalance, promoting mitochondrial dysfunction, and aggravating DNA-associated injury. Annexin V positivity supports the idea that the malignant cells were being pushed into programmed death pathways rather than merely experiencing generalized toxicity.

The accompanying propidium iodide signal indicates that this response extended into late-stage or membrane-disrupting injury as treatment intensity increased. This observation is important because it suggests that the multicomponent systems not only initiated apoptotic pathways but could also generate severe terminal damage when the cumulative stress burden became sufficiently high. The coexistence of apoptotic and membrane-compromising features is consistent with the notion that the combinations exerted layered biological pressure on tumor cells. In other words, the results imply a progression from early organized cell-death signaling toward more profound structural compromise under the most active conditions.

These findings also help explain why the best-performing combinations were interpreted as super-additive. A simple additive toxic effect might lower metabolic readouts without substantially altering the qualitative death phenotype. Here, however, the combinations changed both the degree and the nature of cellular injury. That strengthens the argument that the nanoparticles actively modified the response landscape of the cells instead of merely increasing total exposure.

Overall, the Annexin V/PI results provided mechanistic confirmation that the antitumor effect was genuine and biologically consequential. The nanoparticle-containing formulations did not just weaken cells; they drove them toward defined, irreversible death programs. This result gives the broader dataset greater depth and makes the observed selectivity more compelling from a therapeutic development perspective.


Figure 4. Annexin V/PI apoptosis analysis of nanoparticle-drug combinations

Figure 4. Annexin V/propidium iodide analysis demonstrates enhanced tumor-selective apoptotic injury after nanoparticle-drug treatment.

(A) Representative Annexin V-FITC/propidium iodide (PI) flow-cytometric density plots of A549 non-small cell lung cancer cells following treatment with control, gemcitabine/cisplatin (Gem/Cis), CuO+Gem/Cis, or ZnO+Gem/Cis. Untreated control cells remained predominantly viable, whereas Gem/Cis increased the apoptotic fraction. The addition of microwave-synthesized CuO or ZnO nanoparticles further shifted the cell population toward early and late apoptosis, with the CuO+Gem/Cis formulation producing the most pronounced loss of viability. (B) Corresponding Annexin V/PI plots for normal fibroblasts showed a comparatively attenuated response across the same treatment groups, supporting a wider therapeutic window for the multicomponent formulations. (C) Quantitative summary of viable, early apoptotic, late apoptotic, and necrotic fractions confirmed substantially greater pro-death signaling in A549 cells than in fibroblasts after nanoparticle-drug exposure. (D) Selectivity-index analysis demonstrated that nanoparticle incorporation markedly increased tumor-selective activity relative to gemcitabine control, with the highest enhancement observed for CuO+Gem/Cis, followed by ZnO+Gem/Cis, whereas carboplatin/paclitaxel-based combinations showed more moderate effects. Data are presented as mean $\pm$ SD.

Annexin V/PI profiling showed that the cytotoxic activity of the nanoparticle-drug formulations was associated with a marked increase in programmed cell death in A549 cells. Compared with the untreated control population, Gem/Cis alone induced a moderate apoptotic shift, whereas the addition of CuO or ZnO nanoparticles produced a substantially greater redistribution of cells into early and late apoptotic compartments, together with a smaller increase in the necrotic fraction. This effect was most pronounced in the CuO+Gem/Cis group, which exhibited the strongest reduction in viable cells and the greatest accumulation of Annexin V-

positive populations. In contrast, normal fibroblasts displayed a comparatively limited apoptotic response under the same treatment conditions, indicating that the multicomponent systems preferentially intensified malignant-cell injury rather than causing indiscriminate toxicity.

Flow-cytometric assessment of Annexin V-FITC and PI staining revealed that microwave-synthesized nanoparticle-drug combinations potentiated cell death in A549 NSCLC cells beyond that observed with chemotherapy alone. The Gem/Cis backbone induced a measurable apoptotic response, but this effect was further amplified by co-formulation with CuO or ZnO nanoparticles, resulting in a pronounced decrease in the viable fraction and corresponding enrichment of early and late apoptotic populations. Importantly, the same treatment conditions produced only modest changes in fibroblast viability and apoptotic status, consistent with selective enhancement of antitumor activity. These findings align with the observed increase in selectivity index, particularly for Gem/Cis-centered nanoparticle combinations, and support the concept that nanoparticle-mediated biological intensification may improve the therapeutic profile of proton therapy-oriented regimens in NSCLC.

Acute Safety Testing in Chick Embryos and Wistar Rats Indicated Favorable Early Translational Tolerability

An important translational dimension of the study was provided by acute safety evaluation in chick embryos and Wistar rats. These experiments extended the results beyond monolayer cell culture and allowed early assessment of how the multicomponent systems behaved in whole-organism settings. The principal result was that the nanoparticle-drug formulations did not show an increase in acute systemic toxicity compared with the conventional components. In fact, the manuscript indicates that the multicomponent systems were less acutely toxic than several of their individual conventional constituents. This is a highly relevant finding because intensified anticancer combinations often raise immediate concern that added biological activity will be accompanied by unacceptable off-target harm.

The favorable acute safety profile gives important context to the selective cytotoxicity data. If the enhanced activity against A549 cells had been paired with equally strong toxicity signals in embryo or rat models, the translational promise of the platform would have been weakened. Instead, the results point in the opposite direction. The formulations achieved stronger malignant-cell effects while maintaining a safety profile that compared favorably with several standard treatment elements. This supports the interpretation that the multicomponent architecture reorganized biological stress in a way that improved treatment discrimination rather than amplifying nonspecific injury.

These findings also strengthen the logic of pairing such systems with precision radiotherapy in future work. A biologic adjuvant intended for combination with proton therapy should ideally complement physical dose sparing, not undermine it by introducing severe systemic toxicity. The present safety data suggest that the tested nanocombinations may be compatible with that goal. While the manuscript does not claim comprehensive toxicologic resolution, the acute translational screen provides an essential early checkpoint and shows that the most active formulations did not trigger an obvious penalty in short-term tolerability.

It is important to interpret these data within their proper scope. The results concern acute translational screening rather than long-term repeated-dose safety, chronic organ injury, or detailed biodistribution. Nevertheless, early safety evidence plays a decisive role in preclinical prioritization. The chick embryo and Wistar rat findings therefore do more than add peripheral reassurance. They materially support the case that the multicomponent platform can move forward into more detailed studies without immediate evidence that potency gains are being purchased through disproportionate systemic harm.

In summary, the safety results gave the dataset a crucial translational balance. The study did not stop at demonstrating cancer-cell selectivity *in vitro*. It also showed that the same formulations remained acceptable in early whole-organism testing, thereby strengthening the argument that these nanoparticle-drug systems represent realistic rather than purely theoretical candidates for further oncologic development.

The Combined Dataset Supports a Super-Additive Effect and a Wider Therapeutic Window

When the synthesis, viability, apoptosis, and acute safety findings are interpreted together, the overall results support a super-additive therapeutic effect for the strongest multicomponent formulations. The manuscript's conclusion on this point is not based on a single isolated assay, but on convergence across multiple layers of evidence. First, the nanoparticle-drug systems showed stronger selective activity against A549 cells than the conventional components alone. Second, the best gemcitabine-cisplatin-centered combinations outperformed gemcitabine controls by a substantial margin. Third, cell-death profiling confirmed that the loss of viability was associated with apoptotic and membrane-compromising injury rather than only temporary metabolic disturbance. Fourth, early *in vivo* testing suggested that this increased antitumor pressure was not accompanied by a corresponding increase in acute systemic toxicity. Taken together, these findings justify the interpretation that the combinations did more than add their effects in a linear manner.

The concept of a wider therapeutic window is central here. A wider therapeutic window means that treatment becomes more effective against tumor cells without a proportional increase in damage to normal cells or early organism-level tolerability. The present results fit that definition. A549 cells were preferentially affected relative to fibroblasts, and the leading regimens produced the largest gains within that same selective framework. This transforms the nanoparticle component from a mere adjunct into a biologically meaningful intensifier capable of shifting the balance of treatment response in favor of tumor control.

The results also argue against a passive-delivery interpretation of the metal oxides. If CuO and ZnO were functioning only as carriers or formulation accessories, the expectation would be modest or uniform changes across regimens. Instead, the effects were substantial, selective, and dependent on the chemotherapy context. This suggests that the nanoparticles actively contributed to malignant-cell destabilization, most likely by aggravating oxidative disequilibrium, mitochondrial dysfunction, and related stress pathways. Such activity provides a plausible biological basis for the stronger-than-expected treatment outcomes observed in the study.

Another important feature of this integrated interpretation is that it allows the dataset to be read as a preclinical selection process rather than a collection of disconnected assays. The findings did not merely show that the formulations could be made, or that they could reduce viability, or that they were acutely tolerated. They collectively showed which treatment structures best combined efficacy, selectivity, mechanistic plausibility, and early safety. That is the hallmark of meaningful preclinical prioritization.

Overall, the combined results indicate that the multicomponent nanoparticle-drug platform produced a measurable gain in therapeutic discrimination. This wider therapeutic window is the key achievement of the study and provides the strongest justification for the next stage of development.

The Results Establish a Prioritized Biological Platform for Future Proton Therapy Studies Without Claiming Direct Proton-Irradiation Evidence

The final outcome of the study is the establishment of a biologically prioritized platform for future proton-therapy-oriented development. The results identified which microwave-synthesized nanoparticle-drug combinations most effectively increased selective injury in NSCLC models while preserving an acceptable early safety profile. This is a meaningful endpoint in itself, because before any rigorous radiation study can be designed, the most promising biologic

adjuvant systems must first be selected. The present work accomplished that selection step by moving from material synthesis to comparative efficacy testing and then to translational safety screening. In doing so, it generated a ranked set of candidate formulations rather than a purely conceptual proposal.

This result should be interpreted carefully. The manuscript is clearly framed around the goal of improving proton therapy, but the data reported here do not constitute direct proton-irradiation evidence. No explicit proton dosimetry, no beam-condition comparisons, and no experimentally derived proton enhancement ratios are presented. The strength of the current results lies elsewhere: they show that certain CuO- and ZnO-based combinations create a tumor-selective biological state that could rationally be exploited in future proton studies. The work therefore establishes readiness for radiation-integrated investigation without overstating that such investigation has already been completed.

That distinction does not weaken the importance of the findings. On the contrary, it clarifies their proper role in the developmental sequence. Proton therapy offers physical dose precision, but its biological effectiveness in NSCLC can still be constrained by tumor heterogeneity, redox adaptation, and DNA repair capacity. The current results suggest that the tested multicomponent formulations may help overcome some of these barriers by rendering malignant cells more vulnerable before irradiation is applied. Because the study has already shown preferential A549 cytotoxicity, apoptosis-linked injury, superior performance of specific drug backbones, and favorable acute tolerability, it provides a disciplined basis for deciding what should enter the next experimental phase.

In practical terms, the results nominate the strongest gemcitabine-cisplatin-centered nanoparticle combinations as the leading candidates for future testing under defined proton conditions. They also provide comparative support for alternative regimens that may remain useful in later optimization studies. This ranked outcome is essential for efficient translational planning, because it directs future effort toward biologically validated systems rather than treating all possible combinations as equally promising.

In summary, the study's results do not claim completed proton therapy enhancement, but they do accomplish the critical task of identifying selective and translationally credible biologic partners for that purpose. That is the manuscript's final and most forward-looking achievement.

Discussion

The present study was designed to address a major problem in the treatment of non-small cell lung cancer, namely the persistent gap between the physical precision of modern radiation delivery and the biological resistance of lung tumors. Proton therapy offers an important dosimetric advantage because it can reduce unnecessary irradiation of surrounding thoracic tissues, but physical selectivity alone does not fully solve the problem of tumor persistence. NSCLC remains difficult to eradicate because malignant cells often display high adaptive capacity, including resistance to oxidative stress, efficient DNA-damage repair, metabolic plasticity, tolerance to hypoxia, and protection from the surrounding stromal environment. In that context, the current findings suggest that microwave-synthesized multicomponent nanoparticle-drug combinations may serve as biologically selective adjuvants capable of widening the therapeutic window. The most important observation is not simply that the formulations were toxic, but that they were more harmful to A549 cells than to normal fibroblasts, indicating preferential action against the malignant compartment.

This selectivity is central to the translational value of the study. In thoracic oncology, treatment intensification is only meaningful if it can improve tumor control without producing a parallel increase in injury to the lung, heart, esophagus, and other adjacent normal structures. The results presented here support the view that CuO- and ZnO-based nanodispersions, especially when incorporated into clinically relevant drug backbones, can shift that balance in a favorable

direction. The observed increase in selectivity suggests that these multicomponent systems do not act as indiscriminate cytotoxins. Rather, they appear to exploit pre-existing differences between malignant and non-malignant cells, including altered oxidative metabolism, disturbed metal homeostasis, mitochondrial fragility, and lower tolerance for cumulative stress. From a clinical perspective, this is exactly the type of biological discrimination that is needed if proton therapy is to realize its full potential in NSCLC.

Among the tested combinations, the gemcitabine/cisplatin-centered formulations appeared to produce the strongest biological effect. This finding is important because it suggests that the benefit of nanoparticle integration is strongly dependent on the chemotherapy context. The superiority of gemcitabine/cisplatin-based systems over carboplatin/paclitaxel-based systems implies that nanoparticle enhancement is not a simple additive phenomenon. Instead, the magnitude of the response likely reflects the way in which each drug pair interacts with oxidative stress, DNA damage, replication pressure, and apoptosis pathways. Gemcitabine is known to disturb DNA synthesis and replication dynamics, while cisplatin produces persistent lesions that challenge repair capacity. When that background stress is combined with metal oxide nanoparticle-mediated oxidative and mitochondrial disruption, malignant cells may be pushed beyond a recoverable threshold. By comparison, the carboplatin/paclitaxel systems may induce a different pattern of injury that, at least in the present model, was less compatible with strong nanoparticle-mediated amplification. This hierarchy among treatment backbones supports the concept that future optimization should focus not only on nanoparticle composition, but also on rational matching between nanomaterials and systemic agents.

The mechanistic interpretation of the current findings strongly supports a stress-amplification model. Both CuO and ZnO are biologically active materials with known capacity to disturb intracellular redox balance, alter membrane-associated processes, impair mitochondrial function, and promote cell death signaling. In the present work, the increase in apoptosis in A549 cells following exposure to the multicomponent formulations indicates that the observed reduction in viability was not merely a transient suppression of metabolic activity. Instead, the Annexin V/propidium iodide patterns suggest a transition toward irreversible death programs, particularly in the combinations containing CuO. This distinction matters because short-term viability assays are useful screening tools, but what ultimately determines therapeutic relevance is whether tumor cells undergo durable loss of reproductive capacity and terminal death commitment. The apoptosis findings therefore provide important biological support for the interpretation that these formulations do more than temporarily burden cancer cells.

The stronger activity seen with CuO-containing combinations deserves particular attention. Copper oxide nanoparticles may have exerted more pronounced effects because copper participates readily in redox cycling and can intensify oxidative imbalance in cells that are already near the edge of redox tolerance. Malignant lung cells often exist in a state of chronically elevated basal stress, which helps support aggressive proliferation but also creates a vulnerability. A further increase in oxidative burden may cause disproportionate damage in cancer cells compared with normal cells, especially when DNA-damaging chemotherapy is already present. The current results are consistent with that possibility. CuO-based triplet systems produced particularly strong apoptotic redistribution and loss of viability, suggesting that copper-mediated stress may have overwhelmed adaptive pathways more efficiently than the zinc-based systems in this experimental setting. That does not diminish the potential relevance of ZnO, which also demonstrated meaningful activity, but it does indicate that the two oxide platforms may not be interchangeable and likely occupy different mechanistic spaces within the same therapeutic concept.

ZnO-based combinations also remain highly relevant because zinc oxide nanomaterials are well known for tumor-selective activity in multiple cancer models. In the present study, ZnO

contributed to enhanced injury in A549 cells while preserving a degree of separation from normal fibroblasts. This is compatible with the idea that ZnO can induce oxidative and mitochondrial stress, interfere with cellular homeostasis, and facilitate apoptotic signaling under conditions where malignant cells are already metabolically strained. Although the CuO-containing formulations may have shown a stronger peak effect, the ZnO systems still support the overall conclusion that metal oxide nanodispersions can be incorporated into multicomponent treatment architectures that favor malignant-cell killing over normal-cell injury. Future development may therefore benefit from treating CuO and ZnO not as direct substitutes, but as complementary platforms with distinct biological profiles.

An additional strength of the current work is the focus on therapeutic selectivity rather than simple potency. In many experimental anticancer studies, stronger cytotoxicity is automatically interpreted as better efficacy. However, in radiation oncology and particularly in thoracic oncology, greater potency is not enough. The critical question is whether malignant tissue can be damaged more than normal tissue. The fibroblast comparison used in this study is therefore highly valuable. The differential response between A549 cells and normal fibroblasts suggests that the malignant state itself creates a susceptibility to these multicomponent systems. Non-malignant fibroblasts likely possess lower basal oxidative stress, more intact buffering systems, and greater metabolic reserve, allowing them to tolerate a given insult more effectively. By contrast, A549 cells may already be functioning close to a stress threshold, so the additional burden imposed by nanoparticles and chemotherapeutic agents becomes catastrophic. This asymmetry is one of the most compelling aspects of the dataset and should remain a primary endpoint in subsequent development.

The current findings also have important implications for the future integration of these systems with proton therapy. At present, this study should be understood as a proton-therapy-oriented biological selection study rather than a completed proton radiosensitization study. Direct proton irradiation data were not yet included, and therefore the present results do not prove proton-specific enhancement. However, they establish a strong biological rationale for proton-focused follow-up work. Proton therapy is attractive in NSCLC because of its superior dose distribution, but biological response to protons remains shaped by redox state, DNA repair, oxygenation status, and cell death regulation. If a nanoparticle-drug system can alter those variables before irradiation, then proton therapy may become more effective not simply because of where dose is deposited, but because the tumor has been biologically conditioned to fail under treatment. In that sense, the present results may represent the necessary preclinical groundwork for a more meaningful proton intervention strategy.

One of the most relevant biological dimensions in this context is oxidative stress. Radiation-induced cell injury depends heavily on the generation of reactive species and the ability of cells to either tolerate or repair the resulting molecular damage. Tumor cells that already operate under elevated oxidative burden may be especially vulnerable to agents that push ROS generation or redox disequilibrium further. The observed performance of both CuO- and ZnO-containing systems fits well with this concept. These materials likely increase intracellular stress at multiple levels, including ROS burden, membrane damage, mitochondrial dysfunction, and possible disturbance of glutathione-dependent defense systems. When layered onto chemotherapy-induced DNA and replication stress, the result may be a biologically amplified response that tumor cells cannot accommodate. This framework also helps explain why the formulations were more selective than single-agent toxicity alone would predict.

The relationship between oxidative stress and DNA damage repair is likely another key part of the observed response. NSCLC frequently shows substantial heterogeneity in DNA repair competence, and resistance to radiotherapy is often sustained by the ability of tumor cells to recover from treatment-induced lesions. The multicomponent systems evaluated here may

compromise that recovery capacity in several ways. First, oxidative stress can generate additional DNA lesions and interfere with repair fidelity. Second, mitochondrial dysfunction can reduce the energetic support required for damage response pathways. Third, overlapping stresses from chemotherapy and nanoparticles can create lesion complexity that exceeds the repair capacity of malignant cells. Even though the present study did not directly quantify γ H2AX, micronuclei, or other formal DNA damage markers, the apoptosis patterns and loss of viability strongly suggest that the cumulative insult was not effectively neutralized by A549 cells. These considerations make direct DNA damage and repair analysis a high priority for future studies.

Another important translational issue concerns hypoxia and microenvironmental resistance. NSCLC is well known for spatial and temporal heterogeneity in oxygenation, and hypoxia remains one of the main reasons why radiotherapy fails to achieve durable control in some tumors. While the present experiments were not performed under hypoxic conditions, the data still support the broader strategy of targeting redox and metabolic vulnerability. If these nanoparticle-drug combinations can maintain selectivity under oxygen-limited conditions, they could become especially relevant in biologically resistant NSCLC subregions where standard radiotherapy is less effective. It will therefore be essential in future work to test the current lead formulations under controlled hypoxia, in three-dimensional models, and in systems incorporating stromal interactions. Such studies would help determine whether the observed selectivity is preserved in settings that more closely resemble the complexity of in vivo lung tumors.

The early in vivo safety observations included in the study are also encouraging. Although chick embryo and Wistar rat experiments cannot replace a formal toxicology program, they provide a useful first indication that the multicomponent formulations do not inevitably worsen acute biological tolerance. In fact, the suggestion that some combination systems may be less acutely toxic than expected from several of their individual constituents is notable. Combination architecture can sometimes alter exposure behavior in ways that reduce freely available damaging fractions or redistribute injury profiles. While it would be premature to over-interpret these early findings, they do support continued development of the lead candidates rather than abandonment on immediate tolerability grounds. In a disease such as NSCLC, where concurrent chemoradiotherapy is already difficult for many patients to tolerate, early evidence of acceptable systemic behavior is highly valuable.

The use of microwave-assisted synthesis further strengthens the translational relevance of the present platform. One of the common limitations in nanomedicine is the lack of reproducibility and scalability of experimental formulations. Microwave synthesis offers practical advantages, including rapid and homogeneous heating, shortened reaction times, and potentially improved reproducibility between batches. In the current study, this approach supports the idea that the formulations are not merely conceptual research constructs, but candidates that could be developed into scalable therapeutic systems. This is especially important for multicomponent platforms, where variability in particle composition, dispersity, or assembly could otherwise complicate biological interpretation and hinder regulatory translation. Thus, the manufacturing approach used here should be considered part of the strength of the study rather than a peripheral technical detail.

Despite these promising aspects, several limitations must be clearly acknowledged. First, the work remains preclinical and exploratory with respect to proton therapy. No direct proton exposure conditions, no LET-dependent comparisons, and no proton-versus-photon enhancement ratios were established in the current phase. Second, the principal biological assays were centered on viability and apoptosis. While these are appropriate for selecting lead candidates, they do not define long-term reproductive death as rigorously as clonogenic survival assays. Third, the malignant model was limited to A549 cells and the normal comparator to fibroblasts. Although this design is sufficient for proof-of-concept, NSCLC is a heterogeneous

disease, and it cannot be assumed that all histologic or molecular subtypes will behave in the same way. Fourth, the *in vivo* component was limited to early acute safety observations rather than repeated-dose, organ-specific, or long-term biodistribution studies. These limitations do not weaken the core conclusion that selective lead candidates have been identified, but they do define the boundary of what can currently be claimed.

Future work should proceed along several integrated lines. The immediate next step is direct irradiation testing using proton beams, with photon comparators included wherever possible. These experiments should prioritize clonogenic survival, apoptosis kinetics, and formal enhancement calculations. It will also be important to evaluate responses at different positions relevant to proton beam structure, especially if higher biological effects are expected in regions associated with increased linear energy transfer. In parallel, mechanistic studies should quantify intracellular ROS, antioxidant depletion, mitochondrial membrane potential, cell cycle redistribution, DNA damage markers, and recovery kinetics. These measurements would allow clearer discrimination between simple additive toxicity and true stress-pathway convergence. Since the current data already suggest superiority of gemcitabine/cisplatin-centered systems, those combinations should likely be advanced first as lead architectures.

Beyond that, model complexity should be increased. Additional NSCLC cell lines representing distinct molecular backgrounds should be tested to determine whether the observed selectivity is a generalizable phenomenon or more restricted to specific tumor phenotypes. Normal bronchial epithelial cells, endothelial cells, and lung-relevant stromal comparators should also be included, since fibroblasts alone do not capture the full range of normal thoracic tissue sensitivity. Three-dimensional cultures, spheroids, and coculture systems would provide a more realistic environment for assessing penetration, diffusion constraints, and stromal protection. Eventually, orthotopic and image-guided *in vivo* models will be necessary to determine whether the biological advantage observed *in vitro* can be preserved in the spatially complex environment of lung tumors.

The modularity of the current platform also creates opportunities for further refinement. One particularly attractive direction is active targeting, such as the addition of folate receptor alpha-based recognition if compatible with the tumor subtype of interest. A targeting layer could improve tumor uptake, reduce off-target exposure, and potentially increase the therapeutic margin even further. The fact that the current system already demonstrates baseline selectivity means that active targeting would not be compensating for a fundamentally nonselective backbone; instead, it could reinforce an already promising biological distinction. That is a stronger starting point for translational development than many nanoparticle systems that depend entirely on speculative targeting efficiency.

More broadly, the findings reported here support a change in how adjuvants to proton therapy may be conceptualized. Instead of viewing sensitizers only as generic amplifiers of radiation response, it may be more useful to think in terms of biological conditioning. In this model, the role of the multicomponent nanoparticle-drug formulation is to drive the tumor into a state of unstable redox balance, impaired repair capacity, mitochondrial dysfunction, and heightened apoptotic susceptibility before or during irradiation. Proton therapy can then act on a tumor that is already biologically compromised, rather than relying on physical precision alone to secure treatment success. This approach is particularly relevant to NSCLC, where both the need for normal tissue sparing and the burden of biological resistance are unusually high.

In summary, the present study identifies microwave-synthesized CuO- and ZnO-based nanoparticle-drug combinations as promising selective adjuvant platforms for NSCLC, with gemcitabine/cisplatin-centered formulations emerging as the most potent and biologically favorable candidates. The data support a model in which these systems selectively intensify malignant-cell stress through overlapping effects on oxidative balance, mitochondrial integrity, and cell death signaling, while preserving a measurable degree of separation from normal

fibroblasts. Although direct proton irradiation experiments remain to be completed, the current findings establish a strong foundation for that next stage of work. By combining clinically recognizable drug backbones, biologically active nanomaterials, scalable microwave synthesis, and early safety signals, this study provides a credible basis for developing a new class of selective proton-therapy adjuvants for NSCLC.

References

- Ahamed, M., Siddiqui, M. A., Akhtar, M. J., Ahmad, I., Pant, A. B., & Alhadlaq, H. A. (2010). Genotoxic potential of copper oxide nanoparticles in human lung epithelial cells. *Biochemical and Biophysical Research Communications*, 396(2), 578-583.
- Ahamed, M., Akhtar, M. J., Raja, M., Ahmad, I., Siddiqui, M. K. J., AlSalhi, M. S., & Alrokayan, S. A. (2011). ZnO nanorod-induced apoptosis in human alveolar adenocarcinoma cells via p53, survivin and bax/bcl-2 pathways: Role of oxidative stress. *Nanomedicine: Nanotechnology, Biology and Medicine*, 7(6), 904-913.
- Ahamed, M., Akhtar, M. J., Siddiqui, M. A., Ahmad, J., Musarrat, J., Al-Khedhairi, A. A., AlSalhi, M. S., & Alrokayan, S. A. (2011). Oxidative stress mediated apoptosis induced by nickel ferrite nanoparticles in cultured A549 cells. *Toxicology*, 283(2-3), 101-108.
- Ahamed, M., Javed Akhtar, Kumar, S., Khan, M., Ahmad, J., & Alrokayan, S. A. (2012). Zinc oxide nanoparticles selectively induce apoptosis in human cancer cells through reactive oxygen species. *International Journal of Nanomedicine*, 845.
- Bawankule, A. K., Tatode, A. A., Patil, P. S., & Umekar, M. J. (2023). Folate-mediated paclitaxel nanodelivery systems: A comprehensive review. *Turkish Journal of Pharmaceutical Sciences*, 20(1), 58-67.
- Belani, et al. (1998). The emerging role of paclitaxel plus carboplatin in non-small-cell lung cancer.
- Bonomi, et al. (1999). Paclitaxel plus carboplatin versus paclitaxel plus cisplatin in advanced non-small-cell lung cancer: A randomized phase III trial.
- Bonvalot, S., Rutkowski, P., Thariat, J., et al. (2019). OC-0271 First randomized study of hafnium nanoparticles activated by radiotherapy in soft tissue sarcoma. *Radiotherapy and Oncology*, 133, S133-S134.
- Boyce-Fappiano, D., Nguyen, Q. N., Chapman, B. V., et al. (2021). Single institution experience of proton and photon-based postoperative radiation therapy for non-small-cell lung cancer. *Clinical Lung Cancer*, 22(5), e745-e755.
- Brooks, E. D., Ning, M. S., Verma, V., Zhu, X. R., & Chang, J. Y. (2019). Proton therapy for non-small cell lung cancer: The road ahead. *Translational Lung Cancer Research*, 8(S2), S202-S212.
- Chang, J. Y., Jabbour, S. K., De Ruyscher, D., et al. (2016). Consensus statement on proton therapy in early-stage and locally advanced non-small cell lung cancer. *International Journal of Radiation Oncology, Biology, Physics*, 95(1), 505-516.
- Chen, Y., Yang, J., Fu, S., & Wu, J. (2020). Gold nanoparticles as radiosensitizers in cancer radiotherapy. *International Journal of Nanomedicine*, 15, 9407-9430.
- Chen, Z., Dominello, M. M., Joiner, M. C., & Burmeister, J. W. (2023). Proton versus photon radiation therapy: A clinical review. *Frontiers in Oncology*, 13.
- Chen, et al. (2016). Spatial distributions of dose enhancement around a gold nanoparticle irradiated by proton beams.
- Cui, L., Her, S., Borst, G. R., Bristow, R. G., Jaffray, D. A., & Allen, C. (2017). Radiosensitization by gold nanoparticles: Will they ever make it to the clinic? *Radiotherapy and Oncology*, 124(3), 344-356.
- Davis, D. W., Neal, C., Gupta, V., et al. (2012). Antibody-independent ApoStream technology isolates folate receptor alpha (FRA)-positive circulating tumor cells from blood of non-small cell lung adenocarcinoma patients. *Journal of Clinical Oncology*, 30(15_suppl), e21028.

- Deng, J., Wu, G., Yang, C., et al. (2015). Rosuvastatin attenuates contrast-induced nephropathy through modulation of nitric oxide, inflammatory responses, oxidative stress and apoptosis in diabetic male rats. *Journal of Translational Medicine*, 13(1).
- Dhas, et al. (2021). Current state and prospects of proton boron capture therapy.
- Dorsey, J. F., et al. (2013). Gold nanoparticles in radiation research: Potential applications for imaging and radiosensitization. *Translational Cancer Research*, 2(4), 280-291.
- Doyen, J., Falk, A. T., Floquet, V., Hérault, J., & Hannoun-Lévi, J. M. (2016). Proton beams in cancer treatments: Clinical outcomes and dosimetric comparisons with photon therapy. *Cancer Treatment Reviews*, 43, 104-112.
- Fahmy, H. M., Ebrahim, N. M., & Gaber, M. H. (2020). In-vitro evaluation of copper/copper oxide nanoparticles cytotoxicity and genotoxicity in normal and cancer lung cell lines. *Journal of Trace Elements in Medicine and Biology*, 60, 126481.
- Harada, H., & Murayama, S. (2017). Proton beam therapy in non-small cell lung cancer: State of the art. *Lung Cancer: Targets and Therapy*, 8, 141-145.
- He, J., Liu, Y., Zhang, X., et al. (2024). Comparison of proton therapy and photon therapy for early-stage non-small cell lung cancer: A meta-analysis. *Biomarker Research*, 12(1).
- Her, S., Jaffray, D. A., & Allen, C. (2017). Gold nanoparticles for applications in cancer radiotherapy: Mechanisms and recent advancements. *Advanced Drug Delivery Reviews*, 109, 84-101.
- Hideghéty, K., Brunner, S., Cheesman, A., Szabó, E. R., Polanek, R., Margarone, D., Tóké, T., & Mogyórosi, K. (2019). ¹¹Boron delivery agents for boron proton-capture enhanced proton therapy. *Anticancer Research*, 39(5), 2265-2276.
- Hoffmann, M., Murdzek, J. A., George, S. M., et al. (2022). Atomic layer etching of ferroelectric hafnium zirconium oxide thin films enables giant tunneling electroresistance. *Applied Physics Letters*, 120(12).
- Isherwood, P. J. M. (2017). Copper zinc oxide: Investigation into a p-type mixed metal oxide system. *Vacuum*, 139, 173-177.
- Iwakiri, S., Sonobe, M., Nagai, S., et al. (2008). Expression status of folate receptor α is significantly correlated with prognosis in non-small-cell lung cancers. *Annals of Surgical Oncology*, 15(3), 889-899.
- Kim, Y. J., Lee, J. S., Lee, Y. U., Cho, S. H., Kim, Y. H., & Han, M. K. (2010). Solution-processed oxide thin-film transistor with spin-coated zinc tin oxide active layer and indium zinc oxide source/drain electrodes. *ECS Transactions*, 33(5), 289-294.
- Krishna, A. B., Arjun, S., Babu, J. S., & Vamadevan, R. (2023). Zinc oxide and copper oxide surfaces as potential adsorbent layers for greenhouse gases and hydrogen: A molecular dynamics analysis.
- Kuncic, Z., & Lacombe, S. (2018). Nanoparticle radio-enhancement: Principles, progress and application to cancer treatment. *Physics in Medicine & Biology*, 63(2), 02TR01.
- Lazarev, S., Rosenzweig, K., Samstein, R., et al. (2021). Where are we with proton beam therapy for thoracic malignancies? Current status and future perspectives. *Lung Cancer*, 152, 157-164.
- Liao, Z., & Simone II, C. B. (2018). Particle therapy in non-small cell lung cancer. *Translational Lung Cancer Research*, 7(2), 141-152.
- Manegold, C., Zatloukal, P., Krejcy, K., & Blatter, J. (2000). Gemcitabine in non-small cell lung cancer (NSCLC). *Investigational New Drugs*, 18(1), 29-42.
- Marill, J., Anesary, N. M., Zhang, P., et al. (2014). Hafnium oxide nanoparticles: Toward an in-vitro predictive biological effect? *Radiation Oncology*, 9(1).
- Martinkova, P., Brtnicky, M., Kynicky, J., & Pohanka, M. (2017). Iron oxide nanoparticles: Innovative tool in cancer diagnosis and therapy. *Advanced Healthcare Materials*, 7(5).
- Mesko, S., & Gomez, D. (2018). Proton therapy in non-small cell lung cancer. *Current Treatment Options in Oncology*, 19(12).

- Moloudi, K., Khani, A., Najafi, M., et al. (2023). Critical parameters to translate gold nanoparticles as radiosensitizing agents into the clinic. *WIREs Nanomedicine and Nanobiotechnology*, 15(6).
- Nabavinia, M., & Beltran-Huarac, J. (2020). Recent progress in iron oxide nanoparticles as therapeutic magnetic agents for cancer treatment and tissue engineering. *ACS Applied Bio Materials*, 3(12), 8172-8187.
- Nagi, N. M. S., Khair, Y. A. M., & Abdalla, A. M. E. (2017). Capacity of gold nanoparticles in cancer radiotherapy. *Japanese Journal of Radiology*, 35(10), 555-561.
- Natale, R. B. (2002). Gemcitabine-based doublets for advanced non-small-cell lung cancer: Beyond gemcitabine/cisplatin. *Clinical Lung Cancer*, 3, S10-S16.
- Nazemof, N., Breznan, D., Dirieh, Y., et al. (2024). Cytotoxic potencies of zinc oxide nanoforms in A549 and J774 cells. *Nanomaterials*, 14(19), 1601.
- Nichols, R. C., Jr., Huh, S. H., Henderson, R. H., et al. (2012). Selective nodal irradiation of regionally advanced non-small-cell lung cancer with proton therapy and IMRT: A dosimetric comparison. *Thoracic Cancer*, 3(2), 169-174.
- Nunez, M. I., Behrens, C., Woods, D. M., et al. (2012). High expression of folate receptor alpha in lung cancer correlates with adenocarcinoma histology and mutation. *Journal of Thoracic Oncology*, 7(5), 833-840.
- Patel, N. V., Yu, N. Y., Koroulakis, A., et al. (2021). Proton therapy for thoracic malignancies: A review of oncologic outcomes. *Expert Review of Anticancer Therapy*, 21(2), 177-191.
- Penninckx, S., Heuskin, A. C., Michiels, C., & Lucas, S. (2020). Gold nanoparticles as a potent radiosensitizer: A transdisciplinary approach from physics to patient. *Cancers*, 12(8), 2021.
- Peukert, D., Kempson, I., Douglass, M., & Bezak, E. (2019). Gold nanoparticle enhanced proton therapy: Monte Carlo modeling of reactive species' distributions around a gold nanoparticle and the effects of nanoparticle proximity and clustering. *International Journal of Molecular Sciences*, 20(17), 4280.
- Predina, J. D., Newton, A. D., Connolly, C., et al. (2018). Identification of a folate receptor-targeted near-infrared molecular contrast agent to localize pulmonary adenocarcinomas. *Molecular Therapy*, 26(2), 390-403.
- Ricciardi, V., Bláha, P., Buompane, R., et al. (2021). A new low-energy proton irradiation facility to unveil the mechanistic basis of the proton-boron capture therapy approach. *Applied Sciences*, 11(24), 11986.
- Rinaldi, M., & Crinò, L. (2001). Induction chemotherapy with gemcitabine and cisplatin in stage III non-small cell lung cancer. *Lung Cancer*, 34, 25-30.
- Scaranti, M., Cojocaru, E., Banerjee, S., & Banerji, U. (2020). Exploiting the folate receptor α in oncology. *Nature Reviews Clinical Oncology*, 17(6), 349-359.
- Scher, N., Poortmans, P., & Calugaru, V. (2020). PO-1827: Clinical application of radiation-enhancing nanoparticles. *Radiotherapy and Oncology*, 152, S1019.
- Schild, S. E. (2014). Proton beam therapy for locally advanced lung cancer: A review. *World Journal of Clinical Oncology*, 5(4), 568.
- Schonewolf, C. A., Jolly, S., & Dess, R. T. (2021). Particle beam therapy for cardiac-sparing radiotherapy in non-small cell lung cancer. *Seminars in Radiation Oncology*, 31(2), 112-119.
- Sharker, S. M. (2019). Hexagonal boron nitrides (white graphene): A promising method for cancer drug delivery. *International Journal of Nanomedicine*, 14, 9983-9993.
- Shen, H., Huang, H., & Jiang, Z. (2023). Nanoparticle-based radiosensitization strategies for improving radiation therapy. *Frontiers in Pharmacology*, 14.
- Shepherd, A. F. (2018). Proton therapy for post-operative radiation therapy of non-small cell lung cancer. *Translational Lung Cancer Research*, 7(2), 205-209.
- Steuer, et al. (2017). The role of chemotherapy in advanced stage non-small cell lung cancer.

- Strauch, B. M., Niemand, R. K., Winkelbeiner, N. L., & Hartwig, A. (2017). Comparison between micro- and nanosized copper oxide and water soluble copper chloride: Interrelationship between intracellular copper concentrations, oxidative stress and DNA damage response in human lung cells. *Particle and Fibre Toxicology*, 14(1).
- Tran, N. H., Shtam, T., Marchenko, Y. Y., Konevega, A. L., & Lebedev, D. (2023). Current state and perspectives for proton boron capture therapy. *Biomedicines*, 11(6), 1727.
- Varzandeh, M., Sabouri, L., Mansouri, V., et al. (2023). Application of nano-radiosensitizers in combination cancer therapy. *Bioengineering & Translational Medicine*, 8(3).
- Volpe, S., Piperno, G., Colombo, F., et al. (2022). Hypofractionated proton therapy for non-small cell lung cancer: Ready for prime time? A systematic review and meta-analysis. *Cancer Treatment Reviews*, 110, 102464.
- Wang, B., Zhang, J., Chen, C., et al. (2018). The size of zinc oxide nanoparticles controls its toxicity through impairing autophagic flux in A549 lung epithelial cells. *Toxicology Letters*, 285, 51-59.
- Wang, Z., Shi, H., Guo, J., & Li, C. (2015). A current review of folate receptor alpha as a potential tumor target in non-small-cell lung cancer. *Drug Design, Development and Therapy*, 9, 4989-4996.
- Wongrakpanich, A., Mudunkotuwa, I. A., Geary, S. M., et al. (2016). Size-dependent cytotoxicity of copper oxide nanoparticles in lung epithelial cells. *Environmental Science: Nano*, 3(2), 365-374.
- Zou, et al. (2020). Concurrent chemo-proton therapy using adaptive planning for unresectable stage III non-small cell lung cancer: A phase II study.

Medical Sciences

UDC: 616.441-006.6

THYROID CANCER: CURRENT UNDERSTANDING AND TRENDS

Arman Khozhayev

Professor of the S.N. Nugmanov Department of Oncology, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Raikhon Shlymova

Associate Professor of the Department of Internal Medicine, Astana Medical University, Astana, Kazakhstan

Gulmira Balshikbayeva

Resident endocrinologist, Astana Medical University, Astana, Kazakhstan

Marianna Shopanova

Resident endocrinologist, Astana Medical University, Astana, Kazakhstan

Tansholpan Ukash

Resident endocrinologist, Astana Medical University, Astana, Kazakhstan

Sholpan Kydyrmanova

Resident endocrinologist, Astana Medical University, Astana, Kazakhstan

Aizhan Mustafa

Resident endocrinologist, Astana Medical University, Astana, Kazakhstan

Balnur Sovetova

Resident endocrinologist, Astana Medical University, Astana, Kazakhstan

Annotation: this scientific and analytical work presents modern world and local-regional data on incidence, mortality, lethality and five-year survival rate of such a common oncological pathology as thyroid cancer. The issues of etiology and pathogenesis, modern approaches and principles of complex diagnostics, prospects for improving treatment results, as well as the prognosis are covered in detail. The epidemiological characteristics of this pathology in our republic are given in the context of the regions of the country.

Key words: oncology, endocrinology, primary care, thyroid gland, thyroid cancer, biomarkers, RNA, ultrasound examination, epidemiology, incidence, mortality, lethality, five-year survival rate, prognosis.

Thyroid cancer (TC) is a malignant tumor that develops from thyroid tissue. The following diagnostic criteria for TC are distinguished. Complaints about: enlargement of the gland; appearance of a tumor on the anterior and lateral surface of the neck; change in voice (with tumor growth into the recurrent nerve); rapid tumor growth; shortness of breath, feeling of lack of air (with tumor growth into the recurrent nerve, upper respiratory tract). Anamnesis: thyroid disease (hypothyroidism, euthyroidism, hyperthyroidism, thyroiditis); long-term use of antithyroid drugs; ionizing radiation; history of radiation therapy to the head and neck. Physical examination: 1) upon examination, neck deformity (uniform swelling on the anterior surface of the neck, asymmetry due to an increase in any part of the thyroid gland, an increase in regional lymph nodes); 2) palpation examination of the thyroid gland - the presence of a nodular formation in the thickness

of the thyroid gland, dense consistency; 3) palpation examination of regional lymph nodes - dense consistency, painful, mobile, immobile, partially mobile.

Laboratory tests: cytological examination; histological examination. Immunohistochemical examination: TTF-1, determination of calcitonin, fine-needle aspiration biopsy. All patients diagnosed with medullary TC or a family history of medullary TC or multiple endocrine neoplasia syndrome type 2 are recommended to undergo genetic testing to determine the germline mutation rearranged during transfection (RET) in order to determine the prognosis of the disease.

Instrumental studies: 1) ultrasound examination of the thyroid gland (determines the structure of the gland and tumor, the presence of a nodular formation, cystic cavities, size, echogenicity); the protocol for ultrasound examination of the thyroid gland includes determining the size, localization, ultrasound characteristics of the tumor; suspicious signs are (assessed only in solid nodes or in solid areas of the nodes) hypoechoic solid structure; uneven, fuzzy or polycyclic contour; point hyperechoic inclusions (microcalcifications); predominance of the anteroposterior size of the node over the width ("higher/than/wider"); 2) ultrasound examination of the cervical, submandibular, supraclavicular, subclavian lymph nodes (the presence of enlarged lymph nodes, structure, echogenicity, size); The protocol for ultrasound examination of the thyroid gland and regional lymph nodes should include assessment of the following parameters: size (it is necessary to assess the diameter or anteroposterior size, and not the length; for all cervical lymph nodes, except for level II - the fascial cellular space of the neck (submandibular zone), the largest size is no more than 0.6 cm, for level II - no more than 0.8 cm); the ratio of the long and short axes; the presence / absence of the gate; cystic changes; point hyperechoic inclusions (microcalcifications); the nature of vascularization (gate or the entire lymph node); increased echogenicity of the lymph node (similarity to normal thyroid tissue); the most specific signs that allow us to suspect metastatic lesions of the lymph node are microcalcifications, a cystic component, peripheral vascularization, and similarity of the lymph node tissue to the thyroid gland; less specific signs are an increase in size, rounded contours, and the absence of a hilum; 3) computed tomography and/or magnetic resonance imaging of the soft tissues of the neck and mediastinum (with contrast - in the presence of invasion into the main vessels, with a retrosternal location), fine-needle aspiration biopsy from the tumor (allows us to determine tumor and non-tumor processes, the benign and malignant nature of the tumor); 4) skeletal scintigraphy (prescribed if bone metastases are suspected); 5) positron emission tomography, positron emission tomography/computed tomography of the whole body (performed to diagnose the prevalence of the tumor process or the progression of the disease, or to assess the dynamics of the effectiveness of specialized treatment) [1].

The thyroid or glandula thyroidea is an endocrine gland located in the neck below the larynx in front of the trachea in mammals. In humans, it has the shape of a butterfly. It consists of two lobes connected by a narrow bridge called the isthmus. Thyroid carcinoma or TC is a malignant tumor of the thyroid gland. It is the most common malignancy of the endocrine (hormonal) system, but is very rare, accounting for about 1% of all malignant tumors, however, it has been increasing in frequency in recent years. TC is a malignant tumor of the glandular tissue of the thyroid gland. There are different types of TC that arise from different cells in the thyroid gland. TC comprises several categories: (1) differentiated TC (DTC), including papillary (PTC), follicular (FTC), and Hürthle cell tumours, (2) medullary TC (MTC) and (3) anaplastic TC. The long-term survival rate of patients with differentiated TC is about 90%, whereas patients with poorly differentiated TC types show a long-term survival rate of below 10% due to their resistance to standard treatment options [2]. The latest Global Cancer Observatory survey from 2020 reports that TC is responsible for 586,000 cancer cases worldwide [3].

Horgan D. et al. in their work they say that TC is the most common malignancy of the endocrine system that affects the thyroid gland. It is usually treatable and, in most cases, curable.

The central issues are how to improve knowledge on TC, to accurately identify cases at an early stage that can benefit from effective intervention, optimise therapy, and reduce the risk of overdiagnosis and unnecessary treatment. Our colleagues focus on the fact that the approach to TC needs a rethink to early and correct identification of patients and improve their patient journey and treatment outcomes, including improved quality of life. All patients should be referred to comprehensive cancer centres. Such an approach would instate an optimal patient management mitigating overdiagnosis and overtreatment and would improve access to biomarker testing, clinical trials, and appropriate systemic therapies for patients with advanced forms of TC. It would also help establish focused national expertise on rare TC cases, promote research, training, awareness, and facilitate international collaboration [4].

Treatment and molecular testing guidelines should be regularly updated at regional and national levels to facilitate the reimbursement and availability for the most effective diagnostics and therapies. In the most recent update of the clinical practice guidelines, ESMO highlights for the first time the need to test for actionable cancer alterations in TC. It is essential that national guidelines are coordinated with the European and international ones [5].

Quality comprehensive genomic testing should be incorporated in clinical practice (tissue or liquid samples) for all TC patients that can benefit from targeted therapies. In order to facilitate correct diagnosis, pathology practice, data collection and analysis, as well as communication with the treating physicians should be improved, with the provision of registers based on pathology. National cancer registries should distinguish specific diseases with standardised, quality-controlled systems, including details of case management and including long-term survival data. National and international data bases are needed not only for refractory TC, but for all types of TC. Thyroid gland examination practices in the asymptomatic general population need updating. With the rapid growth of big data analytics in genomics, imaging, and clinical outcomes, health systems should make it possible to generate a personalised, data-driven risk profile to customise therapy for individual patients, aiming for both long-term tumour control and manageable adverse effects [4].

Silva S.N. [6] notes that TC is not just a common type of cancer, it is the most frequently diagnosed endocrine malignancy worldwide. The etiology of TC is essentially multifactorial and radiation is the best documented risk factor related to the disease. However, many questions are still open and seeking clarification, especially regarding the genetic aspects of this pathology, with clear implications not only on a scientific basis of the disease, but foremost in clinical oncology. Thyroid gland tumours are a heterogeneous group of neoplasms that may arise from virtually any of the different cell types that are present in the thyroid gland. Although the malignant tumours are most frequently identified in thyroid follicular cells, it is clear that the molecular-genetic characterization is crucial and should be further explored to emphasize differences in tumour biological behaviours, aggressiveness, and disease prognostics. Papillary and follicular thyroid carcinomas (PTC and FTC, respectively) represent 85-90% and 5-10% of TC cases, respectively, arising from thyroid follicular cells. These tumour histotypes retain their morphologic features and are often referred to as DTC. However, the etiology of DTC is still unknown. Considerable progress has been made in the understanding of thyroid carcinogenesis, in part based on retrospective and prospective studies published worldwide in recent decades, but also in the development of high-throughput approaches and the availability of improved diagnostic methodologies that lead to early diagnosis. In fact, over the last few decades, the research in TC has highlighted the mutational landscape leading to better understanding of the molecular pathogenesis of DTC.

The hallmarks of cancer have been identified with several potential targets involved in gene expression deregulation, leading to the promotion of genetic instability and cancer development. The identification of genetic variants related to TC has been a long way, though it is crucial to identify possible potential biomarkers of susceptibility. Some genetic variants have been identified

in specific subtypes, which are related to the increased risk to develop this malignancy, such as the BRAF V600E mutation in PTC patients with a more aggressive phenotype if telomerase reverse transcriptase gene promoter mutation coexists [7].

However, mutations in RET and Retrovirus Associated DNA Sequences genes have also been identified as biomarkers in TC patients.

Alongside with genetic variants, epigenetic events and alterations in the expression of microRNA (miRNA) and long noncoding RNA (lncRNA) may also, through modulation of gene expression, drive the aberrant activation of oncogenic signalling pathways and the downregulation of thyroid-specific genes, thus contributing to the development, progression, and dedifferentiation of TC [8].

Connected to this, the genetic instability inflicted in this malignancy, involving genetic and epigenetic alterations, might also compromise the treatment response. The standard treatment for TC patients consists of surgical resection accompanied by post-thyroidectomy radioiodine (RAI) adjuvant therapy. The radioiodine therapy relies on the ability of ¹³¹I to be preferentially taken up in normal or neoplastic thyroid follicular cells. Its accumulation induces high DNA damage, which leads to cytotoxicity. However, the ionizing radiation does not only affect tumour cells, but the lesions may also impair normal cells. The most common lesions induced by radiation are double-strand breaks, which are processed by enzymes involved in DNA repair pathways. The presence of genetic variants in these enzymes might impair the repair efficiency but also could influence the cytotoxic potential of RAI therapy, hence its efficacy in DTC treatment. The development of induced DNA damage approaches can help in the evaluation of the efficacy of therapeutics as it has been shown to be an important tool for establishing biomarkers of susceptibility. Although the most frequent variants identified in TC contribute to sporadic disease, about 5 to 15% of all diagnosed cases are familial (first degree relatives) in nonMTC, increasing to 25% in MTC cases. This adds to the clear existence of genetic predisposition factors related to this pathology. Advances in molecular genetics and several candidate gene studies developed worldwide have linked the occurrence of this malignancy to some hereditary syndromes, some of which are related to germline mutations in RET genes [6].

Macvanin M.T. et al. [9] in their study note that after the metabolic syndrome and its components, thyroid disorders represent the most common endocrine disorders, with increasing prevalence in the last two decades. Thyroid dysfunctions are distinguished by hyperthyroidism, hypothyroidism, or inflammation (thyroiditis) of the thyroid gland, in addition to the presence of thyroid nodules that can be benign or malignant. TC is typically detected via an ultrasound fine-needle aspiration biopsy, cytological examination of the specimen and measurements of traditional biochemical markers, such as TSH, FT4, Tg, TgAb, and TPOAB. Novel RNA-based markers of thyroid neoplasms are identified by expression profiling of the thyroid gland tissue and/or blood samples of patients using high-throughput platforms for RNA analysis and identification, such as next-generation sequencing. Other emerging biomarkers of thyroid neoplasms are identified using flow cytometry, enzyme-linked immunosorbent assays, genetic tests, and immunohistological analyses. Due to the rapid advancement of high-throughput molecular biology techniques, it is now possible to identify new biomarkers for thyroid neoplasms that can supplement traditional imaging modalities in postoperative surveillance and aid in the preoperative cytology examination of indeterminate or follicular lesions. In conclusion, the authors draw attention to the fact that due to the rapid advancement of high-throughput molecular biology techniques, it is now possible to identify novel biomarkers for thyroid neoplasms that can supplement or replace existing biomarkers. Current circulating biomarkers, such as Tg or TgAb, are routinely used in postoperative monitoring; however, at the preoperative stage, they cannot distinguish between benign and malignant neoplasms or between low- and high-risk malignant lesions. Several new targets are emerging as potentially useful prognostic circulating biomarkers for TC. Evidence for

miRNA, lncRNA and circular RNA (circRNA) dysregulation in several thyroid neoplasms and their potential use as sensitive diagnostic and prognostic biomarkers is particularly interesting. However, the data currently available in the literature is derived from small-scale clinical studies in specific patient cohorts. Thus, further validation is required to demonstrate their potential for clinical application. Large-scale studies are needed to confirm and validate novel biomarkers in the diagnosis, prognosis, and surveillance of thyroid neoplasms, such as miRNAs, lncRNAs, and circRNAs.

As they note in their work Saenko V., Mitsutake N. [10], radiation is an environmental factor that elevates the risk of developing TC. Actual and possible scenarios of exposures to external and internal radiation are multiple and diverse. In this case: 1) radiation is a risk factor for TC; the risk steadily increases up to the dose of 10 Gy, levels off in the 10- to 30-Gy interval, and asymptotically declines at higher doses but remains elevated; once exposed, the risk persists for many decades; 2) risks from the external and internal irradiation are comparable; 3) there is no evidence of dose-response departure from linearity at low doses (<0.1 Gy) and of the existence of a “safe” threshold dose; 4) the magnitude of radiation risk for TC is highest if exposure takes place at a young age; 5) after the Chornobyl nuclear reactor accident, due to internal exposure to radioactive iodine, a dramatic increase in the incidence of childhood TCs was observed, especially among children less than 5 years old at the time of the accident; 6) although many TCs were found by the thyroid-screening program after the Fukushima nuclear power plant accident, comparisons of exposures and characteristics of TC diagnosed after the Chornobyl and Fukushima nuclear accidents do not support a causative role of radiation in the latter; 7) reduction of the risk for TC may be achieved by following the As Low As Reasonably Achievable principle, and iodine thyroid blockage may be performed to protect from anticipated internal exposure. A substantial progress in understanding of radiation-related TC has been achieved since the discovery of this phenomenon about 60 years ago. Irradiation of the head, neck, and chest areas has been learned to increase the risk for developing thyroid malignancy during the lifespan. This stimulated numerous investigations in medical, industrial, and military settings whenever radiation exposure was relevant. Radiation risks have been quantified and found to be comparable for the external and internal radiation. According to this knowledge, certain groups at elevated risk could be determined, including those with medical, occupational, or emergency exposures. Now, the focus of radiation risk studies is shifting toward low-dose exposures in view of growing number of various radiological procedures, especially in pediatric patients. The markers of radiation-related TC have not been found so far. Overlaps in the histological types, oncogenic driver spectrums, and corresponding gene expression profiles between radiation-related and sporadic tumors suggest that these parameters were unlikely to serve as a marker. Clinical studies have demonstrated that TCs diagnosed in irradiated patients are of the same histological types as in nonirradiated patients and that disease prognosis is determined by tumor characteristics regardless of etiology. This is rather good news for clinicians to know that standard treatment and follow-up approaches could be used for radiation-exposed patients, but it is necessary to keep in mind that TC phenotype is changing with patient age and latency period.

Lukasiewicz M. et al. [11] emphasize that the etiology of TC is complex, and a variety of factors contribute to its development. Among these factors, disorders of lipid metabolism have emerged as a notable area of interest. Lipids, including fatty acids (FA), play a fundamental role in cell structure and function. Consequently, disturbances in lipid metabolism can have profound effects on various cellular processes, potentially favoring the development and progression of TC. Understanding the intricate relationship between lipid metabolism disorders and TC is of paramount importance as it may provide new insights into the prevention and treatment of this malignancy. TC is a neoplasm with an increasing incidence worldwide. Its etiology is complex and based on a multi-layered interplay of factors. Among these, disorders of lipid metabolism have

emerged as an important area of investigation. Cancer cells are metabolically reprogrammed to promote their rapid growth, proliferation, and survival. This reprogramming is associated with significant changes at the level of lipids, mainly FA, as they play a critical role in maintaining cell structure, facilitating signaling pathways, and providing energy. These lipid-related changes help cancer cells meet the increased demands of continued growth and division while adapting to the tumor microenvironment. Recent scientific efforts have revealed disturbances in lipid homeostasis that are specific to TC, opening up potential avenues for early detection and targeted therapeutic interventions. Understanding the intricate metabolic pathways involved in FA metabolism may provide insights into potential interventions to prevent cancer progression and mitigate its effects on surrounding tissues.

Luzón-Toro B. et al. [12] emphasize in their publication that TC, a cancerous tumor or growth located within the thyroid gland, is the most common endocrine cancer. It is one of the few cancers whereby incidence rates have increased in recent years. It occurs in all age groups, from children through to seniors. Most studies are focused on dissecting its genetic basis, since our current knowledge of the genetic background of the different forms of TC is far from complete, which poses a challenge for diagnosis and prognosis of the disease. TC is the most common endocrine cancer, with an increasing overall incidence in recent decades of about two fold in the last 25 years and accounting for 2% of all cancers. TC is the sixth most common cancer in women, who are three times more likely to have TC than men. About 2% of cases occur in children and teens. Overall, the 5-year survival rate of TC is 98%. However, survival rates depend on many factors, such as the specific type of TC and stage of disease. TC is a disease induced by progressive genetic and epigenetic molecular abnormalities. Most studies describe several classical aberrations involved in the tumorigenesis and progression of this tumor, such as point mutations, gene copy number variations, and aberrant gene methylation. The genetic landscape of TC is growing rapidly. Therapies that are targeted at genetic mutations related to this tumor are being used in patient care and clinical trials. In comparison with traditional disease-specific trials, molecular allocation studies ("basket studies") are testing targeted therapies in patients whose tumors carry particular mutations, in spite of the tumor type or origin. These studies are more informative on anticancer therapies because they include a greater number of patients. The correlation of molecular profile (obtained by new sequencing technologies) with clinicopathological characteristics will lead to the development of novel precision therapies, reducing incidence and mortality in TC patients. In this sense, differential response to a mitogen-activated protein kinase inhibitor was found to be related to the thyroid cancer genotype. Molecular testing of mutation hotspots, rearrangements, and gene expression is now an effective diagnostic tool to better select patients for potential thyroid surgery. The authors note that the diagnosis and treatment of TC is nowadays influenced by the molecular characterization of TC types. The improvement of such techniques would help to reduce the amount of TC treatment needed and improve outcomes in patients with clinically aggressive forms of cancer.

Chen D.W. et al. [13] emphasize in their work that the past 5-10 years have brought in a new era in the care of patients with TC, with the introduction of transformative diagnostic and management options. Several international ultrasound-based thyroid nodule risk stratification systems have been developed with the goal of reducing unnecessary biopsies. Less invasive alternatives to surgery for low-risk TC, such as active surveillance and minimally invasive interventions, are being explored. New systemic therapies are now available for patients with advanced TC. However, in the setting of these advances, disparities exist in the diagnosis and management of TC. As new management options are becoming available for TC, it is essential to support population-based studies and randomised clinical trials that will inform evidence-based clinical practice guidelines on the management of TC, and to include diverse patient populations in research to better understand and subsequently address existing barriers to equitable TC care.

Now, regarding this pathology in our country at the republican level. The incidence of TC in the Republic of Kazakhstan in 2023 was 5.4 per 100 thousand population (4.8 in 2022) with a growth rate of 13.1% compared to the previous year, taking 3rd place together with connective and soft tissue tumors, second only to prostate cancer (16.7%) and laryngeal cancer (15.5%), and amounting to 1084 people in absolute numbers (939 cases a year earlier). The proportion of cases diagnosed for the first time in life, recorded by oncology organizations, was 2.9% (2.7% in 2022). In this case, 167 men fell ill (the proportion is 1.0%), women - 917 (the proportion is 4.4%) [14].

The TC rate above the national average was established in 9 regions of the country: North Kazakhstan - 12.6 (the maximum rate); East Kazakhstan - 10.6; Pavlodar - 8.5; the city of Astana - 8.2; the city of Almaty - 7.9; Kyzylorda - 7.6; Karaganda - 7.0; Akmola - 6.5; Abay - 5.9. This indicator is below the national average in 11 regions: Turkestan - 1.7 (the lowest rate); the city of Shymkent - 2.4; Atyrau - 2.6; Almaty - 3.0; West Kazakhstan - 3.8; Aktobe - 4.0; Zhambyl and Kostanay - 4.1; Ulytau - 4.5; Mangistau - 4.9; Zhetysu - 5.0 regions per 100 thousand population. Mortality from this pathology was 0.3 per 100 thousand population with an increase rate of 19.1% compared to the previous year, second only to non-melanoma skin cancer (26.0%).

The regions where the TC mortality rate is higher than the national average (0.3 per 100 thousand population) include: Abay - 1.0 (maximum level); Aktobe - 0.7; East Kazakhstan and Pavlodar - 0.5; Zhambyl, Karaganda, North Kazakhstan and the city of Almaty - 0.4. Zhetysu region and the city of Shymkent are on par with the national average. The lowest rates are noted in Atyrau and Ulytau - 0.0; Akmola, West Kazakhstan, Kostanay, Mangistau and Turkestan - 0.1; Almaty, Kyzylorda regions and the city of Astana - 0.2 per 100 thousand population [14].

One-year lethality was 2.3% (2.4% in 2022). At the same time, the ratio between one-year lethality and neglect (stage IV) was, as in 2022, 0.5, and this is the best indicator among all nosological forms of malignant tumors after prostate cancer (0.3). At the same time, we recall that the farthest from "1" is the worst ratio between one-year lethality and neglect.

Now, regarding preventive examinations. It should be noted that during large-scale preventive examinations of the population in 2023, significantly more patients with malignant neoplasms were actively identified than in 2022. This is 25,193 patients versus 23,623 patients identified in 2022, i.e. +6.6%. This is due to the further abatement of the epidemiological situation with coronavirus and the increased availability of preventive care for the population. The proportion of patients identified during routine examinations increased from 62.0% to 62.4% of the total number of patients identified over the year.

Of course, when analyzing the epidemiological situation, early diagnosis indicators are very important issues.

As for TC, the early detection of this pathology during routine examinations increased from 78.6% to 83.7%. The absolute number of TC patients identified during routine examinations was 900 people (732 a year earlier). At the same time, 849 are patients with early stages (in 2022 - 683 patients) [14].

In general, according to the amount of detected cases of cancer of all localizations, in 2023 the proportion of forms detected at early stages (0, I-II stages) increased from 66.3% to 67.9%. At the same time, detection at 0, I-II stages in TC increased from 93.3% to 94.3%. The regions where the proportion of patients with early stage I of the pathology in question is above the national average (71.5% and 2nd rank place among the best indicators after non-melanoma skin cancer) include the following regions: Kyzylorda - 85.9% (the best indicator); the city of Almaty - 84.8%; the city of Astana - 83.3%; North Kazakhstan - 80.0%; West Kazakhstan - 76.9%; Karaganda - 73.4%; Zhambyl - 72.0%; Almaty - 71.7%.

The lowest rates of early diagnosis were recorded in: East Kazakhstan - 50.6% (the worst rate); Atyrau and Turkestan - 55.6%; Mangistau - 56.8%; Zhetysu - 57.1%; Akmola - 58.8%; Aktobe - 59.5%; Ulytau - 60.0%; Kostanay - 60.6%; Abay - 65.7%; Pavlodar - 69.8% regions and in the city

of Shymkent - 71.4%.

TC is in the top three in early diagnosis (stages I-II) - 92.4%. First place goes to non-melanoma skin cancer (98.4%), third - to lip cancer (90.7%). The regions where the proportion of patients with TC detected at stages I-II is above the national average (92.4% - 2nd rank place) include the following regions. The leaders are our two megacities - the city of Astana (98.2%) and the city of Almaty (97.1%). Next come: Kyzylorda - 96.9%; Zhambyl - 96.0%; Karaganda - 94.9%; Aktobe - 94.6%; Atyrau and Turkestan - 94.4%; East Kazakhstan - 93.5% regions and the city of Shymkent (92.9%). Low rates of early diagnosis were recorded in Ulytau - 70.0% (the worst result in the country); Kostanay - 72.7%; Abay - 80.0%; Akmola - 80.4%; Zhetysu - 82.9%; North Kazakhstan - 90.8%; Almaty - 91.3%; Mangistau - 91.9%; Pavlodar - 92.1%; West Kazakhstan - 92.3% regions [14].

As is clearly seen from the above data, there is a very large spread in early diagnostic rates across the country, from very good to thought-provoking. Of course, it is necessary to take into account migration processes and other factors affecting early diagnostic rates, but nevertheless, the results obtained give reason not to stop there, both for oncologists and endocrinologists, ultrasound diagnostic doctors, otolaryngologists, and general practitioners, since improving early diagnostic rates of malignant tumors has remained one of the main postulates and one of the main tasks of medicine in general, and continues to be relevant today.

The proportion of stage IV TC among all nosological forms of malignant neoplasms was 3.9%, and this is the 4th rank place after tumors of the central nervous system (2.5%), lip cancer (0.9%) and non-melanoma skin cancer (0.4%). In general, in 2023, the share of stage IV malignant neoplasms in the republic for the sum of all nosologies decreased from 12.58 to 11.7% (from 4790 to 4735 patients). As for the average republican indicator of the share of stage IV (3.9%), Aktobe, Atyrau, West Kazakhstan regions and the city of Astana stand out against this background - 0.0%. Then come: the city of Almaty (0.6%); East Kazakhstan (1.3%); Turkestan (2.8%); Kyzylorda (3.1%) regions. Akmola region is on par with the average republican indicator. Lower indicators are in: Kostanay region, where every fifth patient with this visually accessible localization was detected in the terminal stage of the disease (21.2%). Next in line were: Abay - 14.3%, Ulytau - 10.0%, Zhetysu - 8.6%, the city of Shymkent - 7.1%; North Kazakhstan - 6.2%, Mangistau - 5.4%, Karaganda - 5.1%, Pavlodar - 4.8%, Almaty - 4.3% and Zhambyl - 4.0% regions.

The morphological verification rate of the disease in the country was 97.0%. In 13 regions out of 20 this figure is 100% (Abay, Aktobe, Almaty, Atyrau, East Kazakhstan, Zhambyl, West Kazakhstan, Karaganda, Mangistau, Pavlodar and Ulytau regions, as well as the cities of Astana and Shymkent. The lowest figure is in Kyzylorda region (68.8%). Further down the list are Zhetysu (88.6%), Kostanay (93.9%), Akmola (96.1%), Turkestan (97.2%), North Kazakhstan (98.5%) and the city of Almaty (98.8%) [14].

The total number of patients with malignant neoplasms registered with specialized oncology organizations of the republic continued to grow and by the end of 2023 amounted to 218,186 people, with an increase of 6.0% compared to the level of the previous year (2022 - 205,822, +5.8%). The overall incidence rate of malignant neoplasms increased by 3.9%, from 1055.3 to 1096.4 per 100 thousand people. The growth of this indicator is due to both the increase in the incidence and detection of pathology, and the increase in the survival rate of cancer patients. In addition, statistical data on patients diagnosed with malignant neoplasms, who have been under observation for 5 years or more, and continue to be observed in 2023, showed that the number of patients under observation by oncological organizations of Kazakhstan for over five years continued to grow and at the end of the reporting year amounted to 117,616 people, with an increase of 6.2% (2022 - 110,790 people, + 6.6%) (form No. 7).

One cannot ignore such an important clinical aspect as the coverage in the Republic of Kazakhstan of special treatment for patients diagnosed with TC for the first time in their lives. In

2023, the number of hospitalizations for all nosological forms of malignant tumors in oncological organizations of the country amounted to 108,252 cases (2022 - 101,095), with an increase of 7.1% compared to the previous year, which is associated with a constant increase in the number of cancer patients, improvement of the standardization of oncological care, and the development of palliative and restorative services. At the end of 2023, the absolute number of TC patients who completed specialized treatment amounted to 560 people, continuing treatment - 414 patients. In percentage terms, the following results were obtained by methods and types of treatment. The overwhelming majority - 90.4% of patients received surgical treatment only, complex - 3.8%, combined - 2.1%, only radiation - 0.4%, only drug - 0.2%.

Further, regarding the five-year survival rate of patients. As for TC, at the end of 2023, 9901 people or 49.8 per 100 thousand of the population were registered at the dispensary (at the end of 2022 - 9121 patients or 46.8 per 100 thousand of the population, respectively); and this is a high 7th rank place among all nosological forms of malignant neoplasms.

At the same time, the mortality rate of the observed contingents in 2023 was 0.6%, as in the previous year.

The five-year survival rate of patients with TC was 63.8% in 2023, while in 2022 it was 64.6% [14].

Summarizing the above, we can conclude that with TC, despite the fact that this localization is visually accessible, despite the increased effectiveness of preventive examinations and fairly high rates of early diagnosis, a high number of people with this pathology is noted annually, and the five-year survival rate does not reach 65%. The scarcity, variability and veiled nature of symptoms, their similarity with various non-core processes, leads to the neglect and progression of the disease, even during dispensary observation. All this requires both oncologists and, first of all, primary health care workers and, of course, endocrinologists, ultrasound diagnosticians, otolaryngologists to increase the level of oncological alertness, inform the population about early symptoms that may indicate this pathology or the onset of proliferative changes and conduct high-tech diagnostic measures, including for the purpose of differential diagnosis and, as a result, timely treatment. People from the risk group are recommended to visit specialized specialists annually and, if necessary, undergo an examination. An epidemiological assessment of the situation with TC in our country suggests that there are sometimes significant differences in the regions not only in incidence rates, but also in the parameters of early diagnosis and mortality from this pathology. In connection with the above, this pathology continues to be a serious problem of modern clinical oncology.

LITERATURE

1 Klinicheskij protokol diagnostiki i lechenija "Zlokachestvennye novoobrazovaniya shhitovidnoj zhelezy» - Odobren Ob#edinennoj komissiej po kachestvu medicinskih uslug Ministerstva zdravooohranenija Respubliki Kazahstan ot 08 sentjabrja 2023 goda. – Protokol №189. – 22 s (In Russ.).

2 Grimm D. Recent Advances in Thyroid Cancer Research. *Int J Mol Sci.* 2022 Apr 22;23(9):4631. doi: 10.3390/ijms23094631.

3 Sung H., Ferlay J., Siegel R.L., Laversanne M., Soerjomataram I., Jemal A., Bray F. Global Cancer Statistics 2020: GLOBOCAN Estimates of Incidence and Mortality Worldwide for 36 Cancers in 185 Countries. *CA Cancer J. Clin.* 2021;71:209–249. doi: 10.3322/caac.21660.

4 Horgan D., Führer-Sakel D., Soares P., Alvarez C.V., Fugazzola L., Netea-Maier R.T., Jarzab B., Kozaric M., Bartes B., Schuster-Bruce J., Dal Maso L., Schlumberger M., Pacini F. Tackling Thyroid Cancer in Europe-The Challenges and Opportunities. *Healthcare (Basel).* 2022 Aug 25;10(9):1621. doi: 10.3390/healthcare10091621.

- 5 Filetti S., Durante C., Hartl D., Leboulleux S., Locati L., Newbold K., Papotti M., Berruti A. ESMO Clinical Practice Guideline update on the use of systemic therapy in advanced thyroid cancer. *Ann. Oncol.* 2022;33:674-684. doi: 10.1016/j.annonc.2022.04.009.
- 6 Silva S.N. Special Issue: Genetic Perspectives in Thyroid Cancer. *Genes (Basel)*. 2021 Jan 20;12(2):126. doi: 10.3390/genes12020126.
- 7 Luzon-Toro B., Fernandez R.M., Villalba-Benito L., Torroglosa A., Antinolo G., Borrego S. Influencers on Thyroid Cancer Onset: Molecular Genetic Basis. *Genes*. 2019;10:913. doi: 10.3390/genes10110913.
- 8 Iacobas D.A. Biomarkers, Master Regulators and Genomic Fabric Remodeling in a Case of Papillary Thyroid Carcinoma. *Genes*. 2020;11:1030. doi: 10.3390/genes11091030.
- 9 Macvanin M.T., Gluvic Z.M., Zaric B.L., Essack M., Gao X., Isenovic E.R. New biomarkers: prospect for diagnosis and monitoring of thyroid disease. *Front Endocrinol (Lausanne)*. 2023 Jul 21;14:1218320. doi: 10.3389/fendo.2023.1218320.
- 10 Saenko V., Mitsutake N. Radiation-Related Thyroid Cancer. *Endocr Rev.* 2024 Jan 4;45(1):1-29. doi: 10.1210/endrev/bnad022.
- 11 Lukasiewicz M., Zwara A., Kowalski J., Mika A., Hellmann A. The Role of Lipid Metabolism Disorders in the Development of Thyroid Cancer. *Int J Mol Sci.* 2024 Jun 28;25(13):7129. doi: 10.3390/ijms25137129.
- 12 Luzón-Toro B., Fernández R.M., Villalba-Benito L., Torroglosa A., Antiñolo G., Borrego S. Influencers on Thyroid Cancer Onset: Molecular Genetic Basis. *Genes (Basel)*. 2019 Nov 8;10(11):913. doi: 10.3390/genes10110913.
- 13 Chen D.W., Lang B.H.H., McLeod D.S.A., Newbold K., Haymart M.R. Thyroid cancer. *Lancet.* 2023 May 6;401(10387):1531-1544. doi: 10.1016/S0140-6736(23)00020-X.
- 14 Kaidarova D.R., Shatkovskaya O.V., Ongarbayev B.T., Zhylkaidarova A.Zh., Seisenbayeva G.T., Lavrentyeva I.K., Sagi M.S. Indicators of the oncology service of the Republic of Kazakhstan, 2023: statistical and analytical materials – Almaty: KIOR JSC, 2024. – 410 p.

UDC: 616-006-071(574)

COMPREHENSIVE EVALUATION OF CANCER SCREENING PROGRAMS IN KAZAKHSTAN: BREAST, CERVICAL, AND COLORECTAL CANCER

Arman Khozhayev

Professor of the S.N. Nugmanov Department of Oncology, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Aruzhan Iniyat

Undergraduate Student, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Madina Issapova

Undergraduate Student, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Aida Baltabay

Undergraduate Student, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Bakdaulet Aitzhanov

Undergraduate Student, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Aigerim Iskakova

Undergraduate Student, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Barfinabonu Shonazarova

Undergraduate Student, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Yesseniya Laptiyeva

Undergraduate Student, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Bayansulu Aimurzina

Undergraduate Student, Asfendiyarov Kazakh National Medical University, Almaty, Kazakhstan

Annotation: In this scientific and analytical work, the indicators of incidence and mortality from cervical cancer, breast cancer and colorectal cancer in the regions of our country are considered. The screening methods currently used and the results of this preventive survey of the population are described in detail. Detailed step-by-step algorithms are presented, and the principles of organization and diagnostic capabilities of the screening program for the active detection of these nosological forms of malignant neoplasms in clinically asymptomatic individuals are reflected.

Key words: oncology, primary care, early diagnosis, cancer screening, cervical cancer, breast cancer, colorectal cancer, epidemiology, incidence, mortality, Pap test, smear for

oncocytology, ultrasound examination, mammography, hemocult test, fecal occult blood test - FOBT, total colonoscopy.

Today, one of the most important postulates of the oncology service continues to be the early diagnosis of malignant tumors. The purpose of screening is to identify asymptomatic (preclinical) cancer or precancerous conditions in an otherwise healthy target population. In this case, screening plays a leading role in secondary cancer prevention. The key concept of cancer screening is to identify pathology at a stage of development when the effectiveness of treatment is maximum and the prognosis is most favorable. When precancerous diseases are detected during screening, secondary prevention methods allow to prevent the transition of the initial pathological state to cancer. In this case, the main conditions for screening are the presence of trained personnel and a standard approach to identifying the trait being studied and evaluating the results. The methods used must be sufficiently simple, reliable and reproducible, as well as have sufficient sensitivity and high specificity [1-3].

Screening plays an important role in improving early diagnosis and treatment outcomes. According to the Guide to Cancer Early Diagnosis by Ilbawi A. et al. [4], screening aims to detect unrecognized cancer or its prior lesions in a typically healthy, asymptomatic population through tests or other procedures that can be applied quickly and are widely available to the target population. In screening, the target population is assessed for unrecognized cancer or precancer, and most people tested will not be diagnosed with the disease. Screening should be seen as a process and not as the performance of a specific test, examination, or procedure. The screening process includes a system of informing and inviting the target population to participate; administering the screening test; following-up with test results and referral for further testing among those with abnormal test results; ensuring timely pathologic diagnosis, staging and access to effective treatment with routine evaluation to improve the process. A screening program encompasses the process from invitation to treatment and requires planning, coordination and monitoring and evaluation.

To date, the republican cancer screening program includes three nosological forms of malignant neoplasms - cervical cancer (CC), breast cancer (BC), colorectal cancer (CRC). Let's consider the current epidemiological indicators, methodology and results of cancer screening in our country.

CC in the structure of all malignant tumors of both sexes of the population in 2022 took 6th place with a share of 5.51% (2021 - 4th place, 5.54%), in women - stable 2nd place - 9.7% (9.7%) [5].

The incidence rate per 100 thousand population increased from 9.4 to 9.92. In 10 regions of the republic, the incidence rate is higher than the national average: Pavlodar - 17.2 per 100 thousand people (2021 – 16.7) – the highest level, East Kazakhstan – 14.3 (10.8), North Kazakhstan – 14.3 (10.2), Atyrau – 13.2 (13.8), Zhetysu - 11.7, Karaganda - 11.7 (12.0), Abay - 11.1, Akmola - 11.1 (11.9), Mangistau - 11.1 (9.7), Kostanay - 10.8 (10.6) regions.

Low incidence rates in Zhambyl region - 5.8 per 100 thousand population (5.7), Turkestan region - 6.1 (5.2), Aktobe region - 8.3 (11.6), Kyzylorda region - 8.5 (8.2) areas.

CC in the structure of causes of death from malignant tumors of the population of both sexes in 2022 rose from 9th to 8th position, with a share of 4.6% (2021 - 4.3%), mortality from CC is stable at 3.1 per 100 thousand population (3.1).

The mortality rate from CC in 10 regions is higher than the national average: Akmola - 4.2 per 100 thousand population (2021 - 3.1) - maximum level, West Kazakhstan - 4.1 (4.8), Pavlodar - 3.8 (5.6), Almaty – 3.7 (2.5), Zhetysu – 3.7, Atyrau – 3.4 (4.0), East Kazakhstan – 3.3 (3.8), Karaganda - 3.2 (4.7), Kostanay - 3.2 (2.4) regions and Almaty city - 3.4 (2.9).

Below the national average, mortality was recorded in Abay region, cities Astana,

Shymkent - 2.9 per 100 thousand population, Mangistau - 2.8 (3.0), Turkestan - 2.3 (2.2), Aktobe - 2.2 (3.0), North - Kazakhstan - 2.0 (2.6), Kyzylorda regions - 1.7 (3.5) - the best result [5].

In 12 regions, a 100% level of morphological verification of the diagnosis was ensured, the lowest or worst indicator for the third year was in the Kyzylorda region - 94.3%, below the national average indicators in Akmola - 98.8%, Atyrau - 98.9%, Kostanay - 98, 9%, Mangistau - 97.6%, Pavlodar - 96.6%, regions and Almaty city - 98.5%;

In a number of regions, the frequency of diagnosis of stage I-II CC was below the national average (88.1%) - in Akmola - 76.2% (2021 - 73.6%) - the worst result in the country, in Karaganda - 77, 2%, Zhetysu - 82.9%, Abay - 83.8%, Kostanay - 84.3%, Aktobe - 85.5%, West Kazakhstan - 85.7%, Pavlodar - 81.3%, while that in the Atyrau region - 100.0% result.

The proportion of stage IV CC is higher than the national average (2.7%) in the following regions: the worst result is in Zhetysu (6.1%), above the national average in Karaganda - 5.1% (2021 - 5.6%), Akmola - 4.8% (2.3%), Kostanay - 4.5% (4.4%), North Kazakhstan - 3.9% (7.4%), Almaty - 3.7 % (5.1%), Zhambyl - 2.9% (0.0) regions, cities Almaty – 3.6% (1.8%) and Shymkent – 3.8% (5.9%). The lowest neglect is in the East Kazakhstan region - 1.0% (0.7%).

Late diagnosis rates (III-IV stages) for CC are above the national average - 11.9% (15.4% in 2021) were noted in Akmola - 23.8% (2021 - 26.4%) - worst result, Karaganda - 22.8% (35.2%), Pavlodar - 18.8% (20.8%), Zhetysu - 17.1% (24.2%), Abay - 16.2% (12.8%), Kostanay - 14.6% (15.6%), Aktobe - 14.5% (9.6%), West Kazakhstan - 14.3% (32.4%) regions. The lowest neglect is in the Mangistau region - 6.0% (20.8%).

Across the country, the five-year survival rate of patients with CC registered in 2018 was 59.9% in 2022, with a decrease from the level of 2021 (67.5% for those registered in 2017), and with a significant range in by region, from the maximum – 72.9% (2021 – 70.7%) in the North Kazakhstan region, to the minimum – 34.9% (64.4%) in the Atyrau region [5].

CC screening is a periodic, comprehensive examination of women of a certain age group as part of a special medical program to prevent and reduce incidence and mortality from CC.

Type of screening - population. The purpose of screening is to identify pre-invasive diseases of the cervix with subsequent recovery. The screening method is a cytological examination of a smear for oncocytology from the cervix (traditional and liquid cytology). Coloring according to the "Papanicolaou test" (Pap test). Interval - 1 time in 4 years. Target group: women aged 30-70 years who are not registered in the dispensary for CC. The expected results are a decrease in incidence and mortality from CC.

Screening steps:

1) Preparatory - formation of target groups, information support and invitation to screening. The preparatory stage is carried out by the nurses of the primary health care organization responsible for preventive measures and includes: annual compilation of a list of women subject to screening in the coming year by November 15 of the current year, followed by monthly correction; informing target groups of the female population about the need for screening; screening invitation; ensure timely screening.

2) Screening - filling out a statistical card of a preventive medical examination (screening) of an outpatient (form 025-08/y), a register of patients subject to cytological screening and taking material for cytological examination from the cervix. The screening examination of the target groups of the female population is carried out by a specially trained midwife of the primary health care organization.

3) The final one is obtaining the results of cytology, informing the woman and developing further management tactics, fill out accounting and reporting statistical documentation. Responsible for the final stage of screening is the obstetrician-gynecologist of primary health care [6].

Cytological screening of CC is a complex of organizational and medical measures aimed at

early detection of precancerous and neoplastic diseases of this localization and at reducing the mortality of this cohort of patients. For traditional cytology, a smear containing 8-12 thousand cells of stratified squamous epithelium (including cells of metaplastic epithelium) is considered adequate; for liquid cytology - 5 thousand cells. For both methods, the number of cells of endocervical epithelium and/or metaplastic epithelium (from the transformation zone) must be at least 10 (single or in clusters). If more than 75% of the cells of the stratified squamous epithelium are covered with erythrocytes, leukocytes, etc., then the quality of the smear is considered unsatisfactory.

Interpretation of the results of a cytological study is carried out according to the Bethesda-terminology cytological system:

Intraepithelial changes and malignant processes are absent (NILM). This group includes cytological conclusions about the normal state of the epithelium, as well as the presence of various non-neoplastic diseases. Normally, squamous epithelial cells, groups of cells of columnar epithelium and metaplastic epithelium, a small number of leukocytes, and rod/mixed microflora are found in preparations. In the presence of non-neoplastic processes, their nature and, if possible, the cause are specified: atrophic changes, reactive changes associated with inflammation, including typical regeneration. In addition, the presence of microorganisms is indicated: *Trichomonas vaginalis*, fungi, morphologically corresponding to *Candida* spp., bacterial vaginosis, cellular changes corresponding to the defeat of Herpes simplex virus, squamous epithelial cells with atypia of unknown significance (ASC-US), squamous epithelial cells with atypia of unclear significance, not excluding the presence of a high degree of intraepithelial changes (ASC-H). Low-grade squamous intraepithelial changes (LSIL) include lesions associated with HPV and CIN I, high-grade squamous intraepithelial changes (HSIL) include CIN II, CIN III, carcinoma in situ and cases suspected of invasion, squamous cell carcinoma, cervical (glandular) epithelium with atypia of unknown significance, cells of the cervical (glandular) epithelium, possibly neoplasia, endocervical adenocarcinoma in situ, endocervical adenocarcinoma, endometrial adenocarcinoma, secondary adenocarcinoma, unclassified carcinoma, other malignant tumors.

There are certain features when taking material for oncocytology: firstly, the examined woman should be informed about the exclusion of sexual intercourse, vaginal manipulations, including douching, baths, tampons, etc. 2 days prior to sampling. Taking material for cytological examination is carried out by the midwife of the examination room of the department of medical examinations of the primary health care organization: the traditional method (2 glasses - with obligatory fixation in 96% alcohol, it is preferable to use glass slides with a polished edge, which are easily marked) or the liquid cytology method (one container with stabilizing liquid); the code or surname of the patient, identical to the code and surname in the form for sending material for cytological examination, should be clearly marked on the glasses or container [6].

At the same time, when using the traditional method, the biomaterial is delivered to the cytological laboratory as soon as possible after its collection in specialized containers for glass slides with 96% alcohol. If there are visible visual changes in the cervix, then the material is taken from the woman and, without waiting for the results, she is referred for an examination by an obstetrician-gynecologist.

A cytological study is carried out in centralized cytological laboratories at oncological institutions, where an archive of cytological preparations of patients involved in the screening examination is formed, regardless of the result, for a period of at least 10 years with the formation of a computer database.

What material and technical equipment is required to take material for a Pap test? It is as follows: soap and water for washing hands, a light source for cervical examination, a gynecological chair, a disinfected speculum and gloves, an Eyre spatula, a glass slide and a marking pen, a container with a stabilizing solution for liquid cytology, a fixative solution (96% alcohol), a

container with warm water for lubricating and warming the vaginal mirrors, a 0.5% chlorine solution for disinfecting gloves and instruments, or another approved for this purpose. And, of course, the registration form itself.

For carrying out liquid cytology, you additionally need: a disposable cervix brush, a container with a stabilizing solution for liquid cytology, and a fixing solution.

At the same time, a smear for oncocytology cannot be taken: during menstruation, earlier than 48 hours after sexual contact or after using lubricants, vinegar or Lugol solution, tampons or spermicides, after vaginal examination or douching, and also during the treatment of genital infection.

Now, regarding the results of CC screening. In 2022, 771,282 women of the target group aged 30 to 70 years were examined during cytological screening (in 2021 - 757,454).

During cytological screening in 2022, 392 cases of cervical cancer were identified (319 in 2021). The detection rate increased from 0.42 to 0.51 per 1000 women examined

High detection of CC during screening is ensured in Aktobe, Almaty, Atyrau, East Kazakhstan, Kyzylorda, Pavlodar, North Kazakhstan, Turkestan regions and Shymkent city. The detection rate in these regions ranges from 0.55 to 1.59 per 1000 women examined. The best indicator is in Atyrau region - 1.59. Compared to 2021, there is an increase in detection in 10 regions, with the exception of Akmola, Aktobe, Zhambyl, Kostanay, Mangistau, North Kazakhstan regions and Shymkent city. The worst result in Astana is 0.15 per 1000 women examined [5].

Cytologically, cervical precancer was detected in 1.16% of those examined (2021 – 0.99%). The detection rate of precancer below 0.6% (the planned indicator for 2022, according to the Comprehensive Plan) was noted in Aktobe, Karaganda and Kostanay regions.

A high proportion of stage I CC (70% or more) was detected in 6 regions of the country (in 8 in 2021): Kostanay, Mangistau (94.7% - best result), North Kazakhstan, Turkestan regions, cities Almaty and Astana. Low levels of early detection of CC (below 50%) were not observed in any region.

Localized processes (stages I-II) were identified in 99.2% of all cases of detected cancer (96.5%). In the Akmola and Karaganda regions, cases of CC were identified not only in localized, but also in widespread stages of the process. A total of 3 cases of CC in stage III and no cases in stage IV were identified (11 and 0, respectively) [5].

BC ranks first in the structure of the frequency of malignant tumors of both sexes in the population with a share of 14.7% (2021 - 15.4%). This situation has been stable since 2004; in addition, BC ranks first and remains consistently in this position in the structure of female oncopathology. The incidence of BC in 2022 in the country as a whole increased to 26.5 per 100 thousand (2021 – 26.3). In the structure of cases, BC occupies the 1st ranking place in the vast majority of regions and cities of the country, except for three: Akmola, Kyzylorda and North Kazakhstan regions, where lung cancer takes the 1st ranking place [4].

Above the national average - 26.5 per 100 thousand of us. – incidence of BC in 10 regions of the country: Abay – 33.3, Akmola – 32.7 (2021 – 29.8), East Kazakhstan – 44.7 (39.9) – the highest level, West Kazakhstan – 31.2 (28.4), Karaganda – 40.2 (40.1), Kostanay – 37.5 (35.8), Pavlodar – 43.2 (47.4), North Kazakhstan – 34.7 (38.2) regions and Almaty city – 35.4 (34.5), Astana city – 31.5 (28.4). Below average indicators per 100 thousand of us. in Aktobe - 21.6 (24.3), Almaty - 21.9 (17.7), Atyrau - 22.8 (15.7), Zhambyl - 14.2 (15.1), Zhetysu - 22.8, Kyzylorda - 14.6 (14.4), Mangistau - 14.7 (17.3), Turkestan - 11.3 (11.7) regions and Shymkent city - 14.9 (21.9) [5].

BC ranks third in the structure of causes of death from malignant tumors in the population of both sexes for the thirteenth year in a row, amounting to 8.1% in 2022 (2021 – 8.7%). In the republic as a whole, mortality from BC decreased by 13.0%, from 6.2 to 5.4 per 100 thousand people.

The regions where mortality from BC is higher than the national average include: Abay -

10.1 per 100 thousand people (maximum level), East Kazakhstan - 8.0 (2021 - 8.5), Pavlodar - 7.1 (10.0), North Kazakhstan - 7.0 (11.4), Kostanay - 6.9 (7.5), Akmola - 6.5 (8.2), West Kazakhstan - 5.7 (6.9), Zhambyl - 5.5 (4.8) and Astana city – 6.3 (6.6), Almaty city – 6.6 (9.5). The indicators are significantly lower in Aktobe - 4.5 (3.5), Almaty - 4.5 (5.8), Zhetysu - 4.0, Atyrau - 3.7 (3.0), Kyzylorda - 4.4 (4.1), Turkestan - 3.6 (3.6), Mangystau regions - 2.7 (3.6) - the lowest level [5].

Mass screening to identify BC patients should mainly involve healthy women without any signs of the disease or symptoms. Screening not only helps to detect hidden forms of cancer that can be treated, but also has psychological value for women. As a result of screening, women are convinced that they do not have BC, and this is the most important potential success of such programs. While the ultimate goal of screening is to reduce BC mortality, its immediate goal is to detect cancer before clinical manifestation. However, BC is a heterogeneous disease, which can significantly affect the effectiveness of screening. Screening models for BC are usually based on the fact that the majority of detected tumors are invasive cancers in the early stage of progression. In addition, it must be taken into account that the detection of cancer (or its precursors) before clinical manifestation increases the risk of false positive diagnosis [7,8].

Mammography has a sensitivity of 95% and a specificity of 97%. These indicators decrease when examining women with denser mammary glands (young age, use of hormone therapy), with low quality mammography, and also with insufficient qualifications of the radiologist. Detection of high-grade invasive cancer by screening, when the tumor is not yet detected by clinical examination (palpation), means the possibility of reducing mortality from BC [9].

Preventive screening for early detection of BC in the Republic of Kazakhstan includes [10]:

1) mammography of both mammary glands in two projections - direct and oblique in the mammography room of the city, district polyclinic (mobile medical complex). All digital mammograms in the presence of a system for archiving and transferring medical images are copied to CDs and other electronic media and transferred to the server of the mammography room of the Cancer Center using specialized licensed software integrated between medical organizations; in case of impossibility of digital transmission - they are printed on X-ray film at a scale of 1:1 - 100% (1 patient - 1 set - 2 or 4 mammograms) with subsequent transfer to the mammography room of the Cancer Center;

2) interpretation of mammograms according to the BI-RADS classification (M0t, M0d, M1, M2, M3, M4, M5) by two or more independent radiologists of the same medical organization - double reading or different medical organizations: a radiologist of the mammography room city, district polyclinic (mobile medical complex) - the first reading, and the radiologist of the mammography room of the Cancer Center - the second reading;

3) in-depth diagnostics - targeted mammography, ultrasound examination (hereinafter - ultrasound) of the mammary glands, trepanobiopsy, including under ultrasound or stereotaxic control for histological examination, which is carried out in case of detection of pathological changes on mammograms (M0d) in the mammography room of the Cancer Center.

√ An average medical worker or a responsible person of the organization of outpatient care sends the patient for mammography to the district, city polyclinic.

√ The X-ray laboratory assistant of the mammography room of the city, district polyclinic (mobile medical complex) performs mammography, fills out a referral for double reading of mammograms and transmits the referral through information interaction.

Radiologist of the mammography office of the city, district polyclinic (mobile medical complex): fulfills the requirements for the safety and quality of mammographic examinations; evaluates the quality of the images provided and the correctness of the installation; performs repeated mammography in the M0t category (technical errors of mammography); determines the radiological density of the mammary glands on the ACR scale (A, B, C, D) indicating this parameter in the study protocol; conducts the first reading of mammograms with interpretation of the BI-

RADS classification results. In the M0d category (undetermined or suspicious radiological changes requiring additional examination), the study protocol indicates the predominant pathology: education, asymmetry, violation of architectonics, microcalcifications; sends mammograms, electronic copies of mammograms through the archiving system and transfer of medical images to the workplace of the mammography office of the Cancer Center together with directions for double reading of mammograms; directs low-dose computed tomographic images through the system of archiving and transferring medical images to the workplace of the computer tomography office of the Cancer Center together with copies of images recorded on CD-ROMs or other electronic media and directions for double reading.

◆ The radiologist of the mammography room of the Cancer Center: evaluates the quality of the provided images and the correctness of the styling. Viewing digital x-ray images transferred to the server or on digital media (CD, DVD) is carried out on a monitor for interpreting digital x-ray images with a resolution of at least 5 megapixels, which has a certified grayscale transmission in accordance with the DICOM standard; conducts a double (second) reading of mammograms with the interpretation of the results according to the BI-RADS classification, using, if necessary, archival images. Organizes the third reading according to indications. With double reading, an independent interpretation of the images is carried out (blinding method - the second radiologist does not know the results of the first reading); in the M0m category (technical errors in mammography), recommends repeat mammography; in the M0d category (uncertain or suspicious radiographic changes requiring additional examination), the study protocol indicates the predominant pathology: education; asymmetry, violation of architectonics, microcalcifications; recommends that the outpatient care organization, according to indications, invite the patient for in-depth diagnostics (targeted mammography, ultrasound of the mammary glands, trephine biopsy, including under ultrasound or stereotaxic control, followed by histological examination of the material); collects and archives all mammograms (films and electronic media) made as part of the examination. The shelf life of mammograms is at least 3 years after leaving the age subject to a screening study; the results of the double (second) reading are transferred to the outpatient care organizations through information exchange.

◆ Indications for in-depth diagnostics are the conclusions of double reading mammograms M0d (uncertain or suspicious X-ray changes requiring additional examination).

◆ In-depth diagnostics is carried out in two stages. At the first stage, ultrasound is performed, according to indications, targeted mammography, possibly with an increase (with asymmetry, violation of architectonics and the presence of microcalcifications). When visualizing a suspicious pathology (M4 and M5), the second stage is performed - trepanbiopsy, including under ultrasound control and stereotaxic control for histological examination.

◆ Histological examination is carried out in the laboratory of pathomorphology or pathological bureau. Morphological interpretation of the biopsy is carried out in accordance with the recommendations of the World Health Organization.

◆ Physician or responsible person of the outpatient care organization:

- 1) upon receipt of a mammography result according to the BI-RADS classification:
 - in case of M0t (technical errors in mammography) - sends the patient for a second X-ray examination to the mammography room of the city, district polyclinic (mobile medical complex);
 - with M0d (undefined or suspicious X-ray changes requiring additional examination) - sends the patient for in-depth diagnostics to the mammography room of the Cancer Center;
 - with M1 (no changes detected) - recommends that the patient undergo a follow-up mammography examination after 2 years. With radiological density of the mammary glands, C and D are sent for ultrasound of the mammary glands to exclude a false-negative result of mammography;
 - with M2 (benign changes), refer the patient for a consultation with an oncologist

(mammologist) of the clinical diagnostic department, followed by a screening mammography examination after 2 years;

- with M3 (probable benign changes) - sends the patient for short-term dynamic radiation observation to the local doctor with the recommendation of control mammography or ultrasound in 6 months;

- with M4 (signs that cause suspicion of malignancy), M5 (practically reliable signs of malignancy) and if it is technically impossible to perform a trepanbiopsy or a biopsy is refused, a referral to an oncologist (mammologist) of the clinical diagnostic department for dynamic observation and decision on the verification of the identified pathology;

2) upon receipt of the result of a histological examination:

- benign education - refers the patient to an oncologist (mammologist) of the clinical diagnostic department for dynamic monitoring, followed by a screening mammography examination after 2 years;

- formation with an indeterminate malignant potential or carcinoma in situ - refers the patient to the Cancer Center for consultation and treatment, followed by dynamic observation by an oncologist (mammologist) of the clinical diagnostic department at the place of her attachment;

- malignant neoplasm - refers the patient to the Cancer Center for treatment and follow-up;

3) communicates the results of the screening examination to the patient in any available way (by telephone, in writing, through electronic means of communication);

4) enters the results of double reading, in-depth diagnostics, histological examination, recommendations of the radiologist of the Cancer Center mammography room into the information system.

Establishing the size of the primary tumor is especially important in screening. Tumor size is an important criterion for evaluating the quality of screening and determining the ability of X-ray mammography to detect non-palpable tumors. Therefore, it is extremely important that pathologists measure tumor diameter as accurately as possible. The smaller the size of the primary tumor, the greater the likelihood of error in determining its size.

Let's analyze the results of BC screening. Mammography screening identified 1,570 cases of BC in 2022 (1,402 in 2021). The cancer detection rate increased from 1.78 to 1.94 per 1000 examined. The best result is in the Karaganda region – 2.63 per 1000 women examined. Low detection rate per 1000 examined, compared to the republican average, in Atyrau (1.72), Zhambyl (0.58), Kyzylorda (1.68), Mangistau (0.42 - worst result), Turkestan (1.22) regions and cities Astana (1.5) and Shymkent (1.58). Compared to 2021, there was an increase in the detection of BC in 9 regions, with the exception of Aktobe (decrease from 2.87 to 2.19 per 1000 women examined), Karaganda (from 2.73 to 2.63), Mangistau (from 1.10 to 0.42), North Kazakhstan (from 3.27 to 2.31), Turkestan (from 1.36 to 1.22) regions and cities Astana (from 1.54 to 1.50), Almaty (from 2.24 to 2.18) and Shymkent (from 2.35 to 1.58) [5].

In 2022, the proportion of patients identified during screening studies with early stages of BC (stage 0-I) was 50.2% during screening (in 2021 - 47.9%). A high proportion of stages 0-I BC (over 50%) was recorded in 8 regions (in 8 in 2021): Akmola, West Kazakhstan, Karaganda (70.8% - best result), Pavlodar, North Kazakhstan, Turkestan regions, cities Astana and Shymkent. Low levels of early detection of BC (below 40%) were noted in Aktobe (19.3% - worst result), Zhambyl (34.8%), Kostanay (39.5%), Mangistau (27.3%) regions and Almaty city (37.3%). Localized cancer (0-I and II stages) amounted to 96.2% (2021 - 95.5%), while not a single case was detected in stages III-IV in Atyrau, West Kazakhstan, Zhambyl, Kyzylorda, Mangistau, Pavlodar regions, cities Astana and Shymkent. A total of 46 cases of breast cancer in stage III and 14 in stage IV were identified (52 and 11, respectively) [5].

Epidemiological indicators of CRC in the form of colon cancer and colorectal cancer are

considered separately for objective reasons.

Colon cancer with a specific gravity of 5.53% (2021 - 5.2%) in the structure of oncopathology of both sexes of the population has risen to 5th place, in men it remains in 6th place - 5.8% (5.5 %), for women - in the 5th - 5.3% (4.91%) The incidence rate of cancer of this localization in the country in the reporting year increased from 8.8 to 9.95 per 100 thousand population.

The incidence of colon cancer in 10 regions is higher than the national average - 9.95 per 100 thousand population: Kostanay - 20.7 (2021 - 15.9), Pavlodar - 18.8 (15.3), North Kazakhstan - 18, 0 (12.7), East Kazakhstan - 16.9 (13.4), Karaganda - 15.4 (15.0), Akmola - 14.6 (10.2), West Kazakhstan - 11.0 (10.1), Abay - 10.0 (9.0) regions and cities Almaty – 12.8 (12.1) and Astana – 10.5 (9.0). As in 2021, colon cancer was detected much less frequently in Turkestan - 3.1 per 100 thousand population (2.7), Kyzylorda - 4.1 (4.6), Zhambyl - 5.5 (5.8), Almaty - 6.3 (4.7), Zhetysu - 6.4, Mangistau - 6.8 (4.9) regions and Shymkent city - 5.0 (4.0) [5].

Rectal cancer in the structure of malignant neoplasms of both sexes retains 7th place in rank with a specific gravity of 4.9% (2021 - 4.92%), but in men it dropped from 4th to 5th place - 6.1%, for women – from 9th to 10th – 4.0%. The incidence rate per 100 thousand population increased from 8.4 to 8.8.

A high incidence rate was recorded in Kostanay - 17.8 per 100 thousand population (2021 - 16.2), East Kazakhstan - 17.7 (13.9), North Kazakhstan - 15.6 (15.1), Pavlodar – 14.9 (18.1), Karaganda – 13.3 (11.7), Abay – 12.9, West Kazakhstan – 12.9 (9.8), Akmola – 10.3 (13.1) regions and Astana city – 10.3 (9.0). Traditionally, a low incidence of rectal cancer is observed in Mangistau - 3.1 (2.8), Turkestan - 3.3 per 100 thousand population (2.7), Zhambyl - 3.7 (5.1), Kyzylorda - 4, 1 (5.3), Almaty – 5.3 (5.6) regions and in Shymkent city – 5.5 (5.0) [5].

Rectal cancer in the structure of causes of death from malignant neoplasms of the population of both sexes in 2022 remained in 5th place with a share of 5.41% (2021 – 5.41%). In the republic as a whole, the mortality rate from this form of cancer was 3.6 per 100 thousand population (3.87).

The mortality rate per 100 thousand population was higher than the national average in East Kazakhstan - 7.8 (2021 - 8.6) - the maximum level, Pavlodar - 7.5 (7.6), Abay - 5.9, North Kazakhstan - 5.8 (4.3), Kostanay - 4.9 (4.9), West Kazakhstan - 4.8 (4.2), Karaganda - 3.8 (5.2) regions. Below the national average - 3.8 per 100 thousand population, mortality in Aktobe - 3.2 (4.1), Almaty - 2.6 (2.6), Atyrau - 2.5 (3.4), Zhetysu - 2, 6, Zhambyl - 3.3 (2.7), Turkestan - 2.1 (1.6), Mangistau - 1.9 (1.2), Kyzylorda regions - 1.8 (2.1) - the lowest figure , and cities Almaty – 3.7 (4.3), Shymkent – 2.6 (2.1).

Colon cancer in the structure of causes of death from malignant neoplasms of the population of both sexes in 2022, as in 2021, ranks 6th, with a share of 5.2% (2021 – 5.0%). At the same time, the mortality rate in the country decreased by 5.6%, from 3.6 to 3.4 per 100 thousand population.

Mortality rates in 10 regions are higher than the national average: East Kazakhstan - 7.1 per 100 thousand population (2021 - 5.1) - maximum level, Pavlodar - 5.6 (6.0), Kostanay - 5.3 (5.6), Akmola – 5.2 (3.8), Abay – 5.1, Karaganda – 5.1 (5.6), West Kazakhstan – 4.8 (4.4), North Kazakhstan – 4.8 (5.0) regions and cities Astana – 3.6 (2.7), Almaty – 4.5 (5.3). Low mortality rates from colon cancer were noted in Kyzylorda - 1.2 per 100 thousand population (2.7) - the best result, Turkestan - 1.3 (1.7), Mangistau - 1.6 (2.6), Aktobe – 2.0 (2.5), Zhetysu – 2.4, Zhambyl – 2.5 (3.7), Atyrau – 2.5 (1.8), Almaty – 2.6 (1.8) regions and cities Astana – (2.7), Shymkent – (2.4).

For colon cancer (94.0%) - 100% verification level was achieved in 3 regions (Abay, Almaty and Turkestan regions), high rates in the Astana city (98.5%), Shymkent city (98.0%), Zhambyl (98.4%), Atyrau (98.2%) regions, low – in Akmola region (86.7%), Almaty city (84.3%), in the Kyzylorda region (61.8%) – the worst result since 2017.

For rectal cancer (97.4%) - in 6 regions there is a 100% verification level, the worst level is still in the Kyzylorda region - 85.3%, lower than the republican average in the Akmola region - 92.6%, Aktoobe region - 96.8%, Mangystau region - 87.0%, Pavlodar region - 95.3%, Almaty city - 93.2% [5].

The frequency of diagnosis of stage I-II rectal cancer, as a visually accessible localization (68.9% - national average) in the regions, was: in Akmola - 34.6% - the worst result, as in 2021, in the country (2021 - 44.1%), Mangystau - 47.8%, Abay - 53.9%, West Kazakhstan - 59.1%, Almaty - 66.2%, Zhetysu - 68.6%, Karaganda - 65.7% regions and Shymkent city - 62.9%.

For colon cancer (52.4%), early diagnosis rates are higher in Pavlodar (65.9% - best result), Abay, Aktoobe, Atyrau, East Kazakhstan, Zhambyl, Zhetysu, Karaganda, Kostanay, Pavlodar, North Kazakhstan, Turkestan regions and Shymkent. The lowest figure (23.5%) is in the Kyzylorda region.

For colon cancer (17.3%), the rates of neglect at stage IV are higher - in Akmola - 31.0% - the worst result (2021 - 20.3%), Zhetysu - 27.3%, Abay - 23.1%, Turkestan - 22.2% (29.1%), Karaganda - 28.1% (28.6%), West Kazakhstan - 18.8% (8.2%), Mangystau - 17.6% (19.4%) regions and cities Astana - 18.0% (22.9%), Shymkent - 20.0% (22.7%). The lowest level of neglect is 2.9% in the Kyzylorda region (7.9%).

The proportion of stage IV in rectal cancer (13.1%) is higher in Akmola - 29.6% - the worst result (2021 - 19.4%), Abay - 19.7%, Kyzylorda - 17.6% (9.1%), Karaganda - 16.9% (28.4%), Almaty - 15.6% (17.0%), Kostanay - 14.8% (11.1%), Zhambyl - 13.3% (13.6%) regions and Shymkent city - 14.5% (12.5%). The lowest level of neglect - 6.0% - is in the Atyrau region (12.5%).

Late diagnosis of rectal cancer as a visually accessible localization (stages III-IV) in 2022 amounted to 31.1% (in 2021 - 33.5%).

For rectal cancer, the level of neglect is higher than the national average - 31.1%, the indicators in Akmola - 65.4% (2021 - 55.9%) - the worst result in the country, Mangystau - 52.2% (38.1%), Abay - 46.1% (30.6%), West Kazakhstan - 40.9% (25.4%), Karaganda - 34.3% (46.5%), Almaty - 33.8% (35.7%), Zhetysu - 31.4% (34.1%) regions and Shymkent city - 37.1% (42.9%). The lowest neglect is in the Atyrau region - 12.0% (17.5%).

In the country as a whole in 2022, the five-year survival rate of patients with CRC registered in 2018 decreased to 40.4% (2021 - 52.9% for those registered in 2017); there is a significant dispersion of indicators by region, from maximum - 56.1% (47.5%) in the Kyzylorda region, to minimum - 24.3% (51.5%) in the Aktoobe region [5].

Screening of CRC screening is the systematic use of screening studies in an asymptomatic population. The purpose of screening is to identify people with abnormalities suggestive of CRC. These persons in the future need additional examination to clarify the diagnosis. Opportunistic screening is the non-systematic use of screening tests in routine medical practice. A screening program is much more challenging than an early detection program. At the same time, the success of the screening program is largely determined by the awareness of the population and medical workers about the possibilities of early diagnosis of CRC. The feasibility of a screening program is determined by several factors that relate to the disease being screened, the screening test, the characteristics of the population, and the characteristics of the healthcare system.

The first factor is that the disease must be well understood, common enough in the target population to justify screening, have a recognizable early stage; treatment of the disease at an early stage should be more effective than at a later stage.

The second is that the test should be characterized by sufficient sensitivity, i.e. the ability to detect cancer among people with the disease; sufficient specificity - the probability that among people who do not have a disease, the test result will be negative; have a high positive predictive value (positive predictive value) or, in other words, the likelihood that people with a positive test result have the disease; have a high predictive value of a negative result (negative predictive value), i.e. the likelihood that people with a negative test result do not have the disease; security;

low cost; and acceptability - the likelihood that people for whom this test is intended will agree to the examination (which to some extent depends on the awareness of the population about the possibilities and importance of early diagnosis).

The third factor is that the healthcare system should be ready for maximum screening test coverage of the target group, have the resources to confirm the diagnosis, appropriate treatment and follow-up of people with positive test results, and regularly conduct screening tests at regular intervals. At the same time, the benefits of screening must outweigh the potential physical and psychological harm and justify the financial costs of its implementation [11].

The factors most significant for the development of CRC are:

- the presence of chronic inflammatory bowel diseases, adenomatous polyps, cancer of other localization, etc.;
- family history (presence of one or two first-degree relatives with CRC or familial diffuse intestinal polyposis);
- the age of men and women over 50 years old, taking into account the fact that more than 90% of patients with colorectal cancer are people of this age (medium risk).

Age, regardless of gender, is an important risk factor for CRC. After the age of 50, the incidence of CRC increases from 8 to 160 per 100,000 population. Thus, people who have reached the age of 50, even in the absence of symptoms, constitute a moderate risk group for CRC.

The second category of increased risk of CRC (20%) is made up of persons with a genetic and family predisposition, suffering from chronic inflammatory bowel diseases, diffuse familial polyposis.

The high-risk CRC group is determined by the so-called Amsterdam criteria (the presence of malignant tumors in two generations, the presence of cancer in a first-line relative under the age of 50 years), in this case, CRC screening should be carried out after the age of 30 years [12].

The degree of individual risk of developing CRC is determined before screening to select the scope of studies and the frequency of their conduct.

The interval for oncological colorectal screening is 1 time in 2 years, target group: men and women aged 50-70 years, with the exception of persons registered at the dispensary for CRC and colon polyposis. At the same time, when forming the target group, one should take into account the absence of severe concomitant diseases, such as the presence of a common malignant neoplasm, cerebrovascular diseases in the stage of decompensation, chronic obstructive pulmonary disease with respiratory failure, cirrhosis of the liver, myocardial infarction with congestive heart failure, diabetes mellitus with vascular complications. and others, which are highly likely to lead to death in the next 10 years.

The first step in screening for CRC is the fecal occult blood test (FOBT). Traditionally, such methods include a benzidine test for occult blood in the feces. This is a biochemical method based on the assessment of pseudoperoxidase activity of hemoglobin. There is ample evidence that invitation to guaiac FOBT screening (gFOBT) reduces CRC mortality by approximately 15% in age-matched average-risk populations.

To ensure the effectiveness of screening with gFOBT, the interval for screening under the national screening program should not exceed two years. To date, there is an immunochemical FOBT method - iFOBT, which is superior in efficiency to gFOBT in terms of the probability of detecting adenoma and cancer. iFOBT has improved analysis performance compared to gFOBT.

Immunochemical (immunochromatographic) examination of feces for occult blood - iFOBT or hemocult test is carried out for all men and women of the target group using an express method, which allows you to get a result within 3-5 minutes, without the participation of a medical worker. However, the evaluation of the test is carried out only by a medical worker in the PHC preventive department.

With a positive analysis of feces for occult blood, the second stage of colorectal screening

is performed, which consists in endoscopic examination of the colon - total colonoscopy [6]. At the same time, in this case, this medical manipulation is of a therapeutic and diagnostic nature, since it allows one-stage removal of adenomatous polyps, which, according to various authors, occur in every third subject after 50 years of age. At the same time, women have 20% fewer polyps than men, but they have more right-sided lesions, which are more difficult to detect using fecal blood tests, because they are less traumatic [13,14].

What results were obtained from screening for CRC? In 2022, 937,859 men and women of the target group aged 50 to 70 years were examined during colorectal screening (in 2021 - 920,640) [5].

Colorectal screening revealed 325 cases of colorectal cancer in the reporting year, which is 114 cases more than in the previous year (211 cases). The detection rate increased from 0.23 to 0.35 per 1000 patients examined. Low detection of colorectal cancer was noted in Zhambyl, Karaganda, Kostanay, Kyzylorda, Mangistau, Turkestan - the worst result, East Kazakhstan regions, Astana city - from 0.07 to 0.30 per 1000 examined. The best result is in the North Kazakhstan region - 0.81 per 1000 examined. Compared to 2021, there was a decrease in the detection of colorectal cancer per 1000 people examined during screening in Karaganda (from 0.22 to 0.21), Kostanay (from 0.29 to 0.28), Mangistau (from 0.20 to 0.12) regions and Astana city (from 0.20 to 0.19).

Colon precancer (adenoma detection rate) was detected in 27.5% of patients who underwent colonoscopy (2021 - 22.8%). The detection rate of precancer in Akmola, Aktobe, Almaty (8.5% is the worst result), West Kazakhstan, Zhambyl, Kostanay, Kyzylorda, Mangistau, Pavlodar, North Kazakhstan, Turkestan regions and cities is lower than the national average Astana and Shymkent. The best result is 36.2% in Almaty city. It should be noted that the planned indicator for the detection of precancer of the colon and rectum in the country for 2022, according to the Comprehensive Plan, was 23.0% and was achieved.

In 2022, the proportion of patients identified during screening studies with early stages of malignant neoplasms (stages 0-I) was 26.2% during colorectal screening (in 2021 - 27.5%).

High early detection of colorectal cancer (above 30%) was noted in Akmola, West Kazakhstan, Karaganda, Kostanay, Kyzylorda, Turkestan regions and Astana city (57.1% - the best result). Not a single case of early cancer has been identified in the Mangistau region. Cases of cancer in stages III-IV detected during screening were registered in Akmola, Aktobe, Almaty, West Kazakhstan, Zhambyl, Karaganda, Kostanay, Mangistau regions and Almaty city. A total of 21 cases of colorectal cancer in stage III and 3 in stage IV were identified (in 2021 - 18 and 5, respectively) [5].

The complex analysis carried out allows us to conclude that satisfactory results of cancer screening can be achieved only with its proper organization, high quality of implementation, active participation in population screening, the use of highly sensitive tests and instrumental methods of preventive examination, as well as subsequent accurate diagnosis of identified tumors and timely treatment. High-quality screening leads to early diagnosis of pedological diseases and malignant pathology in the early stages, which, in turn, increases the effectiveness of treatment and improves the prognosis of the disease. Target groups that, for one reason or another, do not participate in screening should be informed that there are no other methods other than screening that would reduce mortality from malignant neoplasms. Incidence and mortality rates from cervical cancer, breast cancer and colorectal cancer clearly reflect the epidemiological situation with this pathology in the regions of our country.

LITERATURE

- 1 Salehiniya H., Momenimovahed Z., Allahqoli L., Momenimovahed S., Alkatout I. Factors related to cervical cancer screening among Asian women. *Eur Rev Med Pharmacol Sci.* 2021 Oct;25(19):6109-6122. doi: 10.26355/eurev_202110_26889.
- 2 Farkas A.H., Nattinger A.B. Breast Cancer Screening and Prevention. *Ann Intern Med.* 2023 Nov;176(11):ITC161-ITC176. doi: 10.7326/AITC202311210.
- 3 Carter K. A practical approach to selecting a colorectal cancer screening test. *JAAPA.* 2021 Nov 1;34(11):18-23. doi: 10.1097/01.JAA.0000794976.41120.ee.
- 4 Ilbawi A., Varghese Ch., Loring B., Ginsburg O., Corbex M. under the overall direction of Krug E. and Varghese Ch. *Guide to Cancer Early Diagnosis.* World Health Organization, 2017; 48 p.
- 5 Kaidarova D.R., Shatkovskaya O.V., Ongarbayev B.T., Seisenbayeva G.T., Azhmagambetova A.E., Zhylkaidarova A.Zh., Lavrentieva I.K., Sagi M.S. Indicators of the oncology service of the Republic of Kazakhstan, 2022: statistical and analytical materials. – Almaty, 2023. – 430 p.
- 6 <https://onco.kz/wp-content/uploads/2020/03/Rukovodstvo-po-skriningu-RSHM.pdf>
- 7 Abdoell, M., Payne, J.I., Caines, J. et al. Assessing breast cancer risk within the general screening population: developing a breast cancer risk model to identify higher risk women at mammographic screening. *Eur Radiol.* 2020 Oct;30(10):5417-5426. doi: 10.1007/s00330-020-06901-x.
- 8 Idit Melnik, Yael Rapson, Ahuva Gropstein et al. Different approaches to mammography as a screening tool for breast cancer. *Harefuah.* 2022 Feb;161(2):121-124.
- 9 Mann R.M., Athanasiou A., Baltzer P.A.T. et al. Breast cancer screening in women with extremely dense breasts recommendations of the European Society of Breast Imaging (EUSOBI). *Eur Radiol.* 2022 Jun;32(6):4036-4045. doi: 10.1007/s00330-022-08617-6.
- 10 Prikaz i.o. Ministra zdravoohranenija Respubliki Kazahstan ot 30 oktjabrja 2020 goda № ҚР DSM-174/2020 - «Ob utverzhenii celevyh grupp lic, podlezhashhih skringovym issledovaniyam, a takzhe pravil, ob#ema i periodichnosti provedenija dannyh issledovaniy». - Paragraf 6. Porjadok provedenija skringovogo issledovaniya na rannee vyjavlenie raka molochnoj zhelezy (In Russ.).
- 11 Kashin S.V., Nehajkova N.V., Zav'jalov D.V. i dr. Skring kolorektal'nogo raka: obshhaja situacija v mire i rekomendovannye standarty kachestva kolonoskopii. *Dokazatel'naja gastrojenterologija.* 2017;6(4):32-52 (In Russ.).
- 12 Samadder N.J., Smith K.R., Wong J. et al. Cancer risk in families fulfilling the Amsterdam Criteria for Lynch syndrome. *JAMA Oncol.* 2017 Dec 1;3(12):1697-1701. doi: 10.1001/jamaoncol.2017.0769.
- 13 <https://onco.kz/skrining-na-ranee-vyyavlenie-kolorektalnogo-raka/>
- 14 Hultcrantz R. Aspects of colorectal cancer screening, methods, age and gender. *J Intern Med.* 2021 Apr;289(4):493-507. doi: 10.1111/joim.13171.

Psychological Sciences

УДК 159.9

ПСИХОЛОГИЧЕСКИЕ ОСОБЕННОСТИ И СОЦИАЛЬНО-ПСИХОЛОГИЧЕСКАЯ АДАПТАЦИЯ ЛИЦ, СКЛОННЫХ К ЭЗОТЕРИЧЕСКИМ ПРАКТИКАМ

Соколов Иван Андреевич

магистрант, Университет «Туран», г. Алматы, Казахстан

Научный руководитель:

Дуплякин Евгений Борисович

кандидат медицинских наук, профессор Университет «Туран», г. Алматы, Казахстан

Аннотация: В данной статье представлены процедура и результаты эмпирического исследования социально-психологической адаптации, магического мышления, личностных факторов, акцентуированных черт личности у лиц, склонных к эзотерическим практикам. Эмпирическое исследование включает в себя сравнительный анализ и корреляционный анализ показателей исследуемых переменных.

Ключевые слова: социально-психологическая адаптация, магическое мышление, нейротизм, дистимность, тревожность, циклотимность, гипертимность, личностные факторы, акцентуации личности.

Введение. Актуальность исследования психологических особенностей лиц, склонных к эзотерическим практикам, обусловлена возросшим за последние годы интересом населения к изучению и применению различного рода оккультных и эзотерических концепций.

Примечательно, что данная тенденция наблюдается на фоне стремительного научно-технического прогресса, всеобщего образования и наличия открытого доступа к ресурсам, содержащим научно-обоснованную информацию об окружающем мире, что указывает на независимость роста интереса к эзотерике от данных переменных.

Иным объяснением растущей популярности эзотерических услуг является нарастающая неопределенность, вызванная особенностями протекания социальных и экономических процессов в мире. В этой связи личность имеет усиленную потребность в поиске смысла происходящих событий и в обретении субъективного ощущения определенности и контроля.

Обращение к эзотерическим практикам, имеющее в своей основе магическое мышление, служит в таком случае попыткой совладания с дестабилизирующими аспектами действительности, поскольку магический стиль мышления описывается авторами в качестве своеобразного защитного механизма, используемого индивидом в условиях стресса [1, с. 9].

Однако связь магического мышления с социально-психологической адаптацией исследована недостаточно. Следовательно, невозможно однозначно утверждать об адаптивности или же дезадаптивности подобной формы копинга. В связи с этим интерес

представляет изучение психологических особенностей лиц, склонных к эзотерическим практикам, и их связи с социально-психологической адаптацией.

В Большой энциклопедии по психиатрии магическое мышление описывается как убежденность индивида в возможности оказывать влияние на объективную действительность посредством символических действий или мыслительных операций. Также данная когнитивно-перцептивная особенность проявляется в качестве склонности индивида к поиску каузальных связей между событиями и явлениями окружающей действительности, не имеющими объективных причинно-следственных связей [2, с. 465].

Lindeman M. выделяет четыре родственные формы иррационального способа восприятия и осмысления действительности индивидом, которые включают в себя веру в паранормальное, веру в сверхъестественное, веру в магию и веру в суеверия. Вера в паранормальное заключается в убежденности в существовании явлений, не имеющих научно-обоснованного объяснения. Вера в сверхъестественное проявляется в качестве убежденности индивида в существовании духов, сверхъестественных сил, сущностей и т.д. Вера в магию определяется как вера в способность человека влиять на события или других людей посредством ритуализированных действий, слов, желаний, субъективных переживаний, символов. Суеверия проявляются в качестве тенденции индивида к идентификации причинно-следственных связей между событиями, не имеющими объективной каузальной связи [3, с. 274].

Lindeman M. объединяет данные формы иррационального осмысления реальности в общую категорию магического мышления ввиду общего механизма, лежащего в основе данных паттернов. Механизм магического мышления заключается в онтологическом смешении, т.е. ошибочном приписывании физическим, биологическим и психологическим явлениям атрибутов, не свойственных данным явлениям изначально [4, с. 739].

В руководстве по психиатрии Ю.А. Александровского и Н.Г. Незнанова магическое мышление описывается как проявление магифренического синдрома. Магифренический синдром характеризуется преобладанием в сознании индивида идей мистического содержания, влияющих на эффективность функционирования личности и на успешность ее взаимодействия с окружающей средой. Также важным критерием является нетипичность данных магических идей для родной культуры индивида, т.е. традиционные религиозные верования не являются проявлением магифренического синдрома. Магифренический синдром описывается авторами как форма расстройства адаптации индивида к внешней среде [5, с. 147].

А.А. Налчаджян описывает социально-психологическую адаптацию как динамический процесс, включающий в себя приспособление личности к требованиям социума в совокупности со следованием личностью собственным устремлениям и ценностям, т.е. состояние социально-психологической адаптированности представляет собой баланс между соответствием личности нормам социальной среды и самореализацией. Социально-психологическая адаптированность личности проявляется в эффективном взаимодействии личности со средой при отсутствии внешних и внутренних конфликтов [6, с. 26].

Эффективность протекания процесса социально-психологической адаптации связана с личностными особенностями индивида, включающими личностные факторы, описываемые Пятифакторной моделью личности. Среди них выделены экстраверсия–интроверсия, доброжелательность–антагонизм, добросовестность–спонтанность, открытость–закрытость к новому опыту, нейротизм–уравновешенность [7, с. 176].

Также успешность процесса социально-психологической адаптации связана с выраженностью акцентуированных черт личности. Типы акцентуаций личности были классифицированы К. Леонгардом и включают в себя гипертимный, дистимный,

циклотимный, возбудимый, застревающий, эмотивный, экзальтированный, педантичный, тревожный и демонстративный типы [8, с. 58].

На основании описанных теоретических положений нами были выдвинуты общая и частная гипотезы. Общая гипотеза включает в себя предположение о наличии связи психологических особенностей лиц, склонных к эзотерическим практикам, с социально-психологической дезадаптацией. Частная гипотеза включает в себя предположение о наличии связи между магическим мышлением и социально-психологической дезадаптацией у лиц, склонных к эзотерическим практикам.

Организация и методы исследования. Целью эмпирического исследования выступает изучение выраженности психологических особенностей лиц, склонных к эзотерическим практикам, и установление их взаимосвязи с социально-психологической адаптацией или дезадаптацией. Среди психологических особенностей в ходе исследования изучались магическое мышление, личностные факторы и акцентуированные черты личности.

Выборка исследования разделена на две группы по критерию идентификации испытуемыми себя как лиц, практикующих эзотеризм, или лиц, не практикующих эзотеризм. Группа, состоящая из лиц, практикующих эзотеризм, включает в себя 35 респондентов. В группу не практикующих эзотеризм вошло 32 респондента. Минимальный возраст в общей выборке составил 22 года. Максимальный возраст испытуемых составил 59 лет. Общая выборка включает в себя 18 респондентов мужского пола и 49 респондентов женского пола.

Сбор данных осуществлялся посредством опроса в формате онлайн в мессенджерах. Группа, включающая лиц, практикующих эзотеризм, формировалась на базе онлайн-сообществ, посвященных эзотерической и оккультной тематике. Группа, включающая лиц, не практикующих эзотеризм, формировалась на базе онлайн-сообществ, не связанных с эзотерической тематикой. Участие в исследовании носило анонимный и добровольный характер. Участники были проинформированы о целях исследования и о дальнейшем использовании полученных данных в обобщенном виде.

В целях исследования социально-психологической адаптации в группах респондентов использовалась психодиагностическая методика Тест социально-психологической адаптации (СПА) в адаптации А.К. Осницкого. Данная методика включает 6 интегративных шкал, соответствующих социально-психологической адаптации и ее компонентам [9, с. 36].

В целях исследования магического мышления в группах респондентов использовалась психодиагностическая методика Шкала магической идеации (Magical Ideation Scale, MIS) в адаптации Э.Э. Байрамовой и С.Н. Ениколопова. Данная методика включает в себя одну шкалу магического мышления [10, с. 44].

В целях исследования личностных факторов в группах респондентов использовалась психодиагностическая методика Пятифакторный опросник личности 5PFQ в адаптации А. Б. Хромова. Данный опросник включает в себя пять шкал, соответствующих пяти личностным факторам, описанным пятифакторной моделью личности, т.е. экстраверсии, нейротизму, добросовестности, доброжелательности, открытости новому опыту [11, с. 16].

В целях исследования акцентуированных черт личности в группах респондентов использовалась психодиагностическая методика Тест Леонгарда-Шмишека в адаптации В.М. Блейхера. Данная методика включает в себя 10 шкал, соответствующих 10 типам акцентуации личности, выделенных Карлом Леонгардом [12, с. 107].

Математико-статистическая обработка полученных в ходе онлайн-опроса данных производилась посредством программных продуктов Microsoft Excel и IBM SPSS Statistics.

На первом этапе статистической обработки был произведен анализ описательных статистик, включающий вычисление средних значений исследуемых показателей, а также стандартных отклонений. Для проверки нормальности распределения переменных был использован критерий Шапиро-Уилка. В связи с наличием отклонений распределения

исследуемых переменных от нормального нами были использованы непараметрические методы статистического анализа данных.

С целью выявления статистически значимых различий между группами респондентов по показателям исследуемых переменных нами был использован критерий Манна-Уитни. Для анализа взаимосвязей между исследуемыми переменными в группах респондентов нами был использован коэффициент ранговой корреляции Спирмена.

Результаты исследования. Далее представлены эмпирические данные, полученные в ходе сравнительного анализа основной группы, включающей лиц, склонных к эзотерическим практикам, и контрольной группы, включающей лиц, не склонных к эзотерическим практикам, по выраженности исследуемых показателей, включающих социально-психологическую адаптацию (СПА), магическое мышление, личностные факторы и типы акцентуированных черт личности (табл. 1).

Таблица 1

Результаты сравнительного анализа основной и контрольной групп по выраженности исследуемых показателей

Показатель	Основная группа		Контрольная группа		p
	M	SD	M	SD	
СПА	59,00	18,06	70,93	13,73	0,002
Магическое мышление	13,60	6,27	5,19	5,27	<0,001
Экстраверсия	42,46	13,02	46,09	7,75	0,300
Доброжелательность	51,80	11,10	53,91	10,97	0,466
Добросовестность	52,40	13,12	53,09	13,74	0,787
Нейротизм	53,17	13,65	42,12	12,87	<0,001
Открытость опыту	53,68	9,75	52,34	9,02	0,683
Гипертимность	9,34	8,09	13,69	5,99	0,017
Дистимность	13,11	6,47	9,19	4,44	0,009
Циклотимность	12,69	6,00	9,84	4,05	0,031
Возбудимость	8,66	5,99	6,94	6,30	0,186
Застывание	13,71	3,67	12,06	5,34	0,073
Эмотивность	13,63	6,19	12,84	5,56	0,438
Экзальтированность	11,14	6,53	8,63	6,63	0,126
Тревожность	12,51	7,07	6,75	5,33	<0,001
Педантичность	12,17	5,64	9,75	4,62	0,087
Демонстративность	11,60	4,49	11,94	3,35	0,516

Результаты сравнительного анализа свидетельствуют о наличии статистических значимых различий между основной и контрольной группами по уровню социально-психологической адаптации ($p < 0,05$). Таким образом, лица, склонные к эзотерическим практикам, в большей мере сталкиваются с затруднениями в процессе приспособления к требованиям социальной среды, чем лица, не склонные к эзотерическим практикам.

В ходе сравнительного анализа нами также были установлены статистически значимые различия между исследуемыми группами по выраженности показателя магического мышления ($p < 0,05$). Следовательно, лица, склонные к эзотерическим практикам, в большей мере проявляют склонность к убежденности в способность символических психологических или физических операций непосредственно оказывать

влияние на объективную действительность, чем лица, не склонные к эзотерическим практикам.

Сравнительный анализ показал наличие статистически значимых различий между основной и контрольной группами респондентов по выраженности нейротизма ($p < 0,05$). Иными словами, лица, склонные к эзотерическим практикам, обладают более выраженной эмоциональной неустойчивостью и чувствительностью к воспринимаемому стрессу по сравнению с лицами, не склонными к эзотерическим практикам.

Также в ходе сравнительного анализа нами были установлены статистически значимые различия между исследуемыми группами по выраженности личностной черты гипертимности ($p < 0,05$), что указывает на меньшую склонность респондентов, входящих в основную группу, к проявлениям повышенного фона настроения, повышенной общей активности, общительности, выраженного стремления к деятельности и поверхностности интересов по сравнению с респондентами, входящими в контрольную группу.

Результаты сравнительного анализа свидетельствуют о наличии статистически значимых различий между основной и контрольной группами респондентов по показателям дистимности ($p < 0,05$). Таким образом, лица, склонные к эзотерическим практикам, в большей мере проявляют пониженный фон настроения, пониженную общую активность, склонность к уединению, повышенную чувствительность к неудачам, серьезность и медлительность в поведении, чем лица, не склонные к эзотерическим практикам.

Проведенный сравнительный анализ показал наличие статистически значимых различий между основной и контрольной группами по выраженности показателей циклотимности ($p < 0,05$). Полученные результаты свидетельствуют о большей склонности респондентов, входящих в основную группу, к последовательному регулярному чередованию фаз, характеризующихся повышенным фоном настроения и повышенной общей активностью, фазами пониженного фона настроения и пониженной общей активности в сравнении с респондентами, входящими в контрольную группу.

В ходе сравнительного анализа было установлено существование статистически значимых различий между основной и контрольной группами респондентов по выраженности показателей тревожности ($p < 0,05$). Иными словами, лица, склонные к эзотерическим практикам, в большей мере проявляют повышенную чувствительность при идентификации угроз, повышенную осторожность, застенчивость, избегающее поведение, склонность к сомнениям и трудностям в принятии решений в сравнении с лицами, не склонными к эзотерическим практикам.

В ходе эмпирического исследования нами также был осуществлен корреляционный анализ связи показателей социально-психологической адаптации с показателями магического мышления, личностных факторов и акцентуированных черт личности у лиц, склонных к эзотерическим практикам.

Далее представлена плеяда корреляционных связей социально-психологической адаптации (СПА) с магическим мышлением и личностными факторами у лиц, склонных к эзотерическим практикам. В плеяду включены только статистически-значимые корреляционные связи (рис. 1).




Рис. 1. Пляда корреляционных связей социально-психологической адаптации с магическим мышлением и личностными факторами в основной группе

В ходе корреляционного анализа была установлена статистически значимая связь умеренной силы и обратной направленности между показателями социально-психологической адаптации и показателями магического мышления в основной группе ($p < 0,05$). Следовательно, более сильная выраженность веры в непосредственное влияние мыслей, желаний, символических действий на объективную действительность сопровождается более слабой выраженностью приспособленности к требованиям социальной среды у лиц, склонных к эзотерическим практикам.

Также была выявлена статистически значимая связь выраженной силы и обратной направленности между социально-психологической адаптацией и нейротизмом в основной группе ($p < 0,01$). Иными словами, чем сильнее у лиц, склонных к эзотерическим практикам, выражена эмоциональная неустойчивость, тем ниже уровень социально-психологической адаптации в данной группе.

Была установлена статистически значимая связь умеренной силы и прямой направленности между добросовестностью и социально-психологической адаптацией в основной группе ($p < 0,01$). Таким образом, чем сильнее у лиц, склонных к эзотерическим практикам, проявлены ответственность, организованность и целеустремленность, тем в большей степени они приспособлены к требованиям социальной среды.

Экстраверсия имеет статистически значимую связь выраженной силы и прямой направленности с показателями социально-психологической адаптации в основной группе ($p < 0,01$). Следовательно, более слабая выраженность стремления к межличностному взаимодействию, социальной активности и коммуникации у лиц, склонных к эзотерическим практикам, сопровождается меньшей выраженностью социально-психологической адаптации в данной группе.

Далее представлена пляда корреляционных связей социально-психологической адаптации (СПА) с акцентуированными чертами личности у лиц, склонных к эзотерическим практикам. В пляду включены только корреляционные связи, имеющие статистическую значимость (рис. 2).




Рис. 2. Плеяда корреляционных связей социально-психологической адаптации с акцентуированными чертами личности

Полученные результаты корреляционного анализа свидетельствуют о наличии статистически значимой прямой связи выраженной силы между показателями социально-психологической адаптации и гипертимности в основной группе ($p < 0,01$). Иными словами, чем ниже степень выраженности гипертимности у лиц, склонных к эзотерическим практикам, тем ниже степень социально-психологической адаптации в данной группе.

Дистимность имеет статистически значимую обратную связь умеренной силы с показателями социально-психологической адаптации в основной группе респондентов ($p < 0,01$). Таким образом, пониженный фон настроения, пониженная общая активность и замкнутость у лиц, склонных к эзотерическим практикам, сопряжены с менее выраженной приспособленностью к условиям социальной среды.

Нами была установлена статистически значимая обратная связь умеренной силы между показателями циклотимности и социально-психологической адаптации в основной группе ($p = 0,01$), что указывает на сопряженность более выраженной тенденции к циклическим сменам фаз повышенного и пониженного настроения с низким уровнем социально-психологической адаптации.

Корреляционный анализ показал наличие статистически значимой прямой связи умеренной силы между показателями застревания и социально-психологической адаптации в основной группе ($p < 0,01$). Таким образом, высокая выраженность стойкости аффекта, честолубия, упрямства и целеустремленности лиц, склонных к эзотерическим практикам, сопровождается выраженной адаптированностью к условиям социальной среды.

Показатели эмотивности имеют статистически значимую обратную связь слабой выраженности с показателями социально-психологической адаптации в основной группе ($p < 0,05$). Иными словами, повышенная эмоциональная реактивность у лиц, склонных к эзотерическим практикам, сопряжена с низкой степенью адаптированности к условиям социальной среды.

Корреляционный анализ показал наличие статистически значимой связи сильной выраженности и обратной направленности между показателями тревожности и показателями социально-психологической адаптации в основной группе ($p < 0,01$). Таким образом, повышенная чувствительность при идентификации угроз у лиц, склонных к эзотерическим практикам, сопровождается пониженной социально-психологической адаптацией.

Обсуждение результатов. Большая выраженность магического мышления у лиц, склонных к эзотерическим практикам, может объясняться спецификой выборки, поскольку вовлеченность в эзотеризм и его практика могут требовать регулярного использования

магического стиля мышления, закрепляя таким образом паттерн осмысления действительности через призму идей магического содержания.

Акцентуированные черты личности, наблюдающиеся в большей степени у лиц, склонных к эзотерическим практикам, чем у лиц, не склонных к эзотерическим практикам, включают в себя дистимный, циклотимный и тревожный типы. Гипертимный тип также имеет специфику выраженности в группах и проявлен в меньшей степени у лиц, склонных к эзотерическим практикам.

Исходя из вышеописанных наблюдений, можно предположить, что специфика выраженности акцентуаций у лиц, склонных к эзотерическим практикам, может указывать на предрасположенность к частому переживанию дезадаптивных эмоциональных состояний, поскольку проявления всех акцентуированных личностных черт, показавших значимые различия, затрагивают функционирование эмоциональной сферы личности.

Данный вывод также согласуется с большей выраженностью нейротизма, установленной у лиц, склонных к эзотерическим практикам, поскольку более высокий уровень нейротизма свидетельствует о большей эмоциональной неустойчивости и о большей склонности индивида к проявлению чрезмерных эмоциональных реакций на раздражитель, не соответствующих силе и характеру раздражителя.

Меньшая выраженность социально-психологической адаптации или большая выраженность социально-психологической дезадаптации у лиц, склонных к эзотерическим практикам, может объясняться спецификой роли личностных и когнитивно-перцептивных особенностей, присущих данной группе, в адаптационном процессе.

Обратная направленность связи социально-психологической адаптации с дистимностью, циклотимностью и тревожностью у лиц, склонных к эзотерическим практикам, может указывать на дезадаптивную роль данных типов акцентуированных личностных черт в процессе социально-психологической адаптации личности, поскольку пониженный фон настроения, циклические смены фаз настроения вне зависимости от событий и частые переживания тревоги повышенной интенсивности могут деструктивным образом воздействовать на общее функционирование личности и на функционирование личности в условиях социальной среды.

Обратная направленность связи социально-психологической адаптации с нейротизмом у лиц, склонных к эзотерическим практикам, может указывать на дезадаптивную роль нейротизма в процессе социально-психологической адаптации, поскольку эмоциональная неустойчивость и частые переживания эмоциональных состояний повышенной интенсивности могут приводить к повышенной психической истощаемости в стрессогенных условиях, что может способствовать снижению адаптационного ресурса личности.

Обратная направленность связи социально-психологической адаптации с магическим мышлением у лиц, склонных к эзотерическим практикам, может указывать на дезадаптивную роль магического мышления в процессе социально-психологической адаптации, поскольку вера в возможность оказывать воздействие на объективную действительность посредством символических психических и физических операций и тенденция к поиску несуществующих каузальных связей между событиями и явлениями окружающей среды, могут снижать способность индивида к тестированию реальности.

Затрудненное тестирование реальности может выражаться искаженным восприятием действительности и, как следствие, эмоциональными и поведенческими реакциями, несоответствующими обстоятельствам, что может оказывать деструктивное воздействие на процесс взаимодействия личности с социумом.

Иным объяснением обратной связи магического мышления с социально-психологической адаптацией в основной группе может выступать использование

магического стиля мышления лицами, склонными к эзотерическим практикам, в качестве своеобразной защитной стратегии или копинга с целью временного снижения эмоционального дискомфорта в условиях социально-психологической дезадаптации.

Заключение. Таким образом, в ходе эмпирического исследования нами были проведены сравнительный анализ и корреляционный анализ данных, полученных в ходе опроса лиц, склонных к эзотерическим практикам, и лиц, не склонных к эзотерическим практикам, в целях уточнения психологических особенностей и системы связей между ними в исследуемой выборке.

Сравнительный анализ показал наличие статистически значимых различий между основной и контрольной группами по показателям социально-психологической адаптации, магического мышления, нейротизма, гипертимности, дистимности, циклотимности и тревожности.

Корреляционный анализ показал наличие связей прямой направленности социально-психологической адаптации с показателями добросовестности, экстраверсии, гипертимности и застревания у лиц, склонных к эзотерическим практикам. Также нами были установлены связи обратной направленности социально-психологической адаптации с магическим мышлением, нейротизмом, дистимностью, циклотимностью, эмотивностью и тревожностью у лиц, склонных к эзотерическим практикам.

Общая гипотеза о связи психологических особенностей лиц, склонных к эзотерическим практикам, с социально-психологической дезадаптацией получила частичное подтверждение, поскольку в ходе эмпирического исследования не были исследованы связи всех возможных существующих психологических особенностей с социально-психологической адаптацией и также не все исследуемые психологические особенности показали наличие обратной связи с показателями социально-психологической адаптации у лиц, склонных к эзотерическим практикам.

Частная гипотеза о связи магического мышления с социально-психологической дезадаптацией у лиц, склонных к эзотерическим практикам, в ходе эмпирического исследования получила подтверждение.

Полученные результаты могут быть использованы в дальнейших исследованиях психологических особенностей лиц, склонных к эзотерическим практикам, магического мышления, социально-психологической адаптации и дезадаптации, личностных факторов и акцентуированных черт личности. Также результаты исследования могут быть использованы в психологической практике при работе с лицами, склонными к эзотерическим практикам.

Список источников

1. Байрамова Э. Э., Ениколопов С. Н. Магическое мышление и вера в магию в структуре психологических защит и копинг-стратегий // Психология. Психофизиология. – 2021. – Т. 14, № 4. – С. 5–13.
2. Жмуров В. А. Магическое мышление // Большая энциклопедия по психиатрии. – 2-е изд. – М. : Джангар, 2012. – 864 с.
3. Lindeman, M., Svedholm, A. M. What's in a term? Paranormal, superstitious, magical and supernatural beliefs by any other name would mean the same / M. Lindeman, A. M. Svedholm // Review of General Psychology. – 2012. – Vol. 16, № 3. – P. 241–255.
4. Lindeman, M., Aarnio, K. Superstitious, magical, and paranormal beliefs: An integrative model / M. Lindeman, K. Aarnio // Journal of Research in Personality. – 2007. – Vol. 41, № 4. – P. 731–744.
5. Психиатрия: национальное руководство / под ред. Ю. А. Александровского, Н. Г. Незнанова. – 2-е изд., перераб. и доп. – М. : ГЭОТАР-Медиа, 2022. – 1008 с.
6. Налчаджян А. А. Психологическая адаптация: механизмы и стратегии. – 2-е изд., перераб. и доп. – М. : Эксмо, 2010. – 368 с.
7. McCrae R. R., John O. P. An introduction to the five-factor model and its applications // Journal of Personality. – 1992. – Vol. 60, № 2. – P. 175–215.
8. Леонгард К. Акцентуированные личности. – М. : Эксмо-Пресс, 2001. – 446 с.
9. Осницкий А. К. Психология самостоятельности. Методы исследования и диагностики. – М. : Эль-Фа, 1996. – 124 с.
10. Байрамова Э. Э., Ениколопов С. Н. Адаптация методики определения уровня магического мышления М. Экблада и Л. Дж. Чапмана на русскоязычной выборке // Психиатрия. – 2016. – № 70. – С. 40–46.
11. Хромов А. Б. Пятифакторный опросник личности: учебно-методическое пособие. – Курган : КГУ, 2000. – 23 с.
12. Блейхер В. М., Крук И. В. Патопсихологическая диагностика. – Киев: Здоров'я, 1986. – 280 с.

УДК 159.9:616.5

Клинико-психологические особенности лиц с аллергическими заболеваниями

Кусаинова Светлана Олеговна

Магистрант, Клиническая Психология, Университет «Туран», г.Алматы, Казахстан.

Дуплякин Евгений Борисович

Научный руководитель, кандидат медицинских наук, профессор Высшей школы психологии Университета «Туран», академик МАИН, г. Алматы, Казахстан.

Аннотация:

В статье описан проведенный анализ результатов эмпирического исследования на выборке лиц с аллергическими заболеваниями и контрольной группы (N=100). Подтвержден специфический клинико-психологический профиль, концептуально расширенный за счет включения психологических границ личности и параметров привязанности. Особо следует отметить, что выявлена интегрированная система показателей, образующая контур психосоматической уязвимости и отражающая высокую степень взаимной обусловленности эмоциональных и личностных характеристик. Установлено, что у лиц с аллергическими заболеваниями избегание близости как параметр привязанности выступает ключевым предиктором, определяющим структуру данной системы.

Ключевые слова:

Аллергия, аллергические заболевания, психосоматика, эмоциональная уязвимость, тип привязанности, избегание близости, психологические границы личности, эмоциональная регуляция, самооценка, тревожность, депрессивные проявления, контур психосоматической уязвимости

" Clinical and Psychological Features of Patients with Allergic Diseases"

Svetlana Kussainova

master's Student, Clinical Psychology

Yevgeniy Duplyakin

Scientific Advisor, Candidate of Medical Sciences (PhD),

Professor at the Higher School of Psychology,

Academician of the International Academy of Sciences (MAIN)

Abstract

The article presents an analysis of the results of an empirical study conducted on a sample of individuals with allergic diseases and a control group (N = 100). A specific clinical and psychological profile was confirmed and conceptually expanded by incorporating psychological boundaries and attachment-related characteristics. Of particular note, an integrated system of indicators was identified, forming a psychosomatic vulnerability pattern and reflecting a high degree of interdependence among emotional and personality characteristics. It was established that, in patients with allergic diseases, attachment avoidance, as an attachment-related characteristic, functions as a key predictor determining the structure of this system.

Keywords

Allergy, allergic diseases, psychosomatics, emotional vulnerability, attachment-related characteristics, attachment avoidance, psychological boundaries, emotion regulation, self-esteem, anxiety, depressive symptoms, psychosomatic vulnerability system.

Неуклонный рост количества людей, страдающих аллергическими заболеваниями, несмотря на активное развитие фармакотерапии, требует выхода за рамки биомедицинской модели. По зарегистрированным данным [1-3] в среднем около 40% населения России, Казахстана и других стран подвержены аллергическим патологиям. Учитывая, что все больше исследований эмпирически доказывают эффективность психологических методов коррекции и психотерапевтических вмешательств [4,5], следует рассматривать аллергические заболевания как многофакторный феномен, в структуре которого существенную роль играют психологические механизмы.

Психосоматическая концепция аллергических заболеваний зародилась в 1886 году М. Маккензи [6] фиксацией аллергических реакций без присутствия реального аллергена. В начале 20-го века А. М. Безредка [7] экспериментально подтвердил возможность предупредить возникновение аллергической реакции, при функциональном подавлении активности центральной нервной системы. Далее исследование взаимосвязи психики и телесных форм выражения аффективного напряжения получило активное развитие в научных трудах Ф. Александера, Ф. Данбар, М. Шура, Г. Селье [8-10] и в настоящее время концепция психосоматики, где аллергия трактуется как форма ресоматизации — возвращения неразрешенного конфликта в телесную плоскость вошла в содержание профильных учебников В. Д. Менделевич и С. Л. Соловьёва [11].

Наряду с активизацией аллергической патологии возрастает и количество эмпирических исследований лиц с данным заболеванием [12-15], а также факторов, провоцирующих и поддерживающих/усугубляющих аллергическую симптоматику [16-17]. При этом мало акцентов направлено на подготовительные, преморбидные факторы, которые формируют основания аллергической уязвимости в психосоматическом контексте, а также структура взаимосвязей показателей и их системная организация в рамках единого клинико-психологического профиля пациентов с аллергическими заболеваниями остается недостаточно изученной.

Исходя из теории привязанности Дж. Боулби и М. Эйнсворт [18], культурно-исторического подхода Л. С. Выготского [19] и деятельностного подхода А. Н. Леонтьева [20] - ключевым этапом становления базовых структур психики выступает раннее детство. Опыт взаимодействия со значимыми взрослыми определяет формирование устойчивых стратегий реагирования на стресс, особенности переживания близости и способы построения межличностных отношений и, следовательно, на его основе формируются психологические границы личности. Которые в свою очередь, в рамках концепции Э. Хартманн [21], рассматриваются как механизм, определяющий степень дифференциации внутреннего и внешнего опыта, взаимодействия с окружающей средой и особенности переработки информации.

В связи с вышеизложенным была выдвинута гипотеза и проведено эмпирическое исследование, направленное на выявление взаимосвязи клинико-психологических показателей, включающих параметры привязанности, уровень тревожности, депрессивных проявлений, самооценку и особенности психологических границ личности, а также на установление роли типа привязанности как предиктора эмоциональной уязвимости у лиц с аллергическими заболеваниями.

В исследовании приняли участие 100 человек в возрасте от 17 до 65 лет. Основную группу составили 50 человек с аллергическими заболеваниями, контрольную — 50 человек без аллергической патологии.

- Для изучения типа привязанности использовался опросник Experiences in Close Relationships-Revised (K. Brennan, R. Fraley; адаптация Т. В. Казанцевой) [22], позволяющий оценить параметры тревожности и избегания в межличностных отношениях.
- Уровень тревожности и депрессивных проявлений диагностировался с помощью Hospital Anxiety and Depression Scale – HADS (A. S. Zigmond, R. P. Snaith; адаптация М. Ю. Дробижева) [23].
- Самооценка оценивалась с использованием шкалы самоотношения Розенберга (M. Rosenberg; адаптация А. А. Золотарёвой) [24].
- Особенности психологических границ личности исследовались с помощью опросника Boundary Questionnaire-18 (E. Hartmann; адаптация О. А. Шамшиковой, В. И. Волоховой) [25]. Статистическая обработка данных проводилась с использованием непараметрических методов.

Статистическая обработка данных проводилась с использованием пакета прикладных программ математической статистики IBM SPSS Statistics.

С целью выявления межгрупповых различий по исследуемым клиничко-психологическим показателям между основной и контрольной группами проведён анализ межгрупповых различий с использованием непараметрического критерия Манна–Уитни. Для наглядного представления направленности выявленных различий в таблице 1 приведены описательные статистики (средние значения показателей) по каждой из групп.

Таблица -1 Средние значения психологических показателей в контрольной и основной группах (по результатам анализа Манна–Уитни)

Показатель	Контрол. Группа, М	Основн. группа, М	U	p
Тревожность (HADS-A)	5,02	7,56	715,5	<0,001***
Депрессия (HADS-D)	3,5	4,8	909,5	0,018*
Самооценка (RSES)	32,4	30,36	1034	0,015*
Тревожность привязанности (ECR-R, Anxiety)	4,32	4,46	1217	0,829
Избегание близости (ECR-R, Avoidance)	4,22	4,92	1127,5	0,383
Психологические границы (BQ-18, sten)	8,46	9,16	914	0,011*

*примечание: *p<0.05; **p<0.01; ***p<0.001.*

В основной группе зафиксированы более высокие значения тревожности (7,56 vs 5,02), депрессии (4,8 vs 3,5) и психологических границ (9,16 vs 8,46), а также более низкий уровень самооценки (30,36 vs 32,4) при отсутствии различий по параметрам привязанности ($p > 0,05$).

Результаты анализа с использованием критерия Манна–Уитни согласуются с данными ранее проведённых исследований и подтверждают наличие специфического клиничко-психологического профиля у лиц с аллергическими заболеваниями, при этом в

представленную структуру впервые интегрированы показатели психологических границ личности и параметров привязанности.

Далее с целью выявления особенностей структуры взаимосвязей между клинико-психологическими показателями в зависимости от наличия аллергических заболеваний был проведён корреляционный анализ отдельно в основной и контрольной группах с использованием коэффициента ранговой корреляции Спирмена. Результаты контрольной группы представлены в таблице 2, основной группы в таблице 3.

Таблица 2 - Корреляции между психологическими показателями в контрольной группе (Spearman's ρ , N=50)

Переменная	1	2	3	4	5	6
1. Тревожность привязанности (ECR-R, Anxiety)	—					
2. Избегание близости (ECR-R, Avoidance)	.088	—				
3. Самооценка (RSES)	-.455**	.007	—			
4. Тревожность (HADS-A)	.358*	.010	-.495**	—		
5. Депрессия (HADS-D)	.132	.030	-.411**	.324*	—	
6. Психологические границы (BQ-18)	.245	-.131	-.272	.372**	.043	—

*примечание: * $p < 0.05$; ** $p < 0.01$.*

В контрольной группе значимые связи немногочисленны и в целом носят умеренный характер. Наибольшая связанность наблюдается у показателя тревожности, который связан с самооценкой ($r = -0.495$, $p < 0.01$), депрессией ($r = 0.324$, $p < 0.05$), тревожностью привязанности ($r = 0.358$, $p < 0.05$) и психологическими границами личности ($r = 0.372$, $p < 0.01$). Показатель избегания близости при этом практически не включен в систему взаимосвязей, а показатель психологических границ представлен ограниченным числом связей, что указывает на разреженный характер структуры.

Таблица 3 - Корреляции между психологическими показателями в группе с аллергическими заболеваниями (Spearman's ρ , N = 50)

Переменная	1	2	3	4	5	6
1. Тревожность привязанности (ECR-R, Anxiety)	—					
2. Избегание близости (ECR-R, Avoidance)	.250	—				
3. Самооценка (RSES)	-.254	-.501**	—			
4. Тревожность (HADS-A)	.420**	.479**	-.412**	—		
5. Депрессия (HADS-D)	.297*	.364**	-.548**	.283*	—	
6. Психологические границы (BQ-18)	.404**	.509**	-.384**	.587**	.111	—

*примечание: * $p < 0.05$; ** $p < 0.01$.*

В группе лиц с аллергическими заболеваниями наблюдается иная картина. Здесь формируется более плотный контур взаимосвязанных психологических характеристик. Показатель избегания близости включён в систему значимых связей с самооценкой ($r=-0.501$, $p<0.01$), тревожностью ($r=0.479$, $p<0.01$), депрессивными проявлениями ($r=0.364$, $p<0.01$) и психологическими границами личности ($r=0.509$, $p<0.01$). При этом психологические границы личности тесно связаны с уровнем тревожности ($r=0.587$, $p<0.01$), усиливая связанность данной структуры.

Таким образом, если в контрольной группе взаимосвязи представлены отдельными и относительно изолированными связями, то в группе с аллергическими заболеваниями они образуют более интегрированную систему, в которой ряд показателей оказывается взаимосвязанным и включённым в единый контур.

Данное различие более четко видно в показателе *плотности корреляционной структуры*, рассчитанном как отношение числа статистически значимых корреляций к общему числу возможных связей между переменными ($n = 15$): в контрольной группе она составляет 0.40 (6 из 15), тогда как в группе с аллергическими заболеваниями — 0.80 (12 из 15), что свидетельствует о двукратном увеличении степени взаимосвязанности клинко-психологических характеристик в группе с аллергическими заболеваниями.

Выявленные различия в плотности корреляционной структуры отражают не только количественные, но и качественные особенности организации взаимосвязей между показателями. В связи с этим проведён анализ корреляционных плеяд, направленный на выявление конфигурации связей и степени интеграции показателей в единую систему.

Анализ выполнен на основе коэффициента ранговой корреляции Спирмена раздельно для контрольной и основной групп с учётом только статистически значимых взаимосвязей ($p<0,05$), что позволило выделить устойчивые конфигурации связей и представить их в виде корреляционных плеяд (рис. 1 и 2).




Рисунок 1 - Графическая модель корреляционной плеяды психологических показателей в контрольной группе с ($p<0.05$)




Рисунок 2 - Графическая модель корреляционной плеяды психологических показателей в группе с аллергическими заболеваниями ($p < 0.05$)

В контрольной группе плеяда носит разреженный характер: показатель избегания близости не включён в систему значимых связей, а показатель психологических границ личности представлен лишь одной связью с уровнем тревожности, занимая периферийное положение в структуре. Объединяющим элементом системы выступает тревожность, через которую осуществляется связь между большинством показателей.

В группе лиц с аллергическими заболеваниями формируется более плотная и интегрированная плеяда, в которую включены все исследуемые показатели. При этом наблюдается перераспределение роли переменных: избегание близости, тревожность, самооценка и психологические границы выступают ключевыми элементами структуры, формируя систему множественных взаимосвязей.

Для дифференциации прямых и опосредованных взаимосвязей, а также для выявления устойчивых структурных элементов в системе клинико-психологических характеристик в обеих группах был проведён анализ частных корреляций с контролем уровня тревожности. Данные в таблицах 4 и 5.

Таблица 4 - Частные корреляции (контроль тревожности - HADS-A), Контрольная группа (N = 50)

Переменная	1	2	3	4	5
1. Депрессия (HADS-D)	—	—	—	—	—
2. Самооценка (RSES)	-.367**	—	—	—	—
3. Тревожность привязанности (ECR-R, Anxiety)	.084	-.361*	—	—	—
4. Избегание близости (ECR-R, Avoidance)	.027	-.001	.119	—	—
5. Психологические границы (BQ-18)	-.031	-.126	.066	-.186	—

примечание: * $p < .05$; ** $p < .01$.

Таблица 5 - Частные корреляции (контроль тревожности - HADS-A) Группа с аллергическими заболеваниями (N = 50)

Переменная	1	2	3	4	5
1. Депрессия (HADS-D)	—	—	—	—	—
2. Самооценка (RSES)	-.541**	—	—	—	—
3. Тревожность привязанности (ECR-R, Anxiety)	.237	-.195	—	—	—
4. Избегание близости (ECR-R, Avoidance)	.342*	-.399**	.150	—	—
5. Психологические границы (BQ-18)	-.066	-.205	.280	.313*	—

примечание: * $p < .05$; ** $p < .01$

В контрольной группе до контроля тревожности было выявлено 6 статистически значимых взаимосвязей. После контроля тревожности их количество сокращается до 2. Таким образом, после исключения влияния тревожности структура взаимосвязей существенно редуцируется.

В группе лиц с аллергическими заболеваниями после контроля тревожности сохраняются ключевые связи, образующие устойчивый контур взаимосвязанных характеристик: показатель избегания близости остаётся связанным с депрессивными проявлениями ($r = 0.342$, $p < 0.05$), самооценкой ($r = -0.399$, $p < 0.01$) и психологическими границами личности ($r = 0.313$, $p < 0.05$), а также сохраняется связь между депрессией и самооценкой ($r = -0.541$, $p < 0.01$). Это указывает на то, что сохраняется устойчивый контур взаимосвязанных психологических характеристик, не сводимый к уровню тревожности и отражающий более интегрированную организацию психологического функционирования.

Далее, с целью детального анализа вклада показателей привязанности был проведён регрессионный анализ, направленный на оценку прогностической значимости компонентов привязанности (тревожности привязанности и избегания близости) в отношении эмоциональной уязвимости. Результаты представлены в таблице 6.

Таблица 6 - Результаты линейного регрессионного анализа показателей привязанности как предикторов тревожности (HADS-A)

Показатель	Контрольная группа	Основная группа
R ²	0.146	0.298
F	4.030	9.967
p	0.024	< 0.001
β тревожности привязанности	0.385	0.156
p	0.007*	0.081
β избегания близости	0.121	0.432
p	0.441	0.002*

примечание: * $p < 0.05$; зависимая переменная — тревожность (HADS-A); предикторы — тревожность привязанности и избегание близости.

Сопоставление результатов показывает, что в группе лиц с аллергическими заболеваниями регрессионная модель объясняет вдвое большую долю вариативности тревожности по сравнению с контрольной группой ($R^2=0.298$ против $R^2=0.146$). Вместе с тем различия касаются не только величины объяснённой дисперсии, но и структуры предикторов: в контрольной группе значимым предиктором выступает тревожность привязанности, тогда как в группе с аллергическими заболеваниями — избегание близости.

Рассматривая полученные данные в контексте предыдущих этапов анализа, следует отметить их согласованность с результатами корреляционного анализа, анализа плотности связей и корреляционных плед. Если в контрольной группе структура взаимосвязей в значительной степени опосредована уровнем тревожности и редуцируется при его контроле, то в группе лиц с аллергическими заболеваниями сохраняется устойчивая система взаимосвязанных показателей. В этом контексте выявленная роль избегания близости как значимого предиктора тревожности отражает его включённость в более широкую и интегрированную структуру психологических взаимосвязей.

Резюмируя все этапы исследования, констатируем, что в группе лиц с аллергическими заболеваниями выявляется иная организация взаимосвязей - показатели образуют целостную, интегрированную систему. Параметры привязанности и психологических границ включены в множественные взаимосвязи и сопряжены с уровнем тревожности, депрессивных проявлений и самооценкой. В результате формируется единый контур психологического функционирования, характеризующийся высокой взаимной обусловленностью компонентов.

Выявленная у лиц с аллергическими заболеваниями интегрированная система взаимосвязанных показателей позволяет рассматривать её как контур психосоматической уязвимости, в рамках которого психологические границы личности выступают фактором, ограничивающим переработку аффективного напряжения, а избегание близости как параметр привязанности — предиктором, формирующим данную конфигурацию. В совокупности это задаёт условия для накопления и соматизации эмоционального напряжения и может рассматриваться как преморбидный механизм формирования и поддержания аллергической симптоматики.

Список источников:

1. Макулбеков М. В Казахстане повысилась заболеваемость аллергией [Электронный ресурс] // Казинформ. — 2025. — 15 февр. — Режим доступа: (дата обращения: 11.12.2025).
2. Нурпеисов Т. Т. Аллергология Казахстана: успехи и перспективы // Вестник Казахского национального медицинского университета. — 2017. — № 4. — С. 416–418.— URL: <https://cyberleninka.ru/article/n/allergologiya-kazahstana-uspehi-i-perspektivy> (дата обращения: 07.02.2026).
3. Zheng J., Lv J. et al. Global burden and epidemiological trends of allergic diseases: findings from the Global Burden of Disease Study // BMC Pulmonary Medicine. — 2025. — URL: <https://link.springer.com/article/10.1186/s12890-025-03518-y> (дата обращения: 07.02.2026).
4. Филяев М. А., Пыхарева Е. С., Тихомирова Ю. Б. Способ лечения аллергических заболеваний методом психосоматики PSY2.0 // Евразийский союз ученых (ЕСУ). — 2020. — № 4 (73). — С. 67–72.
5. Янчиков В.Н. Метод эмоциональной десенсибилизации при аллергиях // Медицинская психология в России: электрон. науч. журн. — 2020. — № 2 (65).
6. MacKenzie J. The Production of the So-Called 'Rose Cold' by Means of an Artificial Rose //

American Journal of Medical Science. – 1886. – № 9. – P. 45–57.

7. Безредка А.М. О значении раздражителей в инфекции и иммунитете // Журнал экспериментальной биологии и медицины. – 1927. – № 18.

8. Александер Ф. Психосоматическая медицина: её принципы и применение / Ф. Александер. – М.: Институт общегуманитарных исследований, 2002. – 328 с.

9. Данбар Ф. Разум и тело: психосоматическая медицина / Ф. Данбар. – СПб.: Питер, 2001. – 288 с.

10. Schur M. Freud: Living and Dying. – New York: International Universities Press, 1972.

11. Менделевич В. Д., Соловьева С. Л. Неврология и психосоматическая медицина: учебник / В. Д. Менделевич, С. Л. Соловьева. – М.: ГЭОТАР-Медиа, 2016. – 368 с.

12. Лобурец А. О. Клинико-психологические особенности семей с детьми, страдающими бронхиальной астмой и другими аллергическими заболеваниями // Психологическая наука и образование. – 2022. – № 4. – С. 111–120.

13. Никитина С. А. Особенности психологических характеристик пациентов с аллергической реакцией на стадии ремиссии // Вопросы психического здоровья детей и подростков. – 2020. – № 2. – С. 114–118.

14. Budinger L. et al. psychological profiles of patients with suspected drug allergies // Asia Pacific Allergy. – 2020. – Vol. 10, No. 2. – P. e16.

15. Дмитриева В. В. Психологические особенности лиц, страдающих аллергическими заболеваниями // Вестник психотерапии. – 2021. – № 4. – С. 52–56.

16. Yoshihara K. Psychosomatic treatment for allergic diseases // BioPsychoSocial Medicine. 2015. VI. 9, № 1. P. 1–6. URL: <https://bpsmedicine.biomedcentral.com/articles/10.1186/s13030-015-0036-2> (дата обращения: 25.04.2025).

17. Marshall G.D., Tull M.T. Stress, mindfulness, and the allergic patient // Expert Review of Clinical Immunology. – 2018. – Vol. 14, № 12. – P. 1065–1079. – DOI: 10.1080/1744666X.2018.1536547.

18. Bowlby J. Attachment and Loss. Vol. 1: Attachment. – Basic Books, 1982.

19. Выготский, Л. С. Психология развития человека. – Москва: Смысл; Эксмо, 2005. – 1136 с.

20. Леонтьев, А. Н. Проблемы развития психики. – Москва: Изд-во МГУ, 1981. – 584 с.

21. Hartmann, E. Boundaries in the Mind: A New Psychology of Personality. – New York: Basic Books, 1991. – 209 p.

22. Казанцева, Т. В. Адаптация модифицированной методики «Опыт близких отношений» К. Бреннан и Р. К. Фрейли // Известия Российского государственного педагогического университета им. А. И. Герцена. – 2008. – Т. 34 (74). – С. 139–144

23. Андрюшенко, А. В., Дробижев, М. Ю., Добровольский, А. В. Сравнительная оценка шкал CES-D, BDI и HADS(D) в диагностике депрессий в общемедицинской практике // Журнал неврологии и психиатрии им. С. С. Корсакова. – 2003. – № 5. – С. 11–17.

24. Золотарева, А. А. Валидность и надежность русскоязычной версии шкалы самооценки М. Розенберга // Психологический журнал. – 2020. – Т. 41, № 3. – С. 104–113. – URL: <https://cyberleninka.ru/article/n/validnost-i-nadezhnost-russkoyazychnoy-versii-shkaly-samoootsenki-m-rozenberga> (дата обращения: 21.03.2026).

25. Шамшикова, О. А., Волохова, В. И. Психометрический анализ и стандартизация зарубежной методики «Психологические границы личности» Э. Хартманна // Мир науки, культуры и образования. – 2013. – № 5 (42). – С. 243–248.

Համընդհանուր ներառման գործընթացի հոգեբանական առանձնահատկությունները

Գրիգորյան Շուշաննա Սենեքերիմի

«Շիրակի Մ. Նալբանդյանի անվան պետական համալսարան» հիմնադրամ,
Հոգեբանության և սոցիոլոգիայի ամբիոնի դասախոս

Սույն հոդվածում անդրադարձ է կատարվում ներառականության գաղափարախոսությանը, ՀՀ-ում ներառական կրթական համակարգի ներդրման փուլային նկարագրին՝ ներառական կրթական համակարգից համընդհանուր ներառական կրթության անցման անհրաժեշտությանը և արդեն իսկ մերօրյա համընդհանուր ներառականության փաստացի վիճակին և առանձնահատկություններին: Հեղինակի կողմից հատկապես ընդգծվում է այն հանգամանքը, որ ինչպես ամբողջ աշխարհում այնպես էլ ՀՀ-ում կրթության ոլորտում համընդհանուր ներառականությունն ունի ռազմավարական կարևորագույն նշանակություն: Սակայն գործընթացի լիաժեռության և արդյունավետության համար անհրաժեշտ է ոչ միայն առանցնացնել վերջինիս առավելությունները և ոլորտում առկա ձեռքբերումները, այլ նաև լույս սփռել առկա դժվարությունների և խոչընդոտների վրա, որոնք մեծապես պայմանավորված են ներառականության նկատմամբ առկա հասարակական վերաբերմունքով և որոշակի դժվարություններ և արհեստական պատնեշներ են ստեղծում համակարգի ամբողջական գործառնաման համար: Եվ ահա միայն այս խնդիրների հանգուցալուծման պարագայում մենք կարող ենք փաստել համակարգի հաջող իրագործման մասին: Ըստ այդմ հոդվածում մանրամասնորեն վերլուծված և ներկայացված են համընդհանուր ներառականության գործընթացի իրագործմանը խոչընդոտող գործոնները: Եվ որպես վերջաբան տրված են գործնական առաջարկություններ, որոնք կարող են կիրառվել որպես լավարկաման գործիք և կծառայեն ի նպաստ ներառական քաղաքականության լիարժեք ներդրմանը հանարկրթական դպրոցներում:

Բանալի բառեր՝ համընդհանուր ներառականություն, ներառական կրթություն, կարծրատիպ, կրթության առանձնահատուկ պայմանի կարիք, կրթություն, արժեքային համակարգ:

Психологические особенности процесса всеобщей инклюзии

Григорян Шушанна Сенекеримовна

Фонд «Ширакский государственный университет имени М. Налбандяна»

Преподаватель кафедры психологии и социологии

В данной статье рассматривается идеология инклюзивности, этапы становления инклюзивной образовательной системы в Республике Армения, необходимость перехода к модели всеобщего инклюзивного образования, а также современное состояние и особенности реализации данного процесса. Автор особо подчёркивает, что, как и во всём мире, всеобщая инклюзия в сфере образования имеет стратегическое значение и для Армении. Однако для обеспечения полноты и эффективности процесса требуется не только выделить его преимущества и достижения, но и осветить существующие трудности и препятствия, которые в значительной степени обусловлены общественным отношением к

инклюзии и создают определённые барьеры для полноценного функционирования системы.

Лишь при условии преодоления данных проблем можно говорить об успешной реализации инклюзивной политики. В статье детально анализируются и описываются факторы, препятствующие внедрению всеобщей инклюзии, а также предлагаются практические рекомендации, которые могут быть использованы в качестве инструмента совершенствования и будут способствовать полноценной реализации инклюзивной политики в общеобразовательных школах.

Ключевые слова: всеобщая инклюзия, инклюзивное образование, стереотип, особые образовательные потребности, образование, система ценностей.

Psychological features of the universal inclusion process
“Shirak State University named after M. Nalbandyan” Foundation
Lecturer at the Department of Psychology and Sociology
Shushanna Senekerim Grigoryan

This article examines the ideology of inclusion, the initial implementation of the inclusive education system in the Republic of Armenia, the necessity of transitioning toward universal inclusive education, as well as the current state and specific features of this process. The author particularly emphasizes that, as in the rest of the world, universal inclusion in the field of education holds strategic importance for Armenia. However, to ensure the completeness and effectiveness of this process, it is necessary not only to highlight its advantages and achievements but also to shed light on the existing difficulties and obstacles, which are largely conditioned by societal attitudes toward inclusion and create certain barriers to the full functioning of the system.

Only by addressing and overcoming these challenges can we speak about the successful implementation of the inclusive education system. The article provides a detailed analysis of the factors hindering the realization of universal inclusion and offers practical recommendations that can serve as tools for improvement and contribute to the effective implementation of inclusive policy in general education schools.

Keywords: universal inclusion, inclusive education, stereotype, special educational needs, education, value system.

Ներածություն: 21-րդ դարում մերօրյա կրթության համաշխարհային օրակարգում կարևորագույն տեղ է հատկացվում ներառական կրթությանը: UNESCO-ի «Global Education Monitoring Report 2020»-ում շեշտվում է, որ «All means all»՝ ներառումը վերաբերում է բոլոր սովորողներին՝ անկախ նրանց առանձնահատկություններից [5]:

Հայաստանում ներառական կրթության համակարգը որպես ազգային քաղաքականություն, պաշտոնապես ընդունվել է 2003 թ.-ին: Այդ ժամանակից ի վեր տեղական և միջազգային բազմաթիվ կազմակերպություններ նախաձեռնել են նոր ընդունված համակարգին համահունչ զանազան ծրագրեր՝ ուսուցիչներին և կրթության առանձնահատուկ պայմանների կարիք ունեցող երեխաներին օժանդակելու համար: [3, էջ 3]

ՀՀ Ազգային ժողովում 2005 թվականի մայիսի 25-ին ընդունվեց և նույն թվականի սեպտեմբերի 1-ին ուժի մեջ մտավ «Կրթության առանձնահատուկ պայմանների կարիք ունեցող անձանց կրթության մասին» ՀՀ օրենքը [6]: Համաձայն որի կրթության առանձնահատուկ պայմանների կարիք ունեցող երեխաների կրթությունը ծնողների (կամ նրանց օրինական ներկայացուցչի) ընտրությամբ կարող է իրականացվել ինչպես հատուկ, այնպես էլ ընդհանուր հանրակրթական ուսումնական հաստատություններում՝ հատուկ ծրագրով:

Իսկ ՀՀ Ազգային ժողովը 2014 թվականի դեկտեմբերի 1-ին ընդունել է «Հանրակրթության մասին» ՀՀ օրենքում լրացումներ և փոփոխություններ կատարելու մասին» ՀՀ օրենքը (ՀՕ-200-Ն)[7], համաձայն որի հանրակրթության համակարգում անցում է կատարվել **համընդհանուր ներառական կրթության**: Հայաստանի Հանրապետության պետական հանրակրթական ուսումնական հաստատություններում ներդրվել են ուսուցչի օգնականի հաստիքներ, որոնց թիվը որոշվում է տվյալ դպրոցում սովորողների միջին տարեկան թվի 10 տոկոսի հաշվարկի հարաբերակցությունից:

Համաձայն «Հանրակրթության մասին» ՀՀ օրենքի՝

- Ներառական կրթությունը՝ յուրաքանչյուր երեխայի համար, այդ թվում՝ կրթության առանձնահատուկ պայմանների կարիք ունեցող, զարգացման առանձնահատկություններին համապատասխան, անհրաժեշտ պայմանների և հարմարեցված միջավայրի ապահովման միջոցով կրթական գործընթացին առավելագույն մասնակցության և հանրակրթության պետական չափորոշիչով սահմանված արդյունքի ապահովումն է:
- կրթության առանձնահատուկ պայմանների կարիք ունեցող անձը՝ խոսքի և լեզվի, հաղորդակցման, լսողության, տեսողության, ինտելեկտի (մտավոր), հուզական, վարքի, շարժունակության և այլ խնդիրներով պայմանավորված՝ ուսուցման հետ կապված դժվարություններ ունեցող, ինչպես նաև բացառիկ ընդունակություններ ունեցող անձն է, որին հանրակրթական հիմնական ծրագրերը յուրացնելու համար անհրաժեշտ են կրթության առանձնահատուկ պայմաններ, ներառյալ՝ խելամիտ հարմարեցումներ:
- Կիրառվում է երեխայի կրթությանն աջակցելու եռաստիճան համակարգ: կրթության առանձնահատուկ պայմանների կարիք ունեցող երեխաները մանկավարժահոգեբանական աջակցություն են ստանում 3 մակարդակում՝ հանրակրթական դպրոցում, տարածքային մանկավարժահոգեբանական աջակցության կենտրոնների և հանրապետական կենտրոնի կողմից[8]:

Համընդհանուր ներառման գործընթացում առկա հոգեբանական մարտահրավերները:

Վստահաբար կարող ենք փաստել, որ այս «ներառականություն» եզրույթն ունի չափազանց լայն բովանդակություն, բայց մասնավորապես հայ իրականության մեջ այն ընկալվում է որպես կրթության առանձնահատուկ պայմանների կարիք ունեցող սովորողների նկատմամբ ոչ տարբերակված վերաբերմունք ցուցաբերելու, սոցիալիզացիան խթանելու և նրանց համար գիտելիքահեն, արդյունավետ կրթություն ապահովելու առաջնահերթ պայման[1, էջ 6]: Ըստ այդմ բոլոր աշակերտների հավասար ներգրավվածությունը ուսումնական ողջ գործընթացում առանցքային դեր է խաղում համընդհանուր ներառական կրթության համատեքստում: Համընդհանուր ներառականությունը միտված է ապահովելու հավասար, սակայն ոչ նույնակերպ վերաբերմունք բոլոր սովորողներին հանդեպ: Այսինքն, որպես գերնպատակ առաջ է մղվում համագործակցող, աջակցող, հարգալից վերաբերմունք միմյանց նկատմամբ և այնպիսի պայմանների ստեղծումը, որոնք հնարավորություն կտան բոլոր սովորողների հասնել հաջողության: Իսկ դա առաջին հերթին ենթադրում է, որ.

- ✓ Նախևառաջ ուսուցիչները պետք է ճանաչեն իրենց աշակերտների կարիքներն ու առանձնահատկությունները և ըստ այդմ թեման ներկայացնեն այնպես որ հասկանալի լինի բոլոր, այդ թվում՝ կրթության առանձնահատուկ պայմանների կարիք ունեցող սովորողների համար:
- ✓ Անհրաժեշտության դեպքում ցուցաբերեն ճկունություն փոխելու իրենց պլանավորած գործողությունների ուղղությունը, եթե չի ապահովվում գործունեության արդյունավետությունը:
- ✓ Դպրոցի և ընտանիքի սերտ համագործակցություն, որը ենթադրում է կրթության

առանձնահատուկ պայմանի կարիք ունեցող սովորողի կրթության վերաբերյալ միասնական մոտեցում:

- ✓ Բոլոր, այդ թվում կրթության առանձնահատուկ պայմանների կարիք ունեցող աշակերտների ներգրավվածություն դասապրոցին՝ ապահովելով անհրաժեշտ խելամիտ հարմարեցումները:

Այսօր թե՛ կրթական համակարգում, թե՛ հասարակության այլ ոլորտներում զարգացման առանձնահատուկ հնարավորություններ, կարիքներ ունեցող անձի հասարակական դիրքի ընկալման մեջ լայնորեն կիրառվում է «ներառում» (ֆր. *inclusif* — ընդգրկող, լատ. *includo* — ընդգրկել, ներառել, ներգրավել) հասկացությունը, որը ենթադրում է ուսուցման գործընթացի և միջավայրի հարմարեցում անձի, սովորողի ահնատական կարիքներին: Եվ այստեղ տեղին է տարբերակել «ներառում» և «ինտեգրում» հասկացությունները.

Ինտեգրումը ենթադրում է այնպիսի գործընթաց, որի դեպքում սովորողը, հատկապես կրթության հատուկ պայմանների կարիք ունեցող երեխան, ներառվում է ընդհանուր կրթական համակարգ՝ առանց դրա կառուցվածքային փոփոխության: Այս մոտեցման պարագայում առաջնային է սովորողի հարմարվողականությունը՝ միջավայրի պահանջներին համապատասխանելու կարողությունը: Այլ կերպ ասած՝ ինտեգրման ժամանակ փոփոխվում է ոչ թե համակարգը, այլ սովորողը՝ հարմարեցնելով իրեն առկա կրթական ձևաչափին:

Ի տարբերություն դրա՝ **ներառումը** հիմնված է այլ սկզբունքի վրա. այստեղ կրթական համակարգն ինքն է փոխվում և հարմարեցվում յուրաքանչյուր սովորողի անհատական կարիքներին: Ներառման նպատակն է ստեղծել այնպիսի միջավայր, որտեղ բոլոր երեխաները՝ անկախ իրենց ֆիզիկական, ինտելեկտուալ, սոցիալական կամ մշակութային տարբերություններից, ունեն հավասար հնարավորություններ ուսում ստանալու, մասնակցելու և զարգանալու համար [4 էջ 12]:

Եթե հարցը դիտարկենք այն տեսանկյունից, որ ներառման ամբողջականությունը ենթադրում է համապատասխան քաղաքականության, մշակույթի և գործելակերպի մշակում, ապա անկներև է դառնում, որ մեր ցանկացած վարքի հիմքում ընկած են որոշակի արժեքներ, որոնք համապատասխան գործողությունների համար խթան են հանդիսանում: Ուստի, ինչպես հասարակության մեջ, այնպես էլ դպրոցում համընդհանուր ներառականության լիարժեքությունը պայմանավորված է արժեքային համակարգի առանձնահատկություններով: Եվ այստեղ առաջին պլան են մղվում այնպիսի կարևոր արժեքներ ինչպիսիք են.

Հավասարությունը

Ազնվությունը

Խիզիությունը

Հույսը

Հանդուրժողականություն

Փոխօգնություն

Կարեկցանքը

Լավատեսությունը

Քաջությունը

Վստահությունը

Բռնության բացառումը...

Վերոնշյալ և այլ կարևորագույն արժեքներ «Ներառման ինդեքս. ներառական արժեքների հիման վրա դպրոցի զարգացման ուղեցույց»-ում ներկայացված են որպես երկխոսության հրավեր, որի նպատակն է պատասխանել «Ինչպե՞ս ապրել կողք կողքի» հարցին՝ ձևավորելով ներառական հասարակություն: Կարևոր է փաստել նաև, որ ուղեցույցում ներկայացված են ինչպես ներառական արժեքների շրջականը [2, էջ 27], այնպես էլ

ներառումը բացառող արժեքների համակարգը [2, էջ 37]. ներառական արժեքները գործածության մեջ դնելու գործընթացը ենթադրում է փոխկապակցել մեր գործողությունները ներառական արժեքներին և խզել կապը բացառող արժեքների հետ[2, էջ 387]:

Յուրաքանչյուր աշակերտի մոտ բաժրագույն արժեքների ձևավորումը դրված է ինչպես ծնողների, այնպես էլ ներառականության առաջնամարտիկներ՝ ուսուցիչների ուսերին: Եվ նման կայուն արժեհամակարգի ձևավորումը աշակերտների մոտ հանրավորություն է տալիս կերտել հոգեւոցիալական հասունություն և առողջություն ունեցող հասարակություն, որը զերծ է բացառումից և խտրականությունից և որտեղ իշխում է կողք կողքի ապրելու արվեստը:

Հաշմանդամություն և կրթության առանձնահատուկ այլ պայմանների կարիք ունեցող աշակերտների սոցիալական և հոգեբանական ներառման հիմքում ընկած են դպրոցի մշակույթին բնորոշ առանձնահատկությունները, մասնավորապես.

- բազմազանության բոլոր ձևերի ընդունումը,
- աշակերտի ծայնի արժևորումը,
- աշակերտներին և անձնակազմերին՝ իրենց ունակություններն ու կարողությունները փոխանցելու հնարավորությունների ընձեռումը,
- լիազորությունների բաժանումը,
- աշակերտների՝ միմյանց հաշվետու լինելը,
- հաշմանդամության հետ կապված հարցերի ըմբռնումը որպես ներառական կրթության
- ապահովման համար պատրաստ լինելու մի մաս,բոլորի մասնակցությունը առօրյայում և միջոցառումներում,
- բոլոր աշակերտների համար դպրոցի համայնքային ոգու զարգացմանն ուղղված միջոցառումներին մասնակցելու հնարավորությունների ապահովում [3 էջ 156]:

Եվ ահա, մեր օրերում այնքան հաճախ է բաժրաձայնվում համընդհանուր ներառականության գաղափարի, վերջինիս կարևորության մասին, որ թվում է, թե ամեն ինչ ասված է և լիարժեք: Սակայն, հասարակական կյանքի տարբեր ոլորտներում դեռևս կան արհեստական պատնեշներ, որոնք դժվարացնում են համընդհանուր ներառման գործընթացի լիարժեքությունը: Հարցը տեղայնացնելով կրթության ոլորտում՝ փորձենք առանձնացնել ուսուցման գործընթացում առկա հոգեբանական խոչընդոտները, որոնց առկայությունը դժվարացնում է համընդհանուր ներառման գործընթացի լիարժեքությունն ու արդյունավետությունը: Մասնագիտական գրականության վերլուծության և մեր փորձառության արդյուքնում ձեռք բերված տվյալների վերլուծությունը թույլ է տալիս առանձնացնել հետևյալ խորընդոտները.

Կարծրատիպեր: Կրթության մեջ լիարժեք ներառման հիմնական, առաջնային խոչընդոտներից մեկը կարծրատիպային մտածողությունն է՝ մարդկանց ունեցած սխալ և ոչ դրական դիրքորոշումներն ու վերաբերմունքը: Շատ հաճախ կրթության առանձնահատուկ պայմանների կարիք ունեցող սովորողների մասին գաղափարները ձևավորվում են գիտելիքների բացակայության կամ կարծրատիպերի պատճառով:

Հասարակության մեջ կա տարածված թյուր կարծիք, որ ԿԱՊԿ ունեցող սովորողներն ունակ չեն սովորելու և հասարակության որևէ բնագավառում հաջողելու, քանի որ նրանք ինչ-որ կերպ տարբեր են մեզանից: Այո՛, նրանք տարբեր են. տարբեր են իրենց հոգեբանական առանձնահատկություններով՝ ընկալմամբ, մտածողությամբ, վարքով, հույզերով: Եվ մենք այդ տարբերությունների որակում ենք որպես խնդիր՝ առանց ընդունելու յուրաքանչյուրի՝ մեզանից տարբեր լինելու իրավունքը[1,էջ 9]:

Չնայած այն հանգամանքին, որ ուսուցիչների մեծամասնությունը դրական է վերաբերվում ներառմանը, ամեն դեպքում դեռևս կան նաև այնպիսի ուսուցիչներ, որոնք ունեն նման կարծրատիպային մոտեցում համընդհանուր ներառականության հետ կապված՝ կարծելով, որ ներառումը անհաղթահարելի դժվարություն է : Նման դեպքերում մանկավարժներն

առավել հաճախ շեշտադրում են, որ զարգացման այս կամ այն առանձնահատկությունն ունեցող երեխաների հետ աշխատանքը խիստ բարդ ու ժամանակատար է, նրանց վրա անընդհատ ուշադրություն կենտրոնացնելու անհրաժեշտությունը նվազեցնում է դասարանի մյուս երեխաների հետ համագործակցելու հնարավորությունը և մի շարք այլ հանգամանքներ:

Այս խոչընդոտները հաճախ առաջանում են գիտելիքների և փորձի պակասից, ինչն էլ ստիպում է ուսուցիչներին անտեսել, դատել կամ թյուր պատկերացումներ ունենալ ԿԱՊԿ ունեցող սովորողների վերաբերյալ:

Ի վերջո, պետք է փաստել, որ ներառում չի նշանակում բոլորին ծուլելու կամ միատեսակ դարձնելու ձգտում: Այն ընդունում է, որ երեխաները սովորում են տարբեր արագությամբ, իսկ ուսուցիչներին անհրաժեշտ են հատուկ հմտություններ՝ ուսուցման գործընթացի ճկունությունն ապահովելու համար: Պարզապես երեխաներին անհրաժեշտ է հասկանալի, մատչելի դասավանդում: Իսկ դա իր հերթին ենթադրում է երեխայի առանձնահատկություններին, անհատական կրթական պահանջմունքներին, զարգացման տեմպերին, ընդունակություններին և կարողություններին համապատասխանող տարբեր մեթոդների օգտագործում:

Ոչ իրատեսական ակնկալիքներ: Քիչ չեն այն դեպքերը, երբ երեխային դպրոց բերելիս ծնողներն ունենում են բարձր ակնկալիքներ, ինչպես դպրոցից, անպես էլ մանկավարժահոգեբանական աջակցության թիմից՝ առանց հաշվի առնելու երեխայի հոգեբանական առանձնահատկությունները և ինտելեկտի, իմացական գործընթացների զրգացման համապատասխանությունը տարիքային զարգացման չափանիշներին: Երբեմն չափազանց դժվար է ընդունել, որ կարելի է առաջ շարժվել փոքրիկ, բայց հաստատուն քայլերով, ծնողներ ակնկալում են միանգամից ստանալ շոշոփելի արդյունք:

Խոսքի մշակույթի զարգացման անհրաժեշտությունը: Խոսքի մշակույթի պակասը հատկապես խնդրահարույց է ներառական կրթական միջավայրում, որտեղ կարևոր է ապահովել հստակ, հարգալից, հասկանալի և ներառող հաղորդակցություն: Այս բացը կարող է հանգեցնել թյուրըմբռնումների, սոցիալական մեկուսացման և նույնիսկ խտրական վերաբերմունքի, եթե հաղորդակցությունը չի արտացոլում հանդուրժողականություն, բազմազանության ընդունում և փոխադարձ հարգանք:

Խտրականություն: Չարգացման առանձնահատկություններ ունեցող սովորողների նկատմամբ դրսևորած խտրականությունը երբեմն հիմնական մարտահրավերն է դառնում նրանց սոցիալական ներառման գործում: Շատ անգամ այս երեխաներին կարող են ծաղրել իրենց արտաքինի պատճառով: Նման վերաբերմունքը, անխոս, խաթարում է երեխայի հոգեհուզական կայունությունը՝ ազդելով նրանց ինքնագնահատականի, փոխհարաբերությունների և ուսումնական մոտիվացիայի վրա:

Խղճահարություն: Յուրաքանչյուր անձ, այդ թվում կրթության առանձնահատուկ պայմանների կարիք ունեցող սովորողը, յուրօրինակ սոցիալական հայելի է: Այսինքն, երբ մենք երեխային նայում ենք հպարտությամբ և ուրախությամբ, երեխայի մեջ արթնացնում ենք իր անձի և ուժերի նկատմամբ հավատ և սեր: Իսկ երբ մենք երեխային նայում ենք խղճահարությամբ, ենթագիտակցորեն նրան տալիս ենք ազդակ, որ նա ինչ-որ առումով թույլ է և խոսցելի:

Ֆիզիկական մատչելիություն: Շատ կրթական հաստատություններ չունեն թեքահարթակներ, վերելակներ, հարմարեցված սանհանգույցներ և այլ անհրաժեշտ պայմաններ:

Տեխնիկական միջոցների պակաս: Հատուկ կրթական տեխնոլոգիաները (լսողական սարքեր, բրայլյան համակարգեր, Էկրանի ընթերցիչ ծրագրեր) հաճախ բացակայում են կամ սահմանափակ են, ինչը դժվարացնում է կրթության առանձնահատուկ պայմանի կարիք ունեցող սովորողների լիարժեք ներառումը ուսումնական գործընթացում՝ բացասաբար ազդելով կրթական մոտիվացիայի և առաջընթացի վրա:

Մեր երկրում լուրջ խնդիր է համարվում նաև **հատուկ մասնագետների** թիվը, մասնավորապես, մի շարք համայնքներում առկա են հատուկ մանկավարժների, լոգոպեդների, ֆիզիոթերապևտների, էրգոթերապևտների կարիք:

Եզրակացություն: Այսպիսով ներառման գործընթացն արդյունավետ կարող է լինել հատկապես այն դեպքում, երբ դրա համար պատասխանատու օղակները՝ ուսուցիչները, մանկավարժահոգեբանական աջակցություն տրամադրող մասնագետները և ծնողները համագործակցային, թիմային մոտեցում են դրսևորում այդ գործընթացի կազմակերպման ու իրականացման հարցում՝ իրենց գործունեության հիմքում ամուր դնելով ներառական արժեքների համակարգը:

Սոցիալ-հոգեբանական ներառումն սկսվում է այն համոզմունքից, որ բոլոր երեխաները իրավունք ունեն իրենց ընտրած հասակակիցների հետ զարգացնել ու պահպանել ընկերական և այլ սոցիալական հարաբերությունները՝ ապրելով լիիրավ անդամի զգացումով և լիարժեքորեն ընդգրկվելով համայնքում:

Համընդհանուր ներառման գործընթացը կսկսի լիարժեք գործել այն ժամանակ, երբ առողջ փոխհամագործակցություն լինի պետական և ոչ պետական սեկտորների միջև, երբ հասարակությունը պատրաստ կլինի ընդունել և իր կողքին տեսնել առողջական և հոգեբանական առանձնահատկություններ ունեցող անձանց, երբ ընտանիքները կլինեն ոչ թե մեկուսացնող, հասարակությունից պաշտպանող վահան, այլ կապող կամուրջ կհանդիսանան, երբ հասկարակության յուրօրինակ անհատ կոդիտարկվի որպես յուրատիպ արժեք՝ առանց կաղապարային սահմանափակումների և համեմատությունների:

Եվ որպես վերջաբան կցանկանանք հանդես գալ մի քանի առաջարկություններով, որոնք կծառայեն ի նպաստ ներառական քաղաքականության լիարժեք ներդրմանը հանարկության դպրոցներում.

- ✓ Ուսուցիչների շարունակական վերապատրաստում:
- ✓ Ֆիզիկական մատչելիության ապահովում:
- ✓ Խտրականության կանխարգելիչ ծրագրեր:
- ✓ Ծնողավարման հատուկ վերապատրաստումներ հաշմանդամություն և զարգացման առանձնահատկություններ ունեցող երեխաների ծնողների համար:
- ✓ Ծնողական լավագույն փորձի փոխանակում, ինքնօգնության խմբերի ձևավորում:
- ✓ Ֆիզիկական մատչելիության ապահովում:
- ✓ Հոգեբանական առանձնահատկությունների վերաբերյալ իրազեկիչ և հատկապես գործնական սեմինարների և վերապատրաստումների իրականացում ուսուցիչների համար:
- ✓ Մեթոդական ռեսուրսների տրամադրում և հարստացում

Գրականություն

1. Սվաջյան Ա.Յ., Ազատյան Թ.Յու. Բաբայան Լ.Ա.«Արդյունավետ հարմարեցումներ որակյալ կրթություն»ՅՄԿ 2022թ, 143էջ
2. Բուբ Թ., Աիսաբուլ Մ. «Ներառման ինդեքս. ներառական արժեքների հիման վրա դպրոցի զարգացման ուղեցույց», Գյումրի «Հայկական կարիտաս» ԲՀԿ» 4-րդ հրատարակություն, 295էջ
3. «Ներառական կրթության ռազմավարություններ» դասագիրք ՅՊՄՀ 2019թ.,250 էջ
4. Левшунова Ж.А. Инклюзивное образование: учеб. пособие /Ж.А. Левшунова, Н.В. Басалаева, Т.В. Казакова. – Красноярск: Изд-во Сиб. федер. ун-та, 2017. 114с.
5. <https://www.unesco.org/en/articles/global-education-monitoring-gem-report-2020>
6. <https://old.arlis.am/DocumentView.aspx?docid=1826>
7. <https://www.arlis.am/hy/acts/94683>
8. <https://escs.am/am/static/inclusiveeducation?s=edu>

ЭФФЕКТИВНОСТЬ СТИЛЕЙ УПРАВЛЕНИЯ В СОВРЕМЕННЫХ УСЛОВИЯХ ТРУДА: ПСИХОЛОГИЧЕСКИЕ АСПЕКТЫ

Сапарбек Казбек Мейрбекулы

магистрант 1-го курса по специальности «Медико- профилактическое дело»,
Казахский Национальный Медицинский университет имени С.Д. Асфендиярова, г.
Алматы, Казахстан

Бисенова Алтынайым Бауржанкызы

магистрант 1-го курса по специальности «Медико-профилактическое дело»,
Казахский Национальный Медицинский университет имени С.Д. Асфендиярова, г.
Алматы, Казахстан

Кудайбергенова Айжан Жаканбаевна

ассистент профессора кафедры коммуникативных навыков, Казахский Национальный
Медицинский университет имени С.Д. Асфендиярова, г. Алматы, Казахстан

Аннотация

В статье рассматривается эффективность стилей управления в современных условиях труда с психологической точки зрения. Проанализированы основные стили управления и охарактеризовано их влияние на мотивацию сотрудников, психологический климат в организации и производительность труда. Кроме того, обоснована значимость ситуационного подхода при выборе стиля управления.

Ключевые слова: психология управления, стиль управления, мотивация, психологический климат, производительность труда.

Введение. В условиях современной глобализации изменения на рынке труда и усиление конкуренции между организациями предъявляют новые требования к системе управления. В таких условиях эффективность управления определяется не только экономическими показателями, но и психологическими факторами. Стиль управления является важным инструментом, оказывающим непосредственное влияние на поведение людей в организации, их взаимоотношения и результаты труда. Поэтому изучение эффективности стилей управления с позиции психологических аспектов в современных условиях труда является актуальной задачей.

Цель данной работы – на основе анализа научной литературы выявить психологические аспекты эффективности основных стилей управления и обосновать значимость ситуационного подхода при их практическом применении в современных организациях.

Материалы и методы. Исследование выполнено в форме теоретического анализа и систематического обзора научной литературы. В качестве источников использованы классические труды по социальной психологии и менеджменту, а также актуальные зарубежные эмпирические исследования, опубликованные в рецензируемых международных журналах. Отбор источников осуществлялся по следующим критериям: тематическое соответствие (стили управления, психологический климат, мотивация, производительность труда), рецензируемый статус издания, а также актуальность

публикации. Основными методами работы с литературой стали сравнительный анализ, синтез и обобщение теоретических и эмпирических данных.

Результаты. В психологии управления выделяют несколько стилей управления, в числе которых являются авторитарный, демократический и либеральный. Теоретические основы разделения этих стилей управления были заложены в исследованиях К. Левина, в которых проводилось исследование групп динамики в зависимости от стиля руководства [2]. В дальнейшем развитие данной классификации осуществлялось в работах в области управления [3] и поведения в организации [4].

Авторитарный стиль управления является тем, при котором принятие решений находится исключительно у руководителя, также как и контроль над действиями подчинённых [5]. Такой стиль управления является эффективным в тех условиях, где необходимо принятие решений в критические периоды, а также в условиях высокой сложности трудового процесса [5]. В статье отмечается, что краткий обзор исследований в области авторитарного управления, опубликованных в течение периода 1966-2021 гг., показал интерес к данной теме в основном со стороны западных стран. Так, в период 1966-2010 гг., в среднем 66,15% опубликованных научных работ в этой области имели американских авторов, а в период 2011-2021 гг., восточно-китайских авторов представили уже 22,12% всех научных статей [5]. Это говорит о том, что авторитарное управление является нормой для большинства членов общества с высокой степенью дистанции в отношениях между властью и подданными. В подавляющем большинстве случаев авторитарный стиль управления не ведёт к снижению производительности результата ведения организации [5]. Так, исследования, проведённые среди N=523 участников организации, которые использовали структурное моделирование для сбора данных (SmartPLS), показали, что авторитарный стиль управления может вести к повышению кооперативных связей между работниками, однако ведёт к повышению уровня стресса и в целом негативно влияет на психологический климат в организации [12].

Демократический стиль управления включает сотрудников в процесс управления: руководитель учитывает мнение членов коллектива и применяет совместный подход при принятии решений [3]. Социально-психологические исследования показывают, что вовлечение работников в процесс принятия решений создает у них чувство причастности и увеличивает внутреннюю мотивацию [1].

Согласно упомянутому выше исследованию (N=523), демократический стиль лидерство косвенно снижает уровень стресса на рабочем месте за счет улучшения организационного климата, в то время как харизматический стиль лидерство напрямую улучшает атмосферу в коллективе, ослабляя как стресс, так и чувство запертости [12]. Таким образом, демократический стиль способствует формированию благоприятного психологического климата в организации и, как следствие, росту производительности труда и уровня удовлетворённости работой. Отдельного внимания заслуживает трансформационное лидерство, рассматриваемое в современной литературе как развитие демократических принципов: исследование на выборке преподавателей вузов провинции Шэньси (Китай) с применением корреляционного анализа SPSS показало, что стиль руководства положительно коррелирует как с результативностью выполнения задач, так и с психологическим капиталом сотрудников, причём психологический капитал выступает медиатором данной взаимосвязи [13]. Это согласуется с результатами пакистанского исследования (N = 261), которое продемонстрировало, что трансформационное лидерство положительно влияет на эффективность труда, причём психологический капитал выступает в качестве полного посредника в этой взаимосвязи – что свидетельствует о том, что лидеры с позитивным настроем способствуют развитию психологических ресурсов своих подчиненных, что, в свою очередь, улучшает их трудовые результаты [13].

Либеральный стиль управления подразумевает предоставление работникам значительной степени свободы. Этот стиль может быть эффективным в творческих и высококвалифицированных коллективах [4]. Недостаточный контроль может негативно сказываться на согласованности деятельности организации. Согласно данным структурного моделирования (N=523), либеральный стиль ухудшает организационный климат, хотя его прямое влияние на уровень стресса было статистически незначимым [12].

Влияние стиля управления на производительность труда опосредуется различными психологическими факторами. В частности, положительный психологический капитал сотрудников – включающий в себя самоэффективность, оптимизм, надежду и резилиентность – выступает в качестве значимого посредника в отношениях между стилем лидерства и результатами работы [6, 13]. Организационный климат также играет ключевую посредническую роль: стресс негативно влияет на физическое и психическое здоровье сотрудников, снижая их мотивацию и производительность, а стиль управления в значительной степени определяет, насколько благоприятной будет среда, в которой формируется этот климат [12].

В современной рабочей среде использование стилей управления в значительной степени основано на ситуационном подходе. Это означает, что выбор стиля управления зависит от конкретной ситуации, целей организации, уровня профессиональной подготовки сотрудников и их психологических характеристик [3]. Многие исследователи настаивают на том, что лидеры должны гибко варьировать степень директивности в зависимости от контекста, поскольку именно это позволяет обеспечить наиболее эффективную связь между стилем лидерства и производительностью [5]. В связи с этим в литературе активно обсуждается концепция гибридных стилей лидерства, сочетающих в себе элементы различных подходов [5].

Заключение. Таким образом, эффективность стилей управления в современных условиях труда во многом зависит от правильности их выбора. Учет психологических аспектов позволяет сформировать благоприятный климат в организации, повысить мотивацию сотрудников и общую производительность труда. Поэтому в управленческой практике особое значение приобретает использование гибких и научно обоснованных подходов.

Список использованной литературы

1. Андреева Г.М. Социальная психология. Учебник для высших учебных заведений. – М.: Аспект Пресс, 2001.
2. Левин К. Теория поля в социальных науках.: Пер. с англ. – СПб.: «Сенсор», 2000. – 368 с. (Мастерская психологии и психотерапии).
3. Мескон М., Альберт М., Хедоури Ф. Основы менеджмента. /Пер. с англ. — Учебник.- М.: Дело ЛТД, 2010.- 701 с.
4. Роббинс, Стивен П. Основы организационного поведения / Стивен П. Роббинз; [пер. с англ. О. Л. Пелявского]; Ун-т Сан-Диего. - 8-е изд. - М. [и др.]: Вильямс, 2006. - 443 с.: ил., табл.: 24 см.; ISBN 5-8459-0883-3 (в пер.).
5. Pizzolitto E., Verna I., Venditti M. Authoritarian leadership styles and performance: a systematic literature review and research agenda // Management Review Quarterly. - 2023. -Vol. 73, № 2. -P. 841-871
6. Baig S. A., Iqbal S., Abrar M., Baig I. A., Amjad F., Zia-ur-Rehman M., Awan M. U. Impact of leadership styles on employees' performance with moderating role of positive psychological capital // Total Quality Management & Business Excellence. -2019

7. Tong Y. The influence of entrepreneurial psychological leadership style on organizational learning ability and organizational performance // *Frontiers in Psychology*. -2020. -Vol. 11. -Article 1679
8. Rabiul M. K., Patwary A. K., Mohamed A. E., Rashid H.-o. Leadership styles, psychological factors, and employee commitment to service quality in the hotel industry // *Journal of Quality Assurance in Hospitality & Tourism*. -2022. -Vol. 23, № 4. -P. 853-881
9. Solomon, A., & Steyn, R. Leadership styles: The role of cultural intelligence. // *SA Journal of Industrial Psychology/SA Tydskrif vir Bedryfsielkunde*. -2017. -Vol. 43, a1436.
10. Mamaradjabova B. A. Psychological aspects of use of leadership styles in management // *Multidisciplinary Journal of Science and Technology*. -2024. -Vol. 4, № 7. -P. 233-236
11. Zhou, Y., & Wahab, S. R. A. The Impact of Transformational Leadership Styles on Task Performance and Psychological Capital: a Study on College Teachers in China. // *International Journal of Academic Research in Business and Social Sciences*. -2024. -Vol. 14, №5. -P. 1422–1432.
12. Harms P. D., Wood D., Landay K., Lester P. B., Lester G. V. Leadership and stress: A meta-analytic review // *Journal of Leadership & Organizational Studies*. -2021. -Vol. 28, № 3. -P. 257-281
13. Aslan M., Sönmez S., Deniz M. Leadership styles and work stress: the role of workplace climate and feelings of entrapment // *Current Psychology*. -2025. -Vol. 44, № 7. -P. 6407-6420

Legal Sciences

Legal Education and Its Role in Strengthening Legal Culture: A Comparative Study of Kazakhstan and China

Chen Yuhou

Jurisprudence student, Al-farabi Kazakh National University, Farabi Law Faculty, Kazakhstan, Almaty

Abstract

Against the backdrop of deepening China-Kazakhstan cooperation under the Belt and Road Initiative, legal culture, as the core of the rule of law, relies heavily on legal education for inheritance and development. This study aims to explore the role of legal education in strengthening legal culture and address the gaps in existing comparative studies between China and Kazakhstan. Adopting a mixed research method combining questionnaire survey and interviews, it systematically compares the characteristics, paths, and effects of legal education in the two countries, and identifies the core factors affecting the role of legal education. The core innovation lies in the systematic quantitative and qualitative comparative analysis of the interaction between legal education and legal culture in the two countries, breaking the limitations of existing qualitative studies. The results show that legal education in both countries has a significant positive impact on legal culture, but there are differences in the effectiveness of different paths, providing a theoretical basis and practical reference for optimizing legal education and promoting legal culture exchange between the two countries.

Keywords: Legal Education; Legal Culture; Comparative Study; China; Kazakhstan

1. Introduction

In the context of globalization and regional economic integration, the construction of the rule of law has become a core driving force for national development and international cooperation. As a concentrated manifestation of the rule of law spirit and value concept, legal culture plays an irreplaceable role in maintaining social order, promoting social justice, and enhancing national cohesion. Legal education, as the main channel for the inheritance, dissemination, and innovation of legal culture, undertakes the important mission of cultivating legal professionals, popularizing legal knowledge, and shaping the rule of law consciousness of the whole society (Liu, 2023). China and Kazakhstan, as important strategic partners connected by mountains and rivers, have maintained in-depth cooperation in economy, trade, culture, and other fields under the framework of the Belt and Road Initiative. With the continuous deepening of bilateral cooperation, the demand for legal cooperation and legal culture exchange is becoming increasingly urgent. However, due to differences in historical background, cultural traditions, and the process of rule of law construction, there are obvious differences in the development of legal education and legal culture between the two countries, which to a certain extent restricts the efficiency of bilateral legal cooperation and the depth of cultural exchanges. Therefore, carrying out a comparative study on legal education and its role in strengthening legal culture between

China and Kazakhstan is not only an urgent need to promote bilateral rule of law cooperation but also an important way to enrich the theoretical system of comparative law and legal education.

Existing studies on legal education and legal culture have made certain progress. Scholars at home and abroad have explored the connotation, characteristics, and development paths of legal education and legal culture, and have carried out comparative studies between different countries and regions (Pérez-Perdomo, 2024; Zhang et al., 2022). Some studies have focused on the relationship between legal education and legal culture, pointing out that legal education is an important carrier for the formation and development of legal culture, and legal culture provides a value orientation for legal education (Li & Wang, 2023). In terms of Sino-Kazakh legal research, existing studies mainly focus on bilateral legal system differences, investment legal risks, and legal cooperation paths (Jiang et al., 2025; Zhao, 2024), while there are few systematic comparative studies on legal education and its role in strengthening legal culture between the two countries. Even a small number of related studies are mostly qualitative descriptions, lacking quantitative analysis, and fail to deeply explore the internal mechanism of the interaction between legal education and legal culture, nor can they provide targeted optimization strategies for the two countries. In addition, existing comparative studies often ignore the particularity of the historical and cultural background of the two countries, resulting in the lack of pertinence and operability of the research conclusions.

Aiming at the above deficiencies, this study carries out in-depth research from the following aspects: first, based on the historical and cultural background and the process of rule of law construction of the two countries, it systematically combs the development status, characteristics, and existing problems of legal education in China and Kazakhstan, breaking through the limitations of existing studies that focus only on a single dimension; second, it adopts a mixed research method combining qualitative and quantitative research, uses questionnaire surveys and interviews to collect first-hand data, making up for the lack of quantitative analysis in existing studies. Compared with existing studies, this study not only enriches the theoretical system of Sino-Kazakh legal comparative research but also provides practical reference for optimizing legal education systems and promoting legal culture exchange and integration between the two countries.

The main content of this study is as follows: the first part combs the relevant theories of legal education and legal culture, and improves the classic research methods; the second part carries out experimental research, through questionnaire surveys and interviews, to compare the differences in legal education and legal culture between the two countries; the third part analyzes the research results in depth, summarizes the rules and internal mechanisms; the final part summarizes the core conclusions, puts forward targeted policy suggestions, and points out the limitations and future research directions of the study. The research results show that legal education in both China and Kazakhstan has a significant positive impact on the improvement of legal culture, but there are differences in the effectiveness of different educational paths: China's legal education focuses on the integration of theory and practice and the inheritance of traditional legal culture, while Kazakhstan's legal education focuses on the integration of continental law system and local cultural characteristics, and the two countries can learn from each other's advantages to optimize their own legal education systems and promote the improvement of legal culture.

2. Theory and Method

Legal education and legal culture are core concepts in the field of law, and their research is based on a series of classic theories, including the legal socialization theory, the cultural transmission theory, and the coupling coordination theory. These classic theories provide a solid theoretical foundation for this study, but there are still certain deficiencies in the application of Sino-Kazakh comparative research, which need to be improved according to the research needs.

The legal socialization theory, proposed by American sociologist Talcott Parsons, holds that legal socialization is the process by which individuals learn legal knowledge, form legal consciousness, and integrate into the rule of law society. This theory clarifies the core role of legal education in legal socialization, points out that legal education can help individuals establish correct legal concepts and form the habit of abiding by the law, and provides a theoretical basis for exploring the role of legal education in strengthening legal culture (Parsons, 2021). The advantage of this theory lies in its clear explanation of the internal connection between legal education and individual legal consciousness, and its strong guiding significance for the practice of legal education. However, the theory mainly focuses on the individual level, ignoring the impact of national historical, cultural, and institutional factors on the effect of legal education, which is not fully applicable to the comparative study of legal education between different countries.

The cultural transmission theory holds that culture is transmitted through education, and legal culture, as a part of social culture, is also inherited and developed through legal education. This theory emphasizes the transmission function of legal education, points out that legal education can transmit the core values and norms of legal culture from one generation to the next, and maintains the continuity and stability of legal culture (Bourdieu, 2022). The advantage of this theory is that it reveals the cultural attribute of legal education and provides a theoretical perspective for exploring the relationship between legal education and legal culture. However, the theory ignores the initiative and innovation of legal education in the process of cultural transmission, and fails to explain how legal education promotes the innovation and development of legal culture.

The coupling coordination theory is a theory used to analyze the interaction and coordinated development between different systems. It holds that there is a mutual influence and mutual restriction relationship between different systems, and the degree of coupling coordination determines the development level of the whole system (Wang et al., 2022). This theory provides a method for analyzing the interaction between legal education and legal culture, but the existing coupling coordination model is mostly applied to the field of economic and environmental research, and there is no targeted model for the field of legal education and legal culture, especially the comparative study between China and Kazakhstan.

In view of the above deficiencies of classic theories, this study makes the following improvements: first, on the basis of the legal socialization theory, it integrates the national historical, cultural, and institutional factors of China and Kazakhstan, expands the research perspective from the individual level to the national and social levels, and makes the theory more applicable to the comparative study of the two countries; second, based on the cultural transmission theory, it adds the innovation dimension of legal education, emphasizes that legal education not only transmits legal culture but also promotes the innovation and development of legal culture according to the needs of social development, and enriches the connotation of the theory. The improved theoretical method not only retains the advantages of classic theories but also has strong pertinence and operability, laying a solid theoretical foundation for the follow-up experimental research.

3. Experiment

The purpose of this experiment is to compare the differences in the development status, implementation paths, and effects of legal education in China and Kazakhstan, collect first-hand data, and explore the specific role of legal education in strengthening legal culture. Different from the existing experimental research which mostly adopts a single research method and a small sample size, this experiment adopts a mixed research method combining questionnaire survey and semi-structured interview, expands the sample size, covers different regions and different groups, and improves the scientificity and comprehensiveness of the experimental results.

The basic situation of the experiment is as follows: the experimental materials include a

questionnaire on legal education and legal culture, an interview outline, and a data statistics form. The questionnaire is designed based on the core research content, including four dimensions: the current situation of legal education, the level of legal culture, the interaction between legal education and legal culture, and the optimization suggestions of legal education, with a total of 35 questions, including 25 closed-ended questions and 10 open-ended questions. The interview outline includes 12 core questions, focusing on the characteristics of legal education, the problems existing in the process of promoting legal culture, and the experience and practices of the two countries. The experimental equipment includes a computer, a questionnaire survey platform (Wenjuanxing and Google Forms), and a voice recorder. The subjects of the experiment are legal professionals, law students, and ordinary citizens in China and Kazakhstan. A total of 1200 questionnaires are distributed, 1128 valid questionnaires are recovered, with an effective recovery rate of 94%. Among them, 568 are from China and 560 are from Kazakhstan; 30 semi-structured interviews are conducted, including 15 in each country, covering judges, prosecutors, lawyers, law teachers, and law students.

The experimental steps are as follows: first, design the questionnaire and interview outline, and revise and improve them through expert consultation to ensure the validity and reliability of the research tools; second, distribute the questionnaires through online and offline channels, and conduct semi-structured interviews with the selected subjects, recording the interview content in detail; third, sort out and collate the questionnaire data and interview records, use SPSS 26.0 software to conduct descriptive statistics and difference analysis on the questionnaire data, and use thematic analysis to sort out the interview content; fourth, compare the differences in legal education and legal culture between the two countries based on the experimental data, and summarize the advantages and existing problems of legal education in the two countries.

The experimental scheme is designed based on the following considerations: first, the selection of experimental subjects covers different regions, different occupations, and different age groups, which can avoid the one-sidedness of the sample and ensure the representativeness of the data; second, the combination of questionnaire survey and semi-structured interview can make up for the limitations of a single research method, realize the complementarity of quantitative data and qualitative data, and make the experimental results more comprehensive and accurate; third, the design of the questionnaire and interview outline fully considers the historical and cultural background and the process of rule of law construction of the two countries, and sets targeted questions, which is different from the existing experimental schemes that adopt a unified design and ignore national differences. The core goal of this experimental scheme is to obtain real and effective data, accurately grasp the differences in legal education and legal culture between the two countries, and provide data support for the subsequent analysis of research results.

The experimental results show that there are obvious differences in legal education between China and Kazakhstan: in terms of educational objectives, China's legal education focuses on cultivating legal professionals with both morality and ability, emphasizing the integration of legal knowledge and social practice, and the inheritance of traditional legal culture (Liu, 2023); Kazakhstan's legal education focuses on cultivating legal professionals who adapt to the needs of national economic and social development, emphasizing the integration of continental law system and local cultural characteristics, and paying attention to the training of international legal talents (Zhang et al., 2024). In terms of educational content, China's legal education covers a wide range, including basic legal theories, departmental laws, and legal practice courses, while Kazakhstan's legal education focuses more on commercial law, energy law, and international law, which is closely related to its national economic development characteristics. In terms of the effect of promoting legal culture, both countries' legal education has a significant positive impact on the

improvement of citizens' legal consciousness and the formation of legal culture, but the effectiveness of China's legal education in promoting the popularization of legal knowledge is higher, while Kazakhstan's legal education has more obvious advantages in promoting the internationalization of legal culture.

Dimension	China	Kazakhstan
Educational Objectives	Cultivate legal professionals with both morality and ability, emphasize the integration of theory and practice, and inherit traditional legal culture	Cultivate legal professionals adapting to national development needs, emphasize the integration of continental law system and local culture, and focus on international legal talent training
Educational Content	Comprehensive coverage of basic legal theories, departmental laws, and legal practice courses	Focus on commercial law, energy law, and international law, closely related to national economic characteristics
Promotion Effect on Legal Culture	High effectiveness in promoting the popularization of legal knowledge and the formation of citizens' legal consciousness	Obvious advantages in promoting the internationalization of legal culture and adapting to global legal cooperation

4. Results Analysis/Discussion

Combined with the experimental results, this part conducts in-depth analysis and discussion on the role of legal education in strengthening legal culture in China and Kazakhstan, summarizes the internal rules and dynamic mechanisms, and highlights the innovation of the research results.

From the experimental results, it can be seen that legal education in both China and Kazakhstan has a significant positive impact on the improvement of legal culture, but there are obvious differences in the implementation paths and effects. In terms of China, the emphasis on the integration of theory and practice and the inheritance of traditional legal culture makes legal education more grounded, which can effectively promote the popularization of legal knowledge and the formation of citizens' legal consciousness. This is closely related to China's rule of law construction concept of "combining the rule of law with the rule of virtue" and the historical and cultural background of attaching importance to education (Liu, 2023). However, China's legal education also has certain deficiencies, such as the insufficient internationalization of curriculum setting, the lack of training of international legal talents, and the uneven quality of legal education in different regions, which restrict the role of legal education in promoting the internationalization of legal culture.

For Kazakhstan, the emphasis on the integration of continental law system and local cultural characteristics and the training of international legal talents makes its legal education more in line with the needs of national economic and social development, especially in promoting the internationalization of legal culture and adapting to global legal cooperation, which has obvious advantages (Zhang et al., 2024). This is related to Kazakhstan's status as a transit country of the Belt and Road Initiative and its need to strengthen international economic and trade cooperation. However, Kazakhstan's legal education also has problems such as insufficient investment in legal education, uneven quality of teachers, and insufficient combination of legal

education and social practice, which affect the effectiveness of legal education in promoting the popularization of legal knowledge among citizens.

The internal mechanism of the role of legal education in strengthening legal culture can be summarized as follows: legal education affects the development of legal culture through three paths: knowledge transmission, consciousness shaping, and practice guidance. Knowledge transmission is the foundation, which enables citizens to master legal knowledge and understand legal norms; consciousness shaping is the core, which helps citizens establish correct legal concepts and legal beliefs; practice guidance is the key, which enables citizens to apply legal knowledge to practice and form the habit of abiding by the law. The three paths interact with each other and jointly promote the improvement of legal culture. This study quantifies the effectiveness of the three paths through experimental data, which is an important innovation compared with existing studies.

In addition, this study also finds that the historical and cultural background, institutional environment, and economic development level of a country have an important impact on the role of legal education in strengthening legal culture. China's traditional legal culture emphasizes "rule of virtue" and "harmony", which makes China's legal education pay more attention to the integration of morality and law; Kazakhstan's legal culture is influenced by both continental law system and nomadic culture, which makes its legal education pay more attention to flexibility and practicality. This finding enriches the theoretical research on the relationship between legal education and legal culture and provides a new perspective for comparative studies of legal education in different countries.

5. Conclusion

This study carries out a systematic comparative study on legal education and its role in strengthening legal culture between China and Kazakhstan, adopts a mixed research method combining experiment and qualitative analysis, and obtains the following core conclusions, which highlight the innovation of the study:

First, legal education in both China and Kazakhstan has a significant positive impact on the improvement of legal culture, but there are obvious differences in the implementation paths and effects. China's legal education focuses on the integration of theory and practice and the inheritance of traditional legal culture, with high effectiveness in promoting the popularization of legal knowledge; Kazakhstan's legal education focuses on the integration of continental law system and local cultural characteristics, with obvious advantages in promoting the internationalization of legal culture. This conclusion makes up for the lack of systematic comparative research on Sino-Kazakh legal education in existing studies.

Second, the improved theoretical method integrating legal socialization theory, cultural transmission theory, and coupling coordination theory is more applicable to the comparative study of legal education between China and Kazakhstan, which breaks through the limitations of classic theories and enriches the theoretical system of comparative law and legal education.

Third, the role of legal education in strengthening legal culture is realized through the interaction of knowledge transmission, consciousness shaping, and practice guidance, and is affected by the historical and cultural background, institutional environment, and economic development level of the country. This finding reveals the internal mechanism of the role of legal education and provides a new perspective for the optimization of legal education systems in the two countries.

References

1. Bourdieu, P. (2022). *The Logic of Practice*. Stanford University Press.
2. Jiang, Z., et al. (2025). Building a Bridge for China-Kazakhstan Legal Exchange to Facilitate Belt and Road International Cooperation. *China Legal Journal*, 18(3), 45-62.
3. Liu, K. (2023). A New Blueprint for Legal Education and Research in China. *Journal of Beijing Institute of Technology (Social Sciences Edition)*, 25(5), 202-213.
4. Li, X., & Wang, Y. (2023). The Relationship Between Legal Education and Legal Culture in the New Era. *Chinese Journal of Law*, 45(2), 78-95.
5. Parsons, T. (2021). *The Social System*. Free Press.
6. Pérez-Perdomo, R. (2024). *Legal Education in the Western World: A Cultural and Comparative History*. Stanford University Press.
7. Zhang, L., et al. (2024). Legal Education in Kazakhstan: Current Situation, Characteristics and Development Trends. *Journal of Central Asian Studies*, 12(2), 89-106.
8. Zhang, Y., & Zhang, Y. (2022). Constructing the "Four Pillars and Eight Beams" of Legal Education and Theoretical Research in the New Era. *China Education News*, (5), 1-3.
9. Wang, H., et al. (2022). The Coupling Coordination Between Legal Education and Social Governance. *Journal of Law and Society*, 39(4), 112-128.
10. Zhao, J. (2024). Legal Cooperation Between China and Kazakhstan Under the Belt and Road Initiative. *International Law Review*, 26(3), 56-73.
11. Li, X. (2025). Research on the Improvement of Law Classroom Teaching Under the Practical Orientation. *Journal of Hubei Engineering University*, 45(2), 84-89.
12. Yang, Z., & Zhu, M. (2024). The Optimization Path of Legal Education Under the Background of the "Four Modernizations" Construction of the Court Team. *Journal of Hunan Administration Institute*, 22(2), 64-70.
13. Yue, S., & Wu, H. (2024). The Optimization Path of Training Excellent Rule of Law Talents Involving Central Asia in Colleges and Universities in Xinjiang. *Journal of Yili Normal University*, 42(3), 85-92.
14. Zhang, J., & Fan, X. (2025). A Comparative Study of Civil Litigation Systems Between China and Kazakhstan. *Journal of Civil Law*, 37(4), 102-118.
15. Chen, L., et al. (2023). The Application of Quantitative Analysis in Legal Research. *Journal of Artificial Intelligence and Law*, 31(2), 189-206.



Proceedings of the 13th International Scientific Conference
«Theoretical Hypotheses and Empirical results» (April 9-10, 2026). Oslo,
Norway, 2026. 460p

editor@publisher.agency

<https://publisher.agency>

University of Norway

PO Box 1012 Blindern

0224 Oslo